


AD-A133 910


BUFFALO METROPOLITAN AREA NEW YORK WATER RESOURCES
MANAGEMENT INTERIM REP. (U) CORPS OF ENGINEERS BUFFALO
NY BUFFALO DISTRICT JUL 83

1/9

UNCLASSIFIED

F/G 13/2 NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A


A133910

Buffalo Metropolitan Area, N.Y. ⑤
Water Resources Management

Interim Report On Feasibility
Of Flood Management

AD A133910

**Tonawanda
Creek
Watershed**




(Final Feasibility Report And
Final Environmental Impact
Statement)

DTIC FILE COPY



US Army Corps
of Engineers
Buffalo District

Appendices



83 10 18 024 July 1983

DTIC

OCT 19 83

E

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO. A138910	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Buffalo Metropolitan Area, N.Y. Interim Report on Feasibility of flood Management-Tonawanda Creek Watershed Appendices		5. TYPE OF REPORT & PERIOD COVERED Final Interim
7. AUTHOR(s)		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, Buffalo 1776 Niagara Street Buffalo, New York 14207		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE July 1983
		13. NUMBER OF PAGES 784
		15. SECURITY CLASS. (of this report)
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Unrestricted Distribution		
<div style="border: 1px solid black; padding: 5px; display: inline-block;"> This report is for public distribution is unlimited. </div>		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES This report document (July 1983) replaces an earlier report dated November 1981. Report number AD-A101 224. A120214.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Flood Damage Reduction, Flood Management, Detention Reservoirs, Tonawanda Creek, Buffalo Metro		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This final feasibility report on the Tonawanda Creek Watershed is an interim reply to the study authorization which requested determination of the feasibility of providing flood protection in the Buffalo Metropolitan Area, N.Y. The study area is located in Western New York State and includes an area of 511 square miles. The existing flooding problem causes nearly \$3.0 million in average annual damages to existing urban and agricultural development. A wide range of alternative plans were investigated as solutions to the		

flooding problem including non-structural and structural. The plans were evaluated for engineering, economic, and environmental feasibility.

The Batavia Reservoir Compound-Modified Plan was selected as the Recommended Plan. This plan is described as the shallow (normally dry) detention reservoir upstream of Batavia that act as flood alternators and provides 1-10 year flood protection in the lower reservoir, 500-year flood protection in the lower portion of the Erie Plain floodland (including the city of Batavia) and 1-10 year protection in the Huron Plain floodland downstream. This plan reduces the existing average annual flood damages by approximately 74 percent.

The total first cost is \$2.9 million at October 1982 price levels with a benefit-cost ratio of 1.19 to 1.0. This plan is designated the NED plan.

FINAL FEASIBILITY REPORT

DTIC
COPY
INSPECTED
9

[illegible]

U.S. Army Engineer District, Buffalo
1776 Niagara Street
Buffalo, New York 14207

BUFFALO METROPOLITAN AREA, NEW YORK
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

TABLE OF CONTENTS

APPENDICES

Appendix

- A Hydrology and Hydraulics
- B Evaluation of Flood Damages and Benefits
- C Cost Estimates for Alternative Plans
- D Selected Plan
- E Geotechnical Design
- F Non-Structural Base Plan
- G Public Input
- H Environmental

**BUFFALO METROPOLITAN AREA, NY
WATER RESOURCES MANAGEMENT STUDY**

**TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY**

FINAL FEASIBILITY REPORT

APPENDIX A

HYDROLOGY

AND

HYDRAULICS

**U. S. Army Engineer District, Buffalo
1776 Niagara Street
Buffalo, New York 14207**

FOREWORD

This appendix has been divided into sections to present the results of Generalized Hydrologic Investigations applicable to the entire Tonawanda Creek watershed and investigations at specific locations. Section A1 contains information relative to Generalized Hydrologic Investigations. Sections A2 through A5 contain information relative to investigations for the Considered Reservoirs, Lower Tonawanda Creek watershed, Upper Tonawanda Creek watershed, and Hydraulic Design, respectively. Section A6 and A7 address respectively the comments in the Memorandum of Understanding, 9 February 1977, and 24 April 1980, NCDPD-PF which are applicable to this appendix.

At a meeting in OCE on 14 December 1976, suggested revisions to the 1976 Tonawanda Creek FFR were presented with the understanding that incorporation of these comments would satisfy present OCE policy in having a greater level of hydrology. It was stated that with these comments in the authorizing document, the recommendation should be for authorization of construction with a minimum of Phase 1 activities. Since that time, the study has been redone. Concern for the functional adequacy of the project and the benefits claimed have been mitigated. The regional duration-frequency investigations were updated and improved. Field surveys during high water proved invaluable in determining the path of the water in the lower watershed. Diversion discharge rating curves were developed allowing hydrograph routing and combining simulation to the confluence with Ransom Creek. Surveys in the proposed Lower Reservoir area revealed the path of the water in that area (Plate A2) and the impracticality of the 1976 report location of the emergency spillway.

The operation policy originally proposed was scrutinized and revised with a new operation plan developed. For floods with an annual return period of less than 10 years, the reservoirs are operated to impound floodwaters while making releases such that the routed release combined with local inflow does not exceed damaging discharges at downstream damage centers (forecasting.) For 10-year floods and greater, the reservoirs are operated as flood attenuators which either limit the release to a specific discharge relative to downstream channel capacities or in reducing the discharge through storage of floodwaters (nonforecasting.) Damage reduction is greatest for the more frequent floods. Benefits claimed are conservative as the analysis accounts for a misoperation (when one has to decide whether or not to forecast) during the 10-year balanced flood and that there is a considerable quantity of water in the balanced hydrographs.

At a meeting 18 and 19 March 1980 between the Buffalo District and North Central Division further revisions to the 1979 report were suggested. The major revisions comprise further clarification and enhancement of the hydrologic and hydraulic engineering methods used in the study. The suggestions have been incorporated and this appendix represents the results of that effort.

Recognition is extended to:

Bradford S. Price, Chief, Hydrologic Investigations Section, Corps of Engineers
Michael C. Mohr, Hydraulic Engineer, Corps of Engineers
Lawrence J. Sherman, Hydraulic Engineer, Corps of Engineers

along with engineer trainees, hydraulic technicians, and personnel in the Word Processing Branch for their support and contributions to this appendix. Assistance from USGS and NWS personnel is acknowledged for their time and effort in providing necessary hydrologic data.

CAVEAT

The results of the hydrologic and hydraulic engineering studies presented herein indicate that a viable and functionally adequate plan exists for reducing flooding in the Tonawanda Watershed. These studies, based upon the best available data and the use of available and appropriate techniques of analysis, were performed continuously and painstakingly throughout the previous 5 years. It is hoped, therefore, that reviewers take a sufficient amount of time to read and understand the results presented in this report.

BUFFALO METROPOLITAN AREA, NY
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

TABLE OF CONTENTS

<u>Paragraph</u>	<u>Description</u>	<u>Page</u>
<u>SECTION A1</u>		
<u>GENERALIZED HYDROLOGIC INVESTIGATIONS</u>		
A1.1	Description of Tonawanda Creek Watershed	A-1
A1.2	Climatology	A-1
A1.5	Flood Producing Factors	A-1
A1.6	Maximum Known Floods	A-4
A1.7	Runoff and Streamflow Data	A-4
A1.8	Channel Capacities for Tonawanda Creek	
A1.14	Peak Discharge and Discharge-Duration-Frequency Studies	A-11
A1.23	Discharge-Drainage Area Curves for Selected Durations	A-15
A1.24	Balanced Hydrographs	A-15
A1.28	Unit Hydrograph and Flood Routing Criteria, General	A-16
A1.29	Unit Hydrographs	A-16
A1.33	Routing Criteria	A-17
A1.40	Diversion Rating Curves for Overflow to Mud and Black Creeks	A-19
A1.42	HEC-5C Modeling of the Tonawanda Creek Watershed	A-19
A1.47	Standard Project Flood, SPF, General	A-31
A1.49	Standard Project Flood, SPF, Alexander to Rapids	A-31
A1.53	Standard Project Flood, SPF, Stages	A-35
A1.54	Spillway Design Flood, SDF	A-35
A1.59	Probable Maximum Flood, PMF	A-36
A1.63	Data Needs	A-39
<u>SECTION A2</u>		
<u>CONSIDERED RESERVOIRS</u>		
A2.1	General	A-41
A2.5	Area-Capacity Curves	A-42
A2.6	Rating Curves	A-42
A2.7	Batavia Reservoir Compound, Upper Reservoir, General	A-42
A2.9	Batavia Reservoir Compound, Upper Reservoir, Operation Procedure for Floods with Less than a 10-Year Recurrence Interval	A-42

TABLE OF CONTENTS (Cont'd)

SECTION A2 - CONSIDERED RESERVOIRS (Cont'd)

<u>Paragraph</u>	<u>Description</u>	<u>Page</u>
A2.12	Batavia Reservoir Compound, Upper Reservoir, Operation Procedure for Floods with a 10-Year Recurrence Interval or Greater	A-45
A2.16	Batavia Reservoir Compound, Operation of Upper Reservoir for Floods of Record	A-46
A2.18	Batavia Reservoir Compound, Upper Reservoir, Spillway Design Flood, SDF	A-46
A2.21	Batavia Reservoir Compound, Lower Reservoir, General	A-48
A2.23	Batavia Reservoir Compound, Lower Reservoir, Operation Procedure for Floods with Less than A 10-Year Recurrence Interval	A-48
A2.27	Batavia Reservoir Compound, Lower Reservoir, Operation Procedures for Floods with a 10-Year Recurrence Interval or Greater	A-49
A2.29	Batavia Reservoir Compound, Operation of Lower Reservoir for Floods of Record	A-52
A2.30	Batavia Reservoir Compound, Lower Reservoir Spillway Design Flood, SDF	A-52
A2.33	Batavia Reservoir Compound, Flooding Downstream of Batavia	A-55
A2.35	Summertime Operation of the Reservoirs	A-56
A2.39	Dam Failure, General	A-57
A2.41	Batavia Reservoir Compound, Upper Dam Failure	A-59
A2.43	Batavia Reservoir Compound, Lower Dam Failure	A-59
A2.46	Effect of Dam Failure on Batavia	A-60

SECTION A3

LOWER TONAWANDA, MUD, RANSOM, AND BLACK CREEK WATERSHEDS

A3.1	General	A-61
A3.3	Stage-Discharge Curves, Existing Conditions	A-61
A3.4	Stage-Frequency Curves, Existing Conditions	A-61
A3.7	Stage-Frequency Curves, Improved Conditions	A-64
A3.8	Flooded Areas by Reach, Existing and Improved Conditions	A-64

SECTION A4

UPPER TONAWANDA CREEK WATERSHED, HOPKINS ROAD TO ATTICA, NY

A4.1	General	A-65
A4.2	Stage-Discharge Curves, Existing Conditions	A-65
A4.4	Discharge-Frequency Curves, Existing Conditions	A-65
A4.5	Discharge-Frequency Curves, Improved Conditions	A-66

TABLE OF CONTENTS (Cont'd)

SECTION A4 - UPPER TONAWANDA CREEK WATERSHED, HOPKINS ROAD TO ATTICA, NY

<u>Paragraph</u>	<u>Description</u>	<u>Page</u>
A4.6	Stage-Frequency Curves, Existing Conditions	A-66
A4.7	Stage-Frequency Curves, Improved Conditions	A-66
A4.8	Flooded Areas by Reach, Existing and Improved Conditions	A-66

SECTION A5

HYDRAULIC DESIGN

A5.1	General	A-67
A5.2	Batavia Reservoir Compound, Upper Reservoir	A-67
A5.3	Batavia Reservoir Compound, Lower Reservoir	A-67

SECTION A6

	<u>RESPONSE TO COMMENTS IN THE MEMORANDUM FOR RECORD,</u>	A-70
	<u>9 FEBRUARY 1977</u>	

SECTION A7

	<u>RESPONSE TO COMMENTS IN THE MEMORANDUM OF UNDERSTANDING,</u>	A-74
	<u>30 JUNE 1980</u>	

TABLES

<u>Table No.</u>	<u>Description</u>	<u>Page</u>
A1.1	Stream Slopes and Drainage Areas: Tonawanda Creek and Tributaries	A-2-3
A1.2	Hydrologic Data for Major Floods by Tonawanda Creek at Batavia	A-6
A1.3a	Recorded Peak Discharges for Notable Floods in the Tonawanda and Little Tonawanda Creek Watersheds	A-7-8
A1.3b	Maximum Known Peak Discharges at USGS Gaging Stations for Streams in and Around the Tonawanda Creek Watershed	A-9-10
A1.4	Tonawanda Creek Channel Capacities	A-11
A1.5	Standard Deviation Residual, a_s	A-13
A1.6	Skew Coefficient	A-14
A1.6a	Equivalent Period of Record in Years	A-15
A1.7	500-Year Balanced Hydrograph Routings	A-20
A1.8	200-Year Balanced Hydrograph Routings	A-21
A1.9	100-Year Balanced Hydrograph Routings	A-22
A1.10	50-Year Balanced Hydrograph Routings	A-23
A1.11	20-Year Balanced Hydrograph Routings	A-24
A1.12	10-Year Balanced Hydrograph Routings	A-25

TABLE OF CONTENTS (Cont'd)

TABLES (Cont'd)

<u>Table No.</u>	<u>Description</u>	<u>Page</u>
A1.13	2-Year Balanced Hydrograph Routings	A-26
A1.14	March-April 1960 Flood	A-27
A1.15	September 1977 Flood	A-28
A1.16	March 1978 Flood	A-29
A1.17	Routing Criteria for the March 1978 Flood	A-30
A1.18	Comparative Rainfall and Discharge Data, Tonawanda Creek Watershed above Batavia	A-32
A1.19	Standard Project Flood Discharges	A-32
A1.20	Standard Project and Probable Maximum Floods	A-33
A1.21	Standard Project Local Area Rainfall and Discharges	A-34
A1.22	Standard Project Flood Elevations	A-37
A1.23	Standard Project Flood Damages	A-38
A2.1	Results of Upper Reservoir Operation, Balanced Floods	A-44
A2.2	Results of Upper Reservoir Operation, Floods of Record	A-47
A2.3	Results of Operation for the Lower Reservoir, Batavia Reservoir Compound, Balanced Floods	A-50
A2.4	Results of Operation for the Lower Reservoir, Batavia Reservoir Compound, Balanced Floods	A-51
A2.5	Results of Operation for the Lower Reservoir, Batavia Reservoir Compound, Floods of Record	A-53
A2.6	Results of Operation for the Lower Reservoir, Batavia Reservoir Compound, Floods of Record	A-54
A2.7	Peak Discharge Reduction with Reservoirs in Operation	A-56
A2.8	Duration of Flooding at Rapids, NY	A-58
A2.9	Upper Dam Failure Results	A-59
A2.10	Hazard Potential Classification	A-60
A2.11	Effect of Dam Failure on Batavia Gage	A-61
A3.1	Stage-Frequency Curves, Lower Tonawanda Watershed	A-62
A3.2	Existing and Improved Flooded Areas (Acres) by Return Period	A-63
A5.1	Hydraulic Design Data	A-68
A7.1	SPF Peak Discharges, 1979 and 1980 Analysis	A-75

PLATES

<u>Plate No.</u>	<u>Description</u>
A1	Climatological and Hydrologic Station Map
A1a	March 1960 Flooded Areas: Huron Plain Floodland
A1b	March 1960 Flooded Areas: Floodland in the City of Batavia and Downtown Vicintiy
A1c	March 1960 Flooded Areas: Erie Plain Floodland
A1d	100-Year and SPF Flooded Areas in the City of Batavia
A2	Peak Discharge-Frequency Curve: Tonawanda Creek at Batavia
A3	Peak Discharge-Frequency Curve: Tonawanda Creek at Alabama
A4a	Residual Map for Annual Mean Peak Discharge, a_m
A4b	Mean Annual Discharge-Duration-Drainage Area Curves
A4c	Mean Annual Discharge-Duration-Drainage Area Curves
A5	Residual Map for Standard Deviation (Peak), a_s
A6	Peak and 1-Day Duration Standard Deviation, S, Drainage Area Curves
A7	3 and 7-Day Duration Standard Deviation, S, Drainage Area Curves
A8	15 and 30-Day Duration Standard Deviation, S, Drainage Area Curves
A9	Peak Duration Skew vs. Drainage Area Curves
A10	1-Day Duration Skew vs. Drainage Area Curves
A11	3-Day Duration Skew vs. Drainage Area Curves
A12	7-Day Duration Skew vs. Drainage Area Curves
A13	15-Day Duration Skew vs. Drainage Area Curves
A14	30-Day Duration Skew vs. Drainage Area Curves
A15	Peak Discharge-Frequency Curves from Batavia, Downstream
A15a	Peak Discharge-Frequency Curves from Batavia, Downstream Improved (BRC) Conditions
A16	Peak Discharge-Frequency Curves from Batavia, Upstream
A17	Discharge-Duration-Frequency Curves, Batavia, NY
A18	Peak Duration-Discharge-Return Period - Drainage Area Curves, Upstream from Batavia
A19	1-Day Duration-Discharge-Return Period - Drainage Area Curves, Upstream from Batavia
A20	3-Day Duration-Discharge-Return Period - Drainage Area Curves, Upstream from Batavia
A21	7-Day Duration-Discharge-Return Period - Drainage Area Curves, Upstream from Batavia
A22	15-Day Duration-Discharge-Return Period - Drainage Area Curves, Upstream from Batavia
A23	30-Day Duration-Discharge-Return Period - Drainage Area Curves, Upstream from Batavia
A24	Peak Duration-Discharge-Return Period - Drainage Area Curves, Downstream from Batavia
A25	1-Day Duration-Discharge-Return Period - Drainage Area Curves, Downstream from Batavia
A26	3-Day Duration-Discharge-Return Period - Drainage Area Curves, Downstream from Batavia

TABLE OF CONTENTS (Cont'd)

PLATES (Cont'd)

<u>Plate No.</u>	<u>Description</u>
A27	7-Day Duration-Discharge-Return Period - Drainage Area Curves, Downstream from Batavia
A28	15-Day Duration-Discharge-Return Period - Drainage Area Curves, Downstream from Batavia
A29	30-Day Duration-Discharge-Return Period - Drainage Area Curves, Downstream from Batavia
A30	Pattern Hydrographs
A31	200-Year Balanced Hydrographs at Batavia
A32	200-Year Balanced Hydrographs at Alabama
A33	Clark's "R" vs. Drainage Area
A34	Clark's "T _c " vs. Average Stream Slope
A35	Hydrographs at Batavia, 19-20 May 1957 Storm
A36	3-Hour Unit Hydrographs
A37	Routing Schematic
A38	Existing Conditions Flooded Areas Upstream of Batavia
A39	Nonexistent
A40	Diversion Discharge Curve for Tonawanda Overflow to Mud Creek
A41	Diversion Discharge Curve for Tonawanda Overflow to Black Creek
A42	Upper Reservoir, 200-Year Flood Discharge Hydrographs
A43	Upper Reservoir, 200-Year Flood Stage Hydrographs
A43a	Upper Reservoir, 200-Year Failure Hydrographs
A44	Lower Reservoir, 200-Year Flood Discharge Hydrographs
A45	Lower Reservoir, 200-Year Flood Stage Hydrographs
A45a	Lower Reservoir, 200-Year Failure Hydrographs
A45b	200-Year Dam Failure Stage Hydrograph at Batavia Gage
A46	200-Year Flood Discharge Hydrographs Downstream from Confluence with Ledge Creek
A47	Upper Reservoir, 50-Year Flood Discharge Hydrographs
A48	Upper Reservoir, 50-Year Flood Stage Hydrographs
A49	Lower Reservoir, 50-Year Flood Discharge Hydrographs
A50	Lower Reservoir, 50-Year Flood Stage Hydrographs
A51	50-Year Flood Discharge Hydrographs Downstream from Confluence with Ledge Creek
A51a	Upper Reservoir 20-Year Failure Hydrographs
A51b	Lower Reservoir 20-Year Failure Hydrographs
A51c	20-Year Dam Failure Stage Hydrographs at Batavia Gage
A52	Upper Reservoir 2-Year Flood Discharge Hydrographs
A53	Upper Reservoir 2-Year Flood Stage Hydrographs
A54	Upper Reservoir 2-Year Flood, Operation Hydrographs
A54a	Upper Reservoir Failure Hydrographs
A55	Lower Reservoir 2-Year Flood Discharge Hydrographs
A56	Lower Reservoir 2-Year Flood Stage Hydrographs
A57	Lower Reservoir 2-Year Flood, Operation Hydrographs
A57a	Lower Reservoir Response to Upper Reservoir Failure
A57b	Lower Reservoir 2-Year Failure Hydrographs
A58	2-Year Flood Discharge Hydrographs Downstream from Confluence with Ledge Creek

TABLE OF CONTENTS (Cont'd)

PLATES (Cont'd)

<u>Plate No.</u>	<u>Description</u>
A59	Lower Reservoir, March 1960 Flood Discharge Hydrographs
A60	Lower Reservoir, March 1960 Flood Stage Hydrographs
A61	March 1960 Flood Discharge Hydrographs Downstream from the Confluence with Ledge Creek
A62	Reconstituted March 1960 Flood at Rapids, NY
A63	Upper Reservoir September 1977 Flood Discharge Hydrographs
A64	Upper Reservoir September 1977 Flood Stage Hydrographs
A65	Lower Reservoir September 1977 Flood Discharge Hydrographs
A66	Lower Reservoir September 1977 Flood Stage Hydrographs
A67	Upper Reservoir March 1978 Flood Discharge Hydrographs
A68	Upper Reservoir March 1978 Flood Stage Hydrographs
A69	Lower Reservoir March 1978 Flood Discharge Hydrographs
A70	Lower Reservoir March 1978 Flood Stage Hydrographs
A71	March 1978 Flood Discharge Hydrographs Downstream from Confluence with Ledge Creek
A71a	Standard Project Storm Isohyetal Patterns
A72	Upper Reservoir SPF at Alexander
A72a	Upper Reservoir SPF Stage Hydrographs
A72b	Upper Reservoir SPF Failure Hydrographs
A73	Local SPF for Little Tonawanda Creek
A74	Lower Reservoir SPF at Batavia
A74a	Lower Reservoir SPF Stage Hydrographs
A74b	Lower Reservoir SPF Failure Hydrographs
A74c	SPF Dam Failure Stage Hydrographs at Batavia Gage
A75	SPF at Alabama
A76	Local SPF from Murder-Ledge Creek
A77	SPF at Rapids
A77a	Depth-Area-Duration Curves for Probable Maximum Storm Index
A77b	Probable Maximum Storm Time Distribution Patterns
A78	Upper Reservoir, PMF at Alexander
A78a	Upper Reservoir PMF Stage Hydrographs
A78b	Upper Reservoir PMF Failure Hydrographs
A79	Local PMF Hydrograph at Little Tonawanda Creek
A80	Lower Reservoir PMF at Batavia
A80a	Lower Reservoir PMF Stage Hydrographs
A80b	Lower Reservoir PMF Failure Hdrographs
A80c	PMF Dam Failure Stage Hydrographs at Batavia Gage
A81	Batavia Reservoir Compound, Upper Reservoir Area-Capacity Curves
A82	Batavia Reservoir Compound, Lower Reservoir Area-Capacity Curves
A83	Upper Reservoir, Stage-Discharge Curves
A84	Lower Reservoir, Stage-Discharge Curves
A85	Stage-Discharge Curve, U. S. Face Campbell Boulevard Bridge

TABLE OF CONTENTS (Cont'd)

PLATES (Cont'd)

Plate No.	Description
A86	Stage-Discharge Curve at Rapids Road Gage
A87	Stage-Discharge Curve at Hopkins Road Gage
A88	Stage-Frequency Curve at Hopkins Road Gage
A89	Stage-Frequency Curves, Reach T-1
A90	Stage-Frequency Curves, Reach T-2
A91	Stage-Frequency Curves, Reach T-3
A92	Stage-Frequency Curves, Reach T-4
A93	Stage-Frequency Curves, Reach T-5
A94	Stage-Frequency Curves, Reach T-6
A95	Stage-Frequency Curves, Reach T-7
A96	Stage-Frequency Curves, Reach T-8
A97	Stage-Frequency Curves, Reach T-9
A98	Stage-Frequency Curves, Reach T-10
A99	Stage-Discharge Curve at Reach M-3
A100	Stage-Frequency Curve, Reach M-1
A101	Stage-Frequency Curve, Reach M-2
A102	Stage-Frequency Curve, Reach M-3
A103	Stage-Frequency Curve, Reach M-4
A104	Stage-Frequency Curve, Reach M-5
A105	Stage-Frequency Curve, Reach M-6
A106	Stage-Discharge Curve at Reach RB-2
A107	Stage-Discharge Curve at Reach RB-4
A108	Stage-Frequency Curves at Reach RB-1
A109	Stage-Frequency Curves at Reach RB-2
A110	Stage-Frequency Curves at Reach RB-3
A111	Stage-Frequency Curves at Reach RB-4
A112	Peak Discharge-Frequency Curves at Hopkins Road Gage
A113	Stage-Discharge Curve at Batavia Gage
A114	Stage-Discharge Curve at Reach T-12
A115	Stage-Discharge Curve at Reach B-1
A116	Stage-Discharge Curve at Reaches B-2 and B-3
A117	Stage-Discharge Curve at Reaches B-4 and B-5
A118	Stage-Discharge Curve at Reach T-13
A119	Stage-Discharge Curve at Reach A-1
A120	Stage-Discharge Curve at Reach A-2
A121	Stage-Discharge Curve at Reach A-3
A122	Peak Discharge-Frequency Curves at Batavia Gage
A123	Stage-Frequency Curves, Reach T-11
A124	Stage-Frequency Curves, Reach T-12
A125	Stage-Frequency Curves, Reach B-1
A126	Stage-Frequency Curves, Reaches B-2 and B-3
A127	Stage-Frequency Curves, Reaches B-4 and B-5
A128	Stage-Frequency Curves, Reach T-13
A129	Stage-Frequency Curves, Reach A-1
A130	Stage-Frequency Curves, Reach A-2
A131	Stage-Frequency Curves, Reach A-3

APPENDIX A

A1. GENERALIZED HYDROLOGIC INVESTIGATIONS

A1.1 Description of Tonawanda Creek Watershed

The Tonawanda Creek Watershed encompasses an area of 648 square miles, wholly in Western New York State. Plate A1 shows the location of the watershed within the State and the numerous tributary drainage areas within the Tonawanda Creek Watershed. Tonawanda Creek flows from its source in the Cattaraugus Hills in Wyoming County, through deep valleys with steep slopes, northward for approximately 22 miles to Attica. From there the creek passes through flat bottom land, with limited channel capacity, to Batavia. Turning westward at Batavia, the creek winds its course through more level terrain. The channel is often insufficient; the creek flows sluggishly and often floods extensively during periods of high flow. Ledge-Murder Creek is the principal tributary emptying into Tonawanda Creek between Batavia and Rapids. Below river-mile 11.2, Tonawanda Creek forms a portion of the New York State Barge Canal and continues to the Niagara River. This reach, as part of the Barge Canal system, has an improved channel with flood discharges usually flowing well within the channel. A large portion of the lower watershed drains within this reach. Mud Creek enters immediately upstream of the Barge Canal confluence. Ransom-Black-Gott Creek enters just below this confluence. Ellicott and Bull Creeks join the mainstream near Tonawanda's confluence with the Niagara River. Flood management needs for Ellicott and Bull Creeks are independent of those in the remainder of the watershed and studies of those needs have been accomplished separately. Further discussion on the character of the watershed may be found in the Main Report, Section II. Table A1.1 presents a tabulation of stream slopes and drainage areas for Tonawanda Creek and its tributaries.

A1.2 Climatology

There have been 12 climatological stations located in or adjacent to the Tonawanda Creek Watershed as shown on Plate A1. Of these 12, only eight are still in operation, including the Weather Bureau First-Order station at the Buffalo International Airport. The average annual precipitation for the 12 stations (through 1966) is 36.92 inches. Monthly averages vary from a minimum of 2.53 inches in February to a maximum of 3.33 inches in May.

A1.3 The average annual snowfall for the 12 stations (through 1966) is 82.3 inches. The highest average monthly snowfall is 22.4 inches in January at Arcade, NY.

A1.4 The average annual temperature for 10 of the stations (through 1966) is 46.9 degrees Fahrenheit. The maximum average monthly temperature is 69.2 degrees in July, while the minimum is 24.2 degrees in January.

A1.5 Flood Producing Factors

According to records, most of the floods in the Tonawanda Creek Watershed have been caused by melting snow with moderate amounts of rainfall rather

Table Al.1 - Stream Slopes and Drainage Areas,
Tonawanda Creek and Tributaries

Location	Distance Above Niagara River River Miles	Slope Feet/Mile	Drainage Area Square Miles
Tonawanda Creek at Niagara River	0	4.75	648
Tonawanda Creek at Ellicott Creek	.3	4.75	647
Ellicott Creek at Mouth		5.49	110
Tonawanda Creek at Bull Creek	4.8	4.79	537
Bull Creek at Mouth		6.91	26.9
Tonawanda Creek at Ransom Creek	9.8	5.38	500
Ransom Creek at Mouth		2.76	60
Tonawanda Creek at Mud Creek	13.0	5.68	414
Mud Creek at Mouth		2.16	41.1
Tonawanda Creek at Rapids Gage	18.5	5.76	358
Tonawanda Creek at Beeman Creek	23.3	6.18	356
Beeman Creek at Mouth		10.83	15.4
Tonawanda Creek at Ledge Creek	33.0	7.16	318
Ledge Creek at Mouth		29.0	74.2
Tonawanda Creek at Alabama Gage	41.5	7.92	231

Table A1.1 - Stream Slopes and Drainage Areas (Cont'd)
Tonawanda Creek and Tributaries

Location	Distance Above Niagara River River Miles	Slope Feet/Mile	Drainage Area Square Miles
Tonawanda Creek at Bowen Creek	56.8	7.92	200
Bowen Creek at Mouth		29.8	15.7
Tonawanda Creek at Batavia Gage	63.8	7.92	171
Tonawanda Creek at Little Tonawanda Creek	68.8	9.59	151
Little Tonawanda at Mouth		36.2	38
Tonawanda Creek at Alexander	78.0	18.3	102
Tonawanda Creek at Attica	82.0	24.0	81

than rainfall alone. The magnitude of a snowmelt flood is highly dependent upon the amount of snowpack, and the magnitude and temporal variation of temperature. During the March 1960 flood, only 0.2 inches of rain fell over the basin. With temperatures reaching 66°F, the 5.2 inches of water equivalent snow melted rapidly resulting in the flood of record. During the March 1978 flood, however, with maximum daily temperatures reaching only 45°F, the 2.4 inches of water equivalent of snow melted slowly with minimal flooding. The orientation of the watershed with respect to the usual direction of travel of frontal systems in this area also influences the effect of rainfall on runoff. Tonawanda Creek below Batavia flows generally westward and frontal system direction is typically from west to east. An examination of the streamflow records for the Tonawanda Creek at Alabama gage for the period of record, 1922 through 1977, revealed that approximately 90 percent of flows above bank occurred during December through April. In addition, it should be noted that due to the limited channel capacity of Tonawanda Creek, overbank flooding occurs on the average of approximately three times a year.

Al.6 Maximum Known Floods

Flooding in the Tonawanda Creek Watershed has been recorded as early as March 1904. As mentioned in paragraph Al.5, most floods have been caused by melting snow with moderate amounts of rainfall. In some years, two or three floods have been recorded from successive snowmelts. The most damaging Tonawanda Creek flood of record at Batavia occurred on 31 March 1960, with flooded outlines shown on Plates A2a-A2c for existing and improved (Batavia Reservoir Compound) conditions. Field surveys for highwater marks and flood fringe location during and after the March-April 1960 flood supplied the necessary information to draw the flooded area maps. Flow direction and the discharge under existing and improved conditions are also shown along with the approximate range of channel capacities in the reach. Further description of this flood may be found in paragraph Al.44. The most recent flood occurred in March 1979. A comparison of hydrologic data for several major floods on Tonawanda Creek is shown in Table Al.2. It should be noted that the September 1977 flood is the summertime flood of record, with further discussion to be found in paragraph Al.45. Table Al.3a lists discharge data at gaging stations on Tonawanda Creek for eight floods of record.

Al.7 Runoff and Streamflow Data

The streamflow data for the hydrologic studies of this report were obtained from the records of the United States Geological Survey (U.S.G.S.), New York State Department of Public Works, and city of Batavia for gages on the streams listed in Table Al.3b. Gaging station locations are shown on Plate Al.

Al.8 Channel Capacities for Tonawanda Creek

It is imperative that the channel capacity downstream of flood control reservoirs is adequately investigated and considered in sufficient detail to allow the establishment of sound project formulation and regulation criteria. Past experience has shown that the determination of channel capacity at isolated locations has proven inadequate. For Tonawanda Creek and its tributaries,

channel capacities were determined from stream gage records and field observations made during historic floods. The numerous roads adjacent to Tonawanda Creek allowed Corps personnel to easily and efficiently observe the creek along its entire watercourse during runoff events. Aerial reconnaissance was also used to establish overflow areas. The collected data allowed a range of channel capacities in all reaches to be established with the lower values used during the reservoir operation studies in order to not overstate the benefits attributable to the operation of the considered reservoirs. The adequacy of the field data precluded the need for an expensive backwater analysis.

Al.9 Stream gage locations are shown on Plate Al. Damage reaches were delineated from the mouth to Attica, NY, and are shown on Plates Ala through Alc. Ranges of channel capacities are also shown on these plates and are presented in Table Al.4. Further discussion on channel capacity determinations follow.

Al.10 Tonawanda Creek has the largest capacity near the mouth (Reaches T-1 thru T-3). Channel improvements in this portion of the creek were completed before the turn of the century as part of the Barge Canal System. Depending upon the Niagara River stage the channel capacity will range between 10,000-12,000 cfs. From the confluence with the Barge Canal to River Mile 28.0 (Reaches T-4 thru T-7) the channel capacity is limited to 4,000-6,000 cfs. The rating curve at the Rapids gage was used as the basis for this estimate along with field observations during recent flooding. Although the banks are steep in many sections, the capacity is limited due to the extremely mild slope and meandering channel. From there to Alabama (Reaches T-8 thru T-10) the channel meanders considerably with a bank-full capacity of 3,500-4,500 cfs. Ledge Creek enters in this section and shall be used as a downstream control point for the proposed Batavia Reservoir Compound. The range of channel capacity was again determined utilizing the stage-discharge relation at the Alabama gage and field observations during flooding.

Al.11 Discharge measurements and highwater marks obtained by Buffalo District personnel allowed channel capacity estimates to be made for Ransom-Black Creek and Mud Creek. Limited backwater calculations utilizing cross-section data to be used in a future FIS study substantiated the Mud Creek estimate.

Al.12 From Alabama to Bushville (Reaches T-11 & T-12) there is a 3,200-4,200 cfs range of channel capacity. The slope in this portion of the creek is generally mild except near Indian Falls where Tonawanda Creek flows from the Erie Plain to the Huron Plain with a resulting 120-foot drop in elevation in 1.8 river miles. Within the city of Batavia (Reaches B-1 thru B-5) the Corps of Engineers channel improvement project provides 6,000 cfs channel capacity. This project provided for widening of the creek channel from a point three-quarters of a mile west of the city line of Batavia to the municipal dam in Batavia. Bank protection was provided between Oak and Walnut Streets along with minor channel clearing above the Municipal dam to the Lehigh Valley Railroad bridge. The project was completed in 1956.

Al.13 The reach between Batavia and Alexander has a very mild slope and the channel has many bends which frequently causes debris jams to occur. Because of the numerous bends and jams, a very limited channel capacity of approximately 500 cfs exists. Above Alexander the slope of the creek increases as the Cattaraugus hills are approached. The channel capacity increases partly because of the increased slope to a range of 3,000-5,000 cfs as indicated by discharge measurements at the USGS Attica gage.

Table A1.2 - Hydrologic Data for Major Floods by Tonawanda Creek at Batavia

Year	Date	Peak Discharge : at Batavia, cfs	Rainfall : Inches	Runoff : Inches	Snow on Ground, Inches	Temp °F Max. : Min.
1902	6 July	5,350 (1)	4.2	(2)	0	(2) : (2)
1916	28 March	7,050 (1)	0.4	(2)	(2)	58 : 40
1942	17 March	6,000 (1)	1.5	(2)	(2)	59 : 33
1956	7 March	6,480	2.5	1.9	1-2	46 : 22
1957	23 January	6,090	1.8	2.1	12-18	55 : 12
1959	22 January	5,230	1.5	1.7	12-18	52 : 12
1960	31 March	7,200	0.2	3.3	23 (3)	61 : 33
1977	25 September	5,120	7.7	5.5	0	69 : 56
1978	22 March	3,800	0.6	3.6	15 (4)	45 : 31
1979	5 March	5,570	0.3	3.0	11-18 (5)	52 : 35

(1) Corps of Engineers estimate based on highwater marks and backwater computations.

(2) Unknown.

(3) Average value from snow survey made by Corps of Engineers. Water content of snow was 5.2 inches.

(4) U.S.G.S. New York Cooperative Snow Survey. March 13-15, 1978.

(5) Based upon NWS records and USGS New York Cooperative Snow Survey taken 5-7 February 1978 and 5-7 March 1978.

Table Al.3a - Recorded Peak Discharges for Notable Floods in the Tonawanda and Little Tonawanda Creek Watersheds

Gage Location	Drainage Area : sq. mi.	March 1942		March 1956		Jan. 1957		Jan 1959	
		cfs	:sq. mi.:	cfs	:sq. mi.:	cfs	:sq. mi.:	cfs	:sq. mi.
Linden	22.1	2,130	97	2,700	122	1,500	68	1,630	74
Batavia	171.0	6,000	35	6,480	38	6,090	35	5,230	30
Alabama (Hopkins Rd)	231.0	6,860	30	6,850	30	6,180	27	9,000(1)	39
Rapids (2)	358.0	-	-	5,090	14	5,210	15	4,450	12
(3)		-	-	7,780	22	7,790	22	6,700	19

(1) This discharge was determined by the U.S.G.S. from an ice-affected stage.

(2) Does not include flow which enters Mud and Black Creek upstream from the gage as discussed in Appendix A.

(3) Includes flow to Black and Mud Creek.

Table Al.3a - Recorded Peak Discharges for Notable Floods in the Tonawanda and Little Tonawanda Creek Watersheds (Cont'd)

Gage Location	March 1960			September 1977			March 1978			March 1979		
	Drainage Area	sq. mi.	cfs	sq. mi.	cfs	sq. mi.	cfs	sq. mi.	cfs	sq. mi.	cfs	sq. mi.
Attica	82	-	-	-	-	-	1,380	17	-	-	-	-
Linden	22.1	1,830	85	-	-	-	631	29	913	42	42	42
Batavia	171.0	7,200	42	5,120	30	3,620	22	5,570	33	33	33	33
Alabama (Hopkins Rd)	231.0	7,980	35	5,020	22	3,680	16	6,710	29	29	29	29
Rapids (2)	358.0	6,280	18	-	-	5,100	14	5,500	15	15	15	15
(3)		12,380	35	-	-	7,200	20	9,050	25	25	25	25

- (1) This discharge was determined by the U.S.G.S. from an ice-affected stage.
- (2) Does not include flow which enters Mud and Black Creek upstream from the gage as discussed in Appendix Al.
- (3) Includes flow to Black and Mud Creek.

Table A1.3b - Maximum Known Peak Discharges at USGS Gaging Stations
In and Around the Tonawanda Creek Watershed

Gaging Station	D.A.	Period of Record	Date	Peak Discharge cfs
Little Tonawanda at Linden	22.1	1912-1968 1978-present	7 March 1956	2,700
Cayuga Creek nr. Lancaster	94.9	1938-1968 1971-present	23 June 1972	8,800
Cazenovia Creek at Ebenezer	134.0	1940-present	1 March 1955	13,500
Buffalo Creek at Gardenville	144.0	1938-present	1 March 1955	13,000
Cattaraugus Creek at Gowanda	432.0	1939-present	7 March 1956	34,600
Oatka Creek at Warsaw	41.9	1963-present	23 June 1972	4,010
Ellicott Cr. nr. Williamsville	72.4	1955-1972 (1)	31 March 1960	4,860
	77.6	1972-present		

(1) Gage moved to U. S. Sheridan Drive.

Table A1.3b - Maximum Known Peak Discharges at USGS Gaging Stations
In and Around the Tonawanda Creek Watershed (Cont'd)

Gaging Station	D.A.	Period of Record	Date	Peak Discharge cfs
Tonawanda Creek at Attica	82.0	1978-present	21 March 1978	2,107
Tonawanda Creek at Batavia	171.0	1929-1944 (2) 1944-present	31 March 1960	7,200
Tonawanda Creek at Alabama	231.0	1922-1955 (3) 1955-present	29 January 1959	9,000 (4)
Tonawanda Creek at Rapids	351.0	1955-1965 1978-present	1 April 1960	12,380 (5)
Black Creek at Swormville	2.8	1978-present	25 March 1978	8.82 (6)
Genesee River at Jones Bridge	1,419.	1910-present	17 May 1916	55,100
Genesee River at Rochester	2,457.	1909--present	30 March 1916	48,300

(2) City of Batavia gage during period indicated.

(3) NYS Department of Public Works gage during period indicated.

(4) This discharge was determined by the U.S.G.S. from an ice-affected stage.

(5) Includes flow to Black and Mud Creek.

(6) Gage height.

(7) Only flow data prior to Mt. Morris dam was used.

Table Al.4 - Tonawanda Creek Channel Capacities

Reach	:	Channel Capacity - cfs
T-1 through T-3	:	10,000 - 12,000
T-4 through T-7	:	4,000 - 6,000
T-8 through T-10	:	3,500 - 4,500
M-1 through M-6	:	200 - 400
RB-1 through RB-4	:	200 - 400
T-11 and T-12	:	3,200 - 4,200
B-1 through B-5	:	6,000
T-13	:	2,000
A-1 through A-3	:	3,000 - 5,000

Al.14 Peak Discharge and Discharge-Duration-Frequency Studies

Peak discharge-frequency and discharge-duration-frequency analyses were used in the design of the flood attenuation structures for this study. Streamflow data through water-year 1977 for the gaging stations listed in Table Al.3b, with the exceptions of Tonawanda Creek at Attica and Black Creek at Swormville, were used in a regional frequency study to determine the statistical parameters of mean annual discharge, Q_m ; standard deviation, s ; and skew coefficient, g . The analyses were made using the HEC computer program HEC-46 regional frequency computation for peak, 1-, 3-, 7-, 15-, and 30-day flow duration. The program computes the frequency statistics for recorded events at each station and duration. Missing events are synthesized to form complete sets of events for all years of record at all stations, with intercorrelations preserved. The statistics for each station are adjusted to the complete period of record. Regression analyses were then performed to determine relationships between drainage area and Q_m , s , and g . Peak discharge and discharge-duration-frequency curves were determined by a Log Pearson Type III analysis using the appropriate statistical parameters for the corresponding drainage area with an expected probability adjustment. Paragraphs Al.15 through Al.22 describe the procedures followed and results of the frequency analysis in more detail.

Al.15 A regional frequency analysis used maximum annual instantaneous peak and 1-, 3-, 7-, 15-, and 30-day discharge data from records, through water year 1977, for the gaging stations listed in Table Al.3b. Q_m , s , and g were determined for each station. On Plates A2 and A3 peak discharge curves with and without expected probability adjustment for Tonawanda Creek at Batavia and Alabama are presented.

The observed annual peaks are shown along with the 5 and 95 percent confidence limits. These discharge data reflect natural watershed effects on streamflow. During high flows, floodwaters enter the Ransom and Black Creek Watersheds upstream from the Rapids gage on Tonawanda Creek and are, therefore, not measured at the gage. Thus, the Q_m , s , and g values computed from the Rapids streamflow data were inaccurate and were not used in the final analysis. Further discussion on the interbasin diversions may be found in paragraph A1.40. A linear regression analysis was then made to relate Q_m , s , and g to drainage area for each duration.

A1.16 A plot Q_m for all durations and for each station versus drainage area suggested general groupings by two distinct geographic areas: upstream and downstream of Batavia. This is consistent with the physiography of the area. The Tonawanda Creek watershed includes portions of two physiographic provinces. The Cattaraugus Hills are separated by deeply-eroded valleys with relatively steep sides and slopes, while the Erie-Ontario lowland is slightly undulating with flat slopes. Further discussion of the physiography of the region may be found in the Main Report (Section II, Physiography). The Q_m versus DA relations were further defined by three relations: streams downstream from Batavia and tributary to Tonawanda Creek, areas along the mainstem of Tonawanda Creek downstream from Batavia, and areas upstream from Batavia. Since a perfect correlation does not exist between the mean annual discharge and drainage area, a residual was computed for each station. The residual, A_m , reflects the difference between the discharge computed by the regression equation and the observed value. These values were plotted on a map at the centroid of the drainage area in order to obtain an average value of the residual for areas upstream and downstream from Batavia, and are shown on Plate A4a for the peak duration. The regional residuals for the peak discharge from this were found to be zero. The residuals for the other durations were also found to be zero. Shown on Plates A4a and A4c are the applicable relations between peak and other duration discharges and drainage area.

A1.17 As noted on Plate A4c, Oatka Creek was not used in the peak regression analysis. The reason for this was a lack of confidence in the accuracy of the recorded maximum annual instantaneous peak discharge data and the inconsistency between the peak and other duration regressions. For example, a close examination of the rating curve for the USGS gaging station revealed that the maximum discharge, 4,010 cfs, 23 June 1972, was obtained by extending the rating curve above 1,770 cfs based on a slope-area measurement of peak flow. The 4,100 cfs should have caused considerable damage based on a Corps DM for the completed flood control project at the village of Warsaw. However, based upon field surveys during the flood, floodwaters were observed to be within banks. Consequently, the USGS rating curve was considered inaccurate for peak flows. Further, except for the peak discharge data, good regression fits were obtained for and between other durations as shown on Plate A4c. Consequently, the regression fit was done for peak duration using the remaining stations, which resulted in the expected consistency between durations.

A1.18 The standard deviation for all stations was correlated with the drainage area. Unlike the mean annual discharge, the standard deviation was fitted by one equation. A residual was calculated in a manner similar to the

mean annual discharge analysis. The standard deviation is calculated by using the regression equation with the corresponding residual. Table A1.5 lists the appropriate value for the standard deviation residual, a_s and Plate A5 presents the peak standard deviation residual map. The standard deviation regression relations appear for all durations on Plates A6 through A8.

Table A1.5 - Standard Deviation Residual, a_s

Duration	Residual, a_s	
	D.S. of Batavia	U.S. of Batavia
Peak	0.0	+0.01
1-Day	+0.02	0.0
3-Day	+0.01	+0.01
7-Day	+0.01	0.0
15-Day	0.0	0.0
30-Day	+0.01	0.0

A1.19 The unreliability of the skew coefficient at any single station with a period of record less than 100 years resulted in the determination of a regional skew coefficient. The regional skew coefficients were developed by weighting the station skew coefficient with the period of record as follows:

$$g_r = \sum_{i=1}^N \frac{N_i}{N_{tot}} g_i \quad (1)$$

where

g_r = Regional skew coefficient for the given duration.
 N_i = Number of years of record at station (i).
 N_{tot} = Total number of years of record for all stations.
 g_i = Skew coefficient for station (i).

A1.20 An adopted skew coefficient was then calculated for each station in accordance with the method presented in Bulletin 17A(1). If station records of 25 to 100 years in length are available, a weighted skew coefficient should be calculated with the station skew given a weight of $(N-25)/75$ and the generalized (regional) skew given a weight of $1.0-(N-25)/75$. Thus:

$$g = g_s \frac{(N-25)}{75} + g_r (1.0 - \frac{(N-25)}{75}) \quad (2)$$

(1) Guidelines for Determining Flood Flow Frequency, Bulletin 17A, United States Water Resources Council, Washington, DC, 1977.

where

g = Adopted Station Skew

g_s = Station Skew

g_r = Regional Skew

A1.21 For peak flows, the adopted skew was correlated with the drainage area for the main stem of Tonawanda Creek downstream from Batavia, and for areas upstream from Batavia. For tributaries entering Tonawanda Creek downstream from Batavia, the peak regional skew coefficient was selected. Table A1.6 lists the appropriate skew coefficients. The plotting of the skew coefficient versus drainage area for the peak duration is found on Plate A9. Plates A10-A14 present and adopted and raw station skew versus the logarithm of the drainage area for their respective durations. Since the adopted station skews lie close to the regional skew, the regional skew was used in the calculation of the discharge-duration-frequency curves. Table A1.6 lists the appropriate skew coefficient for the given duration. These skew coefficients were considered applicable to the entire Tonawanda Creek Watershed.

Table A1.6 - Skew Coefficient, g

Duration:		Skew Coefficient	
	: Main Stem -	:	:
	: D.S. of Batavia:	U.S. of Batavia	: Tribs - D.S. of Batavia
	: $g = .388$ (log	: $g = .0986$:
Peak	: D.A.) - 1.21	: (log D.A.) - .3427:	-0.12
	:	:	:
1-Day	: -0.15	:	:
3-Day	: -0.21	:	:
7-Day	: -0.06	Applicable to Entire Watershed	
15-Day	: 0.11	:	:
30-Day	: 0.20	:	:
	:	:	:

A1.22 Peak discharge-frequency curves for selected points along Tonawanda Creek are shown on Plates A15 and A16. The 1-, 3-, 7-, 15-, and 30-day frequency curves are shown on Plate A17 for Tonawanda Creek at Batavia. Also shown is the peak discharge-frequency curve. These curves were computed from Log Pearson Type III analyses using the appropriate drainage and geographic area and applying an expected probability adjustment for an equivalent period of record. The equivalent period of record for the recorded and reconstituted flows for each station, is estimated by HEC-46 by adding the determination coefficient for each year of reconstituted flow to the total years of recorded flows. An arithmetic average of the equivalent years of record for stations upstream and downstream was calculated and is used in computing the expected probability adjustment. Table A1.6a lists the equivalent period of record used for areas upstream and downstream from Batavia.

Table A1.6a - Equivalent Period of Record in Years

Duration	Peak	1 Day	3 Days	7 Days	15 Days	30 Days
Stations up- stream from Batavia	56	60	61	62	63	63
Stations downstream from Batavia	34	31	32	32	32	30

A1.23 Discharge-Drainage Area Curves For Selected Durations

From the results of peak discharge and discharge-duration-frequency studies, discharge-duration-drainage area curves for selected return period floods were determined. Data from these curves, shown on Plates A18 through A29, were used in balanced hydrograph determinations.

A1.24 Balanced Hydrographs

Often hydrologic models are constructed from subarea unit hydrographs and the resulting flood hydrographs for historic events are compared to historic flood hydrograph data as a check of the model performance regarding timing, volume, and flood magnitude reproduction. As indicated in paragraph A1.5, the majority of the floods in the Tonawanda Creek Watershed have been caused by melting snow with moderate amounts of rainfall rather than rainfall alone. The unit hydrograph method was therefore not applicable. A period of record routing would have been the best approach, however discharge information above the proposed Reservoir Compound was not available. The lack of this information demonstrates the need for an improved Cooperative Stream Gaging Program from which funds would be available to support gages before a study is undertaken and not after. Because of the lack of discharge data, the balanced hydrograph approach was used.

A1.25 A balanced hydrograph may be defined as a theoretical flood hydrograph whose peak discharge and flood volume for specified durations have identical frequencies of occurrence. The shape of this theoretical hydrograph is patterned after the observed hydrograph of an actual flood which has occurred in the watershed. The procedure used in determining balanced hydrographs for this study follows.

A1.26 First, a pattern hydrograph was selected having an adequate duration and a shape which was typical of most floods occurring in the watershed. It is important that a pattern hydrograph compatible with the input frequency data is selected, otherwise odd-shaped balanced hydrographs may result. Since the majority of significant floods in the Tonawanda Creek Watershed have been the result of precipitation plus snowmelt during the late winter months, the 28 March through 7 April 1960 floods at Linden, Batavia, Alabama, and the reconstituted hydrograph at Rapids were selected as the pattern floods for watershed and subwatersheds investigated in this study. The

reconstitution of the 1960 flood at Rapids is discussed in paragraph A1.44. For subwatersheds upstream from Batavia, the 1960 flood at Linden was used. For Batavia, Alabama, and Rapids, the 1960 flood at those locations was used. Using the derived routing criteria, discussed in paragraphs A1.33 through A1.39, the reconstituted 1960 flood at Rapids was routed to the confluence of Mud Creek with Tonawanda Creek and used as the pattern hydrograph at the confluence. The 50-year balanced flood at the confluence with Mud Creek was routed to the confluence of Ransom Creek with Tonawanda Creek and used as the pattern hydrograph at the location. The Linden, Batavia, and Alabama pattern hydrographs used in this study are shown on Plate A30. The reconstituted 1960 flood at Rapids is shown on Plate A62.

A1.27 Balanced hydrographs were calculated for 500-, 200-, 100-, 50-, 20-, 10-, and 2-year return periods. These were computed using the proper pattern hydrograph and the peak and 1-, 3-, 7-, 15-day duration discharges from Plate A18 through A29 for the appropriate drainage area and return period. Computer program HEC-1 "Flood Hydrograph Package" was utilized in the above calculations. The 200-year balanced hydrographs for Batavia and Alabama, determined in this manner and labeled "Computed at Gage," are shown on Plates A31 and A32. Also shown for comparison are the Batavia and Alabama 200-year routed hydrographs, labeled "Routed and Combined," determined by routing and combining with 200-year local inflow.

A1.28 Unit Hydrograph and Flood Routing Criteria, General

No further consideration was given the unit hydrograph and flood routing criteria developed in the 1975 Feasibility Report. Attention was focused, however, on the development of flood routing criteria for Tonawanda Creek to the confluence with Ransom Creek. During high flows, streamflow data at the Rapids, NY, gage is inaccurate due to flood water entering the Mud and Ransom-Black Creek Watersheds upstream from the gage. Diversion discharge rating curves, shown on Plates A40 and A41, were developed for this overflow, allowing the usage of the streamflow data at the Rapids gage, and the reconstitution of the 1960 flood.

A1.29 Unit Hydrographs

Under Section 214 of the 1965 Rivers and Harbor Act, the Buffalo District performed hydrologic studies to determine unit hydrograph criteria for numerous streams in Western New York. The following is a presentation of results of prior studies and how they were used in this study.

A1.30 In prior studies, 3-hour unit hydrographs were derived from storm studies at the gaging stations listed in Table A1.3b, with the exception of Oatka Creek at Warsaw and Tonawanda Creek at Alabama and Rapids. Storms studied included the June 1944, October 1945, May 1957, April 1961, May 1961, and April 1963 storms. The Clark method of synthesis was used in determining these unit hydrographs. (No explanation of the Clark method will be given here, but a concise description of the method can be found in most textbooks on hydrology). These unit hydrographs were then adjusted by altering the Clark parameters R and Tc until it was possible to closely approximate the observed hydrographs of the recorded storms. Tc and R are time of runoff

concentration and watershed storage parameters, respectively. Next, an attempt was made to determine a relationship between these Clark parameters and typical watershed characteristics such as stream slope, drainage area, stream length, and drainage area divided by stream length.

Al.31 After considerable examination of the various watershed parameters, it was found that definite relationships existed between average stream slope and Clark's T_c and between Clark's R and drainage area. These relationships are shown on Plates A33 and A34. The reproduction of recorded storms on Tonawanda Creek at Batavia using the T_c and R values from the generalized curves showed good results. To demonstrate this, a storm reproduction is included on Plate A35 for the May 1957 storm for Tonawanda Creek at Batavia. Three-hour unit hydrographs determined using the generalized T_c and R relationships for subwatersheds upstream from Alabama and at Batavia are shown on Plate A36.

Al.32 It should be pointed out that these unit hydrographs were derived from floods that contained no snowmelt. Consequently, Standard Project Flood, SPF, and Probable Maximum Flood, PMF, determinations did not include snowmelt. The rationale for this is described in paragraph Al.60. However, Spillway Design Flood, SDF, determinations for considered structures were made including a volume of runoff from snowmelt preceeding the SDF. This is discussed in more detail in Section A2.

Al.33 Routing Criteria

The development of routing constants and local inflow in areas not previously determined was accomplished mainly through the usage of computer program HEC-1, flood hydrograph package. A complete Tonawanda Creek routing schematic is shown on Plate A37. This routing criteria was used for the balanced hydrograph, 1960 and 1977 flood routings. Routing criteria for the March 1978 flood is discussed in paragraph Al.46.

Al.34 Balanced hydrograph routings began along Tonawanda Creek at Alexander, NY, as inflow to the Upper Reservoir area. A Modified Puls routing was made through this area for existing conditions as the flood wave would experience large attenuation due to the storage upstream of the DL&WRR (Erie RR) embankment. Muskingum routing constants developed in the 1975 report for Tonawanda Creek from Alexander to the mouth of Little Tonawanda were used for this reach. The Little Tonawanda Creek at mouth hydrograph was combined with the routed Tonawanda Creek hydrograph at this confluence. The time of peak for the Little Tonawanda Creek at the mouth was made to coincide with the routed Tonawanda hydrograph. An analysis of the September 1977 and March 1978 floods support this assumption.

Al.35 Considerable field surveys were made to determine the extent of natural storage in the Lower Reservoir area. Plate A38 shows the expanse of area. Previously, Area 1 was only considered in the existing conditions storage routings. It was found that the section bounded by Ellicott Street, the Lehigh Valley Railroad (LVRR), and Town Line Road (Area 2) also is able to contain water beginning with elevation 891 feet USC&GS datum. A road

profile of Rt. 98 indicated a dip in the road near Dodgeson Road. At elevation 901 feet USC&GS datum, storage becomes available in the area bounded by Rt. 98, Dodgeson, Wortendyke, and Pike Road (Area 3). The stored water in Area 3 flows over Pike Road into Area 5. This water eventually drains into Bowen Creek via culverts under Wortendyke Road. Water escapes through the Erie Railroad opening of the LVRR once the pool elevation reaches 899 feet U.S.C.&G.S. datum, filling the area bounded by the LVRR and Conrail tracks west of Batavia (Area 4). These additional storage areas were taken into account during the flood routings.

Al.36 The computer program REVPULS, developed for this report, reverse Modified Puls routed the hydrograph at Batavia through the storage upstream of the LVRR embankment. Subtracting this reverse-routed hydrograph from the combined hydrograph at the confluence with Little Tonawanda Creek resulted in the local inflow above Batavia. The addition of the local inflow with the combined hydrograph results in the total inflow hydrograph at the Lower Reservoir site. This hydrograph was then routed by Modified Puls to obtain the hydrograph at Batavia, NY. An example is shown on Plate A31 where the 200-year balanced hydrographs for subwatersheds upstream from Batavia were routed and combined resulting in the 200-year balanced hydrograph at Batavia labeled "Routed and Combined." Also shown is the 200-year balanced hydrograph determined for Batavia directly from discharge-duration-return period-drainage area curves and the 1960 flood hydrograph at Batavia as a pattern flood.

Al.37 Muskingum routing criteria were computed for the reach between Batavia and Alabama by HEC-1 optimization using the Tonawanda Creek at Batavia and Alabama 1960 flood hydrographs. Local inflow for this reach was determined by subtracting the routed Batavia hydrograph from the Alabama hydrograph. The 200-year balanced hydrograph labeled "Routed and Combined" on Plate A32 for Alabama resulted from routing and combining subwatershed balanced hydrographs. Also shown is the 200-year balanced hydrograph at Alabama determined from discharge-duration-return period-drainage area curves and the 1960 flood hydrograph at Alabama as a pattern flood.

Al.38 An important location along Tonawanda Creek is the confluence with Ledge Creek. A stage recorder does not exist at this location. Hence, hydrographs at this location had to be synthesized. Using the 1960 flood hydrographs at Alabama and Rapids, routing constants and local inflow were derived. The travel time from Alabama to Ledge was proportioned by distance. The local inflow at the confluence was derived by proportioning the local inflow between Alabama and Rapids by drainage area with the timing appropriately adjusted. The resulting synthetic 1960 flood hydrograph at Ledge was used as the pattern hydrograph for the balanced hydrograph routings.

Al.39 Travel times downstream of the Rapids gage were derived by proportion based upon the 1964 flood. A travel time of 10 hours occurred from Rapids to the staff gage on a maintenance building on Tonawanda Creek Road (at river mile 3) for this flood. This was the only travel time information available. A Muskingum attenuation constant (x) of 0.3 was selected because of minimal overbank flooding as shown in the Flood Plain Information Report

for Tonawanda Creek (2). The FPI report is superseded by results of hydrologic analyses presented in this appendix.

Al.40 Diversion Rating Curves For Overflow to Mud and Black Creeks

During high flows, Tonawanda Creek flood water is subject to partial diversion to Mud Creek downstream of Alabama. For computation purposes, the diversion rating curve was based upon the discharge at Alabama. Using high-water marks for the 1962 and 1960 floods on Mud Creek, channel bottom, and Architect Engineer's cross sections, a backwater analysis was made. It was assumed that the peak Mud Creek discharge was the overflow discharge, with the local Mud Creek runoff peaking before Tonawanda Creek. Field observations during flooding support this assumption. The diversion rating curve was determined using information from the 1956 and 1960 flood, and profiles and discharges for the 100-year and SPF floods from the Flood Plain Information Report for Tonawanda Creek(2). Plate A40 presents the diversion rating curve for Mud Creek.

Al.41 Beeman Creek enters Tonawanda Creek approximately one mile upstream of Rapids, NY. Highwater on Tonawanda Creek will back up Beeman Creek to overflow Salt Road (Rt. 268) and enter the Black Creek Watershed. Photo 2 in the Tonawanda Creek Main Report of the 1960 flood shows this effect. A diversion discharge rating curve (Plate A41) was constructed by fitting a curve through measured discharges for the 1956, 1957, and 1960 floods. It was estimated that diversion begins when the flow measured at the Rapids gage is 4,000 cfs. Previous field observations of flooding support this assumption.

Al.42 HEC-5C Modeling of the Tonawanda Creek Watershed

With the routing criteria and local inflow derived using HEC-1, the computer program HEC-5C "Simulation of Flood Control and Conservation Systems" was used to model the Tonawanda Creek Watershed from Alexander, NY, downstream to the confluence with Ransom Creek. Using the diversion discharge rating curves, the program was able to make the necessary diversions and route and combine the overflow hydrographs. Plate A37 shows the complete routing schematic used for the balanced hydrograph routings.

Al.43 Tables Al.7 through Al.13 list the results of the balanced hydrograph routings. The tables give the drainage area of the subwatershed along with the volume and peak discharge of the flood. The total volume in inches reported at each location is the runoff which occurred for the particular flood over a time of 18.75 days. Plates A42 through A58 show the 200-, 50-, 2-year flood hydrographs at selected stream locations. Discussion of the routings with the reservoirs may be found in Section A2.

(2) Flood Plain Information: Tonawanda Creek and Its Affected Tributaries, Erie and Niagara Counties, Corps of Engineers, Buffalo District, 1971.

Table A1.7 - 500-Year Balanced Hydrograph Routings

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Alexander	102	10.6	15,000	10.6	15,000	10.6	15,000
Outflow: Upper Reservoir	102	10.6	12,200	10.6 ⁽¹⁾	12,200	10.6 ⁽¹⁾	12,200
Little Tonawanda at Mouth	38	10.6	6,200	10.6	6,200	10.6	6,200
Local Inflow: Alexander to Batavia	31	7.5	2,600	7.5	2,600	7.5	2,600
Inflow to Lower Reservoir	171	10.0	17,200	10.0	17,200	10.0	17,200
Outflow: Lower Reservoir	171	10.0	9,850	9.9	8,400	9.9 ⁽¹⁾	6,500
Local Inflow: Batavia to Alabama	60	6.4	3,030	6.4	3,030	6.4	3,030
Tonawanda at Alabama	231	8.9	12,000	8.9	10,700	8.8	8,740
Diversion to Mud Creek	231	.7	2,500	.63	2,290	.7	1,920
Tonawanda at Alabama less diversion to Mud Creek	231	8.2	9,520	8.3	8,410	8.1	6,820
Ledge Creek and Tonawanda Local	87	7.4	4,110	7.4	4,110	7.4	4,110
Tonawanda Creek downstream confluence with Ledge	318	7.9	12,600	8.0	11,500	7.9	10,300
Local Inflow: Ledge to Rapids	40	7.8	3,520	7.8	3,520	7.8	3,520
Diversion to Black Creek	358	1.4	6,800	1.4	6,050	1.3	5,150
Tonawanda at Rapids less diversions	358	6.5	6,970	6.6	6,830	6.5	6,600
Mud Creek and Tonawanda Local	56	8.3	2,440	8.3	2,440	8.3	2,440
Tonawanda below confluence with Mud Creek	414	7.1	11,730	7.2	11,300	7.2	10,500
Ransom-Black and Tonawanda Local	86	8.2	3,160	8.2	3,160	8.2	3,160
Tonawanda below confluence with Ransom	500	8.2	20,800	8.2	19,500	8.2	17,900

(1) Quantity of Water Stored in Reservoirs: Upper Res. - 1.2 inches
Lower Res. - 1.7 inches

Table A1.8 - 200-Year Balanced Hydrograph Routings

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Alexander	102	9.5	14,000	9.5	14,000	9.5	14,000
Outflow: Upper Reservoir	102	9.5	11,400	9.5 ⁽¹⁾	11,400	9.5 ⁽¹⁾	11,400
Little Tonawanda at Mouth	38	9.5	5,650	9.5	5,650	9.5	5,650
Local Inflow: Alexander to Batavia	31	7.0	2,440	7.0	2,440	7.0	2,440
Inflow to Lower Reservoir	171	9.0	16,000	9.0	16,000	9.0	16,000
Outflow: Lower Reservoir	171	9.0	9,100	8.9	7,540	8.9 ⁽¹⁾	5,780
Local Inflow: Batavia to Alabama	60	5.0	2,560	5.0	2,560	5.0	2,560
Tonawanda at Alabama	231	7.8	11,300	7.9	9,850	7.8	8,160
Diversion to Mud Creek	231	0.6	2,390	0.5	2,130	0.5	1,810
Tonawanda at Alabama less diversion to Mud Creek	231	7.2	8,940	7.4	7,720	7.3	6,350
Ledge Creek and Tonawanda Local	87	7.4	3,280	7.4	3,280	7.4	3,280
Tonawanda Creek downstream confluence with Ledge	318	7.2	11,670	7.4	10,500	7.3	9,140
Local Inflow: Ledge to Rapids	40	6.7	2,360	6.7	2,360	6.7	2,360
Diversion to Black Creek	358	1.1	5,910	1.1	5,000	1.0	4,050
Tonawanda at Rapids less diversions	358	6.0	6,800	6.2	6,550	6.1	6,260
Mud Creek and Tonawanda Local	56	6.5	1,930	6.5	1,930	6.5	1,930
Tonawanda below confluence with Mud Creek	414	6.4	10,800	6.4	10,200	6.4	9,700
Ransom-Black and Tonawanda Local	86	7.7	3,060	7.7	3,060	7.7	3,060
Tonawanda below confluence with Ransom	500	7.4	18,500	7.4	17,400	7.4	16,200

(1) Quantity of Water Stored in Reservoirs: Upper Res. - 1.2 inches
Lower Res. - 1.5 inches

Table A1.9 - 100-Year Balanced Hydrograph Routings

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Alexander	102	8.8	12,500	8.8	12,500	8.8	12,500
Outflow: Upper Reservoir	102	8.8	10,400	8.8 ⁽¹⁾	10,400	8.8 ⁽¹⁾	10,400
Little Tonawanda at Mouth	38	9.0	5,100	9.0	5,100	9.0	5,100
Local Inflow: Alexander to Batavia	31	6.0	2,500	6.0	2,500	6.0	2,500
Inflow to Lower Reservoir	171	8.3	14,700	8.3	14,000	8.3	14,000
Outflow: Lower Reservoir	171	8.3	8,470	8.3	6,770	8.3 ⁽¹⁾	5,450
Local Inflow: Batavia to Alabama	60	4.8	2,340	4.8	2,340	4.8	2,340
Tonawanda at Alabama	231	7.3	10,500	7.3	8,850	7.3	7,650
Diversion to Mud Creek	231	0.5	2,250	0.4	1,940	0.4	1,680
Tonawanda at Alabama less diversion to Mud Creek	231	6.8	8,240	6.9	6,910	6.9	5,970
Ledge Creek and Tonawanda Local	87	6.1	3,070	6.1	3,070	6.1	3,070
Tonawanda Creek downstream confluence with Ledge	318	6.6	10,800	6.7	9,470	6.6	8,570
Local Inflow: Ledge to Rapids	40	6.5	1,900	6.5	1,900	6.5	1,900
Diversion to Black Creek	358	0.9	5,140	0.8	4,190	0.8	3,550
Tonawanda at Rapids less diversions	358	5.7	6,600	5.8	6,300	5.8	6,120
Mud Creek and Tonawanda Local	56	7.0	1,580	7.0	1,580	7.0	1,580
Tonawanda below confluence with Mud Creek	414	6.1	10,200	6.2	9,560	6.2	9,100
Ransom-Black and Tonawanda Local	86	7.2	2,430	7.2	2,430	7.2	2,430
Tonawanda below confluence with Ransom	500	6.9	17,200	6.9	15,800	6.9	14,700

(1) Quantity of Water Stored in Reservoirs: Upper Res. - 1.2 inches
Lower Res. - 1.3 inches

Table A1.10 - 50-Year Balanced Hydrograph Routings

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Alexander	102	8.0	11,200	8.0	11,200	8.0	11,200
Outflow: Upper Reservoir	102	8.0	9,440	8.0 ⁽¹⁾	9,350	8.0 ⁽¹⁾	9,350
Little Tonawanda at Mouth	38	8.0	4,650	8.0	4,650	8.0	4,650
Local Inflow: Alexander to Batavia	31	8.0	2,080	8.0	2,080	8.0	2,080
Inflow to Lower Reservoir	171	8.0	13,700	7.9	10,000	7.9	10,000
Outflow: Lower Reservoir	171	8.0	7,730	7.9	5,930	7.8 ⁽¹⁾	5,240
Local Inflow: Batavia to Alabama	60	3.3	2,090	3.3	2,090	3.3	2,090
Tonawanda at Alabama	231	6.7	9,540	6.6	7,800	6.6	7,180
Diversion to Mud Creek	231	0.5	2,070	0.3	1,720	0.3	1,540
Tonawanda at Alabama less diversion to Mud Creek	231	6.2	7,470	6.3	6,080	6.3	5,640
Ledge Creek and Tonawanda Local	87	5.9	2,830	5.9	2,830	5.9	2,830
Tonawanda Creek downstream confluence with Ledge	318	6.1	9,920	6.2	8,570	6.2	8,150
Local Inflow: Ledge to Rapids	40	5.1	1,640	5.1	1,640	5.1	1,640
Diversion to Black Creek	358	0.6	4,660	0.5	3,660	0.5	3,370
Tonawanda at Rapids less diversions	358	5.3	6,420	5.5	6,150	5.5	6,060
Mud Creek and Tonawanda Local	56	5.8	1,620	5.8	1,620	5.8	1,620
Tonawanda below confluence with Mud Creek	414	5.6	9,610	5.7	8,960	5.7	8,710
Ransom-Black and Tonawanda Local	86	6.7	2,270	6.7	2,270	6.7	2,270
Tonawanda below confluence with Ransom	500	6.2	15,800	6.2	14,100	6.2	13,600

(1) Quantity of Water Stored in Reservoirs: Upper Res. - 1.2 inches
Lower Res. - 1.1 inches

Table A1.11 - 20-Year Balanced Hydrograph Routings

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Alexander	102	7.0	9,600	7.0	9,600	7.0	9,600
Outflow: Upper Reservoir	102	7.0	8,450	6.9 ⁽¹⁾	4,740	6.9 ⁽¹⁾	4,740
Little Tonawanda at Mouth	38	7.0	3,950	7.0	3,950	7.0	3,950
Local Inflow: Alexander to Batavia	31	5.8	1,820	5.8	1,820	5.8	1,820
Inflow to Lower Reservoir	171	6.7	11,700	6.7	6,930	6.7	6,930
Outflow: Lower Reservoir	171	6.7	6,650	6.7	4,930	6.7 ⁽¹⁾	4,620
Local Inflow: Batavia to Alabama	60	3.3	1,830	3.3	1,830	3.3	1,830
Tonawanda at Alabama	231	5.8	8,260	5.8	6,500	5.8	6,240
Diversion to Mud Creek	231	0.4	1,830	0.2	1,330	0.2	1,240
Tonawanda at Alabama less diversion to Mud Creek	231	5.4	6,430	5.6	5,170	5.6	5,000
Ledge Creek and Tonawanda Local	87	5.7	2,400	5.7	2,400	5.7	2,400
Tonawanda Creek downstream confluence with Ledge	318	5.5	8,600	5.0	7,390	5.6	7,220
Local Inflow: Ledge to Rapids	40	3.1	1,440	3.1	1,440	3.1	1,440
Diversion to Black Creek	358	0.4	3,360	0.4	2,510	0.3	2,400
Tonawanda at Rapids less diversions	358	4.7	6,050	4.9	5,770	4.9	5,730
Mud Creek and Tonawanda Local	56	4.9	1,450	4.9	1,446	4.9	1,446
Tonawanda below confluence with Mud Creek	414	4.9	9,050	5.0	8,200	5.0	8,060
Ransom-Black and Tonawanda Local	86	6.3	1,970	6.3	1,970	6.3	1,970
Tonawanda below confluence with Ransom	500	5.5	13,800	5.5	12,100	5.4	11,900

(1) Quantity of Water Stored in Reservoirs: Upper Res. - 1.2 inches
Lower Res. - .8 inch

Table A1.12 - 10-Year Balanced Hydrograph Routings

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Alexander	102	6.2	8,300	6.2	8,300	6.2	8,300
Outflow: Upper Reservoir	102	6.2	7,400	6.2 ⁽¹⁾	3,550	6.2 ⁽¹⁾	3,550
Little Tonawanda at Mouth	38	6.2	3,400	6.2	3,400	6.2	3,400
Local Inflow: Alexander to Batavia	31	5.1	1,640	5.1	1,640	5.1	1,640
Inflow to Lower Reservoir	171	6.0	10,300	6.1	6,000	5.0	6,000
Outflow: Lower Reservoir	171	6.0	5,870	6.0	4,320	6.0 ⁽¹⁾	4,260
Local Inflow: Batavia to Alabama	60	2.5	1,640	2.5	1,640	2.5	1,640
Tonawanda at Alabama	231	5.1	7,330	5.1	5,740	5.0	5,650
Diversion to Mud Creek	231	0.3	1,580	0.1	1,080	.1	1,050
Tonawanda at Alabama less diversion to Mud Creek	231	4.8	5,750	5.0	4,760	4.9	4,600
Ledge Creek and Tonawanda Local	87	4.4	2,380	4.4	2,380	4.4	2,380
Tonawanda Creek downstream confluence with Ledge	318	4.6	7,900	4.8	6,910	4.8	6,850
Local Inflow: Ledge to Rapids	40	4.8	1,170	4.8	1,170	4.8	1,170
Diversion to Black Creek	358	0.3	2,260	0.3	2,040	0.3	2,000
Tonawanda at Rapids less diversions	358	4.3	5,820	4.5	5,560	4.5	5,540
Mud Creek and Tonawanda Local	56	4.7	1,430	4.7	1,430	4.7	1,430
Tonawanda below confluence with Mud Creek	414	4.4	8,480	4.5	7,550	4.5	7,430
Ransom-Black and Tonawanda Local	86	5.0	1,880	5.0	1,880	5.0	1,880
Tonawanda below confluence with Ransom	500	4.8	12,330	4.8	10,800	4.8	10,670

(1) Quantity of Water Stored in Reservoirs: Upper Res. = 1.2 inches
Lower Res. = .7 inch

Table A1.13 - 2-Year Balanced Hydrograph Routings

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Alexander	102	4.2	5,000	4.2	5,000	4.2	5,000
Outflow: Upper Reservoir	102	4.2	4,570	4.2(1)	1,500	4.2(1)	1,500
Little Tonawanda at Mouth	38	4.2	2,010	4.2	2,010	4.2	2,010
Local Inflow: Alexander to Batavia	31	2.9	1,060	2.9	1,060	2.9	1,060
Inflow to Lower Reservoir	171	4.0	6,340	4.0	3,410	4.0	3,410
Outflow: Lower Reservoir	171	4.0	3,870	4.0	2,530	4.0(1)	2,000
Local Inflow: Batavia to Alabama	60	1.9	1,090	1.9	1,090	1.9	1,090
Tonawanda at Alabama	231	3.3	4,840	3.4	3,530	3.4	2,480
Diversion to Mud Creek	231	0 ⁺	560	0	0	0	0
Tonawanda at Alabama less diversion to Mud Creek	231	3.3	4,280	3.4	3,530	3.4	2,480
Ledge Creek and Tonawanda Local	87	2.8	1,610	2.8	1,610	2.8	1,610
Tonawanda Creek downstream confluence with Ledge	318	3.2	5,780	3.2	4,860	3.2	3,430
Local Inflow: Ledge to Rapids	40	3.5	935	3.5	935	3.5	935
Diversion to Black Creek	358	0.1	1,270	0 ⁺	640	0	0
Tonawanda at Rapids less diversions	358	3.1	5,140	3.2	4,710	3.2	3,950
Mud Creek and Tonawanda Local	56	2.8	685	2.8	685	2.8	685
Tonawanda below confluence with Mud Creek	414	3.0	5,560	3.1	4,930	3.1	4,100
Ransom-Black and Tonawanda Local	86	3.4	1,750	3.4	1,750	3.4	1,750
Tonawanda below confluence with Ransom	500	3.2	8,300	3.2	6,480	3.2	5,730

(1) Quantity of Water Stored in Reservoirs: Upper Reservoir - 1.0 inches
Lower Reservoir - 1.2 inches

Table A1.14 - March-April, 1960 Flood

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Alexander	102	No Data Available		Inflow to Upper Reservoir not available and hence, no routings were made.		Routings begin with inflow to Lower Reservoir and hence, do not show effect of Upper Reservoir.	
Outflow: Upper Reservoir	102	No Data Available					
Little Tonawanda at Mouth	38	No Data Available					
Local Inflow: Alexander to Batavia	31	No Data Available					
Inflow to Lower Reservoir	171	5.5	11,020			5.5	11,020
Outflow: Lower Reservoir	171	5.5	7,200			5.5 ⁽¹⁾	5,610
Local Inflow: Batavia to Alabama	60	4.7	2,420			4.7	2,420
Tonawanda at Alabama	231	5.2	7,980			5.2	6,490
Diversion to Mud Creek	231	.4	1,780			.4	1,320
Tonawanda at Alabama less diversion to Mud Creek	231	4.8	6,200			4.8	5,170
Ledge Creek and Tonawanda Local	87	7.5	3,520			7.5	3,520
Tonawanda Creek downstream confluence with Ledge	318	5.6	9,320			5.6	8,410
Local Inflow: Ledge to Rapids	40	6.2	1,490			6.2	1,490
Diversion to Black Creek	358	.9	4,280			.8	3,580
Tonawanda at Rapids less diversions	358	4.8	6,280			4.8	6,110
Mud Creek and Tonawanda Local	56						
Tonawanda below confluence with Mud Creek	414						
Ransom-Black and Tonawanda Local	86						
Tonawanda below confluence with Ransom	500						

(1) Quantity of Water Stored in Lower Reservoir = 1.4 inches

Table A1.15 - September, 1977 Flood

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Alexander	102	5.5	8,640	5.5	8,640	5.5	8,640
Outflow: Upper Reservoir	102	5.5	7,320	5.5 ⁽¹⁾	2,000	5.5 ⁽¹⁾	2,000
Little Tonawanda at Mouth	38	5.3	2,390	5.3	2,390	5.3	2,390
Local Inflow: Alexander to Batavia	31	5.0	2,500	5.0	2,500	5.0	2,500
Inflow to Lower Reservoir	171	5.5	10,800	5.3	6,860	5.3	6,860
Outflow: Lower Reservoir	171	5.5	5,110	5.3	3,720	5.5 ⁽¹⁾	2,000
Local Inflow: Batavia to Alabama	60	2.5	1,510	2.5	1,510	2.5	1,510
Tonawanda at Alabama	231	4.6	5,010	4.5	3,940	4.5	3,060
Diversion to Mud Creek	231	.6	700	0	0	0	0
Tonawanda at Alabama less diversion to Mud Creek	231	4.0	4,310	4.5	3,940	4.5	3,060
Ledge Creek and Tonawanda Local	87	-	-	-	-	-	-
Tonawanda Creek downstream confluence with Ledge	318						
Local Inflow: Ledge to Rapids	40						
Diversion to Black Creek	358						
Tonawanda at Rapids less diversions	358						
Mud Creek and Tonawanda Local	56						
Tonawanda below confluence with Mud Creek	414						
Ransom-Black and Tonawanda Local	86						
Tonawanda below confluence with Ransom	500						

(1) Quantity of Water Stored in Reservoirs: Upper Res. - 1.1 inches
Lower Res. - 1.6 inches

Table A1.16 - March, 1978 Flood

Location	D.A. Miles ²	Existing		Up. Res. Only		Res. Compound	
		Inches	Peak-cfs	Inches	Peak-cfs	Inches	Peak-cfs
Tonawanda at Attica	82	2.6	2,110	2.6	2,110	2.6	2,110
Local Inflow: Attica at Alexander	20	6.5	650	6.5	650	6.5	650
Tonawanda at Alexander	102	3.4	3,740	3.4	3,740	3.4	3,740
Outflow: Upper Reservoir	102	3.4	2,820	3.4 ⁽¹⁾	1,500	3.4 ⁽¹⁾	1,500
Local Inflow: Alexander to confluence	31	4.3	1,820	4.3	1,820	4.3	1,820
Little Tonawanda at Linden	22.7	3.6	630	3.6	630	3.6	630
Local: Linden to confluence	15.3	3.7	750	3.7	750	3.7	750
Inflow: Lower Reservoir	171	3.6	5,630	3.7	4,070	3.7	4,070
Outflow: Lower Reservoir	171	3.6	3,740	3.7	2,930	2.8 ⁽¹⁾	2,000
Local Inflow: Batavia to Alabama	60	9.0	2,650	9.0	2,650	9.0	2,650
Tonawanda at Alabama	231	5.0	4,340	5.0	3,700	4.4	3,200
Diversion to Mud Creek	231	0 ⁺	230	0	0	0	0
Tonawanda at Alabama less diversion to Mud Creek	231	5.0	4,110	5.0	3,700	4.4	3,200
Local Inflow: Alabama to Ledge	87	3.9	1,820	3.9	1,820	3.9	1,820
Tonawanda at confluence with Ledge Creek	318	4.8	6,050	4.7	5,570	4.2	4,840
Local Inflow: Ledge to Rapids	40	5.5	1,620	5.5	1,620	5.5	1,620
Diversion to Black Creek	358	.4	1,500	.2	840	.1	470
Tonawanda at Rapids less diversions	358	4.4	5,220	4.6	4,870	4.3	4,560

(1) Quantity of Water Stored in Reservoirs: Upper Res. - 0.8 inch
Lower Res. - 1.0 inches

Al.44 Table Al.14 presents the results of routing the March 1960 flood using HEC-5C. Routing begins as inflow to the Lower Reservoir area (upstream of the LVRR) and terminates at the Rapids gage. Plates Ala through Alc present the flooded areas and Plates A59 through A62 exhibit the hydrographs for the flood. Of particular note is Plate A62, reconstituted March 1960 flood at Rapids, NY. Utilizing the diversion discharge information, the total flow at the gage was derived. The reconstructed hydrograph was used as the pattern hydrograph for the balanced hydrograph routings.

Al.45 Unlike the other floods discussed in this report, the September 1977 flood was a rainfall flood. As the summertime flood of record, 7.7 inches of rain fell at Batavia for the period September 16-28 1977 (Table Al.2). Using the Clark unit hydrograph parameters, Tc and R (see Section Al.28-Al.31 and Plates A33-A34 for Clark's parameters description), an attempt was made to recreate the flood. Despite having broken the storm into two events, the storm proved too complex for such a simplistic approach. It would be necessary to separate the storm into more segments to form a more accurate reconstitution. The hydrographs upstream of Batavia were derived by reverse-routing and prorating by drainage area. Table Al.15 gives the routing results and Plates A63-A66 show the hydrographs in the Upper and Lower Reservoir area.

Al.46 Although the March 1978 flood was not a particularly noteworthy event (2-5 year), streamflow records were the most complete. Routings began along Tonawanda Creek at Attica, NY, and terminated at Rapids, NY. The routing criteria used is presented in Table Al.17.

Table Al.17 - Routing Criteria for the March 1978 Flood

Location	Routed to	Method	Number of Subreaches	K(Hrs)	X
Attica	Alexander	Muskingum	1	3	.3
Alexander	Below DLWRR	Mod Puls	-	-	-
Below DLWRR	Conf w/L. Ton.	Muskingum	2	3	.1
L. Ton. at Linden	Conf w/L. Ton.	Muskingum	1	3	.2
Conf. w/L. Ton.	Batavia	Mod Puls	-	-	-
Batavia	Alabama	Muskingum	5	3	.21
Alabama	Ledge	Muskingum	3	3	.2
Ledge	Rapids	Muskingum	3	3	.2

Routing criteria from Attica to Alexander and Linden to the confluence was developed in 1967 when the Sierks and Linden Reservoirs were under consideration. The remaining routing criteria were developed by HEC-1 optimization. Table Al.16 gives the routing results for this flood and Plates A67 through A71 present some of the routed hydrographs.

Al.47 Standard Project Flood, SPF, General

The Standard Project Flood was calculated along Tonawanda Creek between Alexander and Rapids, NY, at the same locations as was done for the balanced hydrograph routings. The Standard Project index precipitation was taken as one-half the Probable Maximum Storm index developed using Hydrometeorological Report No. 51(3). The development of the Probable Maximum Storm index is discussed later in Section Al.59-Al.60. The SPF hydrographs were calculated using the Generalized Computer Program 723-010 HEC-1 and the generalized T_c and R curves discussed in Section Al.28. The individual SPF hydrographs were routed and combined using the Generalized Computer Program 723-500 HEC-5C.

Al.48 A comparison of SPF rainfall and discharge data with other notable storms above Batavia is shown in Table Al.18. The SPF at selected locations along Tonawanda Creek is listed in Table Al.19 and Al.20. The reduction in peak discharge for the SPF between Alexander and Batavia and between Ledge and Rapids is due to natural valley storage.

Al.49 Standard Project Flood, SPF, Alexander to Rapids

As shown in Table Al.19, the results of the SPF determinations for this study differ from those presented in prior reports. A crude estimate of valley storage between Alexander and Batavia in the 1961 Interim Report(4) resulted in the low value for the SPF at Batavia. The unpublished 1976 Tonawanda Creek Report(5) utilized a refined area-capacity curve developed from topographic maps. Extensive field surveys above Batavia during 1977 further refined the area-capacity curves between Alexander and Batavia. Utilizing the refined curves and routing criteria with Hydrometeorological Report No. 51 resulted in the present SPF discharges.

Al.50 The Standard Project Index precipitation for the individual drainage areas were calculated using the isohyetal method to determine mean basin rainfall. The storm isohyetal pattern in EM-1110-2-1411(6) was used and is shown in Plate A71a. The center of the Standard Project Storm was centered over the Tonawanda Creek Watershed above Alexander, which resulted in the maximum SPF peak discharge at Batavia. The mean basin SPF rainfall and discharge for the local areas may be found in Table Al.21.

- (3) Probable Maximum Precipitation Estimates, United States East of the 105th Meridian, Hydrometeorological Report No. 51 (Washington, DC: U. S. Department of Commerce, U. S. Army Corps of Engineers, June 1978)
- (4) Interim Review of Report for Flood Control, Tonawanda Creek, Batavia, NY (Buffalo, NY, U. S. Army Corps of Engineers, 1961)
- (5) Buffalo Metropolitan Area, New York, Interim Report on Feasibility of Flood Plain Management in Tonawanda Creek Watershed, Appendix A (Buffalo, NY, U. S. Army Corps of Engineers, 1976)
- (6) Standard Project Flood Determinations, EM 1110-2-1411, Plate 12 (Washington, DC, U. S. Army Corps of Engineers, March 1965)

Table Al.18 - Comparative Rainfall and Discharge Data,
Tonawanda Creek Watershed Above Batavia

Storm Period	Duration hours	Snow on ground, inches	Total rainfall, inches	Excess rainfall or runoff inches	Peak discharge Batavia gage, cfs.	Ground Conditions
Standard Project	96	-	12.64	11.0	28,500	Saturated
7 Mar 1956	28	1-2	2.5	1.9	6,480	Partly frozen
23 Jan 1957	36	12-18	1.8	2.1	6,090	Partly frozen
31 Mar 1960	72	23	0.2	3.3	7,200	Partly frozen
25 Sep 1977	288	-	7.7	5.5	5,120	Dry

Table Al.19 - Standard Project Flood Discharges, Existing Conditions

Location	Drainage Area sq. miles	Standard Project Flood, Q in cfs		
		Prior Studies	1975 Study	Current Study
Little Tonawanda Creek at mouth	38.0	-	16,400	18,800
Tonawanda Creek at Alexander	102.0	-	34,600	38,500
Tonawanda Creek at Batavia	171.0	14,100	24,000	28,500
Local Area Batavia to Alabama	60.0	18,900	18,900	18,900
Tonawanda Creek at Alabama	231.0	35,200	28,400	38,500
Tonawanda Creek at Confluence with Murder-Ledge	318.0	-	-	38,800
Tonawanda Creek at Rapids	358.0	-	-	37,600

Table Al.20 - Standard Project and Probable Maximum Floods

	Probable Maximum Flood		Standard Project Flood			
	Existing*	Improved	Existing*	Improved	Gates Open	Full Pool
Alexander (Upper Res.)						
Inflow	81,200 cfs	81,200 cfs	38,800 cfs	38,800 cfs	38,800 cfs	38,800 cfs
Outflow	79,800 cfs	80,700 cfs	38,500 cfs	38,600 cfs	38,600 cfs	39,000 cfs
Elev.	928.4 ft.	926.5 ft.	923.8 ft.	924.5 ft.	924.5 ft.	924.5 ft.
Batavia (Lower Res.)						
Inflow	100,300 cfs	102,900 cfs	49,200 cfs	50,200 cfs	51,000 cfs	53,000 cfs
Outflow	71,000 cfs	71,000 cfs	28,500 cfs	28,400 cfs	34,600 cfs	27,500 cfs
Elev.	907.3 ft.	907.3 ft.	902.0 ft.	902.5 ft.	903.4 ft.	901.7 ft.
Alabama	NA	NA	38,500 cfs	38,400 cfs	NA	NA
Rapids	NA	NA	37,600 cfs	36,700 cfs	NA	NA

*Note - Existing condition runs have diversion of flows (less than 1,000 cfs) over Route 98 near Dodgeson Road and, therefore around Batavia from Lower Reservoir as described in paragraph Al.28.

Table A1.21 - Standard Project Local Area Rainfall and Discharges

Local Area	Drainage Area Square Miles	Mean Rainfall Inches	Peak Discharge cfs
Tonawanda at Alexander	102	11.0	38,800
Little Tonawanda Creek and Tonawanda Local: Alexander-Batavia	69	11.0	18,800
Tonawanda Local: Batavia-Alabama	60		18,900(7)
Ledge-Murder Creek	87	10.4	25,400
Tonawanda Local: Ledge Creek conflu- ence - Rapids	40	7.8	1,500

Local Area SPF hydrographs are shown on Plates A72-77.

A1.51 Routing and combining of the SPF was accomplished using HEC-5C with a 3-hour time interval which proved to be insufficient near the peak of the hydrograph. To improve the accuracy of the peak discharge a 1-hour time interval was used near the peak. This resulted in peak discharges which were consistent and credible. The routing criteria was essentially that used for the balanced hydrograph routings with a few minor changes. The outflow SPF hydrograph from the abandoned DL&WRR (Tonawanda at Alexander) was translated with no attenuation to the confluence of Little Tonawanda and Tonawanda Creeks. At this point, the local SPF hydrograph from Little Tonawanda was added. A saddle in Route 98 between Alexander and Batavia allows water to be diverted into the Bowen Creek Watershed for floods well in excess of a 500-year return period. For the SPF, the diversion is less than 1,000 cfs for the peak discharge. This diversion outflow rejoins the SPF hydrograph at the confluence of Bowen and Tonawanda Creeks. The SPF hydrograph at the Batavia less the diversion was routed using the Muskingum Method (1-step, K=3 hours, X=.21) to the confluence with Bowen Creek where it was combined with the diversion. The SPF hydrograph at Bowen Creek was then routed to Alabama by a 4-step Muskingum routing with K=3 hours and X=.21. The routing from Alabama to Rapids uses the same criteria as the balanced hydrograph routings with the exception that diversions to Mud and Black Creeks are omitted. Diversions were not taken into account because the large discharge associated with the SPF would submerge Tonawanda Creek and its tributaries.

- (7) This local area SPF discharge was used in developing an SPF at Alabama for the Flood Plain Information Report, Tonawanda Creek and Tributaries, Erie and Niagara Counties, NY (Buffalo, NY, U. S. Army Corps of Engineers, August 1967, reprinted 1971)

Al.52 The Standard Project Flood was not determined downstream from Rapids as the peak discharge would experience little change. The local SPF hydrographs from the areas downstream of Rapids would contribute little to the flow traveling downstream from Rapids.

Al.53 Standard Project Flood, SPF, Stages

Standard Project Flood stages were calculated for each index point along Tonawanda Creek in the same manner as the elevations were determined for the stage-frequency curves (see Section A3 and A4.) The SPF elevations can be found on Table Al.22. Considerable judgement was exercised in making these determinations due to the lack of available cross sectional data and back-water studies. SPF damages by reach may be found on Table Al.23. In the northeastern United States, SPF determinations are not based on a rigorous statistical analysis of streamflow or rainfall records and; hence, no return period was assigned. Peak SPF discharges and elevations may be found on all applicable rating and stage-frequency curves in this appendix. These SPF elevations along with city sewer maps and USGS quadrangle maps were used in the construction of the approximate SPF flooded area map for the city of Batavia shown on Plate Ald. The SPF discharges in Batavia for with and without project conditions are approximately the same, hence only one flooded outline is shown.

Al.54 Spillway Design Flood, SDF

Spillway Design Flood (SDF) determinations were made using criteria established in the following references:

a. EC 1110-2-27, "Policies and Procedures Pertaining to Determination of Spillway Capacities and Freeboard Allowances for Dams," dated 1 August 1966.

b. EC 1110-2-163, "Spillway and Freeboard Requirements for Dams," dated 25 August 1975.

c. Snyder, Franklin F., "Hydrology of Spillway Design: Large Structures - Adequate data," Journal of the Hydraulics Division, ASCE, Vol. 90, No. 1443, Proc. Paper 3915, May 1964.

Al.55 A high degree of conservatism is adhered to in all phases of design, construction and operation of dam and reservoir projects to assure adequate security to downstream areas against possible effects of partial breaching or failure of any structure. Functional design standards necessary to meet this requirement during floods will conform with one of four standards described in the referenced EC's. After consideration of these standards, structures in this study were designed following the policies and procedures set forth for Standard 3.

Al.56 Standard 3 calls for, "the dam and reservoir storage regulation facilities to be designed so that any breaching of the structure from overtopping by infrequent floods would occur at gradual rates, such that associated increases in flood heights and adverse effects downstream would be within acceptable limits." Standard 3 must be utilized with unusual caution

and discretion, based on judgement of all pertinent factors, including local conditions and probable future developments. Normally, Standard 3 is applied in new designs, primarily to projects in which maximum storage impoundments to top of nonoverflow portions of the dam would not exceed a few thousand acre-feet; where differences between water levels above and below the dams would be only a few feet when the peak spillway design flood level occurred and where general conditions, with respect to site features and safety requirements, are acceptable. Where Standard 3 is justified by circumstances, the following criteria normally should be observed in the design of projects impounding less than a few thousand acre-feet: (a) normal use regulating outlets and service spillways shall be capable of safely passing floods equal to a 100-year frequency event without flow over the emergency spillway; (b) the top elevation and design of main nonoverflow sections of the dam shall be adequate to avoid overtopping or breaching during a flood at least equal to the Standard Project Flood.

Al.57 The flood attenuation structures considered at Alexander and Batavia, NY, would be low-level structures with differences between water levels above and below the structures of only a few feet. Storage to top of nonoverflow portions of the structure would be only a few thousand acre-feet and emergency spillways and flowage easements would be provided to assure adequate security to downstream areas against possible breaching or failure.

Al.58 After due consideration of standards, policies, and procedures, the Standard Project Flood was selected as the Spillway Design Flood for considered structures in this study. SDF determinations for considered structures are presented in Section A2.

Al.59 Probable Maximum Flood, PMF

The Probable Maximum Flood, PMF, was developed using the guidelines established in Hydrometeorological Report No. 51(8). Rainfall depth-basin area curves for PMF storms of 6-, 12-, 24-, 48-, and 72-hour durations can be found on Plate A77a. The time distribution of the rainfall patterns, similar to those in HM 43(9) are shown on Plate A77b. The selected PMF hydrograph was calculated using Pattern No. 1.

Al.60 Snowmelt in conjunction with rainfall was not considered for Probable Maximum Storm calculations. In a letter dated 15 November 1976, from the National Oceanic and Atmospheric Administration, the average snow water content for the Tonawanda Watershed was estimated to be 10 inches for 15 March, and five inches for 15 April. The Probable Maximum Precipitation estimates to fall upon the above snowpack ranged from 53 percent to 66 percent of the all-season Probable Maximum Precipitation for the period 15 March to 15 April. With the all-season Probable Maximum Precipitation equal to 21.5 inches of rainfall the total water content available on 15 March is 21.4 inches, and for 15 April 19.2 inches, both less than the all-season Probable Maximum Precipitation.

(8) Ibid 3

(9) Hydrometeorological Report No. 43, Probable Maximum Precipitation, Northeast United States (U. S. Department of Commerce and U. S. Army Corps of Engineers, 1966)

Table Al.22 - Standard Project Flood Elevations

	:	Existing	:	Improved
T1	:	572	:	572
T2	:	577	:	577
T3	:	583	:	583
T4	:	588.8	:	588.5
T5	:	591	:	590.7
T6	:	597.3	:	597
T7	:	601.8	:	601.5
T8	:	605.5	:	605.2
T9	:	605.6	:	605.6
T10	:	622	:	622
T11	:	855.1	:	855.1
T12	:	885.4	:	885.4
B1	:	891.2	:	891.4
B2	:	898	:	898.2
B3	:	898	:	898.2
B4	:	896.6	:	896.7
B5	:	896.6	:	896.7
T13	:	902.0	:	902.5
A1	:	932.4	:	932.4
A2	:	961	:	961
A3	:	971.6	:	971.6

Table Al.23 - Standard Project Flood Damages
(Existing and Improved Conditions)

Reach	Residential	Commercial and Industrial	Public and Other
	\$	\$	\$
T1	2,850,000	10,000	30,000
T2	580,000	10,000	410,000
T3	650,000	20,000	800,000
T4	830,000	0	660,000
T5	1,160,000	10,000	1,050,000
T6	800,000	0	365,000
T7	260,000	0	810,000
T8	368,000	10,000	305,000
T9	125,000	0	175,000
T10	14,000	0	37,500
RB1 through RB4	1,330,000	10,000	4,086,000
M1 through M6	541,500	5,000	1,057,000
T11	480,000	0	600,000
T12	1,100,000	240,000	1,500,000
B1	1,540,000	900,000	2,480,000
B2	228,000	62,000	382,000
B3	4,550,000	6,800,000	1,000,000
B4	240,000	20,000	77,500
B5	75,000	680,000	1,125,000
T13	118,000	0	114,000
A1 through A3	379,000	(1)	(1)
Total	18,445,000	12,787,000	18,981,000

(1) Included in Residential Damages

Al.61 In order to maximize the peak discharge at Alexander and Batavia, the Probable Maximum Storm was centered over the Tonawanda Creek Watershed above Alexander. This insured the PMF peak discharges at the Upper and Lower Reservoir were the highest possible to test the performance of the spillways. Discussion of the reservoirs may be found in Section A2a.

Al.62 The PMF was developed for Tonawanda Creek at Alexander and Batavia and the mouth of Little Tonawanda Creek. The local PMF hydrographs were routed in the same manner as the Standard Project Flood. The PMF peak discharge above Alexander is 81,200 cfs and the peak discharge above Batavia is 100,300. The PMF hydrographs are found on Plates A78 through A80.

Al.63 Data Needs

Hydrologic investigations for this study were made, using streamflow records for the gages listed in Table Al.36, to determine generalized relationships. These relationships were then used in discharge-duration-frequency, and unit hydrograph determinations for ungaged areas.

Al.64 The usage of balanced hydrographs in project design is an acceptable hydrologic method; however, they become useless in the real-time operation of the reservoirs. The following needs have been identified to enhance proper operation of the reservoirs.

a. Snow Survey Course in Tonawanda Creek Basin. Since it is desirable to accumulate at least 10 years of data before correlation analyses are made of the snow-survey data in stream flow forecasting, the failure to establish an adequate number of courses initially introduces, later on, difficulties in statistical and correlation analysis. The degree of confidence which can be expected in the forecasts would be reduced until a sufficient number of years has elapsed to establish the value of a particular snow course⁽¹⁰⁾. At present, there is an insufficient number of sampling sites in the watershed to properly assess the water content of the snow. At least six sites will be added to the present survey in Western New York and the measurements will be made on a weekly basis. During periods of melt, measurements need to be taken more frequently. A snow-survey site will be located near the Attica, Linden, and Ledge Creek gages (see below) for correlation with stream records.

b. Establishment of a Telemarked Gage on Mud Creek. The placement of a telemarked gage on Mud Creek will indicate (along with the existing Ellicott Creek gage) the condition of downstream-tributary flooding. Experience has shown that the downstream tributaries in the basin peak well before Tonawanda Creek and these two gages will be sufficient to access the tributary conditions. Of secondary benefit, the gage will collect necessary hydrologic data for upgrading the watershed model.

(10) Chow, Handbook of Applied Hydrology (New York: McGraw-Hill, 1964), p 10-14

c. Upgrade Present River Gages to Telemarked Status. At present, only the Tonawanda Creek at Batavia gage is telemarked. The remaining gages in the watershed (Tonawanda at Attica and Rapids, Murder Creek below Akron, and Little Tonawanda at Linden) will be telemarked to allow river stage information to be known at any time. The Murder Creek below Akron gage was recently installed in response to the data collection need identified in the Tonawanda Creek FFR, Appendix A, November 1981.

d. Stage Recorders at the Reservoirs. At each reservoir, a stage recording gage with accompanying wire weight gage will be installed capable of recording stages up to PMF pool level. Since the reservoir will normally be empty, the recording gages will only be used during the operation of the reservoir. It will prove useful to have the recording gages switch on automatically at a preset level. This will preclude the possibility of the operator forgetting to activate them. A staff gage, protected from possible damage by ice or debris, will be invaluable in the event of failure of the other gages and would prevent the loss of valuable data particularly during a large flood.

e. Telemarked Rain Gages. During rainfall or rainfall/snowmelt floods, precipitation amounts and distribution will be needed to forecast stream runoff. Four telemarked rain gages (for example, the Fischer-Porter BDT) will be placed in the basin and will allow immediate rainfall information to be known by telephone. One will be located at the Attica Sewage Treatment Plant. A structure housing the gage will have to be built and should be located such that it will not be inundated during a flood. Backwater analysis will be done to insure the safety of the gage. A gage will be located at Linden, with the possibility of locating the rain gage on top of the river-stage gagehouse as long as the gage is not affected by the wind or peripheral objects. Another will be located at the operator's shack at the Lower Reservoir and one in the Ledge-Murder Creek Watershed. Again, these may be located on the shack or gagehouse roof, if unaffected.

Al.64 First costs and average annual OM&R costs for the data system described above have been included in the Cost Estimate Section of this report.

A2. CONSIDERED RESERVOIRS

A2.1 General

Hydrologic investigations were made for this study to determine the effects of considered reservoirs on reducing flood damages in the Tonawanda Creek Watershed. This section contains the results of these investigations for two considered flood management reservoirs identified as the Upper and Lower Reservoirs of the Batavia Reservoir Compound. Hydrograph routings were made with the Upper Reservoir only and both reservoirs in place. The local inflow hydrographs developed for existing conditions were used in the routing calculations for improved conditions. The local inflow increase due to reduction in stage on Tonawanda Creek and the resultant decrease in backwater effect on the tributaries was considered minimal as stage reduction along the Tonawanda Creek main channel will be only 1 to 2 feet for most floods. The Upper Reservoir would be located near the village of Alexander, NY, and is the same structure initially described as the Upper Reservoir of the Batavia Compound in the 1976 Tonawanda Creek Feasibility Report. The Lower Reservoir would be located south of the city of Batavia. The location and dimensions of the structure are different from that described in the 1976 report. The Lower Reservoir would be located approximately one-half mile south of the Lehigh Valley Railroad with the embankment serving as the spillway at elevation 900 feet USC&GS Datum. As used in the context of this appendix, the Batavia Reservoir Compound refers to the Upper and Lower Reservoirs in their latest configuration. In subsequent appendices and in the Main Report, the compound will be referred to as the Batavia Reservoir Compound (Modified). Further discussion of the reservoirs may be found in the Main Report.

A2.2 Normally, reservoirs are operated to impound floodwaters while making releases such that the routed release combined with local inflow does not exceed damaging discharges at downstream damage centers. This policy proved possible only for floods with a return period less than 10 years for the Upper and Lower Reservoirs. For floods with a return period of approximately 10 years and greater, the reservoirs are operated as flood attenuators due to a number of constraints which limit operational flexibility.

A2.3 The term "flood attenuator" as used in the context of this report refers to the function of any considered structure in limiting releases to a specific discharge relative to downstream channel capacities or in reducing the discharge through storage of floodwaters. The Upper Reservoir will maintain a maximum outflow discharge of 2,000 cfs as long as possible until the reservoir is filled. The Lower Reservoir, due to hydraulic constraints, will not be able to limit releases to 6,000 cfs, the channel capacity through Batavia. Instead, the inflow discharges will be reduced through storage utilization.

A2.4 A number of factors were considered in arriving at this method of operation for considered structures. These factors include: social constraints, available storage and physical constraints relative to available storage, height of dikes, etc. These factors are discussed in more detail in subsequent paragraphs for each structure.

A2.5 Area-Capacity Curves

Area-capacity curves were determined for the areas upstream from the Batavia Reservoir Compound by planimetering areas within contours of a USGS quadrangle map for the area flooded and use of the prismoidal formula. These area-capacity curves are shown on Plates A81 and A82.

A2.6 Rating Curves

Tailwater and headwater rating curves for the Batavia Reservoir Compound are shown on Plates A83 and A84. The tailwater curve for the Upper Reservoir was determined by slope-area computations using cross sections obtained in the field just downstream from the prospective structure. The tailwater curve for the Lower Reservoir was determined by backwater computations from the USGS gage at Batavia. Utilizing the tailwater curves, the headwater curves were developed using the appropriate hydraulic formulae.

A2.7 Batavia Reservoir Compound, Upper Reservoir, General

The Upper Reservoir would be located in the vicinity of the Delaware Lackawanna and Western Railroad (DLWRR) near North Alexander, NY. The drainage area upstream from this structure is approximately 102 square miles. After consideration of the topography of the site, an elevation of about 924.5 was indicated as the maximum practicable water surface without consideration of freeboard requirements. Water surfaces above this elevation, including the freeboard requirements, would seriously affect the community of Alexander, NY. The capacity at this elevation from Plate A81 is 8,490 acre-feet which is equivalent to 1.6 inches of runoff. The embankment would function as a spillway at elevation 922.5 (6,750 acre-feet, 1.2 inches).

A2.8 The principal function of the Upper Reservoir is to reduce flood damages to the farmland in the area immediately downstream from its dam and slightly reduce natural stages in Batavia and the lower Tonawanda Creek watershed. The operation of the Upper Reservoir also reduces storage requirements for the Lower Reservoir. The channel capacity downstream from the Upper Reservoir is approximately 2,000 cfs under project plan conditions. This was determined from slope-area computations and field observations.

A2.9 Batavia Reservoir Compound, Upper Reservoir, Operation Procedure For Floods With Less Than a Ten-Year Recurrence Interval

For floods with less than a 10-year return period, the reservoir was operated to impound floodwaters while making releases such that the routed release combined with the cumulative local inflow, or "local cumulative," above Batavia did not exceed the channel capacity of 2,000 cfs. The local cumulative in this case is the total runoff contributed by Little Tonawanda Creek and the Tonawanda Creek local inflow between the dam and Batavia. The following is the upper reservoir operation policy for less than a 10-year return period, with the assumption of the forecasting capability limited to 9 hours, which is the approximate travel time from the gage at Attica to the

Upper Reservoir. The real time flow data from this gage will be used during actual flood operations once the recommended plan is implemented.

a. The maximum rate of change of discharge from the upper reservoir will be 700 cfs in 3 hours. This maximum rate of change was selected after studying those floods of record which had caused no serious channel degradation.

b. When the sum of inflow to the Upper Reservoir and local cumulative for Tonawanda Creek below the confluence with Little Tonawanda is less than 1,500 cfs, all gates will be fully open (inflow = outflow).

c. When the inflow is greater than or equal to 1,000 cfs and the sum of the inflow and the local cumulative is greater than or equal to 1,500 cfs maintain 1,000 cfs outflow.

d. When inflows are 4,000 cfs for more than a few time periods, release 2,000 cfs. Maintain that release until outflows recede naturally to less than 2,000 cfs.

e. When inflows are receding and the local cumulative is less than 500 cfs, release 1,500 cfs as long as possible.

A2.10 Plates A52 and A53 present the existing and improved hydrographs for the Upper Reservoir for the 2-year flood. Plate A54 shows the operation of the Upper Reservoir for the 2-year flood using the policy from paragraph A2.9. Initially, the gates were fully opened, allowing the inflow to pass through the reservoir naturally. At time = 120 hours, the outflow was held at 1,000 cfs in accordance with rule A2.9c as the local cumulative was increasing above 500 cfs. This release was maintained until 180 hours when the outflow was increased to 2,000 cfs to facilitate lowering the pool during the period of low local cumulative. This discharge at 240 hours began to recede naturally because of the low pool level. The inflow then began to increase along with the local cumulative so that at time = 288 hours, the outflow was held at 1,000 cfs until it receded naturally.

A2.11 The results of this operational procedure for the 2-year flood are summarized in Table A2.1. An example explaining proper interpretation of the data in columns F, G, and H is provided in footnote 6. The difference between columns G and F represents the decrease in duration of direct flooding due to operating the Upper Reservoir. The difference between columns H and F represents the increase in duration of channel capacity discharge due to operating the Upper Reservoir. Table A1.13 gives the peak discharges for selected stream locations along Tonawanda Creek for the 2-year flood with the Upper Reservoir in place. Plates A55, A56, and A58 demonstrate the effect the Upper Reservoir has on the 2-year flood hydrographs at Batavia and the confluence with Ledge Creek.

TABLE A2.1 - RESULTS OF UPPER RESERVOIR OPERATION, BALANCED FLOODS

RETURN PERIOD OF FLOOD YEARS	A		B		C		D		E		F	G	H
	NAT	IMP	NAT	IMP	NAT	IMP	NAT	IMP	NAT	IMP			
SPF	38800		38500	38600	923.8	924.5	930	980	7900	8490	4.5 (2.4) ⁷	1.4	10.3 (4.0) ⁷
500	15000		12200	12200	917.6	922.5	520	850	3510	6750	3.6	1.5	8.8
200	14000		11400	11400	917.1	922.5	500	850	3250	6750	3.3	1.4	7.8
100	12500		10400	10400	916.4	922.5	470	850	2870	6750	3.1	1.3	7.3
50	11200		9440	9350	915.8	922.5	430	850	2550	6750	3.0	1.1	7.0
20	9600		8450	4740	914.9	922.5	390	850	2160	6750	2.6	1.0	6.0
10	8300		7400	3550	914.1	922.5	320	850	1840	6750	2.5	1.0	4.1
2	5000		4571	1500	911.7	920.9	240	740	1046	5480	1.0	0	0

(1) Elevations are referred to United States Coast and Geodetic Survey U.S.C. & G.S., datum.

(2) Area and Capacity determined from Plate A81 for maximum pool area and storage.

(3) Refers to the number of days the discharge is EQUAL to or GREATER THAN the downstream channel capacity of 2000 cfs for natural conditions without structure. [Same as GREATER THAN case 1.]

(4) Refers to the number of days the discharge is GREATER THAN the downstream channel capacity of 2000 cfs for improved conditions with structure.

(5) Refers to the number of days the discharge is EQUAL to or GREATER THAN the downstream channel capacity of 2000 cfs for improved conditions with structure.

(6) An example for interpreting Columns F, G, and H is as follows: For the 200-year flood the duration of direct flooding, as shown in column F would be 3.3 days for natural conditions. With the structure, the duration of flooding would be only 1.4 days as shown in column G. The area downstream from the dam would therefore be subject to damaging discharges for only 1.4 days instead of 3.3 days. However, column H indicates that, due to the operation the duration of limited conditions would be 7.3 days or 4.5 days longer than natural conditions.

(7) Includes the time needed to drain the volume of runoff from the pool which was assumed to precede the SDF runoff for SDF considerations. Number in () is SPF runoff only.

A2.12 Batavia Reservoir Compound, Upper Reservoir, Operation Procedure
For Floods With a 10-Year Recurrence Interval or Greater

For this scenario, the Upper Reservoir was operated as a flood attenuator with a limiting release of 2,000 cfs. In operating the structure for a given balanced hydrograph, inflows less than 2,000 cfs were allowed to pass with only natural storage affecting outflow. When the inflow exceeded 2,000 cfs, the structure was operated to limit the release to 2,000 cfs until the pool level reached the elevation of the overflow section. From this point, the flood control gates were operated such that inflow equalled outflow until the inflows fell below 2,000 cfs. The outflow was then held at 2,000 cfs until the pool emptied. For floods with return periods between 10 and 100 years, the flood control gates could be operated to pass inflow equal to outflow once the pool level reached the crest of the overflow section without overtopping. Floods in excess of the 100-year flood, up to the PMF, would result in overtopping the spillway.

A2.13 The results of operating the Upper Reservoir for the 200-year balanced flood are shown on Plate A42. During the beginning of the flood, inflows less than 2,000 cfs (the damaging discharge above Batavia) were allowed to pass with only natural storage affecting outflow. When the inflow exceeded 2,000 cfs, the outflow was then regulated to a maximum discharge of 2,000 cfs. Once the elevation of the pool reached 922.5, the gates were fully opened and water began to pass over the spillway with inflow essentially equalling outflow. As the flood recessed and the pool elevation became lower than the spillway crest, the outflow was then held at 2,000 cfs until the pool emptied. The outflow discharge hydrograph resulting from this operational procedure is shown on Plate A42. Plate A43 shows the 200-year stage-hydrograph resulting from operation of the Upper Reservoir for the 200-year balanced inflow hydrograph. Also shown is the 200-year pool stage-hydrograph resulting from routing the 200-year inflow hydrograph through natural storage assuming no Upper Reservoir. Plates A44 through A51 show the remaining flood hydrographs for the 200- and 50-year flood following this operation policy. Tables A1.7 through A1.12 present the peak discharges resulting from operating the Upper Reservoir for the balance hydrographs. Table A2.1 summarizes the results of this operation procedure.

A2.14 During the 18 and 19 March 1980 meeting at the Buffalo District Office with NCD, it was suggested that in order to make the operation of the reservoirs practical, the gate settings should be made as a function of reservoir stage and local (downstream) flows and not as a function of inflow to the project. It is customary policy to operate small reservoirs such as the Batavia Reservoir Compound as a function of inflow, change in storage and downstream discharges. For example, the Corps of Engineers Mt. Morris Dam is operated based upon the actual and predicted discharges at Portageville (inflow to reservoir) along with change of storage in the reservoir. During Tropical Storm Agnes 1972, the Portageville gage was washed out and a reverse storage routing through the reservoir was made so that the inflow would be known at all times and future inflows could be predicted.

A2.15 There was also concern regarding operation policy selection. It is well known that the majority of flooding in the Tonawanda Creek Watershed

is caused by snowmelt or rainfall/snowmelt. The snowpack water equivalent will be known from data gathered along the snow course in the basin. Communication with the Weather Bureau will be maintained in order that weather forecasts will be known. This will leave sufficient lead time before any actual flooding occurs. From this information the flood potential will be known allowing selection of the operation plan. For the purpose of this report, a "misoperation" was assumed for the 10-year balanced hydrograph routings. The reservoirs were operated initially using the "forecasting" (less than 10-year flood) policy but then switched to the "no-forecasting" (10-year flood and greater) policy. This proved to be conservative hydrologically and economically, i.e., benefits would not be overstated.

A2.16 Batavia Reservoir Compound, Operation of Upper Reservoir For Floods of Record

In this scenario, the Upper Reservoir was operated for the September 1977 and March 1978 floods using the Section A2.9 "forecasting" policy. The resulting hydrographs may be found on Plates A63 through A71 and a summation of the resulting discharges in Tables A1.15 and A1.16. Table A2.2 recapitulates the results of the Upper Reservoir operation. The March 1960 flood was not analyzed as inflow to the reservoir was not known for that event.

A2.17 Three factors were considered in selecting 922.5 as the elevation of the crest of the overflow section. These factors include (1) degree of protection and frequency of overtopping; (2) cost of embankment; and (3) SDF considerations. First, as previously mentioned, floods with return periods of 10 years or less would be controlled, thereby providing 10-year protection to the farmland just downstream from the structure. The degree of protection might be higher, but has not been determined, for summer time floods as the predominance of high-volume-peak floods occur during late winter and early spring. Secondly, due to the width of the flood plain, approximately 5,600 feet of embankment would be needed for the structure. The cost of the embankment therefore is directly related to elevation. Thirdly, SDF considerations dictated that the maximum permissible pool elevation of 924.5 not be exceeded in operating the structure for the SPF, selected as the SDF. After due consideration of these factors, an elevation of 922.5 was selected as the elevation of the 5,600-foot long overflow section.

A2.18 Batavia Reservoir Compound, Upper Reservoir, Spillway Design Flood, SDF

As mentioned in paragraphs A1.54 through A1.58, the Standard Project Flood, SPF, was selected as the Spillway Design Flood, SDF, for the Upper Reservoir. This was considered reasonable as the reservoir is only approximately 15 feet high from flood plain level to crest of overflow section, storage at maximum pool level is only 8,500 acre-feet, and the difference between the headwater and tailwater elevations during the routing of the SDF was found to be only about 9.9 feet.

A2.19 In developing a SDF for large reservoirs where the flood control pool extends for miles upstream, the natural conditions unit hydrograph peak

TABLE A2.2 - RESULTS OF UPPER RESERVOIR OPERATION, FLOODS OF RECORD

FLOOD	A		B		C		D		E		F	G	H
	NAT	IMP	NAT	IMP	NAT	IMP	NAT	IMP	NAT	IMP	(3) (4) DAYS	(4) (6) DAYS	(3) (6) DAYS
MAR '60	xxx		xxx	xxx	NO	DATA	AVAILABLE		xxx	xxx	xxx	xxx	xxx
SEPT '77	8640		7320	2600	914.0	921.7	340	790	1700	5420	2.6	0	1.5
MAR '78	3740		2820	1500	909.5	919.0	160	620	600	4100	1.0	0	0

(1) Elevations are referred to United States Coast and Geodetic Survey U.S.C. & G.S., datum.

(2) Area and Capacity determined from Plate A81 for maximum pool area and storage.

(3) Refers to the number of days the discharge is EQUAL to or GREATER THAN the downstream channel capacity of 2000 cfs for natural conditions without structure. [Same as GREATER THAN case.]

(4) Refers to the number of days the discharge is GREATER THAN the downstream channel capacity of 2000 cfs for improved conditions with structure.

(5) Refers to the number of days the discharge is EQUAL to or GREATER THAN the downstream channel capacity of 2000 cfs for improved conditions with structure.

(6) An example for interpreting Columns F, G, and H is as follows: For the SEPT. '77 flood the duration of direct flooding, as shown in column F would be 2.6 days for natural conditions. With the structure, the duration of flooding would be eliminated, as shown in column G. The area downstream from the dam would therefore not be subject to damaging discharges from this flood. However, column H indicates that, due to the operation the duration of bankful conditions would be 1.5 days or 1.1 days less than natural conditions.

is increased and time of concentration decreased. This is done to account for the loss of natural valley storage and translation of the flood wave instantaneously through the reservoir pool. For the Upper Reservoir, the flood pool would only extend approximately 1.5 miles upstream at the maximum permissible pool elevation of 924.5. This represents a 5 percent increase in pool surface area when compared with the natural pondage. The reduction of available natural storage and decrease in time of concentration would not be expected to decrease enough to warrant modifying the Upper Reservoir unit hydrograph. In light of the above, the 3-hour unitgraph for Tonawanda Creek at Alexander, shown on Plate A36 for natural conditions, was used in determining the SDF for the Upper Reservoir.

A2.20 Two starting pool elevations for the Upper Reservoir were used in routing the SPF. Routing the SPF through an empty pool resulted in a peak outflow of 38,600 cfs at a maximum pool elevation of 924.5 and a tailwater elevation of 920.0. The 38,800 cfs represents 10,700 cfs discharging through the flood control gates with the remainder passing over the spillway. Beginning the routing with a full pool (elevation = 922.5) resulted in a peak outflow discharge of 38,800 cfs. Table A1.20 lists results of these routings. Headwater and tailwater rating curves are shown on Plate A83.

A2.21 Batavia Reservoir Compound, Lower Reservoir, General

The Lower Reservoir would be located approximately one-half mile upstream of the Lehigh Valley Railroad near the southerly limit of the city of Batavia. The drainage area upstream from this structure is approximately 171 square miles. After consideration of the topography of the site, an elevation of about 903 was indicated as the maximum practical water surface elevation without consideration of freeboard requirements. The capacity at this elevation is 24,000 acre-feet which is equivalent to 2.6 inches of runoff. The field surveys taken in the Lower Reservoir area in Winter 1977-78, coupled with a cursory hydraulic analysis, indicated that the previous (1976 report) location of the emergency spillway was impossible. Instead, under the latest plan, the embankment would function as a spillway at elevation 900 feet (15,500 acre-feet, 1.7 inches).

A2.22 The function of the Lower Reservoir, in combination with the Upper Reservoir, is to reduce damages in the city of Batavia and the lower Tonawanda Creek Watershed. The channel capacity in the city of Batavia is approximately 6,000 cfs, determined from the USGS rating curve at the Batavia gage and backwater computations.

A2.23 Batavia Reservoir Compound, Lower Reservoir, Operation Procedure For Floods With Less Than a 10-Year Recurrence Interval

For floods with less than a 10-year return period, the prospective reservoir would be operated to impound floodwaters while making releases such that the routed release, combined with local cumulative below the confluence with Ledge Creek, did not exceed the channel capacity of 3,000 cfs. The local cumulative in this case is the local runoff contributed by Murder-Ledge Creek and the Tonawanda Creek local inflow between the dam and the confluence with Ledge Creek. There is an 18-hour delay between the time that the release is

made and the time it reaches the confluence with Ledge Creek. It is usually necessary to match current releases with the local flows expected to occur at the damage center at a travel time later. Since a 9-hour forecast capability was assumed, there is no time for advance warning.

A2.24 The following is the Lower Reservoir operation policy for floods with less than a 10-year return period:

- a. Maximum rate of change of discharge will be 700 cfs in 3 hours.
- b. When the sum of inflow to the Lower Reservoir and local cumulative for Tonawanda Creek below the confluence with Ledge Creek is less than 2,000 cfs, gates will be fully open. Inflow is allowed to pass through naturally.
- c. When the sum of inflow and local cumulative is greater than 2,000 cfs and less than 5,000 cfs, maintain a 1,000 cfs release.
- d. When the sum of inflow and local cumulative is greater than 5,000 cfs, release 2,000 cfs.
- e. When emptying the pool (peak has passed), and the sum of inflow and local cumulative is less than 1,500 cfs and the local cumulative is less than or equal to 500 cfs release 2,000 cfs.

A2.25 Plates A55 and A56 present the existing and improved hydrographs for the Lower Reservoir for the 2-year flood. Plate A57 shows the operation of the Lower Reservoir for the 2-year flood using the policy from paragraph A2.24. Initially, the gates were fully opened, allowing the inflow to pass through the reservoir naturally. At 126 hours, the outflow was held at 1,000 cfs as the local cumulative and inflow were greater than 2,000 cfs. This release was maintained until 252 hours when the outflow was increased to 2,000 cfs to facilitate lowering the pool during the period of low local cumulative. At 285 hours, the outflow was decreased to 1,000 cfs to store the increasing inflow to the reservoir. The event terminated with a steady outflow of 2,000 cfs to drain the pool.

A2.26 The results of this operational procedure for this 2-year flood are summarized in Tables A2.3 and A2.4. Table A1.13 gives the peak discharges for selected stream locations along Tonawanda Creek for the 2-year flood with both reservoirs in place. Plate A58 demonstrates the effect the Reservoir Compound has on the 2-year flood hydrograph at the confluence with Ledge Creek.

A2.27 Batavia Reservoir Compound, Lower Reservoir, Operation Procedure For Floods With a 10-Year Recurrence Interval or Greater

The operation procedure for the balanced hydrograph routings simply involved maintaining the Lower Reservoir gates in full open position. The inflow was attenuated by the storage behind the structure. Operating the structure in this manner resulted in the spillway being overtopped for floods in excess of the 500-year flood.

TABLE A2.3 - RESULTS OF OPERATION FOR THE LOWER RESERVOIR, BATAVIA RESERVOIR COMPOUND, BALANCED FLOODS

RETURN PERIOD OF FLOOD	A INFLOW PEAK DISCHARGE CFS			B OUTFLOW PEAK DISCHARGE CFS			C MAXIMUM POOL ELEVATION FEET (1)			D AREA FLOODED AT MAXIMUM POOL AREAS (2)			E CAPACITY AT MAXIMUM POOL ACRES-FT (2)		
	(1) NAT	(2) IMP. A	(3) IMP. B	(4) NAT	(5) IMP. A	(6) IMP. B	(7) NAT	(8) IMP. A	(9) IMP. B	(10) NAT	(11) IMP. A	(12) IMP. B	(13) NAT	(14) IMP. A	(15) IMP. B
SPF	49200	50200	50200	28500	28500	28400	902.0	902.0	902.5	5150	5150	3050	39500	39500	23500
500	17200	17200	17200	9850	9850	6000	896.7	895.7	900.0	2620	2350	2560	14500	12100	15500
200	16000	16000	16000	9100	7540	5780	896.2	895.2	899.2	2470	2180	2300	13300	11000	13400
100	14700	14000	14000	8770	6770	5450	895.8	894.6	898.3	2350	2020	2020	12400	9700	11700
50	13700	10000	10000	7730	5930	5240	895.4	893.9	897.3	2250	1850	1750	11500	8200	9620
20	11700	6930	6930	6650	4930	4620	894.6	893.0	895.9	2020	1600	1400	9700	6900	7410
10	10300	6000	6000	5870	4320	4260	893.9	891.9	895.1	1850	1350	1220	8200	5200	6600
2	6310	3410	3410	3870	2530	2000	891.8	889.4	892.0	1340	770	1950	5000	2500	10700

(1) ELEVATIONS ARE REFERRED TO UNITED STATES COAST AND GEODETIC SURVEY, U.S.C. & G.S., DATUM.

(2) AREA AND CAPACITY DETERMINED FROM PLATE A22 FOR MAXIMUM POOL ELEVATION, COLUMN C

(3) NAT. REFERS TO NATURAL CONDITIONS WITH NO STRUCTURES.

(4) IMP. A REFERS TO IMPROVED CONDITIONS WITH THE UPPER (ALEXANDER) RESERVOIR ONLY

(5) IMP. B REFERS TO IMPROVED CONDITIONS WITH THE BATAVIA RESERVOIR COMPOUND.

TABLE A2.4 - RESULTS OF OPERATION FOR THE LOWER RESERVOIR, BATAVIA RESERVOIR COMPOUND, BALANCED FLOODS

RETURN PERIOD OF FLOOD	A OUTFLOW PEAK DISCHARGE CFS			B MAXIMUM POOL ELEVATION FEET			C DURATION OF FLOOD NATURAL CONDITIONS DAYS (1) (3)		D DURATION OF CONTROLLED FLOOD - IMP. A DAYS (2) (3)		E DURATION OF CONTROLLED FLOOD - IMP. B DAYS (2) (3)	
	(1) NAT	(2) IMP. A	(3) IMP. B	(4) NAT	(5) IMP. A	(6) IMP. B	OUTFLOW DISCHARGE	POOL ELEVATION	OUTFLOW DISCHARGE	POOL ELEVATION	OUTFLOW DISCHARGE	POOL ELEVATION
SPF	28500	28500	28400	902.0	902.0	902.5	5.5 (2.9) ⁷	15.5 (7.4) ⁷	5.5 (3.0) ⁷	15.5 (4.2) ⁷	5.5 (3.1) ⁷	15.5 (5.4) ⁷
500	9830	8400	6500	896.7	895.7	900.0	1.8	8.6	1.5	10.1	0.5	10.8
200	9100	7540	5780	896.2	895.2	899.2	1.5	7.3	1.3	8.4	0	9.8
100	8470	6770	5450	895.8	894.6	898.3	1.4	4.9	0.9	8.1	0	8.3
50	7730	5930	5240	895.4	893.9	897.3	1.1	4.3	0	7.6	0	8.1
20	6650	4430	4620	894.6	893.0	895.9	0.8	3.3	0	6.1	0	6.8
10	5870	4320	4260	893.9	891.9	895.1	0	3.0	0	3.1	0	5.1
2	3270	2530	2000	291.8	289.4	288.0	0	2.4	0	1.3	0	9.8

- (1) Refers to the number of days the outflow discharge and pool elevation are EQUAL TO or GREATER THAN the channel capacity discharge of 6,000 cfs at Batavia and the elevation corresponding to a channel capacity discharge of 2,000 cfs in the pool area respectively for natural conditions without improvements.
- (2) Refers to the number of days the outflow discharge and pool elevation are EQUAL TO or GREATER THAN the channel capacity discharge of 6,000 cfs at Batavia and the elevation corresponding to a channel capacity discharge of 2,000 cfs in the pool area respectively for improved conditions (imp. A or imp. B).
- (3) An example for interpreting columns C through E is as follows: Column C shows for the 200-year flood that the duration of flooding in the city of Batavia would be 1.5 days and the duration of flooding in the pool area would be 7.3 days for natural conditions without any structures. Column D shows that with the Upper (Alexander) Reservoir flooding in the city of Batavia would be 0.9 days and the duration of flooding in the pool area would be 8.1 days. Column E shows that in operating the Batavia Reservoir compound flooding in the city of Batavia has been eliminated for this flood and that the duration of flooding in the pool area would be 9.8 days.
- (4) Nat. refers to natural conditions with no structures.
- (5) Imp. A refers to improved conditions with the Upper (Alexander) Reservoir only.
- (6) Imp. B refers to improved conditions with the Batavia Reservoir Compound.
- (7) Includes the time needed to drain the volume of runoff from the pool which was assumed to proceed the SDF runoff for SDF considerations. The SDF for this reservoir is discussed in paragraph A2.30 through A2.32. Number in () is SPF runoff only.

A2.28 The results of operating the Reservoir Compound for the 200- and 50-year balanced floods are shown on Plates A42 through A51. Tables A1.7 through A1.12 present the peak discharges resulting from operating the Reservoir Compound for the balance hydrographs. Tables A2.3 and A2.4 summarize the results of the operation procedure. An example explaining the interpretation of columns C, D, and E of Table A2.4 is provided in footnote 3. The difference between columns D and C represents the decrease in duration of direct flooding and increase in duration of pool elevation in the Lower Reservoir area due to operating the Upper Reservoir. The difference between columns E and C represents the decrease in duration of direct flooding and increase in duration of pool elevation in the Lower Reservoir area due to operating the Reservoir Compound. The difference between columns E and D represents the effect of operating the Reservoir Compound over the Upper Reservoir alone. The outflow discharges (existing and improved) from Table A2.4 and the stage-discharge curves (Plates A113 and A115-117) along with limited topographic information were used to construct the approximate 100-year flooded outlines in the city of Batavia for with and without project conditions as shown on Plate A1d.

A2.29 Batavia Reservoir Compound, Operation of Lower Reservoir For Floods of Record

In this scenario, the Lower Reservoir was operated for the September 1977 and the March 1978 floods using the Section A2.23 forecasting policy. Further discussion on the operation policy for a rare summertime flood such as the September 1977 flood is presented in paragraph A2.35 through A2.38.

Operating the Batavia Reservoir Compound for the September 1977 flood resulted in filling the Lower Reservoir, whereas the peak level was 2.8 feet below the spillway crest for the March 1978 flood. Due to the magnitude of the March 1960 flood, the policy described in Section A2.27 was used. Under this operation policy, the maximum elevation obtained in the Lower Reservoir was 1.2 feet below the crest of the spillway. The resulting hydrographs may be found on Plates A59 through A71 and a summation of the resulting discharges for the entire watershed in Tables A1.14 through A1.16. Tables A2.5 and A2.6 present the results in the Lower Reservoir area for the floods of record.

A2.30 Batavia Reservoir Compound, Lower Reservoir Spillway Design Flood SDF

As mentioned in paragraphs A1.54 through A1.58, the Standard Project Flood, SPF, was selected as the SDF for the Lower Reservoir. This was considered reasonable and conservative after reviewing associated regulations and reviewing the research literature. The Lower Reservoir is only approximately 10 feet high from flood plain to top of overflow sections, storage at maximum pool level is only 23,500 acre-feet, and the difference between headwater and tailwater elevations during the routing of the SDF was found to be negligible.

A2.31 As mentioned previously, in developing a SDF for large reservoirs where the flood pool extends for miles upstream, the natural conditions unit hydrograph peak is usually increased and the time of concentration decreased.

Table A2.5 - Results of Operation for the Lower Reservoir, Batavia Reservoir Compound, Floods of Record

FLOOD	A INFLOW PEAK DISCHARGE CFS			B OUTFLOW PEAK DISCHARGE CFS			C MAXIMUM POOL ELEVATION FEET (1)			D AREA FLOODED AT MAXIMUM POOL ACRES (2)			E CAPACITY AT MAXIMUM POOL ACRES-FT (2)		
	(3) NAT	(4) IMP. A	(5) IMP. B	(6) NAT	(7) IMP. A	(8) IMP. B	(9) NAT	(10) IMP. A	(11) IMP. B	(12) NAT	(13) IMP. A	(14) IMP. B	(15) NAT	(16) IMP. A	(17) IMP. B
MAR '60	(7) 11020	(6) —	(7) 11020	(6) 7200	(6) —	(6) 5610	(6) 894.7	(6) —	(6) 898.8	(6) 2050	(6) —	(6) 2170	(6) 10000	(6) —	(6) 12700
SEPT '77	10800	6860	6860	5110	3720	2000	893.1	891.2	899.5	1650	1200	2400	7000	4200	14200
MAR '78	5230	4070	4070	3740	2930	2000	891.5	890.4	897.2	1270	1000	1710	4500	3500	9440

(1) ELEVATIONS ARE REFERRED TO UNITED STATES COAST AND GEODETIC SURVEY, U.S.C. & G.S., DATUM.

(2) AREA AND CAPACITY DETERMINED FROM PLATE A32 FOR MAXIMUM POOL ELEVATION, COLUMN C

(3) NAT. REFERS TO NATURAL CONDITIONS WITH NO STRUCTURES.

(4) IMP. A REFERS TO IMPROVED CONDITIONS WITH THE UPPER (ALEXANDER) RESERVOIR ONLY

(5) IMP. B REFERS TO IMPROVED CONDITIONS WITH THE BATAVIA RESERVOIR COMPOUND.

(6) DATA NOT AVAILABLE

(7) INFLOW OBTAINED BY REVERSE-ROUTING HYDROGRAPH AT BATAVIA GAGE (EXISTING)

(8) ROUTINGS BEGIN WITH INFLOW TO LOWER RESERVOIR AND HENCE DO NOT SHOW EFFECT OF UPPER RESERVOIR

TABLE A2.6 — RESULTS OF OPERATION FOR THE LOWER RESERVOIR, BATAVIA RESERVOIR COMPOUND, FLOODS OF RECORD

FLOOD YEARS	A OUTFLOW PEAK DISCHARGE CFS			B MAXIMUM POOL ELEVATION FEET			C DURATION OF FLOOD NATURAL CONDITIONS DAYS (1) (3)		D DURATION OF CONTROLLED FLOOD - IMP. A DAYS (2) (3)		E DURATION OF CONTROLLED FLOOD - IMP. B DAYS (2) (3)	
	(4) NAT	(5) IMP. A	(6) IMP. B	(7) NAT	(8) IMP. A	(9) IMP. B	OUTFLOW DISCHARGE	POOL ELEVATION	OUTFLOW DISCHARGE	POOL ELEVATION	OUTFLOW DISCHARGE	POOL ELEVATION
MAR '60	7200	—	5610	894.7	—	898.8	1.0	4.0	—	—	0	4.0
SEPT '77	5110	3720	2000	893.1	891.2	899.5	0	3.6	0	3.4	0	10.2
MAR '78	3740	2930	2000	891.5	890.4	897.2	0	2.4	0	2.0	0	6.3

- (1) Refers to the number of days the outflow discharge and pool elevation are EQUAL TO or GREATER THAN the channel capacity discharge of 6,000 cfs at Batavia and the elevation corresponding to a channel capacity discharge of 2,000 cfs in the pool area respectively for natural conditions without improvements.
- (2) Refers to the number of days the outflow discharge and pool elevation are EQUAL TO or GREATER THAN the channel capacity discharge of 6,000 cfs at Batavia and the elevation corresponding to a channel capacity discharge of 2,000 cfs in the pool area respectively for improved conditions (Imp. A or Imp. B).
- (3) An example for interpreting columns C through E is as follows: Column C shows for the 3024 '77 flood that the duration of flooding in the city of Batavia would be 0 days and the duration of flooding in the pool area would be 3.6 days for natural conditions without any structures. Column D shows that with the Upper (Alexander) Reservoir flooding in the city of Batavia would be 0 days and the duration of flooding in the pool area would be 3.4 days. Column E shows that in operating the Batavia Reservoir compound flooding in the city of Batavia has been eliminated for this flood and that the duration of flooding in the pool area would be 10.2 days.
- (4) Nat. refers to natural conditions with no structures.
- (5) Imp. A refers to improved conditions with the Upper (Alexander) Reservoir only.
- (6) Imp. B refers to improved conditions with the Batavia Reservoir Compound.

This is done to account for the loss of natural valley storage and translation of the flood wave instantaneously through the reservoir. For the Lower Reservoir, however, this was not done. The operating plan for the Lower Reservoir was developed to minimize increases in depth and duration of flooding in the pool area for most floods. This applied to the SPF (which is the SDF for the Lower Reservoir) as well, so the extent of the flood control pool would be the same as for natural conditions and would not require modifying the natural conditions unit hydrographs. In light of the above, the 3-hour unit hydrographs for Tonawanda Creek at Alexander and Tonawanda Creek local area, Alexander to Batavia, shown on Plate A36 for natural conditions, were used in determining the SDF for the Lower Reservoir.

A2.32 With the gates of the Lower Reservoir fully open, the SDF was routed through the reservoir assuming two starting water surface elevations, empty and full pool condition. Results of these routings can be found on Table A1.20. Routing the SDF with a peak inflow of 50,200 cfs resulted in a peak outflow of 28,400 cfs (6,000 cfs through gates, remainder over spillway) at elevation 902.5 with a full pool starting condition. At elevation 902 feet, the tailwater curve controls the discharge passing over the spillway. The tailwater curve used can be found on Plate A84 which assumes the Lehigh Valley Railroad Bridge washed out under existing conditions and removed under improved conditions. The SPF flooded area in Batavia will be the same under existing or improved conditions. The 28,400 cfs SPF discharge in Batavia was used with the stage-discharge curves (Plates A113 and A115-A117) and the limited topographic information available to construct the approximate SPF flooded area in the city of Batavia as shown on Plate A1d.

A2.33 Batavia Reservoir Compound, Flooding Downstream of Rapids

Tables A1.7 through A1.16 present the results of the balanced hydrograph and flood of record routings for the entire watershed. Improved conditions discharge-frequency curves were derived using these tables and are shown on Plate A15a. The frequency curves for Tonawanda Creek at Rapids and at the confluence with Mud Creek include the diversion to Mud and Black Creeks. Plates A46, A51, A58, A61, and A71 exhibit the existing and improved hydrographs at the confluence with Ledge Creek. As can be seen in Table A2.7, the impact of the reservoirs on the downstream discharges decreases in a downstream direction both in percentage and net reduction. For example with the proposed reservoirs in operation, the 50-year discharge at Batavia would be reduced by 32 percent. The influence of the Reservoir Compound on the discharge reduces downstream until at the confluence with Ransom Creek the discharge reduction is only 14 percent. The modeling results using the March 1978 flood also substantiate this fact as the peak discharge reduction would be 47 percent at Batavia but only 25 percent at Rapids. The table also demonstrates the decrease in effectiveness of the project as the flood magnitude increases which is mainly due to the limited storage capacity of the reservoirs. The substantial reduction in peak discharge at Batavia (49 percent) for the 2-year flood is due to the operation policy for the small floods (less than 10-year) which effectively utilizes the storage of the reservoirs.

Table A2.7 - Peak Discharge Reduction With Reservoirs in Operation

Location	Percent Reduction in Peak Discharge			
	500-Year	50-Year	2-Year	March 1978
Tonawanda at Batavia	32	32	49	47
Tonawanda at Alabama	28	25	48	26
Tonawanda at Rapids	16	17	40	25
Tonawanda at Confluence:				
with Mud Creek	14	15	37	-
Tonawanda at Confluence:				
with Ransom Creek	14	14	32	-

A2.34 Table A2.8 presents the duration of flooding at Rapids, NY. As shown, the 2-year flood at Rapids under existing conditions would discharge overbank for 1.9 days. With the Upper Reservoir alone, the duration of flooding would be reduced to 0.9 day whereas with the Batavia Reservoir Compound in operation, the flooding would be eliminated. Tonawanda Creek overflow to Mud and Black Creek would also be eliminated for the 2-year flood with the Batavia Reservoir Compound. Depths from floods with intermediate return periods would be about the same with the Upper Reservoir alone or with the Batavia Reservoir Compound and would reflect a one-half foot decrease compared with existing conditions. For floods with a large return period, the duration of flooding would increase slightly with the structures in place. The discharge would decrease approximately 3 percent with the Upper Reservoir only and 5 percent with the compound in place compared to existing conditions.

A2.35 Summertime Operation of the Reservoirs

An analysis of the Tonawanda Creek at Batavia Gage for the 25-year record, 1945-1970, indicated that 90 percent of the peaks above base (1,800 cfs) occurred between the period 1 November - 14 April. As explained in paragraph A1.5, the majority of the floods occurring in the Tonawanda Creek basin are due to snowmelt. Time and cost constraints did not allow the consideration of a seasonal analysis and hence attention was focused on an annual series frequency analysis. The operation policy for the reservoirs for snowmelt and rainfall/snowmelt flooding has proven to be effective in flood damage reduction in the watershed. For rainfall events occurring in late spring and summer, a different operation policy for the reservoirs will be enacted. Further refinement of this policy will be completed during Advanced Engineering and Design Analysis through cooperation with SCS personnel, affected landowners, and the Corps. This policy will reflect the attempt to reduce damages in a manner fair to all parties concerned.

A2.36 Operation of the Batavia Reservoir Compound has shown that it can take over 1 week longer to empty the Lower Reservoir than under natural conditions. Traditionally, the farmers in this area need 1 or 2 weeks to allow the fields to drain before they are able to begin preparing their land. The construction of the reservoirs will not shorten this local area drainage

time. Further, storing water in the Lower Reservoir after 15 April could have an effect on the farming practices in that area.

A2.37 A summer operation plan was developed for small floods (approximately of 2-year annual peak discharge or less) which would lessen flooding in the Lower Reservoir area and to a minor extent areas downstream of Batavia. Outflows from the Upper Reservoir would basically be maintained at 500 cfs unless a large storm would occur. In that case, the operation would switch to the "winter" (snowmelt) operation policy. The gates in the Lower Reservoir would remain fully open. Recently (14 September 1979) the Tonawanda Basin experienced a large rainfall event with almost 5" of rain recorded at the Buffalo Airport in 13 hours. Field observations indicated that downstream local drainage areas and tributaries peaked well before the main stem. This was confirmed by a 700 cfs reduction in peak discharge between Alabama and Rapids. Following the summertime operation plan, much of the overbank flooding in the lower portion area of the Lower Reservoir area would have been reduced. Flows would have been well within bank below the Upper Reservoir and above the confluence with Little Tonawanda Creek. Overbank flooding would have been reduced downstream of the compound with the reduction in flooding decreasing as the distance from the compound increased.

A2.38 As cited in paragraph A2.29, operating the Batavia Reservoir Compound for the September 1977 flood following the winter operation scheme would result in filling the Lower Reservoir. This summertime flood of record caused large agricultural losses throughout the basin. Filling the Lower Reservoir would have aggravated the losses in that area while alleviating damage to crops downstream of the compound. Ninety percent of the farmland in the watershed lies downstream of Batavia. Operating the Reservoir Compound using the "summer" operating policy would result in filling the Lower Reservoir to elevation 893.8 feet (outflow = 3,600 cfs) which is about 6 feet lower than if the Lower Reservoir were operated using the "winter" policy and approximately at the same elevation as natural conditions. As discussed in paragraph A2.33, refinement of the operation policy to handle these rare summertime floods will be accomplished during Advanced Engineering and Design.

A2.39 Dam Failure, General

During Advanced Engineering and Design, the upper and lower dam failure analyses along with flooded area maps will be completed in accordance with ER 1130-2-419, "Project Operation, Dam Operations Management Program" using a sophisticated unsteady flow model. For the purpose of this report a dam failure analysis was completed using "Flood Hydrograph Package HEC-1 for Dam Safety Investigations." The dam failure hydrograph is computed by a weir flow equation for the shape of the breach as the failure progresses with a continuous water balance computed at short time intervals throughout the simulation. The modified Puls (hydrologic) method of channel routing is utilized for routing the dam failure hydrograph. The intent in using the program was to expeditiously evaluate the effect of a dam failure on downstream stages.

Table A2.8 - Duration of Flooding at Rapids, NY

Flood	Discharge at Rapids Gage			Elevation at Rapids Gage			Duration of Flood		
	CFS 1/			Feet - USC&GS Datum 6/			Days 7/		
	NAT 2/	IMP A 3/	IMP B 4/	NAT	IMP A	IMP B	NAT	IMP A	IMP B
SPF 5/	37,600	-	36,700	598.1	-	593.9	5.0	-	5.9
500-Year	6,970	6,830	6,600	589.6	589.4	588.8	9.8	10.1	10.0
200-Year	6,800	6,550	6,260	589.3	588.7	588.3	9.0	9.0	8.9
100-Year	6,600	6,300	6,120	588.8	588.3	587.9	5.9	7.6	7.8
50-Year	6,420	6,150	6,060	588.5	588.0	587.8	4.5	6.0	5.9
20-Year	6,050	5,770	5,730	587.8	587.2	587.2	3.4	3.8	3.8
10-Year	5,820	5,560	5,540	587.3	586.8	586.8	2.8	3.1	3.1
2-Year	5,140	4,710	3,950	586.0	585.2	583.7	1.9	0.9	0
March 1978	5,220	4,870	4,560	586.2	585.6	584.8	3.9	4.8	2.6

1/ Does not include diversion to Mud and/or Black Creek, Gage at river mile 18.6.

2/ NAT refers to natural conditions with no structures.

3/ IMP A refers to improved conditions with the Upper Reservoir only.

4/ IMP B refers to improved conditions with the Batavia Reservoir Compound.

5/ Total discharge for SPF - no diversions taken.

6/ Gage Zero = 571.04 feet USC&GS Datum.

7/ Refers to the number of days the discharge is EQUAL TO or GREATER THAN the channel capacity discharge of 4,000 cfs at Rapids.

A2.40 The selection of breach parameters introduces uncertainty in the results although errors in their description are dampened as the floodwave advances downstream. For earthen dams the suggested range of possible breach widths varies between one-half and four times the height of the dam. (11) The time of failure may be in the range of 1/2 to 4 hours depending on the dam height, dam composition, and the extent of compaction of the materials. A conservative estimate of the dam-failure hydrograph is obtained by selecting a breach width in the uppermost range and a failure time in the lower range. The flood wave propagates often at a speed ranging from 2-10 mph.

A2.41 Batavia Reservoir Compound, Upper Dam Failure

Failure during five flood events was investigated to determine the effect of a structural failure of the Upper Dam. A conservative estimate of the dam failure hydrograph was obtained by selecting a breach width of 70 feet and a failure time of 0.5 hours. Since the temporarily varying tailwater condition is not modeled by the HEC-1 Dam Safety computer program, a conservative estimate of the failure hydrograph was obtained by using the tailwater elevation at time of failure as the bottom of breach. The failure was assumed to commence near the peak reservoir stage.

A2.42 The results of simulating a structural failure of the Upper Dam for the 2-year, 20-year, 200-year, Standard Project, and Probable Maximum Flood are presented in Table A2.9. For comparison purposes, values for project conditions without failure are also presented. The results show that in general, the effect of the failure on the peak outflow from the upper reservoir decreases with the magnitude of the flood event. The Upper Dam failure hydrographs are presented on Plates A43a, A54a, A72b, and A78b.

Table A2.9 - Upper Dam Failure Results

Event	Failure Elevation - ft.	Peak Outflows-cfs	
		With Failure	Without Failure
2-year	921.0	16,900	1,500
20-year	922.2	17,500	4,740
200-year	922.5	19,700	13,500
SPF	924.3	47,300	38,600
PMF	926.	80,500	80,500

(11) Training Notes: Analytical Techniques for Dam Break Analysis. (Davis, California, Hydrologic Engineer Center, U.S. Army Corps of Engineers, 14-18 January 1980).

A2.43 Batavia Reservoir Compound, Lower Dam Failure

Since the Upper Reservoir will fill before the Lower Reservoir, there was sufficient storage in the Lower Reservoir to absorb the 2-year breach hydrograph and usage of the spillway did not occur. The Lower Reservoir obtained a maximum elevation of 898.4 feet with 3,900 acre-feet of storage remaining below the spillway assuming that after the failure of the Upper Reservoir the gates in the Lower Dam were not able to be changed from the constant 1,000 cfs outflow. On Plate A57a the Lower Reservoir response to the Upper Reservoir failure is presented.

A2.44 The Lower Dam was assumed to fail at the time of maximum pool during the operation of the 2-year flood with a rectangular 40-foot breach and 0.5-hour failure time. On Plate A57b the failure hydrograph and reservoir stage hydrograph are presented.

A2.45 Failure of the Upper Reservoir during the 20-year flood similarly resulted in not filling the Lower Reservoir to the spillway crest. Failure was assumed to commence at the maximum pool elevation, 898.4 ft. which is the same elevation obtained during the 2-year failure. A maximum outflow of 7,000 cfs occurred and is greater than the 2-year failure discharge of 4,210 cfs due to the large natural inflow experienced during the 20-year flood. On Plate A51b the 20-year failure hydrograph along with the reservoir outflow hydrograph without failure are presented.

A2.46 During major flood events, a high tailwater condition below the Lower Reservoir will occur at the time of the maximum reservoir stage, and for events such as the Standard Project Flood the Lower Dam will be completely submerged. In order to simulate the worst conditions during a major flood event, the Lower Dam was assumed to fail at the time the reservoir level reached the spillway crest, 900 feet. The breach bottom was assumed equal to the corresponding tailwater elevation, 893.8 feet, which results in bankful conditions on Batavia. Consistent with the assumptions used for the 2-year Lower Dam failure analysis, a rectangular 40-foot wide breach and a failure of the proposed Lower Dam are presented in Table A2.10 and show that the effect of the failure on the peak outflow decreases with the magnitude of the flood event. The Lower Dam failure hydrographs are shown on Plates A45a, A74b, and A80b.

A2.47 Effect of Dam Failure on Batavia

The effect of failure of the Batavia Reservoir Compound may be assessed by comparing conditions within the City of Batavia resulting from structural failure of the dams with conditions occurring without the project. Utilizing the rating curves presented on Plates A113, A115, A116, and A117 with the necessary extrapolation, the peak stages at the index points in Batavia are presented in Table A2.10 along with the stage hydrographs at the USGS gage in Batavia which are shown on Plates A45b, A51c, A74c, and A80c.

A2.48 Failure of the dams during the 2-year event resulted in within bank stages in the City of Batavia despite the reservoirs being full and experiencing minimal tailwater. From the 20- and 200-year stage hydrographs on Plates A51c and A45b it is seen that the maximum stage experienced in Batavia is similar to existing conditions but greater than project conditions without failure. During the 200-year dam failure, the overbank maximum rate of rise is approximately 1 ft/hr compared to about 0.3 ft/hr during existing conditions and will rise about 2.5 feet above the bank near the gage. It should be noted that at this rate of rise a "wall of water" normally associated with a dam failure will not occur. For extremely large events such as the SPF and PMF, the effect of failure of the dams in Batavia will be negligible. Hence, in general the peak stage in Batavia due to the failure of the dams will be about the same as stages without the project.

Table A2.10 - Effect of Upper and Lower Dam Failure on Batavia Stages at Batavia Gage

Event	Channel Capacity: Elev./Discharge	Peak Elevation and Discharge			
		Existing-Elev./Q	w/o Failure-Elev./Q	with Failure-Elev./Q	
2-year	888.50/6,000	885.80/ 3,870	882.40/ 2,000	886.30/ 4,210	
20-year	888.50/6,000	889.10/ 6,650	886.90/ 4,620	889.30/ 7,000	
200-year	888.50/6,000	890.05/ 9,100	888.30/ 5,780	890.10/ 9,390	
SPF	888.50/6,000	891.20/27,800	891.40/38,000	891.40/38,000	
PMF	888.50/6,000	892.30/99,500	892.30/104,000	892.30/104,000	

In Reach B1

Event	Channel Capacity: Elev./Discharge	Peak Elevation and Discharge			
		Existing-Elev./Q	w/o Failure-Elev./Q	with Failure-Elev./Q	
2-year	886.00/6,000	883.70/ 3,870	881.00/ 2,000	884.10/ 4,210	
20-year	886.00/6,000	886.60/ 6,650	884.60/ 4,620	886.90/ 7,000	
200-year	886.00/6,000	888.40/ 9,100	885.80/ 5,780	888.50/ 9,390	
SPF	886.00/6,000	891.10/27,800	891.10/38,000	891.10/38,000	
PMF	886.00/6,000	892.10/99,500	892.10/104,000	892.10/104,000	

Table A2.10 - Effect of Upper and Lower Dam Failure on
Batavia Stages at Batavia Gage (Cont'd)

In Reaches B2 and B3

Event	Channel Capacity: Elev./Discharge	Peak Elevation and Discharge			
		Existing-Elev./Q	w/o Failure-Elev./Q	with Failure-Elev./Q	
2-year	893.20/6,700	890.50/ 3,870	887.90/ 2,000	890.90/ 4,210	
20-year	893.20/6,700	893.15/ 6,650	891.30/ 4,620	893.40/ 7,000	
200-year	893.20/6,700	894.70/ 9,100	892.40/ 5,780	894.90/ 9,390	
SPF	893.20/6,700	897.50/27,800	898.00/38,000	898.00/38,000	
PMF	893.20/6,700	899.00/99,500	899.00/104,000	899.00/104,000	

In Reaches B4 and B5

Event	Channel Capacity: Elev./Discharge	Peak Elevation and Discharge			
		Existing-Elev./Q	w/o Failure-Elev./Q	with Failure-Elev./Q	
2-year	889.00/3,500 B4 891.50/6,200 B5	889.50/ 3,870	887.30/ 2,000	889.80/ 4,210	
20-year	889.00/3,500 B4 891.50/6,200 B5	891.90/ 6,650	890.20/ 4,620	892.10/ 7,000	
200-year	889.00/3,500 B4 891.50/6,200 B5	893.40/ 9,100	891.20/ 5,780	893.60/ 9,390	
SPF	889.00/3,500 B4 891.00/6,200 B5	896.60/27,800	897.10/38,000	897.10/38,000	
PMF	889.00/3,500 B4 891.00/6,200 B5	898.60/99,500	898.60/104,000	898.60/104,000	

A3. LOWER TONAWANDA, MUD, RANSOM, AND BLACK CREEK WATERSHEDS

A3.1 General

The lower Tonawanda Creek watershed comprises the reach from the mouth, at the Niagara River, upstream to Hopkins Road at Alabama, NY, a total distance of 41.5 stream miles. It also includes the areas along Mud, Ransom, and Black Creeks. The flooded area for this tract was divided into 20 damage reaches which include 10 on Tonawanda Creek (T-1 through T-10), six on Mud Creek (M-1 through M-6), and four on Ransom and Black Creeks (RB-1 through RB-4). A detailed damage reach description is included in Appendix B. These reaches are shown on Plate Ala.

A3.2 Overbank flooding on Mud, Ransom, and Black Creeks is normally caused by floodwaters from Tonawanda Creek entering these watersheds. To produce damaging stages on these tributaries, the level of Tonawanda Creek must exceed elevations on the divides between the tributary watersheds and the Tonawanda Creek main stem. Further, levels must remain above this stage for an extended length of time. In determining the stage-frequency curves for these streams, the diversion discharge from Tonawanda Creek was used. The local runoff was not included as this runoff was found to occur prior to overflow from Tonawanda Creek. A description of the diversions was discussed previously in Section A1.

A3.3 Stage-Discharge Curves, Existing Conditions

Plate A85 shows the stage-discharge curve just upstream of the Campbell Blvd. bridge. At lower discharges, the stage is highly dependent upon the Niagara River. For the purpose of this report, the rating curve was based on the mean Niagara River stage. This assumption will have minimal effect on the damage calculations as there is approximately 10,000 cfs channel capacity in this area. Plate A86 shows the discharge rating curve for the Rapids Road Gage. The curve indicating the discharge passing the gage in Tonawanda Creek is labeled "Tonawanda Creek at Rapids Gage less diversions." A stage-discharge curve for the USGS gaging station located at Hopkins Road near Alabama, NY, is shown on Plate A87. This curve was developed from discharge measurements made by the USGS up to 6,700 cfs with further extrapolation accomplished by this office.

A3.4 Stage-Frequency Curves, Existing Conditions

A partial duration stage-frequency curve for the Hopkins Road gaging station, Reach T-10, is shown on Plate A88. This curve was developed from available stage records of the New York State Department of Public Works and USGS. Stages for the 55 years of record were plotted using the Weibull Plotting Position method. A smooth curve was then drawn through these points. Also shown for comparison are stages for selected flood discharges, 500-, 200-, 100-, 20-, 10-, and 2-year floods, determined from the existing conditions discharge-frequency curve, shown on Plate A112 and the stage-discharge curve, shown on Plate A87, for the Hopkins Road Gage, Alabama, NY. A smooth curve was drawn through these points and labeled Annual Duration.

Table A3.1 - Stage-Frequency Curves, Lower Tonawanda Watershed

Rating Curve Description	Plate	Appropriate Discharge from Tables A1.7 - A1.13	Stage Frequency Curve	
			Index Points	Plates
U.S. Campbell Blvd.	A85	Ton BLW Conf w/Ransom	T-1 thru T-3	A89 - A91
Rapids Gage	A86	Ton at Rapids less Diversions	T-4 thru T-7	A92 - A95
Hopkins Road Gage	A87	Alabama less Div. to Mud	T-8 thru T-10	A96 - A98
Mud Creek at M-3	A99	Diversion to Mud Cr.	M-1 thru M-6	A100 - A105
Ransom-Black at RB-2	A106	Diversion to Black Cr.	RB-1 and RB-2	A108 - A109
Ransom-Black at RB-4	A107	Diversion to Black Cr.	RB-3 and RB-4	A110 - A111

Table A3.2 - Existing and Improved Flooded Areas (Acres) by Return Period

Reach	500-year		200-year		100-year		50-year		20-year		10-year		2-year	
	Existing	Improved	Existing	Improved	Existing	Improved	Existing	Improved	Existing	Improved	Existing	Improved	Existing	Improved
T-3	670	220	570	130	480	50	330	0	130	0	30	0	0	0
T-4	160	70	130	10	90	0	60	0	0	0	0	0	0	0
T-5	1,670	1,450	1,550	1,290	1,500	1,220	1,410	1,130	1,120	950	1,120	650	530	0
T-6	3,600	3,380	3,500	3,210	3,400	3,150	3,320	3,070	3,180	2,900	3,030	2,630	2,550	1,000
T-7	1,480	1,400	1,450	1,260	1,420	1,060	1,370	960	1,200	760	960	500	480	0
T-8	2,180	2,020	2,160	2,000	2,150	1,930	2,110	1,890	2,000	1,740	1,890	1,550	1,400	150
T-9	1,970	1,910	1,970	1,850	1,960	1,790	1,940	1,680	1,860	1,480	1,740	1,280	1,100	0
T-10	800	750	800	730	790	690	780	630	730	240	630	150	100	0
RB-1	710	640	675	600	660	550	620	530	530	460	480	350	175	0
RB-2	2,150	1,450	1,970	1,190	1,590	1,040	1,260	970	1,000	800	800	550	400	0
RB-3	3,400	3,010	3,220	2,820	3,060	2,320	2,920	2,520	2,320	2,130	2,180	2,040	1,590	0
RB-4	1,280	1,210	1,260	1,190	1,210	1,130	1,190	1,110	1,130	1,050	1,070	980	890	0
M-1	140	70	120	60	110	60	100	50	60	30	50	10	0	0
M-2	550	530	540	530	540	520	540	520	540	500	520	440	0	0
M-3	1,500	1,150	1,440	1,070	1,380	1,000	1,260	850	1,150	400	850	0	0	0
M-4	580	340	540	310	470	290	400	240	310	150	230	70	0	0
M-5	1,270	1,100	1,220	1,070	1,200	1,050	1,170	1,000	1,070	880	990	720	280	0
M-6	1,030	1,020	1,030	1,010	1,030	1,010	1,020	990	1,020	880	990	100	0	0
T-11	2,740	1,750	2,640	1,150	2,500	780	2,330	540	1,910	0	1,250	0	0	0
T-12	270	190	260	150	250	130	240	110	200	50	160	0	0	0
Low. Res.	2,620	2,560	2,470	2,300	2,350	2,020	2,250	1,750	2,020	1,400	1,850	1,220	1,340	1,950
Upp. Res.	520	850	500	850	470	850	430	850	390	850	320	850	240	740

A3.5 In order to develop stage-frequency curves for existing conditions at the index points, the rating curves described in paragraph A3.3, Tables A1.7 - A1.13, and the 1960 flood profile were used. Highwater marks were used to establish the 1960 water surface profile. The stage-frequency curves were first developed at the stream locations of the rating curves using the appropriate discharge for the various recurrence intervals from Tables A1.7 - A1.13. The differences in stage between the 1960 flood and the stage for the 500-, 200-, 100-, 50-, 20-, 10-, and 2-year recurrence interval were calculated for the above locations. These differences were assumed applicable for a reach encompassing a few index points. Applying these differences to the 1960 flood elevation at the index points resulted in a stage-frequency curve at that location. The absence of data adequate for backwater calculations necessitated the development of the above method to calculate the stage-frequency curves. The determination of the water surface profiles would not have only insured more confidence in the stage-frequency curves but could have also been incorporated into various ongoing FIS reports for Tonawanda Creek. Study cost savings were made, but at the expense of an important aspect of the study.

A3.6 Table A3.1 lists the discharge rating curve and appropriate discharge used as the basis for calculating the stage-frequency curves at the index points. An example of calculating the 100-year stage at T-6 is as follows: From Table A1.9, it is determined that the 100-year discharge at the Rapids Gage less diversions is 6,600 cfs which corresponds to an elevation of 590.0 feet from Plate A86. This is 0.8 foot higher than the 1960 flood elevation. At index point T-6, the 1960 flood elevation was 592.5 feet, and hence the 100-year stage at T-6 is 593.3 feet as shown on Plate A94.

A3.7 Stage-Frequency Curves, Improved Conditions

Stage-frequency curves were developed for the recommended plan and are shown on Plates A89 through A98, A100 through A105, and A108 through A111, along with the stage-frequency curves for the Upper Reservoir only and existing conditions. Improved discharges were obtained by routing and combining the balanced hydrographs with the structures in place. These discharges may be found in Tables A1.7 through A1.13. Following the method explained in paragraphs A3.5 and A3.6, the stage-frequency curves for improved conditions were developed.

A3.8 Flooded Areas by Reach, Existing and Improved Conditions

Table A3.2 presents a tabulation of flooded areas for the 500, 200, 100, 50, 20, 10, and 2-year floods under existing and improved conditions. Stage-area curves from the Tonawanda Creek Watershed Agricultural Activity Study (12) were utilized along with the appropriate stage-frequency curves to construct Table A3.2.

A4. UPPER TONAWANDA CREEK WATERSHED - HOPKINS ROAD TO ATTICA, NY

A4.1 General

This subsection describes the results of hydrologic investigations for the watershed area from Hopkins Road (mile 41.5) upstream to Attica, NY. For purposes of determining average annual damages, the area was divided into 11 damage reaches, T-11, T-12, B-1 through B-5, T-13, and A-1 through A-3. A detailed damage reach description is included in Appendix B. These reaches are shown on Plates Alb and Alc.

A4.2 Stage-Discharge Curves, Existing Conditions

A stage-discharge curve for the USGS gaging station located within the limits of Reach B-2 in Batavia is shown on Plate Al13. This curve was developed from discharge measurements made by the USGS and is fairly well defined for flows up to 6,900 cfs with further extrapolation accomplished by this office. This station has been rerated since completion of the Corps of Engineers local protection project in 1955.

A4.3 Stage-discharge curves were developed for each reach except T-11. A curve for T-11 could not be developed due to the lack of cross sectional data. Reach T-11 was addressed by other methods described in subsequent paragraphs. The rating curve for index point T-12 was developed by means of a conveyance curve and high water marks from several previous floods. The conveyance curve was then adjusted slightly by discharge measurements made at known flows, correlated with the gage at Batavia. The rating curves for the remainder of the damage reaches were calculated by backwater computations using Method I as described in EM 1110-2-1409, dated 7 December 1959 and titled "Backwater Curves in River Channels." Reaches B-2 and B-3 have a common index point in Kibbe Park and the rating curve developed at this point was used for both reaches. Reaches B-4 and B-5 also have a common index point at the Chestnut Street bridge and the rating curve developed for this point was used for both reaches. The rating curves for Reaches T-12, B-1 through B-5, T-13, and A-1 through A-3 are shown on Plates Al14 through Al21.

A4.4 Discharge-Frequency Curves, Existing Conditions

The existing discharge-frequency curve for the Batavia Gage is shown on Plate Al5. This curve is applicable to Reaches T-11, T-12, and B-1 thru B-5. It is reproduced on Plate Al22 for comparison with the improved discharge-frequency curve. The discharge-frequency curves labeled "Tonawanda Creek at Alexander" and "Tonawanda Creek at Attica" on Plate Al6 are applicable to reach A-1 and Reaches A-2 and A-3, respectively. These curves were developed using the procedures discussed in Section Al.

(12) Tonawanda Creek Watershed Agricultural Activity Study Supplemental Report; RECRA Research, Inc., WENDEL Engineers, P.C., 1978.

A4.5 Discharge-Frequency Curves, Improved Conditions

The improved discharge-frequency curves applicable to Reaches T-11, T-12, and B-1 through B-5 are shown on Plate A122. They were developed by operating the recommended structures for balanced hydrographs with various return periods and then plotting the resulting peak outflow versus the return period of the balanced hydrograph. The recommended improvements are downstream from Reaches A-1 through A-3, therefore, the improved discharge-frequency curves for these reaches will be the same as the existing curves.

A4.6 Stage-Frequency Curves, Existing Conditions

For determining existing average annual damages, stage-frequency curves were developed for the index points. The curve for Reach T-11 was developed using the method described in paragraphs A3.5 and A3.6 with the existing conditions discharge-frequency curve for the Batavia Gage as the basis. The curves for Reaches T-12, B-1 through B-5, and A-1 through A-3 were developed from the existing conditions stage-discharge curves for the respective index points and the existing conditions discharge-frequency curves discussed in paragraph A4.4. The curve for Reach T-13 was developed from routing balanced hydrographs through the natural stream system and plotting the resulting stage versus the frequency of the balanced hydrograph. Existing conditions stage-frequency curves for Reaches T-11, T-12, B-1 through B-5, T-13, and A-1 through A-3 are shown on Plates A123 through A131.

A4.7 Stage-Frequency Curves, Improved Conditions

Stage-frequency curves for improved conditions were developed for the index points for the recommended plan and are shown on Plates A122 through A131, along with the curves for existing conditions. The curves for Reach T-11 were developed using the method described in paragraphs A3.5 and A3.6 with the improved conditions discharge-frequency curves at the Batavia Gage as the basis. The curves for Reaches T-12 and B-1 through B-5 were developed from the existing conditions stage-discharge curves for the respective index points and the improved conditions discharge-frequency curves for the Batavia Gage. The curves for Reach T-13 were determined from operating the considered structures for balanced hydrographs with various return periods and plotting the resultant pool level versus the return period of the balanced hydrograph. Curves for Reaches A-1 through A-3 were not developed as the considered structures are located downstream from these reaches and would, therefore, not affect the stage-frequency relationship at these index points. These improved stage-frequency curves in conjunction with the appropriate stage-damage were used to determine residual average annual damages and benefits.

A4.8 Flooded Areas by Reach, Existing and Improved Conditions

Table A3.2 presents a tabulation of flooded areas for the 500, 200, 100, 50, 20, 10, and 2-year floods under existing and improved conditions.

A5. HYDRAULIC DESIGN

A5.1 General

The Batavia Reservoir Compound, located south of the city of Batavia, was considered as part of the flood management measures for Tonawanda Creek watershed. Batavia Reservoir Compound includes an upper impoundment located near the Erie-Lackawanna Railroad embankment and a lower impoundment located approximately one-half mile upstream from the Lehigh Valley Railroad embankment. Hydraulic structures designed consist of earthen dams and dikes, concrete culverts, sluice gates, stilling basins, a diversion channel, and spillways. The locations of these structures are shown on Plate B5 (Batavia Reservoir Compound). Hydraulic design of the structures is based on the information presented in the references: (i) Hydraulic Design of Stilling Basins and Energy Dissipators by A.J. Peterka, Engineering Monograph No. 25, U.S. Department of the Interior, Bureau of Reclamation, July 1963; (ii) Spillway for Typical Low-Head Navigation Dam, Arkansas River, by J.L. Grace, Technical Report No. 2-655, U.S. Army Engineer Waterways Experiment Station, September 1964; and (iii) Open Channel Hydraulics by Ven Te Chow, McGraw-Hill Book Company, 1959. During Advanced Engineering and Design the actual freeboard needed for nonoverflow portions will be determined based upon guidance contained in Civil Works Engineering Bulletin 54-14 and other appropriate guidance.

A5.2 Batavia Reservoir Compound, Upper Reservoir

The principal structure includes an earth embankment, a concrete culvert, and a stilling basin. Details of the culvert and stilling basin designs are shown on Table A5.1. Flow through the culvert would be controlled by five sluice gates each 11 feet wide and 11 feet high. The culvert is designed to pass the discharge of 2,000 cfs at a low stage of 906.2. At full pool, the culvert has a capacity of 10,700 cfs resulting in the spillway being overtopped for events slightly greater than the one hundred year flood. The embankment, having a length of about 5,600 feet, would be used in combination with the gates to pass the Standard Project Flood of 38,600 cfs at a stage of 924.5. The discharge capacity of the overflow spillway was designed using the weirflow equation with a "C" coefficient ranging between 2.5 and 1.6 depending on the tailwater conditions. For the design overflow discharge of 27,900 cfs, a weir coefficient of 1.76 was used when the upper pool level is at 924.5 feet and the tailwater level is at 915.0 feet. The downstream face of the embankment would be riprapped to withstand a sheet flow having a maximum velocity of about 14.5 feet per second. The stilling basin and the shape for placement of riprap are designed from the information presented in the references (ii) and (iii) listed in paragraph A5.1.

A5.3 Batavia Reservoir Compound, Lower Reservoir

The principal structure includes an earth embankment with a rectangular concrete culvert similar to the culvert designed for the Upper Reservoir and a stilling basin. Flow through the culvert would be controlled by four sluice gates 11 feet wide and 11 feet high. The culvert is designed to pass a discharge of 6,000 cfs at a stage of 900.0 which is 6.2 feet above the

Table A5.1 - Hydraulic Design Data

Description	Batavia Reservoir Compound	
	Upper Reservoir	Lower Reservoir
Standard Project Flood Discharges - cfs		
Inflow	38,800	50,200
Outflow	38,600	28,400
Controlled	2,000	6,000
Max. through culvert	10,700	6,000
Overflow	27,900	22,400
Elevations (USC&GS Datum) and Storages		
Top of Embankment - feet	922.5	905.5
Maximum Pool		
Headwater Elevation - feet	924.5	902.5
Tailwater Elevation - feet	915.0	902.0
Storage - inches	1.6	2.5
Flood Control		
Headwater Elevation - feet	922.5	900.0
Tailwater Elevation - feet	910.9	893.9
Storage - inches	1.2	1.7
Channel Bottom Elevation near the dam - feet	900.0	880.0
Maximum Velocities - ft./sec.		
Culvert Outlets	22.0	16.0
Spillways: crest	8.0	4.0
downstream face	14.5	11.5
Culvert and Sluice Gate		
Invert elevation (feet) at:		
Inlet	900.0	880.0
Outlet	900.0	879.0
Height - feet	11.0	11.0
Width - feet	11.0	11.0
Number	5 ^{1/}	4 ^{1/}
Stilling Basin:		
Type	concrete	concrete
End Sill	Yes	Yes
Baffle Blocks	Yes	Yes
Overflow Section:		
Type	paved	paved
Crest elevation - feet	922.5	900.0
Length - feet	5,600	4,000
Contributing Drainage Area - sq. mi.	102	171
Channel Capacity Downstream from Dam - cfs	2,000	6,000

^{1/} Includes one spare gate

tailwater. Velocities of about 16 feet per second would exist near the culvert inlet and outlet areas where a stilling basin would be provided. The embankment functions as an overflow spillway with a crest elevation of 900 feet and overflow length of 4,000 feet. At a reservoir stage of 901.0, one-foot of water over the crest, the total discharge through and over the spillway increases from 6,000 cfs to 14,000 cfs, and the tail water increases 893.8 to 898.7. The maximum velocity on the downstream face of the dam is less than 6.0 ft/sec. Assuming that no tail water exists, the velocity on the downstream face reaches 11.5 ft/sec. Flow would overtop the emergency spillway for floods with an average return period greater than 500 years. For the design overflow discharge of 22,400 cfs, a weir flow coefficient of 1.64 was used when the upper pool level is at 902.5 and the tailwater level is at 902.0 feet. The hydraulic design data for the principal structure and overflow spillway are given in Table A5.1.

A6. RESPONSE TO COMMENTS IN THE MEMORANDUM FOR RECORD, 9 FEBRUARY 1977

Below are responses to comments in the Memorandum for Record, NCDPD-PF, 9 February 1977 which are applicable to this appendix.

1. Route the Probable Maximum Flood (PMF) through the recommended plan. Discuss impacts.

As discussed in paragraph A1.61, the Probable Maximum Storm was centered over the Tonawanda Creek watershed above Alexander in order to maximize the peak discharge at Alexander and Batavia. This insured the PMF discharges at the Upper and Lower Reservoir were the highest possible to test the performance of the spillways. Table A1.20 presents the PMF discharges and elevations.

The HEC-5C hydrograph routings indicated that the outflow from the Lower Reservoir will be the same for existing and improved conditions. This indicates that the spillway discharge will not significantly increase the hazardous condition downstream from the spillway. Hence, in accordance with ER 1110-2-1451, no real estate interest will be required in the city of Batavia.

2. Show impact of upper dam failure.

In paragraphs A2.39 and A2.40 it is indicated that during Advanced Engineering and Design, the dam failure analyses along with flooded area maps will be completed in accordance with ER 1130-2-419, "Project Operation, Dam Operations Management Program," using a sophisticated unsteady flow model. For the purpose of this report a dam failure analysis was completed using "Flood Hydrograph Package HEC-1 for Dam Safety Investigations." Paragraphs A2.41 through A2.44 discuss the impact of the Upper Dam failure with the hydrographs shown on Plates A54a and A57a.

The field surveys taken in the Lower Reservoir area in Winter 1977-1978, coupled with a cursory hydraulic analysis, indicated that the previous (1976 report) location of the emergency spillway was impossible. Instead, under the latest plan, the Lower Reservoir embankment would function as an emergency spillway at elevation 900 feet. Lateral (training) dikes will prevent the diversion of discharge around Batavia.

8. Show frequency curves which represent the split in flows through and around Batavia. Show that the damages and benefits were derived from the split frequency curves.

Comment no longer applicable. See No. 4 above.

9. Define the route of the diverted water.

Comment no longer applicable. See No. 4 above.

10. Hydrographs showing natural and modified conditions should be shown.

Balanced hydrographs for the 200, 50, and 2-year floods are shown on Plates A42 through A58. Inflow/outflow discharge and stage hydrographs for the reservoir along with hydrographs for the confluence with Ledge Creek for existing and modified conditions are shown. Hydrographs for the March 1960, March 1978, and September 1977 are shown on Plates A59 through A71. SPF and PMF hydrographs are shown on Plates A72 through A80.

11. Table A-26, add a column to show the effect of the Upper Reservoir by itself.

The table referenced is nonexistent; however, it was assumed that the comment was addressing Table A2.2 of the 1976 report. Balanced floods and the March 1978 flood were routed through the entire Tonawanda stream network assuming the Upper Reservoir alone in place. Results of these routings may be found in Tables A1.7 through A1.13 and Table A1.16. Tables A2.3 through A2.6 present the effect of the Upper Reservoir only on the balanced and March 1978 flood in the Lower Reservoir area.

14. Provide additional backup for channel capacities.

Channel capacities for Tonawanda Creek are discussed in paragraphs A1.8 through A1.13. The approach used to determine these capacities is considered reasonable in lieu of an expensive backwater analysis. Table A1.4 presents ranges of channel capacities for all Tonawanda Creek reaches. The lowest value in a reach was used in the operation studies in order to not overstate the benefits attributable to the considered reservoirs.

15. Perform a sensitivity analysis to assess the effect of improved mapping of the project.

During the Winter of 1977, Buffalo District personnel completed field surveys in the Lower Reservoir area of the proposed Batavia Reservoir Compound. Part of the information received led to the conclusion that the location of the emergency spillway, as delineated in the 1976 report, was hydraulically impossible. This finding points out the importance of sufficient topographical detail when proposing a project.

16. Evaluate the significance the local area inflows downstream of the project will have on the improved stage-frequency curves at Alabama.

Balanced hydrographs were routed and combined with local area inflow for the Tonawanda Creek watershed from Alexander, NY, to the confluence with Ransom Creek. Existing and improved conditions were investigated. The stage-frequency curves at Alabama are shown on Plate A98.

17. Revise, statistically, the frequency curves without regard to the Standard Project Flood. The frequency curves do not have to conform to the Water Resources Council Bulletin 17 guidelines. Use the new frequency curves in the benefit analysis.

The results of the regional frequency analysis completed for this study were used in the calculation of the balanced hydrographs. The 500, 200, 100, 50, 20, 10, and 2-year hydrographs were routed and combined at selected index points along Tonawanda Creek. This information was used in the calculation of the frequency curves and utilized in the benefit analysis.

18. Assess any adverse effect of increased duration of release on the downstream area.

In many cases when a release is maintained for a considerable period of time, even if within channel capacity, the groundwater table may increase. Low areas which may be one-half mile or more from the channel can begin to fill up or become so swampy that it will not support farm equipment. Study funding constraints precluded the possibility of performing groundwater and backwater studies. Table A2.3 shows that under project conditions, overbank flooding in the Rapids, NY, area will persist for approximately 1 day longer than what would have existed under natural conditions. Flows would be near to or exceeding channel capacity for only a few days longer than existing flooding. This would not be detrimental to drainage of farmland during late fall to early spring months. During months of agricultural activity certain crops may be affected.

19. Discuss sediment storage and the affect it would have on project formulation.

One of the most obvious consequences of sediment deposits is the depletion of reservoir storage capacity. Since the reservoirs will normally be dry and the gates fully open, it is felt that the sediment characteristics of Tonawanda Creek will not be greatly affected.

20. Show the effect the project has on a flood of record.

Beginning as inflow to the Lower Reservoir, the March-April 1960 flood was routed and combined with local area inflow along Tonawanda Creek to Rapids, NY, as described in paragraphs A1.44 and A2.29. Table A1.14 presents the peak discharge at various index points for existing and improved conditions. Tables A2.5 and A2.26 show the effect of the Lower Reservoir on the 1960 flood. The hydrographs are presented on Plates A59-A62.

24. Explain why modified and natural discharge profiles for various frequency floods such as the 10, 100, and 200-year floods cannot be constructed.

Modified and natural discharge profiles were not constructed due to the lack of backwater calculations as indicated in paragraph A1.8. The sufficient streamflow, highwater marks, and field observation data allowed a reasonable range of channel capacities to be established as described in paragraphs A1.8 through A1.13. The 1977 cost estimate for field surveys, aerial mapping, and backwater calculations was in excess of 1.0 million dollars. It was felt that the adequacy of the field data precluded the need for an expensive backwater analysis. Hence, a backwater analysis resulting in natural and modified profiles was not performed.

25. Develop a hydrograph for Ledge Creek near confluences with Tonawanda Creek for the 1960 flood.

Paragraph A1.38 describes the development of the 1960 flood for Tonawanda Creek below the confluence with Ledge Creek with existing and improved hydrographs shown on Plate A61. This was essential in the determination of cumulative local area runoff between the Lower Reservoir to just downstream of the confluence with Ledge Creek. That area was used in the determination of releases from the Lower Reservoir.

A7. RESPONSE TO COMMENTS IN THE MEMORANDUM OF UNDERSTANDING, 39 JUNE 1980

Below are the responses to comments and portions thereof from the Memorandum of Understanding, NCDPD-PF, 30 June 1980, which are applicable to this appendix. The Memorandum of Understanding, 30 June 1980, replaces the MOU sent with NCD 1st Indorsement, 24 April 1980.

Engineering Division - Water Control Center Comments:

2. The report must show the impact of the project on the area flooded downstream by showing the flood (10-year) and the SPF. Plate 14 does not show adequate detail in presenting the flooded area. The map which shows the flooded areas must show streets and individual houses in the town of Batavia.

The 30 June 1980 MOU indicates that flooded area maps should be constructed delineating the flooded outline for a historic flood (March 1960) for with and without project conditions. On the maps, arrows will be drawn showing the path of the water and range of channel capacity in the reach. A tabulation of the flooded area for existing and improved conditions for the balanced hydrograph routings will be made. Flooded area maps for the 100-year and SPF should be constructed in the city of Batavia for with and without project conditions.

Plates A2a through A2c present the flooded outline for existing and improved conditions for the March 1960 flood with arrows showing the path of the water. Table A3.2 presents a tabulation of the flooded areas for existing and improved conditions for the balanced hydrograph routings. Utilizing limited flood evaluation and topographic information, the approximate 100-year and Standard Project flood outlines in the city of Batavia for with and without project conditions are presented on Plate A1d.

5. Revise Table A5.1 to show storage in inches, drainage areas and channel capacities for both reservoirs.

Table A5.1 has been revised.

7. Page A-64, comment No. 1 - Uncertainty in the rating curve for the lower reservoir is not a basis for concluding that the spillway discharge would not significantly increase the hazard condition from the spillway. This is reinforced by the statement that the project would increase the design discharge. The effect of the project increases the design flow, additional area inundated by the higher flow during a SPF event should be delineated and the additional area effected should be purchased.

The effect of the project on the SPF discharges has been reevaluated. Originally a 3-hour time interval was used during the routing and combining of the SPF. This proved to be insufficient near the peak of the hydrograph. To improve the accuracy of the peak discharge a 1-hour time interval was used near the peak. Table A7.1 presents a comparison of the previous SPF peak discharges and the present discharges derived using a 1-hour interval.

As can be seen in Table A7.1, the SPF peak discharge is reduced for with project conditions and hence in accordance with ER 1110-2-1451, no real estate interest will be required in the city of Batavia.

Table A7.1 - SPF Peak Discharges, 1979 and 1980 Analysis

	Existing				Improved			
	1979		1980		1979		1980	
Alexander	:	:	:	:	:	:	:	:
(Upper Reservoir)	:	:	:	:	:	:	:	:
Inflow	:38,800	cfs	:38,800	cfs	:38,800	cfs	:38,800	cfs
Outflow	:40,000	cfs	:38,500	cfs	:39,000	cfs	:38,600	cfs
Elevation	: 923.8	feet:	923.8	feet:	924.5	feet:	924.5	feet
Batavia	:	:	:	:	:	:	:	:
(Lower Reservoir)	:	:	:	:	:	:	:	:
Inflow	:52,100	cfs	:49,200	cfs	:53,000	cfs	:50,200	cfs
Outflow	:28,100	cfs	:28,500	cfs	:29,400	cfs	:28,400	cfs
Elevation	: 901.9	feet:	902.0	feet:	902.6	feet:	902.5	feet

8. Because of the proximity of the project to the city of Batavia, the report must describe (in at least a preliminary manner), the manner and effects of failure of the Lower Dam. Include discussion of the method of riprapping and possible concrete lip.

In paragraphs A2.39 and A2.40 it is indicated that during Advanced Engineering and Design the dam failure analysis along with flood area maps will be completed in accordance with ER 1130-2-419, "Project Operation, Dam Operations Management Program," using a sophisticated unsteady flow model. For the purpose of this report a dam failure analysis was completed using "Flood Hydrograph Package HEC-1 for Dam Safety Investigations." Paragraphs A2.41 thru A2.50 discuss the impact of the Upper and Lower Dam failure with the hydrographs shown on Plates A43a, A45a, A45b, A54a, A57a, A57b, A72b, A74b, A74c, A78b, A80b, and A80c.

9. Page A-65 - The response of comment 14 regarding the determination of downstream channel capacities is not adequate. The determination of accurate channel capacities is an extremely important item in the evaluation of reservoir performance. The sections should be obtained and backwater runs should be completed for all reaches where small changes in the stage have a large impact on damages and resulting benefits. This is a very important item in that an underestimate of downstream channel capacities can have a dramatic effect on the formulation and operation of the project. The report should describe the effects that a reasonable range of channel capacity would have on the operation and economics of the project.

It is agreed that the discussion of channel capacities was not adequate. Paragraphs A1.8 through A1.13 present a discussion of channel capacities and their determination using rating curves at USGS gaging stations coupled with field observations. Table A1.4 presents ranges of channel capacities for Tonawanda Creek reaches.

10. The operation of the reservoir for floods larger than a 10-year event assumes that it is known that such a large flood is in progress. In the actual operation of the project, the regulation personnel would not have this advanced knowledge. There should be a consistent operation policy for all floods. In order to make the operation practical, the gate settings should be determined as a function of reservoir stage and local (downstream) flows and not only a function of the inflow into the project. This operating plan should apply to all floods and should not be limited to floods of a specific frequency.

As indicated in the Memorandum of Understanding between North Central Division and Buffalo District, 30 June 1980, the operation plan for the reservoirs will remain as a function of inflow and downstream flows with a two-scheme operation dependent upon the severity (frequency) of the flood. In paragraphs A2.14 and A2.15, discussion concerning this matter is presented.

11. Tables A-1. and A-1.8 - A1.12, plus A-15 should be used to construct discharge-frequency curves for existing and modified conditions at several locations downstream from the project.

As explained in paragraph A2.33, Table A1.7 through A1.16 were used to construct frequency curves at several locations downstream of the project. It should be noted that the frequency curves at Rapids and the confluence to Mud Creek with Tonawanda Creek include the diversion discharges.

12. The impact of increased local inflow, due to reductions in stage on Tonawanda Creek and resultant decrease in backwater effect on the tributaries, should be evaluated.

The local inflow hydrographs developed for existing conditions were used in the routing calculations for improved conditions, as the decrease in backwater effect on the tributaries will be minimal. Further explanation is given in paragraph A2.1.

13. Discussion in report should be modified. The impact of a reservoir on downstream discharge usually decreases in a downstream direction, both in percentage and net reduction. The tables showing the routings of the balanced hydrographs show that the net effect of the project remains the same and even increases in some cases. This tendency is questioned especially when it is considered that the impact of Comment 19 is to decrease the effect fo the project with respect to distance downstream of the project.

As can be seen in Table A2.7, the impact of the reservoirs on the downstream discharges decreases in a downstream direction both in percentage and net reduction. For further discussion refer to paragraph A2.33.

14. Pages A-18 to 24 - The balanced hydrograph routings should show the inches of runoff stored for with project conditions.

Footnotes have been added to Tables A1.7 through A1.13 and present the quantity of water stored in the Upper Reservoir alone and the Batavia Reservoir Compound for all frequencies.

15. Routings of the historic storms show that the effect of the proposed project decreases downstream. This tendency appears inconsistent with the results of the balanced hydrographs. This point should be discussed in the report.

This comment is similar to comment 13 and is explained in paragraph A2.33. As shown in Table A2.7, the peak discharge reduction at Batavia would be 47 percent for the recurrence of the March 1978 flood, but only 25 percent at Rapids.

16. Page A-33 - Review of EC 1110-2-163 indicates that safety standard 3 is not appropriate for design of the Tonawanda Project. Standard 3 is appropriate only for emergency spillage which may operate in lieu of service spillways. Since the project does not have a service spillway, this standard does not appear appropriate. It appears that standard 2 is more appropriate. This calls for adequate outlet capacity to be available to limit head differences at time of overtopping to reduce risks downstream in the event of breaking.

The Buffalo District maintains the conviction that Standard 3 is the appropriate safety standard for the reservoirs. Comment 16 indicates that Standard 3 is appropriate only for emergency spillage which may operate in lieu of service spillways. This interpretation seems to be in error as EC 1110-2-163 uses that only as a possible example for the application of Standard 3 and not necessarily as a requirement. Comment 16 also indicates that the project does not have a service spillway. It should be clarified that the Upper and Lower Dam of the Batavia Reservoir Compound have "limited service" spillways as they are used infrequently for the operation of the reservoirs and do not incur excessive damage to the spillway structure by erosion or to downstream areas from deposition of eroded material.

Due to the limited fetch, wind-induced wave action will not be a significant factor in determination of the top elevation of the dam. Further discussion may be found in paragraph A1.53 through A1.57 on the selection of the safety standard. It is suggested that during Advanced Engineering and Design the application of the appropriate safety standard be studied further and assistance from the Board of Engineers and OCE be solicited if a disagreement remains.

17. Plate A-74 and A-80 - The report shows that the outflow from the project is increased for both the SPF and PMF. The basis for this increase in flow should be explained.

As shown presently on Plates A-74 and A-80, the outflow from the project is not increased for both the SPF and PMF. As indicated in response to comment 7 and in paragraph A1.50, a refined routing was done near the peak which resulted in more accurate and credible discharges.

18. The report should discuss the sizing of the outlet works and the overflow embankment. The present report gives no basis for the sizing of the components. The outlet works must be able to pass the flow required to minimize the stage at the time of overtopping.

AD-A133 910


BUFFALO METROPOLITAN AREA NEW YORK WATER RESOURCES
MANAGEMENT INTERIM REP. (U) CORPS OF ENGINEERS BUFFALO
NY BUFFALO DISTRICT JUL 83


2/9

UNCLASSIFIED

F/G 13/2

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

In Section A5 a discussion on the sizing of the outlet works is presented. Component sizes are tabulated in Table A5.1.

19. The report should discuss the protection to be used on the overflow embankments including design flow, design velocity and design TW evaluation for both the upper and lower dams.


This discussion may be found in Section A5 and presented in Table A5.1.


20. The report should present more legible plates which show the downstream damages reaches. The report should present flow distribution charts for a large magnitude flood for the flows which enter the downstream tributaries.


On Plate A2a through A2e the Tonawanda Creek reaches are presented along with the flow distributions for the March 1960 flood.


21. Usually hydrologic models are constructed from sub-area unit hydrographs and the resulting flood hydrographs for historic events are compared to historic flood hydrograph data as a check of the model performance regarding timing, volume, and flood magnitude reproduction. The synthetic events in turn are usually checked at locations of gaging records against the independent statistical results of peak flows and volumes. During this process the model loss rates are usually maintained somewhat consistent down through the watershed. This results in the effect that each sub-area will produce a reasonable contribution of runoff compared to the other sub-areas. Since for the Tonawanda study both the analysis for historic events and synthetic events uses results of the gage data directly in their derivation, the above consistency checks are more difficult. The creation of a hydrologic model consisting of sub-area components which match a series of balanced hydrographs throughout an entire watershed is very difficult to create. With respect to Tables A1.7 through A1.13, are the relative contributions of each sub-area reasonably consistent with regard to peaks and volumes?


It is agreed that hydrologic models are often constructed from subarea unit hydrographs and the resulting flood hydrographs for historic events are compared to historic flood hydrograph data as a check of the model performance. However, the balanced hydrograph method was in this case the most appropriate and implementable technique. The upstream balanced hydrographs were routed and subtracted from downstream balanced hydrographs to calculate the local area inflow hydrographs. Necessary minor adjustments were made to insure consistent relative contributions of each subarea with respect to peaks and volumes. If sufficient data had been available a period of record routing would have been the most informative. Further discussion concerning the rationale for selection of the balanced hydrograph approach may be found in paragraph A1.24.














- O - OBSERVED ANNUAL PEAKS
- COMPUTED FREQUENCY CURVE
- WITH EXPECTED PROBABILITY ADJUSTMENT
- CONFIDENCE LIMITS (.05 & .95)

FREQUENCY CURVES DERIVED USING INDIVIDUAL
STATION RECORD AND BULLETIN 17A METHODS
STATISTICS FOR THIS STATION WERE USED
IN THE REGIONAL FREQUENCY ANALYSIS WHICH
RESULTED IN THE FINAL STATION FREQUENCY
CURVE SHOWN ON PLATE A15.

PERIOD OF RECORD: 1929-1977

DRAINAGE AREA: 231. mi.²

WEIBULL PLOTTING POSITION


$Q_m = 3.68$
 $S = .152$
 $g = -.605$


EXCEEDANCE FREQUENCY IN PERCENT

TONAWANDA CREEK WATERSHED, N. Y.

PEAK DISCHARGE -
FREQUENCY CURVE

TON. CR. AT ALABAMA
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979








PEAK	$Q_m = 612 DA^{.75}$
1-DAY	$Q_m = 285 DA^{.77}$
3-DAY	$Q_m = 180 DA^{.79}$
7-DAY	$Q_m = 98.8 DA^{.79}$
15-DAY	$Q_m = 73 DA^{.79}$
30-DAY	$Q_m = 63 DA^{.80}$

NOTE:
THESE CURVES APPLICABLE TO
AREAS UPSTREAM OF TATAVIA

TONAWANDA CREEK WATERSHED, N. Y.
MEAN ANNUAL DISCHARGE -
DURATION-DRAINAGE AREA
CURVES
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979








46 7400

LOG-10 THM C 1 X 3 CYCLES
KEUFFEL & ESSER CO.


N-E


STANDARD DEVIATION, S



46 7400
STANDARD DEVIATION, S

LOGARITHMIC 3 X 3 CYCLES
KEUFFEL & ESSER CO. MADE IN U.S.A.
K-E





PEAK DURATION SKEW VS. DRAINAGE AREA CURVE

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

PLATE A9

9 COEFFICIENT, SKEW

DRAINAGE AREA, D.A., IN SQUARE MILES

RAW SKEL

• + ADOPTED SKEW COMPUTED BY
BUNTING 17 METHOD

APPLICABLE TO ARMS UPSTREAM FROM BATAVIA
AND LOCAL AREAS TRIBUTARY TO THE MAIN STEM
DOWNSTREAM FROM BATAVIA

Q-0986 (Am DA)-B427

$$388 (409 \text{ DAD}) + 1.21$$

APPLICABLE TO AREAS ALONG
THE MAJAI STEM AT
SATARIA AND DOWNSTREAM

ATTACHED IS A COPY OF COMPANY

CAZENOVIA CK # EBBEVEZER

AT LANCASTER

ELLICOTT OR BELOW WILLIAMSVILLE

TOHAWAUA AT LIBRA

— BRIDGE TONES R. E. GINSEY —


SEN. NT ROCH-ESTER


2,000 3,000


WEIGHTED AVERAGE
REGIONAL SKEW
 $q = -0.12$


46 5490

K-E SEMI-LOGARITHMIC PLOTTER DIVISION
KEUFFEL & ESSER CO. MANHATTAN











46 5490

K-E SEMI-LOGARITHMIC 3 CYCLES X 10 DIVISIONS
KEUFFEL & ESSER CO. MADE IN U.S.A.





TONAWANDA CREEK WATERSHED, N. Y.

PEAK DISCHARGE -
FREQUENCY CURVES

FROM BATAVIA, DOWNSTREAM

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

DISCHARGE IN CFS

46 8040

K-E PROBABILITY X 2 LOG CYCLES
KEUFFEL & ESSER CO. MA. U.S.A.




PLATE A150

TONAWANDA CREEK WATERSHED, N. Y.

PEAK DISCHARGE-
FREQUENCY CURVES
FROM BATAVIA, DOWNSTREAM
IMPROVED (BRC) CONDITIONS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

99.99

99.8

99

95

90

80

70

60

50

40

30

20

10

0.01

0.05

0.1

0.2

0.5

1

2

5

10

20

30

40

50

60

70

80

90

95

98

99

99.8

99.99

RECUERRECE INTERVAL IN YEARS

500 200 100 50 20 10 5 2

TONAWANDA CREEK AT ALEXANDER, N.Y. (DRAINAGE AREA = 102 SQ. MI.)
 TONAWANDA CREEK AT ATTICA, N.Y. (DRAINAGE AREA = 81 SQ. MI.)
 LITTLE TONAWANDA CREEK AT MOUTH (DRAINAGE AREA = 32.5 SQ. MI.)
 LITTLE TONAWANDA CREEK AT LINDEN (DRAINAGE AREA = 22.1 SQ. MI.)

TONAWANDA CREEK WATERSHED, N. Y.

PEAK DISCHARGE-
 FREQUENCY CURVES

FROM BATAVIA, UPSTREAM

U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1978


EXCEEDENCE FREQUENCY IN PERCENT

200

99 99.5 99.9 99.99

46 8040

K-E PROBABILITY X 2 LOG CYCLES
KEUFFEL & ESSER CO. MADE IN U.S.A.




TONAWANDA CREEK WATERSHED, N. Y.

DISCHARGE - DURATION FREQUENCY CURVES

BATAVIA, N. Y.

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1978



NOTE:

THESE CURVES APPLICABLE TO
AREAS UPSTREAM OF BATAVIA

TONAWANDA CREEK WATERSHED, N. Y.


PEAK DURATION

DISCHARGE-RETURN PERIOD

DRAINAGE AREA CURVES

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

46 5810
KLUJ FIL & LOGIC CO.



NOTE:

THESE CURVES APPLICABLE TO
AREAS UPSTREAM OF BATAVIA

TONAWANDA CREEK WATERSHED, N. Y.


1 - DAY DURATION

DISCHARGE-RETURN PERIOD

DRAINAGE AREA CURVES


U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

PLATE A19



NOTE:
THESE CURVES APPLICABLE TO
AREAS UPSTREAM OF BATAVIA


TONAWANDA CREEK WATERSHED, N. Y.
3-DAY DURATION
DISCHARGE-RETURN PERIOD
DRAINAGE AREA CURVES
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979



NOTE:
THESE CURVES APPLICABLE TO
AREAS UPSTREAM OF BATAVIA

TONAWANDA CREEK WATERSHED, N. Y.
15- DAY DURATION
DISCHARGE-RETURN PERIOD
DRAINAGE AREA CURVES
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

K-E SEMI-LOGARITHMIC 46 5810
A CIVIL ENGINEERING DIVISION
NEUFELD & ZESSER CO.
NEW YORK, N. Y.



NOTE:

THESE CURVES APPLICABLE TO
AREAS UPSTREAM OF BATAVIA


TONAWANDA CREEK WATERSHED, N. Y.

30-DAY DURATION


DISCHARGE-RETURN PERIOD

DRAINAGE AREA CURVES

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979



K-Σ SEMI LOGARITHMIC 46 5810
 NEUFELD & ASSOCIATES, INC.



NOTE:
 THESE CURVES APPLICABLE TO
 AREAS DOWNSTREAM FROM
 BATAVIA

500 600


TONAWANDA CREEK WATERSHED, N. Y.

1 - DAY DURATION


DISCHARGE-RETURN PERIOD


DRAINAGE AREA CURVES

U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979





K-2 SEMI-LOGARITHMIC 46 5810
 3.0 INCHES DIAMETER
 SUFFEL & LORR CO.





KE SEMI-LOGARITHMIC
 46 5810
 3 CYCLE 1" 40 DIVISION
 NEUFEL & ESSER CO.






LEGEND:

ROUTED AND COMBINED

Determined by routing and combining of sub-basin balanced hydrographs.

COMBINED AT GAGE

Determined from discharge-duration-return period data and the appropriate 1960 flood hydrograph as a pattern.



264 276 288 300 312 324 336 348 360


TONAWANDA CREEK WATERSHED, N. Y.

200 - YEAR BALANCED


HYDROGRAPHS

AT ALABAMA

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979





DRAINAGE AREA IN SQUARE MILES




NOTE: THIS GENERALIZED CURVE IS
CONSIDERED APPLICABLE TO THE
ENTIRE ERIE-NIAGARA BASIN.

TONAWANDA CREEK WATERSHED, NEW YORK
CLARK'S "Tc"
VERSUS
AVG. STREAM SLOPE
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979





TONAWANDA CREEK ROUTING SCHEMATIC




NOTE: DIVERSION TO BOWEN CREEK OCCURS ONLY UNDER EXISTING CONDITIONS AND FOR FLOODS GREATER THAN A 500-YEAR RETURN PERIOD.

TONAWANDA CREEK WATERSHED, N. Y.

ROUTING SCHEMATIC

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979



NOTE:


See paragraph A 1.35 for explanation.

TONAWANDA CREEK WATERSHED, N. Y.

EXISTING CONDITIONS
FLOODED AREAS UPSTREAM
OF BATAVIA

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

PLATE A38



TONAWANDA CREEK WATERSHED, N. Y.
DIVERSION DISCHARGE CURVE
FOR TONAWANDA OVERFLOW
TO MUD CREEK
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979




PLATE A41

TONAWANDA CREEK WATERSHED, N. Y.
DIVERSION DISCHARGE CURVE
FOR TONAWANDA OVERFLOW
TO BLACK CREEK
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979




PLATE A42

TONAWANDA CREEK WATERSHED, N. Y.

UPPER RESERVOIR

200-YEAR FLOOD

DISCHARGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED 1972

ELEVATION IN FEET - U.S.C.G.S. DATUM

PLATE 3A74

EXISTING CONDITIONS
POOL STAGE RESULTING
FROM OPERATING
UPPER RESERVOIR

THIS PLATE SHOWS THE
ELEVATION OF THE FLOOD
IN THE UPPER RESERVOIR
AREA FOR VARIOUS
CONDITIONS.

SPILLWAY CREST

ΔT = 3 HRS

TIME IN HOURS


TONAWANDA CREEK WATERSHED, N. Y.

UPPER RESERVOIR

200-YEAR FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979



46 1020



K-E 10 X 10 TO 5.6 INCH • 10 X 10 INCHES
K-E-EL & ESSER CO. NEW YORK

PLATE A430



TONAWANDA CREEK WATERSHED, N. Y.

LOWER RESERVOIR

200 - YEAR FLOOD

DISCHARGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED 1979




PLATE 245

TIME IN HOURS

AT 3 MRS


TONAWANDA CREEK WATERSHED, N. Y.


LOWER RESERVOIR

200-YEAR FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979





TONAWANDA CREEK WATERSHED, N. Y.

200-YEAR DAM FAILURE

STAGE HYDROGRAPHS AT

BATAVIA GAGE

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED 1978




PLATE A46

TONAWANDA CREEK WATERSHED, N. Y.

200 - YEAR FLOOD


DISCHARGE HYDROGRAPHS

DNSTR. FROM CONFLUENCE

WITH LEDGE CREEK

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979



TONAWANDA CREEK WATERSHED, N. Y.

UPPER RESERVOIR

50 - YEAR FLOOD

DISCHARGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO

EXISTING CONDITIONS
 POOL STAGE RESULTING
 FROM OPERATING
 UPPER RESERVOIR

THIS PLATE SHOWS THE
 ELEVATION OF THE FLOOD
 IN THE UPPER RESERVOIR
 AREA FOR VARIOUS CONDITIONS

ELEVATION OF UPPER
 RESERVOIR SPILLWAY

AT: 3 HRS

TIME IN HOURS


TONAWANDA CREEK WATERSHED, N. Y.


UPPER RESERVOIR

50 - YEAR FLOOD

STAGE HYDROGRAPHS


U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979





ELEVATION IN FEET - USCGS DATUM

PLATE A50




TONAWANDA CREEK WATERSHED, N. Y.


LOWER RESERVOIR


50 - YEAR FLOOD


STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979









TONAWANDA CREEK WATERSHED, N. Y.
 20-YEAR DAM FAILURE
 STAGE HYDROGRAPHS AT
 BATAVIA GAGE
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979

46 1930

K-E 10 X 12 TO THE INCH •
MEUFFEL & ESSER CO. N.Y.




PLATE A52

ELEVATION OF UPPER
RESERVOIR SPILLWAY

THIS PLATE SHOWS THE
ELEVATION OF THE FLOOD
IN THE UPPER RESERVOIR
AREA FOR VARIOUS CONDITIONS

EXISTING CONDITIONS
POOL STAGE RESULTING
FROM OPERATING
UPPER RESERVOIR

$\Delta T = 3 \text{ HRS}$

TIME IN HOURS

PLATE A53


TONAWANDA CREEK WATERSHED, N. Y.


UPPER RESERVOIR


2 - YEAR FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979







TONAWANDA CREEK WATERSHED, N. Y.

**UPPER RESERVOIR
FAILURE HYDROGRAPHS**

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1978




PLATE A55

TIME IN HOURS


TONAWANDA CREEK WATERSHED, N. Y.

LOWER RESERVOIR

2 - YEAR FLOOD

DISCHARGE HYDROGRAPHS

U. S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979




TONAWANDA CREEK WATERSHED, N. Y.

LOWER FESERVOIR

2 - YEAR FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979




TONAWANDA CREEK WATERSHED, N. Y.


LOWER RESERVOIR


2 - YEAR FLOOD

OPERATION

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979







TONAWANDA CREEK WATERSHED, N. Y.
2 - YEAR FLOOD
DISCHARGE HYDROGRAPHS
DNSTR. FROM CONFLUENCE
WITH LEDGE CREEK
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979




PLATE A59

TONAWANDA CREEK WATERSHED, N. Y.

LOWER RESERVOIR

MARCH, 1960 FLOOD

DISCHARGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

EXISTING CONDITIONS

RESULTING FROM ROUTING
THE EXISTING CONDITION
INFLOW THROUGH THE
LOWER RESERVOIR

ELEVATION OF LOWER
RESERVOIR SPILLWAY

THIS PLATE SHOWS THE
ELEVATION OF THE FLOOD
IN THE LOWER RESERVOIR
AREA FOR VARIOUS CONDITIONS

AT 3 HRS.

APRIL, 1960

MARCH, 1960

DATE AT NOON


TONAWANDA CREEK WATERSHED, N. Y.


LOWER RESERVOIR

MARCH, 1960 FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979





TONAWANDA CREEK WATERSHED, N. Y.


RECONSTITUTED

MARCH, 1960 FLOOD

AT RAPIDS, NEW YORK

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979



ELEVATION OF U. RESERVOIR
SPILLWAY

--- EXISTING CONDITIONS
--- POOL STAGE RESULTING
FROM OPERATING
UPPER RESERVOIR

THIS PLATE SHOWS THE
ELEVATION OF THE FLOOD IN
THE UPPER RESERVOIR AREA
FOR VARIOUS CONDITIONS.

$\Delta T = 3$ HRS.

499 ELEVATION IN FEET - U.S.C. & G.S. DATUM

SEPTEMBER, 1977

DATE AT NOON


TONAWANDA CREEK WATERSHED, N. Y.


UPPER RESERVOIR

SEPT., 1977 FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979





EXISTING CONDITIONS
 UPPER RESERVOIR ONLY
 BATAVIA RESERVOIR COMPOUND

ELEVATION OF LOWER
 RESERVOIR SPILLWAY

THIS PLATE SHOWS THE ELEVATION
 OF THE FLOOD IN THE LOWER
 RESERVOIR AREA FOR VARIOUS
 CONDITIONS

$\Delta T = 3$ HRS

SEPTEMBER, 1977

DATE AT NOON

TONAWANDA CREEK WATERSHED, N. Y.

LOWER RESERVOIR


SEPT., 1977 FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED 1978


PLATE A66

ELEVATION IN FEET - U.S.C.G.S. DATUM



46 1930

K-E 10 X 12 TO THE INCH •
KELFEL & ESSER CO. NEW YORK, N. Y.



TONAWANDA CREEK WATERSHED, N. Y.

UPPER RESERVOIR

MARCH, 1978 FLOOD

DISCHARGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

--- EXISTING CONDITIONS
 --- POOL STAGE RESULTING
 FROM OPERATING
 UPPER RESERVOIR

THIS PLATE SHOWS THE
 ELEVATION OF THE FLOOD
 IN THE UPPER RESERVOIR
 AREA FOR VARIOUS CONDITIONS

ELEVATION OF U. RESERVOIR
 SPILLWAY

AT 3 HRS

PLATE A68

DATE: 11:00 AM

MARCH, 1978


TONAWANDA CREEK WATERSHED, N. Y.


UPPER RESERVOIR

MARCH, 1978 FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979





TONAWANDA CREEK WATERSHED, N. Y.

LOWER RESERVOIR

MARCH, 1978 FLOOD

DISCHARGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

EXISTING CONDITIONS
 UPPER RESERVOIR ONLY
 BATAVIA RESERVOIR COMPOUND

ELEVATION OF LOWER
 RESERVOIR SPILLWAY

THIS PLATE SHOWS THE ELEVATION
 OF THE FLOOD IN THE LOWER
 RESERVOIR AREA FOR VARIOUS
 CONDITIONS

$\Delta T = 3$ HRS


MARCH, 1978

DATE AT NOON

TONAWANDA CREEK WATERSHED, N. Y.
 LOWER RESERVOIR
 MARCH, 1978 FLOOD
 STAGE HYDROGRAPHS
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979

ELEVATION IN FEET - U.S.C.G.S DATUM

16 17 18 19 20 21 22 23 24 25 26 27




TONAWANDA CREEK WATERSHED, N. Y.
MARCH, 1978 FLOOD
DISCHARGE HYDROGRAPHS
DNSTR. FROM CONFLUENCE
WITH LEDGE CREEK
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979



PLATE A71a

46 1020

K-E 10 X 10 TO 5/8 INCH • 11 X 11 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.



TONAWANDA CREEK WATERSHED, N. Y.


UPPER RESERVOIR


S P F

AT ALEXANDER

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

PLATE A72





Local SPF for Little Tonawanda

30

DISCHARGE IN THOUSANDS OF C.F.S.

20

10

0

0 2 4 6 8 10 12 14 16 18 20 22 24 26 28 30 32 34 36 38 40

ROUTING PERIOD

TONAWANDA CREEK WATERSHED, N. Y.

LOCAL SPF FOR LITTLE


TONAWANDA CREEK

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

46 1020

K-E 10 X 10 TO 5 1/2 INCH • KEUFFEL & ESSER CO. BALTIMORE, MD.

DISCHARGE IN THOUSANDS OF C.F.S.



TONAWANDA CREEK WATERSHED, N. Y.


LOWER RESERVOIR


SPF


AT BATAVIA

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

PLATE A







THIS PLATE SHOWS THAT THE FAILURE OF THE UPPER AND LOWER DAMS HAS NO EFFECT UPON THE SPF UNDER PROJECT CONDITIONS WITHOUT FAILURE. IT IS ALSO NOTED THAT SPF PEAK ELEVATION WITH AND WITHOUT THE PROJECT IS ABOUT THE SAME AND DOES NOT AGGRAVATE THE DAMAGES IN BATAVIA.

TONAWANDA CREEK WATERSHED, N. Y.
SPF DAM FAILURE
STAGE HYDROGRAPHS AT
BATAVIA GAGE
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979


AD-A133 910


BUFFALO METROPOLITAN AREA NEW YORK WATER RESOURCES
MANAGEMENT INTERIM REP. (U) CORPS OF ENGINEERS BUFFALO
NY BUFFALO DISTRICT JUL 83

3/9

UNCLASSIFIED

F/G 13/2 NL






MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A


46 1020

K-E 10 X 10 TO 5/8 INCH • KEUFFEL & ESSER CO. • NEW YORK, N. Y.



LOCAL SPF FROM MURDER - LEDGE CREEK

DISCHARGE IN THOUSANDS OF C.F.S.



TONAWANDA CREEK WATERSHED, N. Y.


LOCAL SPF FROM

MURDER - LEDGE CREEK


U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

46 1020

K-E 10 X 10 TO 5/16 INCH • KEUFFEL & ESSER CO. NEW YORK, N.Y.




Depth-Area Curves for Probable Maximum Storm Index
 Note: Use For Tonawanda Creek Watershed Only




TONAWANDA CREEK WATERSHED, N. Y.
 DEPTH - AREA - DURATION
 CURVES FOR PROBABLE
 MAXIMUM STORM INDEX
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979

PROBABLE MAXIMUM STORM TIME DISTRIBUTION PATTERNS


PATTERN #1




PATTERN #3




PATTERN #5



PATTERN #2



PATTERN #4



TONAWANDA CREEK WATERSHED, N. Y.


PROBABLE MAXIMUM

STORM TIME

DISTRIBUTION PATTERNS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1978

DISCHARGE IN THOUSANDS OF C.F.S.



TONAWANDA CREEK WATERSHED, N. Y.

UPPER RESERVOIR
PMF
AT ALEXANDER

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

PLATE A78


TONAWANDA CREEK WATERSHED, N. Y.


UPPER RESERVOIR


PROBABLE MAXIMUM FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1978







TONAWANDA CREEK WATERSHED, N. Y.

LOCAL PMF HYDROGRAPH

AT

LITTLE TONAWANDA CREEK


U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

PLATE A7

46 1240

K&E
20 X 20 TO THE INCH - 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.

DISCHARGE IN THOUSANDS OF C.F.S.




TONAWANDA CREEK WATERSHED, N. Y.

LOWER RESERVOIR

PMF

AT BATAVIA

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979



TONAWANDA CREEK WATERSHED, N. Y.

LOWER RESERVOIR

PROBABLE MAXIMUM FLOOD

STAGE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED 1979

DISCHARGE IN THOUSANDS OF CFS

100

90

80

70

60

50

40

30

20

10

OUTFLOW W/O
FAILURE -

DAM FAILURE
HYDROGRAPH

30

40

50

TIME IN HOURS

DAM FAILURE PARAMETERS:

BR WIDTH = 40 FT.

Z = 0.0

EL BM = 893.8 FT.

T FAIL = 0.5 HOURS

FAILED = 900 FT. (SPILLWAY
CREST)

60

70

TONAWANDA CREEK WATERSHED, N. Y.

LOWER RESERVOIR PMF
FAILURE HYDROGRAPHS

U.S. ARMY ENGINEER DISTRICT, BUFFALO

PLATE A 80

461240



K-E 20 X 20 TO THE INCH, 1/4" X 1/4" DIMENSIONS
REPRODUCED BY THE U.S. ARMY ENGINEER DISTRICT, BUFFALO

PLATE A80C

46 1240
ELEVATION IN FEET - U.S.C. & G.S. DATUM



16 18 20 22

TONAWANDA CREEK WATERSHED, NEW YORK


**BATAVIA RESERVOIR COMPOUND
UPPER RESERVOIR
AREA-CAPACITY CURVES**


U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

46 1240

K-E
20 X 20 TO THE INCH, 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.

ELEVATION IN FEET, U.S.C. & G.S. DATUM







TONAWANDA CREEK WATERSHED, N. Y.


UPPER RESERVOIR STAGE-DISCHARGE CURVES

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979




TONAWANDA CREEK WATERSHED, NEW YORK
 STAGE-DISCHARGE CURVE
 U.S. FACE CAMPBELL BLVD BR
 TONAWANDA CREEK
 AT RIVER MILE 8.8
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979





TONAWANDA CREEK WATERSHED, NEW YORK
STAGE-DISCHARGE CURVE
AT RAPIDS ROAD GAGE
TONAWANDA CREEK
AT RIVER MILE 18.5
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979




TONAWANDA CREEK WATERSHED, NEW YORK
 STAGE - DISCHARGE CURVE
 AT HOPKINS ROAD GAGE
 TONAWANDA CREEK
 INDEX POINT T-10 AT MILE 41.5
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979


K-E PROBABILITY X 90 DIVISIONS
KEUFFEL & ESSER CO. MADE IN U.S.A.

46 8000

RECURRANCE INTERVAL IN YEARS



TONAWANDA CREEK WATERSHED, NEW YORK
 STAGE-FREQUENCY CURVE
 AT HOPKINS ROAD GAGE
 TONAWANDA CREEK
 INDEX POINT T-10 AT MILE 41.5
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979



TONAWANDA CREEK WATERSHED, NEW YORK


STAGE-FREQUENCY CURVES

TONAWANDA CREEK

INDEX POINT T-2 AT MILE 8.9

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979



TONAWANDA CREEK WATERSHED, NEW YORK


STAGE-FREQUENCY CURVES


TONAWANDA CREEK


INDEX POINT T-3 AT MILE 12.8

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979







TONAWANDA CREEK WATERSHED, NEW YORK

STAGE-FREQUENCY CURVES

TONAWANDA CREEK

INDEX POINT T-6 AT MILE 22.8

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979

REQUIREMENT INTERVAL IN YEARS

ROUTING WERE NOT ACCOMPLISHED FOR FLOODS GREATER THAN 500-YR (EXCEPT SPE). THE EFFECT OF THE RESERVOIRS WILL DECREASE FOR LARGER FLOOD EVENTS AS INDICATED BY THE EXTRAPOLATED CURVES (DASHED LINES).

EXISTING CONDITIONS

UPPER RESERVOIR ONLY

RESERVOIR COMPOUND

0' DAMAGE

TONAWANDA CREEK WATERSHED, NEW YORK

STAGE-FREQUENCY CURVES

TONAWANDA CREEK

INDEX POINT T-7 AT MILE 28.0


U.S. ARMY ENGINEER DISTRICT, BUFFALO


TO ACCOMPANY REPORT DATED: 1979

EXCEEDENCE FREQUENCY IN PERCENT

ELEVATION IN FEET - U.S.C.G.S. DATUM

KEUFFEL & ESSER CO. 46 6210
5 CYCLES X 70 DIVISIONS
MADE IN U. S. A.





TONAWANDA CREEK WATERSHED, NEW YORK


STAGE-FREQUENCY CURVES


TONAWANDA CREEK


INDEX POINT T-10 AT MILE 41.5

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979







RECURRENT INTERVAL IN YEARS

500 200 100 50 20 10 5 2

5930

5920

5910

5900

5890

ELEVATION IN FEET - USCG DATUM

SPF

EXISTING CONDITIONS

UPPER RESERVOIR ONLY

RESERVOIR COMPOUND

1960

NO DAMAGE

100

EXCEEDENCE FREQUENCY IN PERCENT

10 1 0.1

ROUTING WERE NOT ACCOUNTABLE FOR
FLOODS GREATER THAN 500-YR (EXCEPT
SPF) THE EFFECT OF THE RESERVOIRS
WILL DECREASE FOR LARGER FLOOD EVENTS
AS INDICATED BY THE EXTRAPOLATED
CURVES (DASHED LINES).

TONAWANDA CREEK WATERSHED, NEW YORK


STAGE-FREQUENCY CURVE

MUD CREEK

INDEX POINT M-3 AT MILE 7.0

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979



TONAWANDA CREEK WATERSHED, NEW YORK

STAGE-FREQUENCY CURVE


MUD CREEK

INDEX POINT M-4 AT MILE 10.8

U.S. ARMY ENGINEER DISTRICT, BUFFALO

30 ACCOMPANY REPORT DATED: 1979

K \div E SEMI-LOGARITHMIC
5 CYCLES X 70 DIVISIONS
46 6210
MADE IN U.S.A.
KRUFFEL & ESSER CO.



CONAWANDA CREEK WATERSHED, NEW YORK

STAGE-FREQUENCY CURVE

MUD CREEK

INDEX POINT M-5 AT MILE 12.5

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

RECURRENT INTERVAL IN YEARS

500 200 100 50 20 10 5

6080

6060

6040

6020

ELEVATION IN FEET - U.S. & C.S. DATUM

EXISTING CONDITIONS

SPF

UPPER RESERVOIR ONLY

RESERVOIR COMPLETION

0' DRAINAGE

RAINFALLS WERE NOT ACCOMPANIED BY
FLOODS GREATER THAN 500 YEAR
EVENTS AND THE EFFECT OF THE
RESERVOIR WILL DECREASE FOR
LARGER FLOOD EVENTS AS INDICATED
BY THE FUTURE DOTTED CURVES
(DOTTED LINES)

TONAWANDA CREEK WATERSHED, NEW YORK

STAGE-FREQUENCY CURVE

MUD CREEK


INDEX POINT M-6 AT MILE 15.1


U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979


EXCEEDENCE FREQUENCY IN PERCENT

10 1 0.1





KE SEMI-LOGARITHMIC 46 6210
5 CYCLES X 70 DIVISIONS
MADE IN U.S.A.
KEUFFEL & ESSER CO.




TONAWANDA CREEK WATERSHED, NEW YORK

STAGE-FREQUENCY CURVES

RANSOM AND BLACK CREEKS
INDEX POINT RB-1 AT MILE 2.4

U.S. ARMY ENGINEER DISTRICT, SUFFALO
10 ACCOMPANY REPORT DATED: 1979



TOWAWANDA CREEK WATERSHED, NEW YORK


STAGE-FREQUENCY CURVES


RANSOM AND BLACK CREEKS


INDEX POINT RB-2 AT MILE 4.9

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979









EXCEEDENCE FREQUENCY IN PERCENT

TONAWANDA CREEK WATERSHED, NEW YORK
 PEAK DISCHARGE-
 FREQUENCY CURVES
 AT HOPKINS ROAD GAGE
 TONAWANDA CREEK
 INDEX POINT T-10 AT MILE 41.5
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979

PLATE A112



TONAWANDA CREEK WATERSHED, NEW YORK
STAGE-DISCHARGE CURVE
 TONAWANDA CREEK
 AT BATAVIA GAGE
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1970



2/6

TONAWANDA CREEK WATERSHED, NEW YORK

STAGE-DISCHARGE CURVE


TONAWANDA CREEK

INDEX POINT T-12 AT MILE 60.3

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1978

DISCHARGE IN THOUSANDS OF C.F.S.



TONAWANDA CREEK WATERSHED, NEW YORK

STAGE - DISCHARGE CURVE


TONAWANDA CREEK


INDEX POINT B-1 AT MILE 63.4

UPSTREAM FACE OF SO. LYON ST. BRIDGE

U.S. ARMY ENGINEER DISTRICT, BUFFALO


TO ACCOMPANY REPORT DATED: 1979





461240

K-E 20 X 20 TO THE INCH
KEIFFEL & ESSER CO. NEW YORK



TONAWANDA CREEK WATERSHED, NEW YORK

STAGE-DISCHARGE CURVE


TONAWANDA CREEK


INDEX POINT T-13 AT MILE 65.5


UPSTREAM FACE OF L.V.R.R. BRIDGE

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979







TONAWANDA CREEK WATERSHED, NEW YORK

STAGE - DISCHARGE CURVE


TONAWANDA CREEK

INDEX POINT A-3 AT MILE 82.4

UPSTREAM FACE OF MAIN ST. BRIDGE

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979




TONAWANDA CREEK WATERSHED, NEW YORK

PEAK DISCHARGE-
FREQUENCY CURVES
AT BATAVIA GAGE
TONAWANDA CREEK

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

EXCEEDENCE FREQUENCY IN PERCENT

PLATE 5122



TONAWANDA CREEK WATERSHED, NEW YORK


STAGE-FREQUENCY CURVES

TONAWANDA CREEK

INDEX POINT T-II AT MILE 52.5

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979



TONAWANDA CREEK WATERSHED, NEW YORK


STAGE-FREQUENCY CURVES


TONAWANDA CREEK


INDEX POINT T-12 AT MILE 60.3


U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979










K-E PROBABILITY X 90 DIVISIONS
KEUFFEL & ESSER CO. MADE IN U.S.A.

46 8000

RECUERRENCE INTERVAL IN YEARS

99.9 99.8 200 100 50 20 10 5 2 1 0.5 0.2 0.1 0.05 0.01



TONAWANDA CREEK WATERSHED, NEW YORK
STAGE-FREQUENCY CURVES
TONAWANDA CREEK
INDEX POINT A-1 AT MILE 78.0
UPSTREAM FACE OF RAILROAD AVE. BR.
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979

K-E PROBABILITY X 90 DIVISIONS
KEUFFEL & ESSER CO. MADE IN U.S.A.

46 8000

RECURRENT INTERVAL IN YEARS

200 100 50 20 10 5

99.9 99.8 99.5 99.0 98.5 98.0 97.5 97.0 96.5 96.0 95.5 95.0 94.5 94.0 93.5 93.0 92.5 92.0 91.5 91.0 90.5 90.0 89.5 89.0 88.5 88.0 87.5 87.0 86.5 86.0 85.5 85.0 84.5 84.0 83.5 83.0 82.5 82.0 81.5 81.0 80.5 80.0 79.5 79.0 78.5 78.0 77.5 77.0 76.5 76.0 75.5 75.0 74.5 74.0 73.5 73.0 72.5 72.0 71.5 71.0 70.5 70.0 69.5 69.0 68.5 68.0 67.5 67.0 66.5 66.0 65.5 65.0 64.5 64.0 63.5 63.0 62.5 62.0 61.5 61.0 60.5 60.0 59.5 59.0 58.5 58.0 57.5 57.0 56.5 56.0 55.5 55.0 54.5 54.0 53.5 53.0 52.5 52.0 51.5 51.0 50.5 50.0 49.5 49.0 48.5 48.0 47.5 47.0 46.5 46.0 45.5 45.0 44.5 44.0 43.5 43.0 42.5 42.0 41.5 41.0 40.5 40.0 39.5 39.0 38.5 38.0 37.5 37.0 36.5 36.0 35.5 35.0 34.5 34.0 33.5 33.0 32.5 32.0 31.5 31.0 30.5 30.0 29.5 29.0 28.5 28.0 27.5 27.0 26.5 26.0 25.5 25.0 24.5 24.0 23.5 23.0 22.5 22.0 21.5 21.0 20.5 20.0 19.5 19.0 18.5 18.0 17.5 17.0 16.5 16.0 15.5 15.0 14.5 14.0 13.5 13.0 12.5 12.0 11.5 11.0 10.5 10.0 9.5 9.0 8.5 8.0 7.5 7.0 6.5 6.0 5.5 5.0 4.5 4.0 3.5 3.0 2.5 2.0 1.5 1.0 0.5 0.2 0.1 0.05 0.01

SPF 46.561.0

9590

9580

9570

9560

9550

9540

9530

9520

9510

ELEVATION IN FEET - USC & GS DATUM

EXISTING CONDITIONS

1960

"0" DAMAGE

EXCEEDENCE FREQUENCY IN PERCENT

TONAWANDA CREEK WATERSHED, NEW YORK

STAGE-FREQUENCY CURVES

TONAWANDA CREEK


INDEX POINT A-2 AT MILE 81.6

UPSTREAM FACE OF PROSPECT ST. BR.

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATED: 1979

PLATE A130



BUFFALO METROPOLITAN AREA, NY
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

APPENDIX B

EVALUATION OF

FLOOD DAMAGES AND BENEFITS

U. S. Army Engineer District, Buffalo
1776 Niagara Street
Buffalo, New York 14207

APPENDIX B
EVALUATION OF FLOOD DAMAGES AND BENEFITS

TABLE OF CONTENTS

<u>Item</u>	<u>Description</u>	<u>Page</u>
B1	THE AFFECTED AREA	B-1
B2	PROJECTED DEMOGRAPHIC AND ECONOMIC ACTIVITIES IN THE AFFECTED AREA	B-5
	a. Population	B-5
	(1) Buffalo Standard Metropolitan Area	
	(2) Rochester Standard Metropolitan Area	
	b. Employment	B-8
	(1) Erie and Niagara County	
	(2) Genesee and Wyoming Counties	
	(3) Commercial Employment	
	(4) Manufacturing Employment	
	c. Agricultural Earnings and Output	B-20
	d. Per Capita Income	B-22
B3	PROJECTED LAND USE DEMAND IN THE AFFECTED AREA	B-26
	a. Residential Demand	B-26
	(1) Buffalo Standard Metropolitan Area	
	(2) Genesee and Wyoming Counties	
	b. Commercial Use Demand	B-28
	(1) Buffalo Standard Metropolitan Area	
	(2) Genesee and Wyoming Counties	
	c. Industrial Use Demand	B-30
	(1) Buffalo Standard Metropolitan Area	
	(2) Genesee and Wyoming Counties	
	d. Agricultural Use Demand	B-33
B4	FLOODING AND PHYSICAL CHARACTERISTICS	B-35
	a. Flooding Characteristics	B-35
	(1) Damages from Past Floods	
	(2) Extent of Flooding	
	(3) Existing Use of the Flood Plain	

TABLE OF CONTENTS (Cont'd)

<u>Item</u>	<u>Description</u>	<u>Page</u>
	b. Physical Characteristics of the Flood Plain	B-38
	(1) Physiography	
	(2) Soils	
	(3) Water Resources	
	(a) Groundwater Resources	
	(b) Surface Water Resources	
	(4) Vegetation	
	(5) Climate	
	(6) Water Transportation	
	c. Available Services	B-46
	(1) Canal System	
	(2) Highways	
	(3) Railroads	
	(4) Water Supply and Waste Treatment	
	d. Existing Activities	B-52
B5	PROJECTED LAND USE WITHIN THE FLOOD PLAINS	B-54
B6	URBAN FLOOD DAMAGE AND MANAGEMENT BENEFITS	B-58
	a. Flood Damage Reduction	B-58
	(1) Damage Reaches	
	(2) Damage Surveys	
	(3) Flood Damage	
	(a) Methodology	
	(b) Residential	
	(c) Commercial and Industrial	
	(d) Public and Other	
	(4) Stage Damage Relationships	
	(5) Existing Average Annual Damages	
	(6) Average Annual Damages, Improved Conditions	
	(7) Average Annual Innundation Reduction Benefits	
	b. Area Redevelopment Benefits	B-71
	c. Project Year One (1985) Conditions of Development	B-71
	(1) Urban Development in the Tonawanda Creek Watershed	
	(2) Innundation Reduction Damages and Benefits	
	(3) Urban Damage and Benefits for 1985 Development Conditions	
	d. Future Development Conditions	B-75
	(1) Innundation Reduction Effects	
	(2) Affluence Factor Benefits	
	(3) Site Development Benefits	
	e. Summary of Total Urban Benefits	B-83

TABLE OF CONTENTS (Cont'd)

<u>Item</u>	<u>Description</u>	<u>Page</u>
B7	AGRICULTURAL FLOOD DAMAGE AND MANAGEMENT BENEFITS	B-84
	a. Sources	B-84
	b. General Agricultural Characteristics	B-84
	(1) Agricultural Land Use	
	(2) Crop Yields	
	(3) Crop Prices	
	c. Existing Average Annual Damages and Benefits	B-96
	(1) Projected Growth of Agricultural Inundation Damages	
	(2) Average Annual Agricultural Damages, Existing Conditions	
	(3) Average Annual Agricultural Damages, Improved Conditions	
	(4) Average Annual Equivalent Agricultural Benefits, Existing Conditions	
	d. Future Agricultural Land Use Benefits	B-101
	(1) Future Land Use	
	(2) Intensified Management	
	(3) Intensified Farm Schedules	
	(4) Future Agricultural Benefits	
	e. Summary of Agricultural Benefits	B-109
	f. Sensitivity Analysis	B-111
B8	ECONOMIC EFFICIENCY	B-113

TABLES

<u>No.</u>	<u>Title</u>	<u>Page</u>
B1	Tonawanda Creek Watershed Historical Population of Political Subdivisions	B-3
B2	Historical Population Trends for Selected Areas	B-5
B3	Demographic Statistics Population, Rank, Density, and Area of Selected Counties	B-6
B4	Standard Metropolitan Statistical Areas Historical Population Shifts in Buffalo and Rochester	B-7

TABLE OF CONTENTS (Cont'd)

TABLES (Cont'd)

<u>No.</u>	<u>Title</u>	<u>Page</u>
B5	Projected Population for Selected Areas	B-9
B6	Projections of Population and Employment for Selected Areas	B-10
B7	Distribution of Manufacturing Employment in Genesee County	B-11
B8	Manufacturing Employment Value Added and Employment Statistics for Selected Counties	B-12
B9	Industrial Statistics for Selected Industry Groups in Genesee & Wyoming Counties	B-13
B10	Historical and Projected Manufacturing Employment in Genesee and Wyoming Counties	B-14
B11	Retail Trade Statistics - Change in Retail Trade for Selected Areas	B-15
B12	Commercial Employment	B-16
B13	Future Commercial Employment - Buffalo SMSA	B-17
B14	Future Commercial Employment Genesee & Wyoming Counties	B-18
B15	Industrial Employment - Buffalo SMSA	B-19
B16	Estimated Manufacturing Employment - Buffalo SMSA	B-19
B17	Current Employment in the Buffalo Labor Area	B-20
B18	Agricultural Earnings Projected Agricultural Earnings to 2030	B-21
B19	Agricultural Output - Value of Products Sold by County	B-23
B20	Agricultural Activity Number of Farms, Acreage and Value of Land & Buildings - 1969	B-24
B21	Per Capita Income	B-25
B22	Future Residential Land Use Demand in the Buffalo SMSA	B-27

TABLE OF CONTENTS (Cont'd)

TABLES (Cont'd)

<u>No.</u>	<u>Title</u>	<u>Page</u>
B23	Commercial Land Use Demand in the Buffalo SMSA	B-29
B24	Land in Farms Projected Farmlands in New York State	B-34
B25	Estimated Damages that Recurrences of the 1942, 1956, and 1960 Floods Would Cause Now, December 1975 Prices and Development	B-36
B26	Flood Plain Soil Characteristics	B-41
B27	New York State Barge Canal Annual Tonnage for Selected Years	B-46
B38	Water Treatment Facilities for Selected Areas	B-49
B29	Sanitary Sewage Systems for Selected Areas	B-51
B30	Acreages and Land Use in the Intermediate Regional Flood Plains	B-53
B31	Projected Incremental Land Use Demand in the 100-Year Flood Plain 1980-2030	B-56
B32	Damage Reaches	B-59
B33	Approximate Number of Units and Acres Affected 1975 Conditions of Development	B-61
B34	Estimated Damages for Floods of Various Frequencies Total Residential Damage	B-62
B35	Estimated Average Annual Damages, Existing Conditions By Reach, (December 1975 Development Conditions and Prices)	B-64
B36	Estimated Average Annual Damages, Existing Conditions By Reach, June 1981 Prices and December 1975 Conditions of Development	B-65
B37	Estimated Existing Average Annual Damages and Benefits (December 1975 Development Conditions and Prices)	B-67

TABLE OF CONTENTS (Cont'd)

TABLES (Cont'd)

<u>No.</u>	<u>Title</u>	<u>Page</u>
B38	Estimated Existing Average Annual Damages and Benefits (December 1975 Development Conditions and June 1981 Prices)	B-69
B39	Average Annual Urban Damages and Benefits, 1976-1985, June 1981 Prices	B-76
B40	Summary of Urban Damages and Benefits for 1985 Conditions of Development (June 1981 Prices)	B-77
B41	Projected Demand for Urban Lands	B-78
B42	Average Annual Residential Affluence Factor Benefits (June 1981 Prices)	B-80
B43	Summary of Affluence Factor Benefits (June 1981 Prices)	B-81
B44	IRF Stage Reduction for Selected Reaches	B-82
B45	Summary of Total Urban Benefits (June 1981 Prices)	B-83
B46	Distribution of Crops, by Acre	B-86
B47	Crop Yields of Principal Crops Grown on the Flood Plain	B-87
B48	Prices of Principal Crops Grown on the Tonawanda Creek Flood Plain	B-88
B49	Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: CORN SILAGE (1976 dollars per acre)	B-89
B50	Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: CORN GRAIN (1976 dollars per acre)	B-90
B51	Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: MIXED HAY (1976 dollars per acre)	B-91
B52	Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: WINTER WHEAT (1976 dollars per acre)	B-92

TABLE OF CONTENTS (Cont'd)

TABLES (Cont'd)

<u>No.</u>	<u>Title</u>	<u>Page</u>
B53	Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: OATS (1976 dollars per acre)	B-93
B54	Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: BUCKWHEAT (1976 dollars per acre)	B-94
B55	Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: MISCELLANEOUS CROPS (1976 dollars per acre)	B-95
B56	Annual Agricultural Loss Calculation, Reach T-5	B-98
B57	Calculation of Average Annual Agricultural Damages, Reach T-5	B-99
B58	Summary of Existing Average Annual Equivalent Agricultural Damages and Benefits (1978 Land Use Patterns)	B-100
B59	Shift of Flood Plain Land to Higher Use	B-102
B60	Future (Shifted) Distribution of Crops, by Acre	B-103
B61	Monthly Schedule of Intensified Farm Activities, Production Costs, Revenue and Crop Loss Values: CORN SILAGE (1976 dollars per acre)	B-104
B62	Monthly Schedule of Intensified Farm Activities, Production Costs, Revenue and Crop Loss Values: CORN SILAGE (1976 dollars per acre)	B-105
B63	Monthly Schedule of Intensified Farm Activities, Production Costs, Revenue and Crop Loss Values: MIXED HAY (1976 dollars per acre)	B-106
B64	Monthly Schedule of Intensified Farm Activities, Production Costs, Loss Values: MIXED HAY (1976 dollars per acre)	B-107
B65	Monthly Schedule of Intensified Farm Activities, Production Costs, Revenue and Crop Loss Values: OATS (1976 dollars per acre)	B-108

TABLE OF CONTENTS (Cont'd)

TABLES (Cont'd)

<u>No.</u>	<u>Title</u>	<u>Page</u>
B66	Future Agricultural Benefits (June 1981 Prices)	B-109
B67	Summary of Average Annual Agricultural Benefits (June 1981 Prices)	B-110
B68	Summary Values for Composite Acre	B-110
B69	Comparison of Agricultural Benefits Varying Secular Growth (June 1981 Prices, 7-5/8 Percent Interest Rate)	B-112
B70	Summary of Total Benefits June 1981 Prices, 7-5/8 Percent Interest Rate 1985 Conditions of Development	B-114

PLATES

<u>No.</u>	<u>Title</u>
B1	Political Subdivisions
B2	Existing Land Use
B3	Huron Plain Floodland (Lower Watershed)
B4	Floodland in the City of Batavia and Downstream Vicinity
B5	Erie Plain Floodland (Upper Watershed)
B6	Highways
B7	Proposed Conrail and Chessie Rail Lines in New York State
B8	Rail Lines in Western New York
B9	Stage Damage Curves Reach T-1
B10	Stage Damage Curves Reach T-2
B11	Stage Damage Curves Reach T-3
B12	Stage Damage Curves Reach T-4
B13	Stage Damage Curves Reach T-5
B14	Stage Damage Curves Reach T-6

TABLE OF CONTENTS (Cont'd)

PLATES (Cont'd)

<u>No.</u>	<u>Title</u>
B15	Stage Damage Curves Reach T-7
B16	Stage Damage Curves Reach T-8
B17	Stage Damage Curves Reach T-9
B18	Stage Damage Curves Reach T-10
B19	Stage Damage Curves Reach M-1
B20	Stage Damage Curves Reach M-2
B21	Stage Damage Curves Reach M-3
B22	Stage Damage Curves Reach M-4
B23	Stage Damage Curves Reach M-5
B24	Stage Damage Curves Reach M-6
B25	Stage Damage Curves Reach RB-1
B26	Stage Damage Curves Reach RB-2
B27	Stage Damage Curves Reach RB-3
B28	Stage Damage Curves Reach RB-4
B29	Stage Damage Curves Reach T-11
B30	Stage Damage Curves Reach T-12
B31	Stage Damage Curves Reach B-1
B32	Stage Damage Curves Reach B-2
B33	Stage Damage Curves Reach B-3
B34	Stage Damage Curves Reach B-4
B35	Stage Damage Curves Reach B-5
B36	Stage Damage Curves Reach T-13
B37	Stage Damage Curves Reach A-1
B38	Stage Damage Curves Reach A-2
B39	Stage Damage Curves Reach A-3

81. THE AFFECTED AREA

The area affected by the proposed Tonawanda Creek flood damage management project consists of the flood plain plus all other areas likely to serve as alternative sites for any activity which might use the flood plain if it were protected. Determination of the affected areas for this flood management study was based upon an analysis of existing development in the Tonawanda Creek Watershed which provided an insight to potential future uses of the flood plain.

The Tonawanda Creek Watershed, an area of approximately 648 square miles, is located in western New York and includes substantial portions of Erie, Niagara, Genesee and Wyoming Counties in addition to a minor part of Orleans County. The political subdivisions of the watershed, in addition to climatological and hydrologic stations, are shown on Plate B1. Economic growth in the Buffalo urban area, originally stimulated by Buffalo's historical geographic position as a break-bulk transshipment point for Great Lakes cargo, has induced considerable development in the western portion of the watershed. Towns and villages that were once outside Buffalo have lost their separate identity as suburbanization has spread outward from the city. Development of improved waterway and highway transportation networks has accelerated this expansion and transformed outlying semi-rural areas such as Amherst and Clarence, NY, into growing suburban communities. Analysis of past and present trends indicates that the process of conversion of agricultural and vacant land into residential land use is spreading to the northeast and east of Buffalo, NY, in Erie County. A significant factor in establishing these trends was the major highway construction of the 1960's which reduced the commuting times significantly to the major employment centers.

Much of the western portion of the watershed is directly in the path of these growth corridors. Vacant land in the Ellicott and Tonawanda Creek flood plains is now under pressure to develop into residential subdivisions. The new State University campus and two planned communities in Amherst are already inside flood hazard zones. These developments should act as nodal points for future development in Amherst. Lands in the northern portions of Amherst and Clarence adjacent to Tonawanda Creek consist of idle vacant land with minimal vegetative cover or lands actively farmed, either on a full or part-time basis. Large amounts of open farmland have already been taken out of production in this area as a result of land speculation.

The Buffalo Metropolitan Area is the largest industrial and commercial center in Upstate New York. Its highway network, large supply of skilled labor, access to raw materials, ample electric power, and ready access to markets in the northeast, midwest, and Canada have all contributed to the region's economic development. Almost all of the development in the western portion of the watershed can be attributed to growth in the Buffalo Metropolitan Area. Remaining areas of the watershed are primarily agricultural, however, the Tonawanda Indian Reservation and three extensive wildlife refuges also occupy areas of significant size near the center of the watershed. A secondary manufacturing, commercial and institutional growth center in the watershed

is the city of Batavia, located in Genesee County. Table B1 lists the major population centers, by county, in the watershed.

Existing land use patterns in the Tonawanda Creek flood plain and adjacent areas are depicted in Plate B2. Portions of the watershed included in Erie and Niagara Counties are coming under increasing pressure to accommodate the Buffalo urban area's demand for development of land: commercial, institutional, residential, recreation, and open space. Future estimates of the outer limits of the Buffalo Metropolitan Area have been liberally estimated by regional and local planning agencies to extend outward to the eastern boundary of the town of Clarence, about 13 miles from the center of Buffalo. The area included within a 13-mile radius of the Buffalo CBD also includes undeveloped acreage in other first and second-ring suburban towns which is less distant from the CBD than portions of Clarence or Amherst. These alternate areas are also expected to experience further population growth.

Land in Genesee and Wyoming Counties is used primarily for agriculture, although the manufacturing sector accounts for the largest portion of total employment. Almost 286,000 acres within the watershed, slightly less than 450 square miles, are farmlands. Of this amount, 108,000 acres are designated by State or regional planning agencies as high viability farmlands. High viability farmland is acreage which is extremely productive or suitable for cultivation of a crop which is of high quality and/or not easily produced elsewhere in the State. Several agricultural districts, formed in the upper reaches, should help to maintain the future of active agriculture and discourage the conversion of productive land into nonfarm uses.

Economic and social activity upstream of the Indian Reservation is concentrated in the city of Batavia. Batavia's geographic location midway between Rochester and Buffalo has been a major factor in its cultural and economic dominance of the area. Batavia is in the midst of a rich farm and industrial region and serves as a major center of motor freight service and is a growing wholesale distribution point. Growth in the Batavia area should continue at its present moderate rate. However, this expansion will probably occur outside the city limits but in the town of Batavia. Historically, when sufficient land was available, development was centered inside the city but the growing scarcity of open areas suitable for urban development will redirect future growth to areas outside the city limits.

The type and extent of social and economic activities within the flood plain indicates that the area affected by the proposed project would include Erie, Niagara, Genesee and Wyoming Counties. Any activity which might locate in the lower Tonawanda Creek flood plain (Erie and Niagara Counties) would have many locational options available in either county. Therefore, the two county Buffalo SMSA was designated as the affected area for that portion of the watershed downstream of the Indian Reservation. The eastern part of the Tonawanda Creek Watershed is predominately agricultural with manufacturing and commercial activity centered in Batavia. Approximately 62 percent of the total area in Genesee and Wyoming Counties was actively used for agriculture in 1969. Since farm activities can be practiced over extensive areas of

Table B1 - Tonawanda Creek Watershed
Historical Population of Political Subdivisions

Towns	:	1940	:	1950	:	1960	:	1970
<u>Erie County</u>	:	:	:	:	:	:	:	:
City of Tonawanda	:	6,440	:	14,617	:	21,561	:	21,898
Town of Amherst	:	19,532	:	33,744	:	62,837	:	93,929
Town of Clarence	:	4,402	:	6,331	:	13,267	:	18,168
Town of Newstead	:	1,516	:	4,653	:	5,825	:	6,322
Town of Tonawanda	:	65,000	:	55,270	:	105,032	:	107,282
<u>Niagara County</u>	:	:	:	:	:	:	:	:
City of North Tonawanda	:	20,256	:	24,731	:	34,757	:	36,012
Town of Lockport	:	3,179	:	3,945	:	6,492	:	8,177
Town of Pendleton	:	1,516	:	1,815	:	3,589	:	4,733
Town of Royalton	:	4,626	:	5,297	:	6,585	:	7,375
Town of Wheatfield	:	3,060	:	4,720	:	8,008	:	9,722
<u>Genesee County</u>	:	:	:	:	:	:	:	:
City of Batavia	:	17,267	:	17,799	:	18,210	:	17,338
Town of Alexander	:	1,423	:	1,591	:	1,987	:	2,351
Town of Batavia	:	2,261	:	2,824	:	4,325	:	5,440
Town of Pembroke	:	2,391	:	2,866	:	3,451	:	3,959
Town of Alabama	:	1,763	:	1,766	:	1,931	:	1,872
<u>Wyoming County</u>	:	:	:	:	:	:	:	:
Town of Attica	:	2,387	:	5,722	:	5,781	:	6,171

SOURCE: Business Fact Book, Part 2, 1974 Edition, New York State
Department of Commerce

both counties, the two-county area was delineated as the affected area for agricultural activities upstream of the Tonawanda Indian Reservation.

Twenty-four percent of the 1970 population of the two upstream counties was located in the towns of Batavia and Attica - the remainder of the population resided in outlying towns or villages. This wide dispersion of the rural population indicates that the affected area for future residential activity should also consist of Genesee and Wyoming Counties. Commercial and industrial activity in the upper watershed is concentrated in the city of Batavia, therefore this city was delineated as the affected area for future commercial activity in Genesee and Wyoming Counties.

B2. PROJECTED DEMOGRAPHIC AND ECONOMIC ACTIVITIES IN THE AFFECTED AREA

Projections of demographic and economic activity within the affected area were assumed independent of any flood management project. The following characteristics were projected to 2030: population, employment, manufacturing employment, per capita income, commercial employment and agricultural output.

a. Population.

Historical population changes between 1920 and 1970 are presented in Table B2. Historical population shifts have served as the basis for projecting the level of future population. Numerous sources, including State and Federal agencies, have made projections of future population levels. Most of the counties, with the exception of Wyoming, have already been included for analysis by larger regional planning agencies such as the Erie and Niagara Counties Regional Planning Board (ENCRPB) and the Genesee/Finger Lakes Regional Planning Board. Countywide sewerage studies of Genesee and Wyoming Counties completed in 1970 were also major sources of information for future levels of economic activity in the area.

Table B2 - Historical Population Trends for Selected Areas (1)
(in Thousands)

	: 1920 :	1930 :	1940 :	1950 :	1960 :	1970
New York State	:10,385.6:	12,588.1:	13,479.1:	14,830.2:	16,782.3:	18,241.3
Erie County	: 634.7:	762.4:	798.4:	899.2:	1,064.7:	1,113.5
Town of Amherst	: 6.3:	13.3:	19.5:	33.7:	62.8:	93.9
Niagara County	: 118.7:	149.3:	160.1:	190.0:	242.3:	235.7
City of North Tonawanda	: 15.5:	19.0:	20.3:	24.7:	34.7:	36.0
Genesee County	: 38.0:	44.5:	44.5:	47.6:	54.0:	58.7
City of Batavia	: 11.6:	17.4:	17.3:	17.8:	18.2:	17.3
Wyoming County	: 30.3:	28.8:	31.4:	32.8:	34.8:	37.7
Town of Attica	: 0.7:	0.7:	3.1:	5.7:	5.8:	6.2
Village of Attica	: 2.0:	2.2:	2.4:	2.7:	2.8:	2.9

(1) Including institutions.

SOURCE: U. S. Bureau of the Census, material compiled by New York State Department of Commerce

Within the watershed, the area of greatest population change between 1960 and 1970 was Erie County, Table B3, while the highest rates and growth occurred in Genesee and Wyoming Counties. Population density within the watershed increases as one proceeds downstream to the creek's confluence with the Niagara River. Historically, the greatest population increase in the rural areas of the watershed has been centered in the village and town of Attica and the city of Batavia. Together these three municipal areas contributed between 21 percent and 33 percent of the combined population of Genesee and Wyoming Counties during the period 1920 to 1970.

Table B3 - Demographic Statistics
Population, Rank, Density,
and Area of Selected Counties

P o p u l a t i o n							:
County	April 1		:Change from April :			:Land Area in	
	1960	1970	:1960 to April 1970:	Number	Percent	Per Sq. Mile	Square Miles
Erie	1,064,688	1,113,491	48,803	+	4.6	1,052.	1,058
Niagara	242,269	235,720	-6,549	-	2.7	443.	532
Genesee	53,793	58,722	4,728	+	8.8	117.	501
Wyoming	34,793	37,688	2,895	+	8.3	63.	598

SOURCE: U. S. Bureau of Census, Census of Population, Material compiled by New York State Department of Commerce.

However, since 1940 the relative importance of these three population centers has declined. This trend has also been substantiated by a comprehensive sewage study for Wyoming County completed in 1970 which found a relatively constant population within the villages but population growth (between 1950 and 1970) outside these three urban centers. This trend is most likely attributed to the saturation of the land area contained within these three established towns. Future population growth can reasonably be expected to occur very near these three areas since most of the municipal facilities (sewer, water supply and storm water drainage systems) have already been installed.

Genesee and Wyoming Counties are under the economic umbrella of the Buffalo and Rochester SMSA's. These two economic centers had a combined population in 1970 of more than 2.3 million residents and provided employment for over 874,800 people. The effects of population growth in either or both of these SMSA's will impact on the watershed's residents. An understanding of historical population growth in these large SMSA's will provide an insight into the extent of future population growth anticipated for Genesee and Wyoming Counties.

Historically, the greatest increase in population has occurred in the Rochester SMSA located to the east of the watershed. A substantial population increase occurred in the Buffalo SMSA during the 1950's but population growth has subsequently leveled off to a three percent rise over the past decade, Table B4. Erie and Niagara Counties have experienced a pattern of change similar to other metropolitan areas. Population in the major cities declined (13 percent in the Buffalo and 16 percent in Niagara Falls), while smaller communities and unincorporated areas experienced large increases. After 1960, the population of the Rochester SMSA grew at a greater absolute and relative rate than the Buffalo area.

Table B4 - Standard Metropolitan Statistical Areas
Historical Population Shifts in Buffalo
and Rochester (in thousands)

	: 1900 :	1910 :	1920 :	1930 :	1940 :	1950 :	1960 :	1970
Buffalo SMSA	: 509 :	621 :	753 :	912 :	958 :	1,089 :	1,307 :	1,349
Total Change	: 112	132	159	46	131	218	42	
Percentage Change:	: 22%	21%	21%	5%	14%	20%	3%	
Rochester SMSA	: 383 :	456 :	519 :	595 :	613 :	675 :	801 :	962
Total Change	: 73	63	76	18	62	126	20	
Percentage Change:	: 19%	14%	15%	3%	10%	19%	20%	

SOURCE: New York State Statistical Yearbook - 1974, New York State
Department of Commerce.

(1) Buffalo Standard Metropolitan Area

The two county Buffalo SMSA had a 1970 population of 1,350,000. More than 80 percent of this total was located in Erie County which had a population density of 1,052 per square mile. This figure is twice the population density of Niagara County. Population in this SMSA is concentrated in an urban belt, which fronts on the Niagara River and Lake Erie, located along the western borders of Erie and Niagara Counties. The area's population center is the city of Buffalo which included 462,800 residents in 1970, or 42 percent of Erie County's population. The center of population is anticipated to shift into the first- and second-ring communities as the overall population of the metropolitan area remains the same. The city of Buffalo population is projected to decline to at least 400,000 by 1980, at the same time second- and third-ring towns will be growing in population. This population shift will place heavy demands for land in adjacent suburbs.

(2) Rochester Standard Metropolitan Area

The Rochester area borders on the southern shore of Lake Ontario in New York State's upstate heartland, encompassing two of the larger and

four of the smaller Finger Lakes. Among the upstate economic areas, it ranks first in income and second in population. The city of Rochester is the business and cultural hub of the region, but there are also several smaller commercial centers throughout the district. In 1970, the nine county Rochester Area included over 1,110,000 residents; 64 percent of these people lived in Monroe County. Between 1960 and 1970, population in the area grew by 18 percent, with Monroe County accounting for 126,000 of the overall increase of 173,000. Compared with upstate areas, Rochester ranked first in total growth and second in percentage growth. Monroe County led all other upstate counties in absolute growth and in population density.

Population projections developed by State and local agencies were reviewed and compared to Series E OBERS projections to determine the extent of deviation from baseline Series E data. Series E data was expressly developed by the Bureau of Economic Analysis for use by the Water Resources Council to satisfy a need for basic economic information by public agencies engaged in comprehensive planning for the use, management, and development of the nation's water and related resources.

Population levels for the Buffalo SMSA are based upon Series E data. Population projections prepared by other regional planning agencies were also compared with OBERS projections. However, in the year 2030 there was only a minimal difference between the most conservative and liberal estimates. Therefore, OBERS data was considered an accurate representation of the Buffalo SMSA's growth potential. Series E projections for the Rochester SMSA were also compared with New York State Office of Planning Services (NYSOPS) Demographic Projections for New York State (Revised 6/74). There was only a deviation of four percent from Series E data. NYSOPS data was also utilized by the Genesee/Finger Lakes Regional Planning Board for estimating future populations. Due to this slight deviation from Series E and the consistency gained by using the same statistical series for both major SMSA's, Series E data was the main source of baseline economic data for large economic areas.

Future population levels for Genesee County are based on revised NYSOPS projections. This series was revised downward in June 1974 and was recently referenced in Comprehensive Regional Development Plan published in June 1975 by the Genesee/Finger Lakes Regional Planning Board. Their region of study included Genesee County. NYSOPS was also the major source of data for projected economic activity within Wyoming County. Historical and projected population by decade is included in Table B5.

b. Employment.

(1) Erie and Niagara Counties

Future employment was derived by application of an employment-population ratio (EPR) to projected population levels. The EPR is defined as the percentage of the population within an area which is employed. The historical trend of the EPR in the Buffalo SMSA was used to guide the estimates of future employment levels. Future employment in Genesee County was developed using the predicted trend of the EPR for Subarea 0413 since several counties

Table B5 - Projected Population for Selected Areas

	1970	1980	1990	2000	2010	2020	2030
Genesee County	58,722	64,464	70,935	75,709	83,936	93,033	101,433*
City of Batavia (1):	17,338	19,706	20,350				
Town of Batavia (1):	5,440	8,460	11,550				
Wyoming County (4)	37,688	42,021	46,500	49,533	52,566	55,600	56,000*
Buffalo SMSA	1,350,597	1,319,400	1,370,200	1,419,600	1,470,450 ⁽²⁾	1,521,300	1,597,600 ⁽³⁾
Rochester SMSA	883,574	1,059,000	1,247,000	1,412,500	1,558,200 ⁽²⁾	1,703,900	1,840,212 ⁽³⁾

* Data extended to 2030 based upon historical trend and planned extensions of municipal services into portions of the country.

(1) Data developed by Batavia Area Planning Board

(2) Interpolated value

(3) Estimated value based on observed historical trend

(4) Data for 1980 based on NYSOPS revised data; 1990 and 2020 data based on County Comprehensive Sewerage Study - 1970 (Teetor-Dobbins Consulting Engineers, Rochester, NY); other points represent interpolated or extrapolated values.

Table B6 - Projections of Population and Employment for Selected Areas

	Actual :		Projected							
	1970	1980	1990	2000	2010 (1)	2020	2030 (2)			
Population in Buffalo SMSA	1,350,597	1,319,400	1,370,200	1,419,600	1,470,450	1,521,300	1,597,600			
Employment/Population Ratio	.38	.42	.45	.45	.45	.45	.45			
Estimated Employment	515,261	554,148	589,190	638,820	661,700	684,585	718,920			
Population in Genesee County	58,722	64,464	70,935	75,709	78,000	82,000	85,000			
Employment/Population Ratio	.38	.41	.42	.44	.44	.44	.44			
Estimated Employment	22,548	26,430	29,790	33,310	34,320	36,080	37,400			
Population in Wyoming County	37,688	42,021	46,500	49,500	52,600	55,600	56,000			
Employment/Population Ratio	.36	.37	.38	.39	.40	.41	.42			
Estimated Employment	13,422	15,500	17,600	19,300	21,000	22,800	23,500			

(1) Interpolated value

(2) Estimated value based on historical trend

SOURCE: OBERS, Series E-1972, Volumes 4, 5, 7, U.S. Water Resources Council

which comprise this subarea are rural in nature and more accurately reflects Genesee County's emphasis upon agricultural activity. Employment-population ratios were slightly lower in Subarea 0413 than in either SMSA which borders on the watershed. Table B6 contains estimates of future employment levels. Very little employment growth is projected for Wyoming County since future population growth expected to occur in the western portion of this county contiguous to Erie County will find employment within the Buffalo metropolitan area.

(2) Genesee and Wyoming Counties

Manufacturing employment in the upper portions of the watershed is concentrated primarily within the city of Batavia. Table B7 presents the relative concentration of industrial employment for all of Genesee County's largest population centers.

Most of the larger industrial employers within Genesee County are located in the city of Batavia and account for almost 30 percent of total manufacturing employment within the county. The evolution of Batavia as an industrial center has been based upon several factors; it was the first area settled, it is older than any of the cities and villages which surround it and has long been designated as the county seat. Its geographic location and proximity to extensive interregional rail networks have also contributed to the growth in Batavia's manufacturing sector. As the settlement of this area proceeded, the city became the commercial and manufacturing center which served the surrounding agricultural hinterland. Batavia's central location between two of New York State's largest market centers (Buffalo and Rochester) has attracted many large industrial employers to this location.

Table B7 - Distribution of Manufacturing Employment
in Genesee County (1970)

Area	Employment		Manufacturing as Percent of County Industrial Employment (percent)
	Total	Manufacturing	
Genesee County	22,548	8,160	100
City of Batavia	7,016	2,410	30
Town of Batavia	2,144	610	7
Town of Leroy	3,123	1,450	18
Village of Leroy	2,025	950	12
Town of Pembroke	1,518	500	6
Town of Oakfield	2,025	950	12

SOURCE: Business Fact Book - Rochester Area, New York State Department of Commerce

Genesee County outweighs Wyoming County in terms of total industrial employment, number of manufacturing units and value added by manufacturers. Value added is considered to be the best economic measure now available for comparing the relative importance of manufacturing among industries and

geographic areas. Detailed statistics for both counties are contained in Table B8.

Table B8 - Manufacturing Employment Value Added and
Employment Statistics for Selected Counties

Area	1972			1967		
	Total Establishments	Total Employment	Value Added \$ Millions	Total Employees	Value Added \$ Millions	
Genesee County	93	6,800	90.6	7,600	97.1	
City of Batavia	50	4,000	38.7	4,700	51.2	
Village of LeRoy	14	1,900	37.6	1,800	29.8	
Wyoming County	48	3,900	50.0	3,400	41.8	
Warsaw	6	D	D	D	D	
Perry	7	600	7.9	1,000	6.0	

D - Data withheld to avoid disclosure of individual companies.

SOURCE: 1972 Census of Manufacturers, U. S. Department of Commerce, Bureau of the Census.

The 1972 Census of Manufacturers was also used to determine the relative importance of manufacturing activity by Standard Industrial Classification (SIC) Code. Genesee County's largest concentration of industrial employment was in stone, clay and glass operations whereas manufacturing employment in Wyoming County was centered in the production of electrical and electronic equipment. Value added by SIC category is presented in Table B9.

The successful development of the Batavia Industrial Park has also contributed to the viability of industrial activity within this city. Adequate utilities are supplied to this area by Niagara Mohawk Corporation (electric) and National Fuel Gas (natural gas). The water supply for this area originates from wells and Tonawanda Creek and an existing expansion program will eventually double the filtration plant and storage capacity from 3 MGD to 6 MGD. Water supply is not considered to be a constraint on industrial activity in this area.

Existence of a Genesee Industrial Development Corporation and the New York State Job Development Authority has also contributed to growth in industrial activity. The Industrial Development Corporation is a nonprofit corporation established to assist and promote the development of industry in Genesee County whereas the Job Development Authority guarantees second mortgage loans for industrial building through local development corporations.

Table B9 - Industrial Statistics for Selected Industry Groups in Genesee and Wyoming Counties, 1972

SIC Code	Code	Total Establishments	Employees	Value Added \$ Millions	Employees	Value Added \$ Millions
	Genesee County	93	6,800	90.6	7,600	97.1
20	Food & kindred products	13	600	9.7	700	9.8
32	Stone, clay and glass	9	1,400	26.9	(NA)	(NA)
34	Fabricated metals	11	600	13.0	(NA)	(NA)
35	Machinery, exc elect.	15	800	14.9	900	13.2
	Wyoming County	48	3,900	50.0	3,400	41.8
36	Electric, electronic equipment	5	2,100	26.4	(NA)	(NA)

SOURCE: 1972 Census of Manufacturers, U. S. Department of Commerce, Bureau of the Census.

Future projections of manufacturing employment have considered the role Batavia has historically played in Genesee County. Completion of the Urban Renewal Project in Batavia's Central Business District (CBD) has accelerated the growth in tertiary employment. A half dozen new buildings have already been built in the CBD due to this renewal project while others are now under construction or planned.

In light of this stimulus to commercial employment levels the relative importance of manufacturing employment is anticipated to decline slightly in the foreseeable future. Table B10 presents the estimated levels of manufacturing employment in both Genesee and Wyoming Counties.

(3) Commercial Employment

The total value of retail sales increased almost 22 percent in the Buffalo SMSA, slightly above the increase posted at the State level for the period 1963 to 1967, Table B11. The proportion of retail trade sales recorded outside the city of Buffalo increased during this period. In 1963 almost 42 percent of the total value of retail sales occurred within Buffalo but by 1967 this had declined to 39 percent. Growing suburbs around the cities of Buffalo and Niagara Falls have become increasingly important in recent years. In the SMSA, that portion outside the city of Buffalo accounted for over 61 percent of retail activity, compared with less than 50 percent in 1963.

Table B10 - Historical and Projected Manufacturing Employment in
Genesee and Wyoming Counties

Area	Actual :		Projected							Total	
	1970	1980	1990	2000	2010	2020	2030			Increase	
<u>Genesee County</u>											
Total Employment	22,548	26,430	29,790	33,310	34,320	36,000	37,400			10,970	
Manufacturing Employment	8,160	9,410	10,486	11,590	11,810	12,265	12,565			3,155	
Percent Manufacturing	36.2%	35.6%	35.2%	34.8%	34.4%	34.0%	33.6%				
<u>Wyoming County</u>											
Total Employment	13,422	15,500	17,600	19,300	21,000	22,800	23,500			8,000	
Manufacturing Employment	4,310	4,880	5,440	5,850	6,240	6,635	6,700			1,820	
Percent Manufacturing	32.1%	31.5%	30.9%	30.3%	29.7%	29.1%	28.5%				

SOURCE: Rochester Area Business Fact Book, New York State Department of Commerce

Table B11 - Retail Trade Statistics
Change in Retail Trade for Selected Areas

	Sales in Thousands		Percent Increase	Number of Establishments		Total Retail Employment		Employment per Establishment	
	1963	1967		1967	1967	1967	1967	1967	1967
New York State	23,977,310	29,091,471	21.3	162,194	:	877,835	:	5.4	:
Buffalo SMSA	1,675,205	2,048,828	22.3	11,330	:	67,739	:	6.0	:
Erie County	1,402,688	1,717,947	22.5	9,249	:	57,246	:	6.2	:
Niagara County	272,517	330,881	21.4	2,081	:	10,493	:	5.0	:
Genesee County	80,262	96,717	20.5	551	:	2,431	:	4.4	:
City of Batavia	46,888	59,583	27.0	277	:	1,625	:	5.8	:
Wyoming County	41,138	45,880	11.5	384	:	1,083	:	2.8	:
Village of Attica (1)	4,570	5,652	24.0	42	:	126	:	3.0	:

(1) Wyoming County portion

SOURCE: Buffalo and Rochester Business Fact Books, Part II, NYS Department of Commerce, 1974.

Table B12 - Commercial Employment
(Historical Commercial Employment in the Buffalo SMSA)

Year	Total Nonagricultural Employment	Commercial(1) Employment	Ratio of Commercial Employment to Total Nonagricultural Employment	Percent Wholesale	Percent Retail	Ratio of Retail to Wholesale Trade
1958	423.3	86.6	.200	NA	NA	NA
1959	435.8	85.5	.196	NA	NA	NA
1960	441.7	84.5	.191	NA	NA	NA
1961	423.0	82.2	.194	NA	NA	NA
1962	426.7	83.3	.195	NA	NA	NA
1963	428.4	84.5	.197	NA	NA	NA
1964	437.3	86.2	.197	NA	NA	NA
1965	455.5	88.7	.198	NA	NA	NA
1966	474.4	92.2	.194	NA	NA	NA
1967	483.6	95.4	.197	24%	76%	3.22
1968	493.6	98.9	.200	24%	76%	3.24
1969	503.6	101.6	.202	23%	77%	3.32
1970	496.9	102.2	.206	23%	77%	3.33

(1) Total commercial employment equals sum of wholesale and retail trade

NA Data not available for calculations required

SOURCE: Employment and Earnings, U.S. Department of Labor.

The total value of retail sales increased almost 22 percent in the Buffalo SMSA, slightly above the increase posted at the State level for the period 1963 to 1967, Table B11. The proportion of retail trade sales recorded outside the city of Buffalo increased during this period. In 1963 almost 42 percent of the total value of retail sales occurred within Buffalo but by 1967 this had declined to 39 percent. Rapidly growing suburbs around the cities of Buffalo and Niagara Falls have become increasingly important in recent years. In the SMSA, that portion outside the city of Buffalo accounted for over 61 percent of retail activity, compared with less than 50 percent in 1963.

Historically, commercial employment has varied between 19.1 percent and 20.6 percent of total nonagricultural SMSA employment, Table B12. The ratio of commercial to total nonagricultural employment observed in the past was used to project future commercial employment levels within the Buffalo SMSA, Table B13.

Table B13 - Future Commercial Employment - Buffalo SMSA

	: Actual:			Projected			
	: 1970	: 1980	: 1990	: 2000	: 2010	: 2020	: 2030
Estimated Employment	: 513,227	: 554,150	: 589,190	: 638,820	: 661,700	: 684,585	: 718,920
Historical Commercial:	:	:	:	:	:	:	:
Employment Factor	: .199	: .199	: .199	: .199	: .199	: .199	: .199
Commercial Employment:	: 102,132	: 110,275	: 117,250	: 127,125	: 131,680	: 136,230	: 143,025
	:	:	:	:	:	:	:

Commercial activity within Genesee County is heavily concentrated in the city of Batavia. Between 1963 and 1967 the city increased its share of total county retail transactions from 58 percent to 62 percent. More than one-half of all the county's retail operators are located within the city and employ more than two-thirds of all workers within the commercial sector. Batavia's CBD is the major commercial center not only in Genesee County but in the entire corridor between Rochester and Buffalo.

The commercial sector in Wyoming County is less concentrated although 58 percent of total retail sales were recorded in the villages of Warsaw, Perry, and Attica. Wyoming County also recorded the smallest rate of increase in retail sales of any of the four counties that lie in the watershed.

The methodology for estimating future commercial employment in the rural upstream area of the watershed is slightly different than that used for Erie or Niagara Counties. Commercial employment as a percentage of total employment in 1970 was used as a guide for estimating future levels of commercial employment. This percentage was assumed to trend slightly upward over the planning period. Greater increases in this proportion can be expected for Genesee County than in Wyoming County. Detailed estimates by decade are included in Table B14.

Table B14 - Future Commercial Employment
Genesee and Wyoming Counties

	Actual:			Projected			
	1970	1980	1990	2000	2010	2020	2030
<u>Genesee County</u>							
Total Employment	22,548	26,430	29,790	33,310	34,320	36,080	37,400
Commercial Employ-							
ment as Percent							
of Total	17%	18%	19%	20%	21%	22%	23%
Commercial Employ-							
ment	3,830	4,490	5,060	5,660	5,830	6,130	6,355
<u>Wyoming County</u>							
Total Employment	13,422	15,500	17,600	19,300	21,000	22,800	23,500
Commercial Employ-							
ment as Percent							
of Total	15%	15.5%	16.0%	16.5%	17.0%	17.5%	18%
Commercial Employ-							
ment	2,010	2,400	2,800	3,180	3,570	3,990	4,230

(4) Manufacturing Employment

Manufacturing employment is the largest sector of employment in the Buffalo SMSA as a whole, as well as in each individual county. Manufacturing activity has historically been enhanced by an adequate supply of hydroelectric power available in western New York. More than one-third of this region's labor force was employed in manufacturing in 1970. Niagara County's labor force is more heavily oriented towards industrial activity than the workforce in Erie County (43 vs 32 percent of total employment in 1970). This higher percentage is attributed to a relatively high ratio of nondurable goods production centering around the manufacture of chemicals in Niagara Falls, NY.

Recent developments within the industrial sector of the Buffalo SMSA must be considered before projections of manufacturing employment can be reliably derived for the Buffalo and Niagara Falls metropolitan areas. A slight decrease in manufacturing employment was recorded at the State level between 1950 and 1970. During this interval, manufacturing employment ranged between a high of 2,118,900 in 1953 and a low of 1,769,300 in 1970. The net decline in manufacturing employment was almost eight percent for the twenty-three year period.

On the other hand, the Buffalo SMSA experienced a slightly greater drop in manufacturing employment of 10 percent. Since 1970 average annual employment in the SMSA has dropped to a record low of 155,600 in 1974 while the unemployment rate has risen to record levels in both the State and the Buffalo region. Table B15 further illustrates the dwindling industrial employment base of the Buffalo SMSA. In light of the recent downturn in the local economy and the growing importance of trade, commercial and marketing

activities, future levels of manufacturing employment were held constant at the 1970 level of 171,400. This is well above current employment and would provide for any short-term expansion in SMSA industrial employment and, at the same time, accurately reflect the eroding long-term manufacturing outlook for the Buffalo Metropolitan Area.

Table B15 - Industrial Employment - Buffalo SMSA

Year	Number of Manufacturing Establishments	Number of Employees
1958	1,820	173,874
1963	1,808	162,900
1966	1,681	180,600
1969	1,638	178,300
1973	1,570	159,300

SOURCES: County Business Patterns, U. S. Department of Commerce; New York State Department of Labor, Division of Research & Statistics

Manufacturing employment, as a percentage of total SMSA employment, is expected to decline significantly from its 1970 value of 33.4 percent. Rapid growth in the commercial sector and service industries will result in a declining proportion of total SMSA employment involved with industrial activity in the future. Table B16 presents the rapidly declining proportion of industrial employment relative to total SMSA employment. Recent evidence of the predicted long-term decline in the relative importance of the manufacturing sector in this area was evident in employment statistics for 1973 and 1974, Table B17.

Table B16 - Estimated Manufacturing Employment - Buffalo SMSA

	: Actual:			Projected			
	: 1970	: 1980	: 1990	: 2000	: 2010	: 2020	: 2030
Estimated Employment	:513,230:	554,150:	589,190:	638,820:	661,700:	684,585:	718,920
Manufacturing Employment	:171,420:	171,420:	171,420:	171,420:	171,420:	171,420:	171,420
Estimated Manufacturing/ Employment Ratio	: .334:	.309:	.291:	.268:	.259:	.250:	.238
	:	:	:	:	:	:	:
	:	:	:	:	:	:	:

SOURCE: OBERS, Series E 1972, U. S. Water Resources Council

Table B17 - Current Employment in the Buffalo Labor Area
(in thousands)

Industry	:	1973	:	1974
Contract Construction	:	19.9	:	18.3
Wholesale & Retail Trade	:	107.5	:	108.1
Transportation, Public Utilities	:	30.8	:	29.0
Finance, Insurance, Real Estate	:	20.1	:	20.2
Services, Mining, Miscellaneous	:	83.6	:	84.9
Government	:	80.4	:	82.3
Manufacturing	:	<u>159.3</u>	:	<u>155.6</u>
Total	:	501.6	:	498.4
Manufacturing Employment as Percent of Total Employment	:	32%	:	31%

c. Agricultural Earnings and Output.

Agricultural earnings for all counties within the watershed were projected based upon the predicted increase by OBERs, Projections of Regional Economic Activity in the United States. Actual earnings by all farms in 1969 within Erie and Niagara Counties were projected to grow at the SMSA rate while agricultural revenues projected for the upstream reaches utilize a slightly smaller rate. This smaller growth rate of agricultural earnings was based upon projections for Subarea 0413 which contains Genesee, Wyoming and five other counties situated between Buffalo and Rochester. This area is outside the Buffalo SMSA and was considered to be a more accurate representation of a rural area less exposed to growth pressures originating within a large SMSA. Refer to Table B18 for detailed estimates of agricultural earnings by decade.

Agricultural activity within the watershed contributes substantially to the local economy. Dairy farming is the largest single producer of agricultural revenue in each county. While the number of dairy farms have declined steadily for a number of years, herds have become larger and many individual farms have taken on the character of modest sized industries in themselves. With the emergence of large dairy farms has come the increased dependence upon high degrees of mechanization and technical knowledge. It is the continued reliance on this technology upon which projections of future agricultural earnings are based.

Agricultural output of each county in the watershed is substantial. The most recent year for which agricultural data is available (1969) ranks Erie County

Table B18 - Agricultural Earnings
Projected Agricultural Earnings to 2030
(In Thousands)

	Actual(3):	Projected					Increase in		Percent
		1969	1980	1990	2000	2010(1)	2020	2030(2)	Agricultural : from 1980 Earnings : to 2020
	\$	\$	\$	\$	\$	\$	\$	\$	\$
Erie County	28,016	37,820	39,500	43,425	49,028	54,630	60,235	22,415	59
Niagara County	15,988	21,583	22,540	24,780	27,980	31,175	34,374	12,791	59
Genesee County	19,692	22,645	24,420	26,980	30,325	33,870	37,610	14,965	66
Wyoming County	26,532	30,510	32,890	36,350	40,860	45,635	50,676	20,166	66

(1) Interpolated value

(2) Estimated value

(3) 1969 earnings based upon 1969 Census of Agriculture, material compiled by New York State
Department of Agriculture and Markets.

as the number one producer within the watershed in terms of value of agricultural output. Erie County's agricultural output exceeded \$28.0 million in 1969; Wyoming County followed closely behind with \$26.5 million. Details concerning the value of agricultural output for the other two counties are included in Table B19.

Principal agricultural commodities within the watershed include dairy products, field crops, vegetables, fruits and nuts, and livestock other than poultry. In the lower portion of the watershed (Erie and Niagara Counties) there is a stronger emphasis upon those commodities usually associated with truck farm operations which serve urban centers. Genesee and Wyoming Counties are strongly oriented towards dairy farming and the production of those field crops required to support dairy animals.

A greater percentage of farms in the upper reaches of the watershed are commercial farms which produce at least \$2,500 or more per year of agricultural commodities. Niagara County has the highest proportion of farms which produce less than \$2,500 of output per year, Table B20. In contrast, the highest proportion of farms earnings at least \$2,500 per year are located in Wyoming County. This increased commercial farm activity may be partly attributed to the elimination of inefficient farm operations and the decline in the number of part-time farm operators. Those farms near the Buffalo SMSA are more likely to be operated on a part-time or seasonal basis, whereas farms located farther upstream provide the principal sources of income for their owner-operators and tend to be larger in size with greater capital investment required.

d. Per Capita Income.

Average per capita income in New York State has historically exceeded the per capita income in the Buffalo SMSA. This trend is expected to continue into the future based upon Series E data, Table B21. The per capita income of the Rochester SMSA is also below the State average but above that of the Buffalo SMSA. In 1969, the Rochester area's median family income was \$11,539, the highest of all Upstate economic areas, \$1,323 greater than that for Upstate as a whole and \$922 higher than the State's median. Rochester's relative affluence can be primarily attributed to Monroe County's median family income which was fourth highest among all the State's counties. High incomes in this area are in turn attributed to Rochester's reputation for high quality, precision manufacturing products and the existence of the type of labor force required to produce these types of products.

Skilled workers - craftsmen and foremen - comprise almost 15 percent of the area's working residents, the second highest proportion among all the economic areas. This area is also characterized by a better-than-average representation of people in professional and technical positions due to the extensive research activities of such firms as Eastman Kodak, Xerox Corporation, and Bausch and Lomb, Inc.

AD-A133 910


BUFFALO METROPOLITAN AREA NEW YORK WATER RESOURCES
MANAGEMENT INTERIM REP. (U) CORPS OF ENGINEERS BUFFALO
NY BUFFALO DISTRICT JUL 83


4/9

UNCLASSIFIED

F/G 13/2

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

Table B19 - Agricultural Output
Value of Products Sold by County
(Thousands of Dollars)

County	Value of Products Sold in 1969									
	Total	Dairy Products	Poultry & Products	Other	Field Crops	Livestock	Vegetables	Fruits & Nuts	Nursery & Greenhouse	Forest Products
Erie County	28,016	12,456	2,682	2,845	1,187	3,980	1,397	3,407	62	*
Percent of Total		44	10	10	4	14	5	12		
Niagara County	15,988	4,774	702	2,023	1,438	1,097	4,910	1,025	18	*
Percent of Total		30	4	13	9	9	31	6		
Genesee County	19,692	9,719	1,163	2,101	3,037	2,983	39	605	44	*
Percent of Total		49	6	11	15	15	*	3		
Wyoming County	26,532	18,587	598	3,263	3,644	108	(D)	(D)	165	
Percent of Total		70	2	12	14	*	(D)	(D)	1	

* Less than one percent

D - Data withheld to avoid disclosure of information for individual farm

SOURCE: 1969 Census of Agriculture, U.S. Bureau of the Census, material compiled by New York State Department of Agriculture and Markets.

Table B20 - Agricultural Activity
Number of Farms, Acreage, and Value
of Land and Buildings - 1969

County	Number of Farms			Acres in Farms		Average Value : of Land & Build- ing per acre
	Total	Class 1-5 (1)	All Others (2)	Percent of : Total Area	Average Acres : Per Farm	
Erie County	1,680	983	697	33%	132	\$ 54,492
Niagara County	1,654	731	923	50%	104	39,667
Genesee County	1,029	618	411	61%	191	52,479
Wyoming County	1,140	826	314	63%	210	46,143
New York State	51,909	34,404	17,505	33%	196	53,399

(1) Farms for which sales of farm products amounted to at least \$2,500 or more per year.
(2) Total of all farms minus Classes 1-5 constitutes all others.

SOURCE: 1969 Census of Agriculture, U.S. Bureau of Census, material compiled
by New York State Department of Agriculture and Markets.

Table B21 - Per Capita Income
(Historical and Projected Per Capita Income Levels)
(1967 dollars)

	1950	1960 (1)	1970	1980	1990	2000	2010 (2)	2020	2030 (3)
Buffalo SMSA	2,436	2,613	3,569	4,900	6,300	8,400	11,050	13,700	15,944
Rochester SMSA	2,372	2,905	3,940	5,400	7,000	9,100	11,800	14,500	16,500
Non-SMSA Portions of Water Resource Subareas:	1,833	2,180	3,199	4,400	5,800	7,800	10,350	12,900	13,900
New York State	2,619	3,135	4,252	5,700	7,300	9,500	12,150	14,800	16,720
United States	2,064	2,770	3,476	4,700	6,100	8,100	10,650	13,200	15,324

- (1) Interpolated from 1962 value
(2) Interpolated from actual values available for years 2000 and 2020
(3) Estimated based upon historical trends

SOURCE: OBERS Series E, 1972 Volumes 4, 5, 7, U.S. Water Resources Council.

B3. PROJECTED LAND USE DEMAND IN THE AFFECTED AREA

Future estimates of various land use demands presented in this section are based upon the most recent economic and demographic information available for this area. These figures approximate future land demands which may not actually occur in the affected area due to a major change in the economic health of the Buffalo Metropolitan Area or its hinterland.

a. Residential Demand.

(1) Buffalo Standard Metropolitan Area

Residential land use demand was obtained by converting population projections within the affected area to acres. Population increases by decade were converted into household equivalents by use of a factor for average number of occupants per household. This number was assumed to decline in the foreseeable future, a trend substantiated by research conducted by the Bureau of Census which established that the number of persons living in the average American household declined from 3.19 to 2.97 between 1969 and 1974.

Increases in households in the SMSA were distributed between single family and multi-family housing units. In 1970, 62.9 percent of all housing units were owner-occupied in the SMSA. The number of new single family units to be constructed in the SMSA is expected to be significantly smaller than the number of existing single family units. A range of residential densities was applied to the distribution of households to derive net residential land use demand for the SMSA by decade.

This method of analysis was applied to other population projections to determine their sensitivity on total residential land demand. Residential land demand based on OBERS data did not vary significantly from those determined from other statistical series. Land required for single family units in the SMSA is expected to vary from a low of 4,360 acres to a high of 6,100 acres. Land required for multi-family land demand is expected to vary from a low of 3,370 to a high of 5,640 acres. The total residential land demand in the SMSA, depending upon the various combinations of single or multi-family developments will fall between 7,730 and 11,732 acres. Land demand, viewed as a range of possible values, accurately reflects the potential fluctuation in variables such as employment, population shifts, land costs, building and material costs, and availability of financing which cannot be predicted with accuracy over the 50-year planning period. A summary of residential land demand for the Buffalo SMSA is presented in Table B22.

(2) Genesee and Wyoming Counties

Future residential land use demand in Genesee County is anticipated to occur in and around the town of Batavia. Large areas of open space and low densities will continue to characterize the remaining portion of Genesee County within the watershed. Future population growth will become increasingly urban-oriented.

Table B22 - Future Residential Land Use
Demand in the Buffalo SMSA

	1980	1990	2000	2010	2020	Total
	to	to	to	to	to	
	1990	2000	2010	2020	2030	
Projected Population Increase (1)	50,800	49,400	50,850	50,850	76,300	
Projected Household Size	2.90	2.85	2.80	2.75	2.70	
Estimated Increase in Households	17,520	17,300	18,160	18,490	28,260	
Single Family Distribution Factor	.25	.20	.15	.10	.10	
Increase in Single Family Units	4,380	3,460	2,724	1,849	2,826	
Projected Residential Density (Units per Acre)						
2.5	1,752	1,384	1,090	740	1,130	6,096
3.0	1,460	1,150	908	620	942	5,080
3.5	1,250	990	780	530	810	4,360
Multi-Family Distribution Factor	.75	.80	.85	.90	.90	
Increase in Multi-Family Units	13,140	13,840	15,436	16,641	25,434	
Projected Residential Density (Units per Acre)						
15	876	920	1,030	1,110	1,700	5,636
20	660	690	770	830	1,270	4,220
25	520	550	620	660	1,020	3,370

(1) 1972 Series E-OBERS, Population Projections, Vol. V, U.S. Water Resources Council.

The city and town of Batavia contains a total of about 35,200 acres, or slightly less than 55 square miles. Approximately ten percent (3,667 acres) of the total acreage in the town of Batavia area lies within the city. Of the combined land area in the two communities only 14 percent, or 5,084 acres, was developed as of 1967. The remaining area, 30,110 acres, was vacant or in nonurban uses such as woodlands or agricultural lands.

Future growth in the Batavia area will be influenced by local conditions, as well as external forces originating from the two large SMSA's to the east and west. The existence of large tracts of open land outside the city is expected to provide the necessary area required to house future increases in the area's population.

Minimal residential growth is expected to occur in Wyoming County. Most of the future residential development should occur in those communities located outside and west of the watershed as a result of developmental pressures originating within the city of Buffalo. Communities such as Attica, Orangeville, and the towns of North Java and Wethersfield are expected to maintain a steady-state condition. This stability in population will produce only a modest residential land use demand.

A methodology similar to that used in projecting residential land use demand in the Buffalo SMSA was used to estimate future residential land use demand in Genesee and Wyoming Counties. Land required for new residential use during the 50-year planning period should fall in the range of 1,280 to 2,200 acres for Genesee County and between 600 and 1,100 acres for Wyoming County. A range of values was considered appropriate since the inputs into residential land use demand are numerous and, for the most part, uncertain in the short run.

b. Commercial Use Demand.

(1) Buffalo Standard Metropolitan Area

Historical employment per establishment has been utilized to estimate commercial land use demand within the Buffalo SMSA. Projected commercial employment, in conjunction with an assumed range of site sizes and a distribution of future commercial employment between the retail and wholesale sectors, was used to derive future commercial land use demand. Data on average employment per commercial establishment was presented in Table B11. Future employment per establishment is expected to increase slightly from the 1970 benchmark for both the retail and wholesale sectors. Site sizes were assumed to vary from .75 to 1.00 acres per future retail unit and from 2.0 to 4.0 acres per wholesale unit.

Aggregate commercial land use demand in the Buffalo SMSA ranges from a low of 4,900 acres to a high of 7,500 acres based upon expected population and employment. Although a net land use demand exists for the commercial sector between 1980 and 2030, specific localities within the Buffalo SMSA may have negative or positive commercial land use requirements. Table B23 contains incremental commercial land use demand by decade.

Table B23 - Commercial Land Use Demand in the Buffalo SMSA

	1980	1990	2000	2010	2020	Total
	to	to	to	to	to	
	1990	2000	2010	2020	2030	
Increase in Commercial Employment	6,975	9,875	4,555	4,550	6,795	32,750
Retail - 75 Percent (1)	5,230	7,400	3,415	3,410	5,095	24,550
Employment per Establishment	5.5	5.3	5.1	4.9	4.7	
Increase in Future Retail Establishment	950	1,395	670	695	1,085	
.75 acre per site	712	1,045	500	520	810	3,587
1.00 acre per site	950	1,395	670	695	1,085	4,795
Wholesale - 25 Percent (1)	1,745	2,475	1,140	1,140	1,700	
Employment per Establishment	12.5	12.0	11.75	11.50	11.25	
Wholesale Establishments	140	150	97	100	150	
2.0 acres per site	280	400	190	200	300	1,386
4.0 acres per site	560	824	388	400	600	2,772

(1) Distribution between retail and wholesale sectors was derived from Table B6 and trends during the period 1967-1970.

(2) Genesee and Wyoming Counties

Commercial land use demand in Genesee and Wyoming Counties was estimated using a similar methodology. In general, commercial establishments in Wyoming County were smaller in terms of average employment per retail unit, Table B11. In addition, per capita retail sales was substantially less than its counterparts in Genesee County (\$1,335 vs \$1,719). Retail units in Wyoming County also averaged less total sales value than similar units located in Genesee County (\$119,500 vs \$175,500). Any differences between these two adjoining counties in terms of retail sales is most likely attributable to the closer proximity of Genesee County to economic activity in the Rochester and Buffalo SMSA's. Wyoming County is also well removed from the influence of Monroe County (with retail sales per capita of \$1,840) which accounted for more than 80 percent of all retail transactions in and around the Rochester Metropolitan Area. Genesee County also lies within the development corridor between two major metropolitan areas.

Land demand over the next 50 years by all commercial units in Wyoming County has been estimated to range from 100 to 170 acres. In contrast, Genesee County's future commercial units should require between 215 and 365 acres of land.

c. Industrial Use Demand.

(1) Buffalo Standard Metropolitan Area

All industrial firms located in the downstream reaches of watershed are also within the Buffalo SMSA. Industrial activity in upper reaches is concentrated within the town and city of Batavia.

Industrial land use in the SMSA exceeded 14,890 acres in 1967. This represents approximately 1.5 percent of the total land area that lies within the SMSA. At this time, a great deal of those 14,890 acres were located within the two major metropolitan areas of Buffalo and Niagara Falls.

Future economic development trends, especially those trends relative to industrial activity within Erie and Niagara Counties, were partially quantified by a survey of private and public employers conducted by the Erie and Niagara Counties Regional Planning Board (ENCRPB). This survey was titled Economic Development in the Erie-Niagara Region and was released in October 1975. Portions of that survey were used to obtain an estimate of future industrial land use demand within the affected area.

Growth potential in the Erie-Niagara Region was evaluated by ENCRPB on several points. Firms in the area were questioned for information on the potential for attracting "supplier" firms to the area. Results indicate that over 80 percent of the companies in the SMSA purchase substantial amounts of semi-finished goods, parts, supplies, and/or raw materials from outside of the SMSA. While nonavailability of these items locally is the principal reason for these outside purchases, other respondents indicated that local firms could not sell these items at competitive prices.

The survey also disclosed that trade with Canada is generally at a low level and the majority of firms did not anticipate any improvement. Duties and other trade regulations were given as the major inhibiting factors to expansion of business with Canada.

A very small proportion of all firms surveyed (3.6 percent) have moved into the area within the last 10 years. Industrial firms entering the area have generally located in the outlying areas of both counties. Availability of materials and market potential were the major attractions most often cited by firms who moved into the Buffalo SMSA. Slightly more than 40 percent of industrial firms responding to the survey have expanded their plants over the last three years. The largest additions (in square feet) were located in the city of Buffalo. Expansion plans for 1975 reflected the recent downturn in the economy and were fewer than the annual average of the previous three years.

The majority of firms surveyed indicated that they have sufficient space to expand at their present sites. Firms who did not have additional room for expansion stated that they would be willing to build additional facilities somewhere within the two-county area, while others specifically stated a preference for a location within an industrial park located in the SMSA.

Substantial capital investment by the manufacturing sector has occurred in the Erie-Niagara area. Within the industrial group, the proportion of firms investing in new equipment during the past few years was highest in the outlying areas of both counties. However, the dollar value of investment in plant and equipment was greatest in the cities of Buffalo and Niagara Falls, NY.

The economic health of existing industries will be very important in determining the extent of future industrial land use demand in the area. Gains in employment within the manufacturing sector were used as indicators of the extent of growth which might be anticipated by manufacturing firms over the planning period. Manufacturing employment in the SMSA was assumed to remain constant at its 1970 level of 171,400. This stability in employment does not reflect the expected net growth in nondurable and durable goods components. Manufacturing employment in Erie County is anticipated to decline moderately during the planning period whereas very little change is expected in Niagara County. This is primarily attributed to a much higher proportion of workers in the durable goods sector in Erie County. An anticipated decline in employment in the durable goods sector in Erie County will not offset the slight gain predicted in nondurable goods manufacturing. In Niagara County any drop in employment in the nondurable goods sector will be offset by gains in durable goods employment. This has been the historical pattern and is expected to continue.

Therefore, it was estimated that Niagara County would have a net increase in industrial employment while Erie County would have a moderate decline resulting in minimal net land use demand within the SMSA. However, within Niagara County a net demand for industrial land use would exist due to gains in the nondurable goods sector.

The most significant factor complicating the analysis of industrial land use demand is the lack of information concerning the total number of acres currently held in reserve by the industrial sector. Also, the inability to determine when the available supply of land for expansion at present sites will be exhausted prevents a detailed quantification of net industrial land demand.

Land use demand during the planning period will be exerted primarily by two groups: firms who do not have land available for expansion and new firms entering the region. The extent of undeveloped acreage now in industrial parks will greatly dampen net industrial land use demand within the Buffalo SMSA.

New firms entering the area have the greatest need for land and construction of new facilities (historically, new growth has located outside the city of Buffalo). Very few firms have moved into the city in the last 10 years to increase the existing industrial base.

Approximately 1,700 acres lie within established industrial parks in and around the Buffalo Metropolitan Area. It is estimated that less than one-half (850 acres) of this amount is currently developed. Additional industrial park sites are also available near the city of Niagara Falls although detailed information was not obtained for them. Assuming that industrial land use demand in this area is equivalent to the national absorption rate for land use in industrial parks (15 acres per year) there is sufficient land currently available for at least another 50 years of industrial growth in this area. This time frame is considered reasonable in light of recent developments in the local economy and decline in this area's industrial employment.

(2) Genesee and Wyoming Counties

The availability of a sizable labor force, growing population, adequate supply of land, central location between Buffalo and Rochester, plus access to regional transportation networks is expected to bring additional industrial employment into the Batavia area.

Historically, industrial firms have been attracted to that portion of the city of Batavia south of Route 5 where large tracts of land adjacent to railroad mainlines and railroad sidings has been available. This historical dependence by industry upon access to railroads is expected to diminish in the future.

The major concentration of general industrial development within the Batavia area is planned along the southern boundary of the city extending into the town. Sites designated for general industrial use encompass an area of 1,500 acres. Subtracting the existing railroad rights-of-way and the gravel mines (total of 850 acres) future industrial growth has been allocated 650 acres. An additional 800 acres located north of Thruway Exit 48 has also been designated by local planners for industrial growth. The third category of planned industrial development in the town of Batavia occupies an area of approximately 330 acres and has been designated for future research and development use.

Manufacturing employment is projected to increase by 3,100 over the planning period. To prepare for this growth town planners have already allocated 1,700 acres of land within the city and town for industrial use. This acreage exceeds actual requirements for the projected growth in this county's manufacturing labor force. Although a small fraction of this proposed industrial acreage lies within the 100-year flood plain, the principle of economic rationality is assumed to prevail with the vacant acreage outside the 100-year flood plain developing first.

d. Agricultural Use Demand.

Recent increases in agricultural earnings are in sharp contrast to the projected decline in the future estimates of cropland and total acreage in farms. Projected agricultural acreages in New York State are included in Table B24. Between 1980 and 2020 total cropland harvested is expected to decline at a faster rate (down 30 percent) than total land in farms (down 18 percent). While the Tonawanda Creek Watershed most probably will also experience a decline in cropland, the amount of cropland on the flood plain is not expected to experience a serious decline because of farmers' preference and need to farm the more productive flood plain soils.

The long-term trend towards consolidation of many smaller farms into fewer, but larger, agricultural units is expected to continue in New York State. Consolidation of agricultural activity is also expected to occur in the watershed but at a slower rate than in recent decades. Average farm size and production per farm unit will increase over time. Advances in technology have enabled farmers in New York State to increase their physical output over the last 50 years by 30 percent while the number of farms declined to fewer than 25 percent of their original number. Trends in the dairy sector toward higher milk output with fewer animals and fewer farm laborers is primarily attributed to better feeding and breeding techniques and advances in large-scale milk handling systems. Dairy operators are also becoming increasingly dependent upon specialized labor and equipment which is made available by agribusiness enterprises located in the region. Farmers are able to maintain their operations with less on-the-farm labor and increased reliance upon supportive services provided by Contractors.

Crop yields per acre will increase significantly due to more intensive farm management techniques. Special climatic and market conditions in the Erie-Ontario Lake Plain should also continue to encourage farmers to produce fruit and vegetables.

Table B24 - Land in Farms Projected
Farmlands in New York State

	Actual					Projected					1980-2020	
	1959	1964	1969	1980	1985	2000	2020	New York	United States	Percent Change		
Cropland Harvested (1)	5,032.7	4,742.7	3,835.6	3,687.9	3,612.8	3,011.6	2,500.9	-32			-13	
Feed Crops (2)	4,230.2	4,048.3	Nc	3,127.5	3,069.1	2,549.8	2,110.4	-33			Nc	
Food Crops (3)	759.4	687.1	Nc	540.4	523.8	443.6	376.0	-30			Nc	
Other Crops (4)	72.8	58.8	Nc	62.9	61.8	53.3	43.5	-31			Nc	
Cropland not Harvested	2,088.0	1,727.3	2,246.2	1,957.7	1,958.6	2,350.3	2,618.8	+34			+22	
Percentage of Land Cropped	41	36	59	53	54	78	105					
Total Cropland	7,120.6	6,470.0	6,081.8	5,645.6	5,571.3	5,361.9	5,119.7	-18			0	
Nonproductive	6,368.9	5,805.4	4,066.5	3,616.5	3,482.2	3,079.1	2,471.2	-32			-6	
Total Land in Farms	13,489.5	12,275.4	10,148.3	9,053.5	9,053.5	8,441.0	7,590.9	-18			-4	

(1)sum of feed crops and food crops and other crops may exceed cropland harvested due to double cropping
(2)includes corn, grain sorghum, oats, barley, hay, and silage
(3)includes wheat, rye, rice, citrus and noncitrus fruits, vegetables, sugar cane, sugar beets, Irish potatoes, sweet potatoes, dry beans, and dry peas
(4)includes soybeans, peanuts, flaxseed, cotton, tobacco, and other miscellaneous crops
Nc not calculated

SOURCE: 1972 OBERS Projections of Regional Economic Activity in the U.S.
Volume IV, "States," U.S. Water Resources Council, Washington, DC

B4. FLOODING AND PHYSICAL CHARACTERISTICS

Characteristics of the major flood plains of the watershed were ascertained in order to determine their potential uses. Those characteristics which make the flood plains attractive or unattractive to potential developers include: flooding characteristics, flood plain characteristics, available services, and existing activities.

a. Flooding Characteristics.

The damage caused by any flood depends, in general, on the area flooded, heights of flooding, velocities of flows, rates of rise, durations of flooding, and amount and character of flood plain development. The following section describes the existing flood situation including natural storage, recreation, open space, wildlife, wetlands, and water-oriented transportation in the Tonawanda Creek flood plain.

Annual flooding, usually occurring in the late winter or early spring, has caused extensive damage in the Tonawanda Creek Watershed within an 84-mile reach extending from the village of Attica to the mouth of the creek on the Niagara River. Large tracts of primarily agricultural land, particularly in the area below Hopkins Road (mile 41.5) and upstream from the city of Batavia (mile 65.5 to mile 73.5) have been inundated annually. Extensive damage has resulted when floodwaters have overflowed from Tonawanda Creek into the adjacent Mud, Ransom, and Black Creek Watersheds.

A detailed damage survey was conducted by the Corps of Engineers during the winter of 1975. The area surveyed extends from the mouth of Tonawanda Creek upstream through the city of Batavia, a distance of about 66 miles. The results of this survey were used as the basis for determining average annual losses from estimated future flooding and benefits attributable to the various plans of improvement under consideration.

(1) Damage from Past Floods

Flooding by Tonawanda Creek caused considerable damage during the years 1942, 1956, 1957, 1959, and 1960. Serious flooding was also reported in 1902, 1916, and 1917. In the agricultural reaches damaging floods occur at least once each year. The flood having had the highest discharge at the USGS gage located in the city of Batavia occurred in March 1960. Damages in 1960 were greatly reduced in the city by the Corps of Engineers channel modification project completed in 1955 and by emergency measures taken by the city of Batavia to prevent failure of the existing levee in Kibbe Park. In March 1942, a slightly lesser flood overtopped this levee, resulting in the highest damage experienced to date in the city of Batavia. Table B25 shows estimates of damage which the 1942, 1956, and 1960 floods would now cause in the watershed based on December 1975 price levels and conditions of development.

Table B25 - Estimated Damages that Recurrences of the 1942, 1956, and 1960 Floods Would Cause Now, December 1975 Prices and Development

Flood Date	Lower Tonawanda Creek		Hopkins Road to Attica	
	Recurrence Interval in Years	Estimated Damages (1)	Recurrence Interval in Years	Estimated Damages (1)
1942	2	750,000	11	620,000
1956	5	1,600,000	12	1,350,000
1960	10	2,500,000	30	3,140,000

(1) Estimated damages do not include agricultural damages.

(2) Extent of Flooding

Flooding has been negligible below the confluence of Tonawanda Creek and the New York State Barge Canal (mile 11.0). Maintenance of minimum channel depths and widths for waterborne barge traffic has provided sufficient capacity for most past floods. From this confluence to a point about two miles upstream of the hamlet of Rapids (mile 20.5) flooding has been generally limited to overflow at channel bends, with the inundated area having a maximum width of about 1,000 feet. From this point to Hopkins Road (mile 41.5) Tonawanda Creek annually inundates vast areas on both sides of its channel. In several areas, floodwaters have flowed across natural divides into the Mud, Ransom, and Black Creek Watersheds. In these areas, the flood plain width is as great as four miles. At mile 22.0 on Tonawanda Creek, floodwaters frequently overtop Salt Road and flow into the Ransom and Black Creek Watersheds. When this occurred in 1960, the Ransom and Black Creek flood plains were approximately 8,000 feet in width from Salt Road downstream to a point just upstream of the confluence of Ransom and Tonawanda Creeks. Overflow from Tonawanda Creek to Mud Creek Watershed has occurred frequently just downstream of Hopkins Road. In 1960 the Mud Creek flood plain varied from 500 feet to 8,000 feet in width from a point just downstream of Hopkins Road to a point north of the hamlet of Rapids. The areas inundated by the March 1960 flood on Tonawanda, Mud, Ransom, and Black Creeks are shown on Plate B3.

From Hopkins Road eastward to Bushville, flooding has been minimal. This is attributable to the channels having both high banks and a steep channel bottom slope in this reach. From Bushville eastward to the westerly city limits of Batavia the flood plain has varied from 500 feet to 1,500 feet in width, inundating both Route 5 and South Main Street during the 1960 flood.

In the city of Batavia, the areas subject to flooding lie along both banks of the creek. Since completion of the Corps of Engineers channel improvement project in 1955, there have been only minor economic losses reported in the area from just west of the western city limit to the southerly city limit at

the Lehigh Valley Railroad Bridge. The project was designed for a discharge of 6,000 cfs, the discharge of the 1942 flood. The area inundated by the 1960 flood, the flood of record, inundated only 200 acres in the town of Batavia which includes the hamlet of Bushville. Although the discharge for the 1960 flood, 7,200 cfs, exceeded the design capacity of the existing project, emergency measures taken by the city prevented overtopping of the city levee in Kibbe Park.

Just upstream of the Lehigh Valley Railroad Bridge, which is located near the southerly limit of the city, the flood plain widens to occupy a large lowland area which extends upstream about 12 miles, to the village of Alexander. Flooding at this area reached a width of 12,000 feet in 1960. The area serves as a natural reservoir which helps reduce the discharges of Tonawanda Creek through the city of Batavia. The area inundated by the March 1960 flood is shown on Plate B4.

Within the village of Alexander there is a low, flat area on the right bank nearly 2,000 feet wide which is often flooded. The higher areas on the left bank are seldom flooded. From Alexander to Attica the width of the flood plain varies from 1,000 to 2,000 feet. Within the village of Attica, the flood plain is about 1,000 feet at its widest point, near the upstream village limits. The areas inundated by the March 1960 flood are shown on Plate B4.

(3) Existing Use of the Flood Plains

The flood plain of the lower Tonawanda Creek watershed is used primarily by residential and commercial developments with a scattering of public facilities and agricultural activity. Agricultural activities in the flood plains include dairying and the cultivation of cash or field crops such as wheat, corn, oats, alfalfa, hay, etc. Timber, some virgin, and some second growth, includes oak, elm, hickory, maple, black walnut, cedar, and basswood. Frequent overflow and lack of adequate drainage prevents more intensive cultivation in these areas. Flooding for lengthy periods, often running several weeks, saturates the land, delays spring planting and use of pasture, and in some cases restricts production to a single crop where two crops might be possible.

The flood plain in the vicinity of Bushville is used mainly for medium-value residences and commercial establishments along Route 5. There are several modern motels, some of which have suffered first-floor flooding and have had to evacuate guests. There is also some farmland in this reach, but agricultural damage is inappreciable and no estimate of these losses was made.

The flood plain within the city of Batavia includes residential, commercial, industrial, and public developments. In Reach B1, an area not subject to serious flooding since the Corps project was completed in 1955, most development consists of low- to medium-priced residential units with some commercial development along West Main Street. Reach B2 is primarily affected by sewer backup. It would be seriously affected again by overland flooding if the city levee in Kibbe Park should fail as it did in March 1942. Development

in this reach consists mainly of commercial establishments. Reach B3 is the lowest area in the city of Batavia. The area in the vicinity of Liberty and Sumner Streets is 4 to 5 feet below the level of the Kibbe Park levee. Development in this reach consists of many low- to medium-priced residences, five manufacturing concerns, many commercial establishments along Ellicott Street, three schools, five churches, and other public property. Reaches B4 and B5 consist of low- to medium-value residences. Reach B4 also contains a large undeveloped area. Reach B5 includes two plants of Doehler-Jarvis Corporation, the second largest industry in the city. Although a few homes in Reaches B4 and B5 suffer damage to the first floor furnishings, most damage results from flooded cellars and sewer backup. If the city levee in Kibbe Park should fail as it did in March 1942, water up to 4 or 5 feet deep could flood much of Reaches B3 and B2. State Highways Nos. 5, 33, 63, and 98 pass through the flood plain and traffic occasionally must be rerouted. During periods of minor floods, sections of some streets and many cellars are flooded by reversed flows in the storm and sanitary sewer systems. The sewer system is not adequate to carry high runoff even when the creek is low. Damage may also be caused by reversed flows with negligible local runoff. Reaches B1 through B5 are shown on Plate B4.

The area between the city of Batavia and village of Alexander is generally flat and poorly drained. Some of this area is under cultivation, but at a lesser intensity than the lower part of the watershed. Some residential structures are affected by floodwaters.

The major component of damage in Alexander is to residential development along Railroad Avenue. The flood plain between the villages of Alexander and Attica is used mostly for agriculture. Development in the village of Attica consists of residential structures on Water, North, and Exchange Streets and a variety of commercial establishments on Water, Main, and Market Streets.

b. Physical Characteristics of the Flood Plain.

(1) Physiography

Niagara County borders on Lake Ontario in the Erie-Ontario lowlands, a region of low relief just south of the two Great Lakes. These lowlands are made of lacustrine deposits created beneath glacial lakes; elsewhere there are rolling hills representing ground moraines consisting of irregular masses of boulders, gravel, sand, and clay.

The Ontario Lake Plain extends from Lake Ontario south to the Niagara Escarpment. This escarpment has a steep northward slope with bluffs that are exposed in places. Drainage of the Ontario Plain is northward into Lake Ontario. These streams are shallow and meander through narrow flood plains. Between the Ontario Lake Plain on the north and the Cattaraugus Hills on the south, the south Ontario Plain is a rolling area covered with glacial drift. This plain consists of two subplains, the Huron and Erie plains, separated by the east-west striking Onondaga escarpment. Much of the western portions of these two subplains is within the Buffalo Metropolitan Area.

Tonawanda Creek, the border between Erie and Niagara Counties, is centrally located in the Huron Plain and flows westerly to the Niagara River. The Huron Plain is only slightly undulating with flat slopes. This plain slopes westerly from a height of approximately 650 feet near the Onondaga Escarpment in the Tonawanda Indian Reservation to approximately 600 feet in the town of Tonawanda. The eastern boundary of the watershed in the Huron Plain lies near the western limit of Oak Orchard Swamp. Formerly, the Oak Orchard Swamp was a significant source of runoff to the Mud Creek Watershed. This overland flow is now prevented by an extensive dike network recently constructed by New York State.

The Erie Plain is bounded by the Onondaga Escarpment, which cuts through the village of Akron along a northeasterly axis, and the Portage Escarpment which extends through the village of Attica in an east-west direction. This subplain is rolling with moderate slopes and, within the watershed, slopes in two directions. Eastern portions of the Erie Plain slope northward while the western portion slopes westward. The remainder of the watershed lies in the Cattaraugus Hills - an area composed of a relatively flattopped upland with deep valleys.

(2) Soils

Soil types in the flood plains includes the Genesee, Eel, and Wayland series. These alluvial soils have few limitations for agricultural purposes and are highly rated in terms of productivity. High frequency of flooding and relatively flat slopes results in very slow local flood runoff that severely limit this area for nonfarm uses. Flood water ponding occurs regularly in this area because of flat slopes and limited soil permeability.

Infrequent flooding occurs between the hamlet of Bushville and the Indian Reservation where Tonawanda Creek enters the Huron Plain. Tonawanda Creek, from its junction with the New York State Barge Canal at Pendleton to the Indian Reservation is a straight line distance of 12 miles but the actual channel distance is 27 miles. Lands on either side of the creek have very flat slopes. The creek has cut a channel averaging 10 to 15 feet deep and roughly 80 feet wide. Tributaries on both sides of the mainstream (Mud, Beeman, Ledge, Murder, and Black Creek) follow shallow, winding, overgrown channels. Divides between the watersheds of these streams are low and poorly defined. During periods of high flow, Tonawanda Creek and some of its tributaries merge and flow across divides in either direction equalizing flood levels. The average area flooded annually is about 10,000 acres. Most of this land is utilized for agriculture or is vacant. With the exception of Ransom Oaks, a planned community that includes single family dwellings, townhouses and apartments capable of housing 1,000 families, there are no large-scale residential subdivisions within the 100-year flood plain.

Soil series in the flood plain downstream of the Indian Reservation have severe limitations for nonfarm uses. The Canandaigua-Rhinebeck-Raynham soil association occupies the majority of this area but Lakemont and Odessa soil

series also exist along the southern limits of the flood plain in Erie County. Agricultural productivity of these soils is not as high as that of the soils located in the flood plains of Genesee County but truck and field crops can be grown successfully in many areas. Many low-lying areas lack adequate flood runoff. High water tables in this area may limit nonagricultural construction. Detailed information and the various alluvial soil series in the flood plains is included in Table B26.

The relative advantages and disadvantages of the soil associations within the flood plains for various economic uses were based upon soil survey data collected by the U. S. Soil Conservation Service.

The Palmyra Association is the predominant soil group in the bottomlands between North Pembroke and Alexander in the Tonawanda Creek Valley. This association is made up chiefly of well-drained, gravelly soils on glacial outwash terraces and of loamy soils on flood plains. It occurs in the southern half of Genesee County. The largest tract of glacial terraces in the county extends along the east side of the Tonawanda Creek Valley from the city of Batavia to the village of Attica. In areas having favorable slopes, the soils on terraces are excellent for farming and so are the alluvial soils which occur on the flood plains. These soils are fertile and productive but are susceptible to frequent flooding.

Genesee silt loam is a deep, medium-textured soil within the Palmyra Association which occupies well-drained flood plains and is the most productive soil in the county. It has a very high moisture-supplying capacity and moderate to high natural fertility. This soil is well suited to most crops grown in the county and is especially well suited to row crops. This soil has been utilized more frequently for intertilled crops than for pasture or trees. Row crops can be grown continuously if management is highly skilled. Among the farm practices common to this soil group is liming and fertilizing according to results of soils test and desired yields, as well as minimum tillage of row crops.

Other soils of the Palmyra Association, which consists of deep, nearly level, well-drained soils on glacial outwash terraces and uplands, have moderate to high permeability and water-holding capacity. Soils of this group are suited to practically all crops grown in the county. These soils are well suited to all grains and sod crops and can be row cropped successively under proper farm management.

Soils of the Wayland series are poorly-drained nearly level soils on flood plains. They are wet and are subject to severe flooding and have a high moisture-supplying capacity and high natural fertility. Row crops require artificial drainage and streambank erosion and stream deposition must be controlled. The most dependable use is for hay or pasture consisting of grasses that are tolerant of periodic flooding.

Nonfarm uses of soils on bottom land are severely limited by the risk of flooding. The adjacent glacial outwash terraces offer many excellent sites for residential or industrial purposes. Water is available from underground sources and the soils are sufficiently permeable for disposing of septic tank effluent.

Table B26 - Flood Plain Soil Characteristics

Soil Series	Bedrock	Tables	Slope	Filter Fields	Homesites (1)	Streets	Play +	Parking	Picnic	Field Crops	Truck Crops	Potential (3)
			Percent									
Hamlin	4+	1.5+	0-3	Severe	Severe	Severe	Moderate	Moderate	Moderate	Slight	Slight	1
Genesee	20-60	2.0+	0-3	Severe	Severe	Severe	Slight	Moderate	Moderate	Slight	Slight	1
Eel	4-40	1.5 to 2.5	0-3	Severe	Severe	Severe	Moderate	Severe	Severe	Slight	Slight	2
Wayland	6-40	0	0-3	Severe	Severe	Severe	Severe	Severe	Severe	Moderate	Moderate	4
Rhinebeck	6+	.5 to 1.0	0-3	Severe	Severe	Severe	Severe	Severe	Severe	Moderate	Moderate	3
Raynham	6+	.5 to 1.0	0-3	Severe	Severe	Severe	Moderate	Severe	Severe	Moderate	Moderate	3
Odessa	6+	.5 to 1.0	0-6	Severe	Severe	Severe	Moderate	Severe	Severe	Moderate	Moderate	3
Lakemont	6+	0 to 1.5	0-6	Severe	Severe	Severe	Severe	Severe	Severe	Severe	Severe	4
Canandaigua	6+	0 to .5	0-2	Severe	Severe	Severe	Severe	Severe	Severe	Moderate	Moderate	3

(1) Includes homes with basements.

(2) Utilized by tents and trailers.

(3) Rating for agricultural use is based on agricultural capability classification established by Soil Conservation Service. Highest possible rating is 1; lowest rating is 8.

SOURCES: Soil Survey of Genesee County, New York, U. S. Department of Agriculture, Soil Conservation Service.
 Soil Survey of Niagara County, New York, U. S. Department of Agriculture, Soil Conservation Service.
 Soil Survey of Wyoming County, New York, U. S. Department of Agriculture, Soil Conservation Service.

The primary soil association of the flood plain between the Tonawanda Indian Reservation and the New York State Barge Canal is the Canandaigua-Raynham-Rhinebeck Association. The soils in this association are level and occur in areas that border Tonawanda Creek in the extreme southern part of Niagara County. The association extends westward to the city of North Tonawanda and into portions of Wheatfield and Niagara Falls. This association occupies 11 percent of Niagara County; 26 percent of this association consists of Canandaigua soils, 23 percent is Raynham soils, and 17 percent is Rhinebeck soils. The remaining 34 percent is made up of minor soils.

Canandaigua soils are deep and poorly-drained to very poorly-drained and occupy broad level areas. Rhinebeck soils are also nearly level, occupy broad areas, are deep and somewhat poorly drained. Raynham soils occupy the slightly higher elevations and normally are closely associated with the Canandaigua soils.

This association has medium to low value for farming. Community or farm development is limited mainly by natural drainage. The flatness of the area is the main consideration in planning drainage; group drainage projects are needed in many places to provide suitable outlets. Most of the farmlands are not farmed intensively. Where adequate drainage is provided, the crop potential is good for hay, grain, and certain vegetable crops. In most places the soils are stone-free and vegetables can be grown intensively in many areas if extensive tilling is practiced.

Soils in this association were deposited by glacial lakes and include wet, compressed and unstable layers. Care must be taken in constructing foundations for buildings and roads. Most of this association is open land but small forested areas remain as woodlots. Vegetation on some idle farmland is now reverting to ash, soft maple, and other native hardwoods.

The Canandaigua-Raynham-Rhinebeck Association also extends southward into Erie County. Smaller portions of the flood plain are occupied by the Odessa-Lakemont Association which consists of red clayey, poorly drained, limey lacustrine soils. Agriculture is possible if extensive systems of tile drains are used. Drainage ditches work well in some areas but their usefulness is offset by the general flatness of this portion of the floodlands. Croplands devoted to corn and oats are common in the eastern portion of the town of Clarence and throughout the town of Newstead. Extensive community development in northern Erie County is hampered by a very high water table in this area.

(3) Water Resources

(a) Groundwater Resources

Groundwater throughout the watershed is available in quantities sufficient to supply individual users for domestic purposes. In a few areas groundwater resources are capable of supporting municipal water supply systems. The city of Batavia is currently obtaining 50 percent of its total water requirements from groundwater sources. High yields of groundwater in

this area are related to the extensive aquifers composed of glacial sand and gravel between the village of Attica and the city of Batavia. Limestone and dolomite bedrock downstream from the city of Batavia produce moderate to high yields. Only small yields are available from the remaining shales, lacustrine soils and glacial till. Sand and gravel deposits have high potential for development, since recharge rates range from one-half to four million gallons per day per square mile of surface area. To this potential should be added infiltration from streams that could be induced by pumping out large quantities of groundwater.

The quality of groundwater in the watershed upstream from the city of Batavia is marked by a high hardness but generally not by other unfavorable characteristics. Groundwater in the area between the city of Batavia and the mouth of Tonawanda Creek is harder and otherwise poor in quality. The water in the Camillus Shale (the predominant bedrock in the area downstream from the Onondaga Escarpment) is objectionably high in sulfates and, in some areas, chlorides. The chlorides may be dissolved out of deeply buried salt beds by water moving through a regional flow system from a recharge area in the Appalachian Uplands to a discharge area along Tonawanda Creek. Shallow groundwater from carbonate rocks and sand and gravel deposits locally have often been polluted by septic tank effluent.

(b) Surface Water Resources

Large variations in rainfall occur within the watershed. Average annual rainfall in the Appalachian Uplands upstream from the city of Batavia reaches 44 inches while most of the watershed receives approximately 32 inches of rainfall annually. Rainfall attributed to storms does not vary significantly over the watershed. Stored surface water includes only a few small deepwater bodies and several large shallow-water bodies. Suitable physiography for deep-water storage exists only in the Cattaraugus Hills. Faun Lake, located in the headlands of the East Fork of Tonawanda Creek in the town of Wethersfield, is the largest natural deep-water body in the upland area. Few man-made water storage areas are located in the area; the largest is the Upper Attica Reservoir which has a surface area of 200 acres. The lowlands in the watershed are occupied by many swamps and wetlands which provide natural surface storage for spring runoff and intense precipitation.

(4) Vegetation

Natural vegetation associations within the watershed have developed in response to three major determinants: climate, soils, and the degree and kinds of disturbances that have occurred. This last factor was greatly influenced by the agrarian-oriented settlers of the area. Recently, urbanization of certain areas of the watershed have become an important influence in determining types of vegetation.

Differences in climate account for the broad range of vegetation in the watershed, since plants respond primarily to the number of days in the growing season and fluctuations in temperature during the growing season.

Differences in soil, especially in water retaining capacities, but also in chemical content, result in localized differences in vegetation. Plant associations have developed partially in response to wetness of the soil. Seasonally wet areas display a marshy meadow kind of vegetation made up of grasses and sedges. In better drained areas, shrubby plants are more numerous and various bushes and bushy trees are taking over.

Large areas of New York State are in some stage of recovery from the impact of the early settlers. Land originally cleared for farming has recovered slowly and supports the general plant types and successions expected on unfavorable soils. This sort of succession may take many years, but eventually idle land will become reforested.

The watershed within Erie and Niagara Counties and the majority of Genesee County supports the Elm-Red Maple-Northern Hardwood Association. The remainder of the watershed in Wyoming County supports the Northern Hardwood Association. The widespread poorly-drained areas together with the nearly complete removal of the natural forest on the lake plains has produced an area distinct from other forest zones which surround it. Vegetation in the area is distinguished by the relative frequency of American Elm and Red Maple, although both oak and northern hardwoods are still present in lesser abundance. The amounts of oak are especially reduced because the well-drained soils which it prefers have been cleared and are generally in use for growing crops or for pasture. Farmers were originally attracted to this area by its rolling terrain, its good soils, and its accessibility to major transportation routes. The remainder of this area, not currently used for farming, provides a good habitat for the elm and red maple.

(5) Climate

The climate in the vicinity of the Tonawanda Creek Watershed is moderate and humid. Average monthly temperatures range from approximately 25°F in January to 70°F in July. Air above the watershed is usually brought in by westerly winds carried at low elevation over Lake Erie where it picks up considerable moisture. Before this air reaches the watershed, it is carried over northern parts of the Appalachian Uplands, which lift and cool it and cause it to precipitate much of its moisture. Thus, the lowlands of the watershed lie in a precipitation "shadow" and receive considerably less precipitation than adjacent uplands to the southwest. Within the watershed, intense precipitation usually occurs only in summer, most commonly in the form of thunderstorms in June, July, and August. Approximately 30 thunderstorms occur over the watershed annually. The time distribution of precipitation is fairly uniform; the watershed receives approximately three inches per month. Annually, the watershed receives approximately 34 inches of water, including approximately 76 inches of snow.

(6) Water Transportation

The lower 11.2 miles of Tonawanda Creek is a component of the New York State Barge Canal System. The modern system, referred to as the Barge Canal, roughly parallels the course of its predecessor, the old Erie Canal and enables water traffic to move from the Hudson River to Buffalo providing water transportation service to many economic centers adjacent to the canal.

The Erie Canal was enlarged between 1834 and 1862 and continued to be a significant factor in the economic development of New York State. Freight transported on the canal reached two million tons nearly every year from 1860 to 1900 with 4.5 million tons moved during the peak year of 1880. During the period 1905-1918, the Erie Canal was modernized and incorporated into the New York State Barge Canal System. Canalized rivers and lakes form the main units of the new system. Substantial amounts of petroleum products, sand and gravel, cement, grain, stone, and other heavy bulk commodities continue to be shipped on it. The maximum size of a float (barge and tug or motorized vessel) that can pass through a lock on the canal is: length 300 feet, beam 43.5 feet; and height above water 15 feet. These dimensions apply to a tug with a barge of 2,500 tons capacity. Annual tonnages shipped on the canal are shown for selected years from 1900 to 1973 in Table B27. Currently, the Barge Canal carries approximately one million tons of waterborne cargo each year.

Pipelines, railroads, bulk trucking facilities, and the Saint Lawrence Seaway System contributed heavily to the demise of the Barge Canal. The New York State Barge Canal System today, in addition to its role in commerce, serves as a water resource and drainage system for areas of central and western New York. Canal water has also been used for irrigation, industrial needs, and generation of electricity in western New York. However, its most significant use today is for recreational boating. The system has experienced a dramatic increase in the number of pleasure craft during the past two decades and the canal may eventually be maintained for noncommercial purposes alone.

Table B27 - New York State Barge Canal
Annual Tonnage for Selected Years

Year	:	Annual Tonnage
1900	:	2,145,876
1910	:	2,023,185
1920	:	891,221
1930	:	3,044,271
1935	:	3,898,506
1940	:	3,587,086
1945	:	1,665,447
1950	:	3,620,346
1955	:	2,779,491
1960	:	1,772,789
1965	:	1,508,546
1970	:	983,982
1971	:	926,278
1972	:	789,142
1973	:	896,630

c. Available Services.

The population of the Tonawanda Creek Watershed is concentrated in and around the following major cities: Buffalo, Niagara Falls, North Tonawanda, Lockport, Batavia, and the town of Tonawanda. Each city's population density decreases with distance from the center of its CBD and there is an even spread of settlement in the rural areas. Three major regional transportation networks link urban areas within the watershed. They are the canal system, the railroad network, and the road network on which both people and goods are carried by bus, automobile, and truck.

(1) Canal System

The New York State Barge Canal was partially constructed along the course of the former Erie Canal. The existing facility utilizes the Tonawanda Creek channel for the lower 11.2 miles. It has a navigable depth of 12 feet, a navigable width of 75 feet, and a total width of approximately 200 feet.

Water levels in the canalized section of the Tonawanda Creek channel depend chiefly on the stages of the Niagara River at Tonawanda, NY, which are affected by wind and barometric conditions over the Niagara River and Lake Erie. During the navigation season from April to December approximately 1,100 cfs are diverted from the Niagara River easterly via Tonawanda Creek to the Barge Canal to combine with normal east-west flow in Tonawanda Creek. This water is necessary for operation of locks and maintenance of water levels east of Lockport, NY. During other months a gate is closed on the Barge Canal at Pendleton which allows the creek to flow naturally to the Niagara River. Commercial navigation has declined considerably on the canal. Today, the prime users of this facility are recreational boaters.

(2) Highways

There are approximately 689 miles of highway in the watershed consisting of 50 miles of Federal highway, 239 miles of State highway and 400 miles of county roads. In addition, there are many city and town roads. Urban and nonurban areas have excellent highway transportation networks. The network of principal roads and highways is shown in Plate B6.

Genesee County, with the exception of the city of Batavia, consists mainly of farmland, therefore, the road system is not as extensive as that found in major urban areas in Erie County. The road network is considered adequate to serve the needs of a farm-oriented county.

Of the four counties within the watershed, Erie County has the highest population density and the highest concentration of roads. Public transportation in Erie and Niagara Counties and, to a lesser degree, Genesee County, is of particular importance to densely populated areas where many people have no other means of transportation. Although development of public transportation service in intracity areas has been extensive, availability of public transportation rapidly decreases with distance from the CBD's of the cities.

(3) Railroads

The existing rail network in the flood plains is operated by Conrail Corporation and consists of the Penn-Central, Lehigh Valley, and Erie-Lackawanna trackage. Rail service is predominantly east-west oriented with major north-south linkages located in the Buffalo (Baltimore & Ohio, Norfolk & Western, and Conrail) and Batavia (Conrail and Baltimore & Ohio) areas.

Rail service in western New York, as well as the entire northeast, has been reorganized under the Regional Rail Reorganization Act of 1973 (RRRA). Under this Act, the United States Railway Association has recommended a rail network comprising three major integral systems: Conrail, with Penn-Central as its core and including elements of smaller carriers now in reorganization; an expanded Chessie system that would extend eastward into western New York; and the Norfolk & Western combined with smaller solvent carriers possibly operating some new trackage and providing some additional services. Reorganization of existing railroads into an efficient self-supporting system has resulted in large-scale abandonment of light density branch lines.

Most of the existing trackage in or immediately adjacent to the flood plains has been included in the Conrail network. Western New York railroads are shown in Plate B7. Other lines in or near the flood plains which were earlier scheduled to be abandoned were later considered for inclusion in the Conrail or Chessie systems and are not referred to here.

In general, the flood plains possess adequate rail service and the overall impact of the Regional Rail Reorganization Act on western New York will not be significant in the long run. There will be some dislocations and some firms will be forced out of business. In the long run, the proposed organizational structure not only can help the region's carriers function more efficiently and economically than they have in the past, but can also serve industry by providing a more competitive mode of transportation.

(4) Water Supply and Waste Treatment

Use and the demand on western New York's water resources has been increasing. The increase in water use and the resultant increase in waste water is due to population growth. The principal demands for raw water are for public, private, and industrial water supply systems, waste assimilation, irrigation, wildlife, and livestock watering, fish and aquatic life, recreation, cooling, navigation, and hydroelectric power.

Table B28 indicates the locations and sources of raw water and capacities of major water treatment plants serving the Tonawanda Creek flood plains. The water treatment plants using the Niagara River and Lake Erie as water sources have an almost unlimited supply. However, these plants are limited in their expansion capabilities. Eventually, smaller plants such as those now serving the town of Tonawanda and Grand Island will be phased out. Low capacity water treatment facilities will be replaced by large, economical regional facilities.

Inland water supplies depend upon groundwater sources which have quantity, quality, and availability limitations. Groundwater often requires additional treatment such as softening and demineralization which increase user-costs. The remainder of Erie County, except Akron which obtains its raw water supply from a reservoir located in Wyoming County, uses groundwater. Eventually these systems will be phased out and these areas will be served by the county-wide water authority systems.

Table B28 - Water Treatment Facilities for Selected Areas

Location	Existing Capacity (mgd)	Ultimate Capacity (mgd)	Raw Water Source	Comment
Niagara County Water District	20	114	Niagara River	Regional Facility
North Tonawanda	12	12	Niagara River	
Tonawanda	8	8	Niagara River	Phase Out
Grand Island	1.5	1.5	Niagara River	Phase Out
Town of Tonawanda	24	136	Niagara River	Regional Facility
Lockport	12	12	Niagara River	
Akron Village	0.58	0.58	Reservoir	Phase Out
Akron Village	0.21	1.21	Ground Water	Phase Out
Attica	1.20	1.20	Reservoir	Phase Out
Batavia	6.0	6.0	Ground Water and Tonawanda Creek	Will be Expanded

SOURCE: Adopted Regional Water Supply, Plan and Program, 1973, Erie and Niagara Counties Regional Planning Board.

The four water treatment facilities in Niagara County also utilize the unlimited supply of the Niagara River. The proposed plants are designed to draw water from Lake Ontario, however, these plants will not serve the flood plains. The two proposed plants will be located in the villages of Olcott and Youngstown. They will service the area south of the Niagara Escarpment and are scheduled for completion between 1990 and 2000. Public water supply facilities serving the flood plains are currently located in North Tonawanda, Lockport, and Wheatfield. The Wheatfield facility serves all remaining areas in Niagara County that do not otherwise rely on individual water wells.

Genesee County water supply authorities obtain their water from wells, creeks, or from reservoirs in Wyoming County. The largest water treatment plant in Genesee County is located in the city of Batavia. This plant relies on raw water from Tonawanda Creek and two auxiliary wells. The city plans to increase its dependence on groundwater and substantially reduce its use of Tonawanda Creek. Virtually all rural areas obtain their water supply from public or private wells, except for the village of Alexander which purchases water wholesale from the village of Attica.

In the future, portions of Genesee County may receive their water from Lake Ontario, possibly through the Monroe County Water Authority. The future of small independent water systems is limited since these systems are increasingly difficult to operate efficiently. This is a result of increased costs to maintain high levels of quality and reliability of service.

The increase in water usage over time has resulted in a substantial increase of wastewater and reduced water quality in western New York lakes, rivers, and streams. The regions wastewater treatment facilities are often unable to process wastewater effectively enough to meet New York State and Federal water quality standards. The region's wastewater treatment facilities are being upgraded, expanded, and consolidated to comply with existing standards. There are approximately nine public sewage treatment facilities serving the Tonawanda Creek Watershed, in addition to numerous industrial and other private waste treatment facilities.

The most extensive sanitary system in the flood plains is located in the Buffalo urban area. More easterly areas rely heavily on septic systems or small scale municipal systems. Table B29 lists the existing public wastewater treatment facilities serving the flood plains.

One major wastewater treatment plant now under construction in the flood plain is that of Amherst Sewer District 16 which should be in operation by 1980. This plant will eventually serve western portions of the lower flood plain.

The city of Batavia sewage treatment plant is currently under study for upgrading and expansion. The immediate effect of these efforts will be to provide public sewer systems to areas not previously serviced and to significantly improve the overall quality of effluent. Several obsolete treatment plants will be eventually phased out as outlying areas tie into large consolidated sewer districts. All major population centers and most suburban areas will have public sanitary sewer service by 1990.

Table B29 - Sanitary Sewage Systems for Selected Areas

Location	Type	Existing Capacity	Ultimate (mgd)	Comment
Wheatfield	:Activated Sludge	: -	: 36.0	:Under construction
North Tonawanda	:Activated Sludge	: 13.0	: 35.0	:
Amherst SD #16	:Activated Sludge	: 6.0	: 48.7	:
Amherst SD #1	:Trickling Filter	: 6.3	: 6.3	:
Town of Tonawanda	:Incinerator :(Secondary)	: 30.0	: 48.7	:Activated sludge :expansion underway
City of Tonawanda	:Primary, Tank	: 6.0	: 6.0	:Will become :pumping station
Akron	:Trickling Filter	: 0.37	: 0.37	:Future site of :pump station
Batavia	:Activated Sludge	: 2.5	: 2.5	:Under study for :expansion
Alexander	:Trickling Filter	: 0.2	: 0.2	:Under study for :expansion

SOURCE: Regional Sanitary Sewage Plan and Program, 1972 Erie and Niagara
Counties Regional Planning Board.

d. Existing Activities.

The land use pattern in the Tonawanda Creek flood plain was shown in Plate B2. The western portion of the Huron plain floodland in the vicinity of Buffalo has extensive residential activity, whereas east of the suburbs of Amherst and Clarence it is primarily agricultural or open space. Land use within the Intermediate Regional Flood Plain is shown in Table B30.

To facilitate flood damage analysis and evaluation of alternative flood management measures, the damage areas along Tonawanda Creek, Mud Creek, and Black and Ransom Creeks, were divided into 31 reaches. The damage reaches below Hopkins Road (mile 41.5) are within what is referred to as the Lower Tonawanda Creek Watershed and include 10 reaches along Tonawanda Creek (T1 through T10), four reaches along Ransom and Black Creeks (RB1 through RB4) and the six reaches along Mud Creek (M1 through M6).

For the 21.2 mile reach between Hopkins Road and the westerly city limit of Batavia, two damage reaches, T11 and T12, were designated. Reach T12 includes the hamlet of Bushville, a small community just west of the city of Batavia. In the city of Batavia, five reaches (B1 through B5) were used to develop damage-frequency relationships. The greatest number of structures within the Standard Project Flood Plain are located in the Huron Plain floodland and in the city of Batavia. There are approximately 5,665 residential, 283 commercial and industrial, and 45 public and other structures within the Tonawanda Creek SPF.

Table B30 - Acreages and Land Use in the Intermediate
Regional Floodplains (1)

Land Use Type	: T1 to : T10 (2):	: T11 and : T12	: B1 thru : B5	: T13	: Total
Agriculture	: 19,800	: 1,850	: 35	: 3,830	: 25,515
Forestlands	: 5,330	: 1,465	: -	: 600	: 7,395
Wooded Wetlands	: 4,980	: 3,290	: 75	: 735	: 9,080
Residential	: 270	: 45	: 320	: 25	: 660
Commercial & Industrial	: 70	: 55	: 245	: -	: 370
Public and Other	: 250	: 5	: 35	: -	: 290
Total	: 30,700	: 6,710	: 710	: 5,190	: 43,310

1/ Stream mile 0.0 to stream mile 78.0.

2/ No overbank flooding from 100-year discharge in Reaches T1 + T2;
T1 - T10 includes all tributary reaches.

SOURCE: New York State Office of Planning Services, Land Use Natural Resources, 1968 Comprehensive Master Plan - City and Town of Batavia, Genesee County Planning Board.

NOTE: Flood plain acreages for agricultural land use do not agree with Table S1 in "Supplement to Appendix B" as a result of more recent and detailed field surveys.

B5. PROJECTED LAND USE WITHIN THE FLOOD PLAINS

Existing land use in the 100-year flood plains was presented in Table B30. The largest concentration of floodprone residential development in these flood plains is in Reaches B1 through B5 in the city of Batavia. Other significant centers of residential activity occur along Ransom and Black Creeks in Reaches RB1 through RB4, an area located within the towns of Amherst and Clarence in Erie County.

Agriculture is the predominant land use in every reach except T1, T12, and B1 through B5 in the city of Batavia. Extensive tracts of wooded wetlands, forest lands, and inactive agricultural lands are also present in most other nonurban reaches.

Flood plain acreage upstream from the Tonawanda Indian Reservation is expected to remain viable for agriculture. Although increased economic activity is projected for the city and town of Batavia, substantial additional urban encroachment into the Intermediate Regional Flood Plain is not expected because of the availability of large tracts of undeveloped land in the northeastern portion of the city and in the town of Batavia contiguous to the city limits. Future residential development is expected to occur outside the city of Batavia and will be served by city water and waste treatment facilities. Local planning officials expect future industrial growth to occur in areas already designated by town and country planners. The largest of these sites is the new industrial park adjacent to Pearl Street. Completion of an urban renewal project in the Central Business District will also increase future levels of commercial activity in Batavia.

Availability of sewer and water supplies often spurs industrial, commercial, and residential development since proximity of available utilities to a site greatly increases its potential for development. Dependence upon private utilities (wells and septic tanks) by residents upstream of Reach T10 is high. Only in areas such as the town of Amherst, city of North Tonawanda, and the town of Tonawanda are there extensive networks of municipal sewer and water facilities.

Future municipal facilities capable of inducing residential growth into portions of the flood plain will consist of extensions from existing systems located in communities in the western portion of the Huron Plain floodland (i.e., the towns of Tonawanda, Amherst, and Wheatfield and the city of North Tonawanda). These extensions should serve that component of growth expected to extend from the Buffalo Metropolitan Area in easterly and northeasterly directions.

At present, the town of Amherst has a more extensive system of municipal services than the town of Clarence, which is only partially served by sewer and water systems. Therefore, the town of Amherst should continue to outpace Clarence in terms of population growth. Ransom Oaks, a planned community in northeastern Amherst, should remain the site of the largest outlying residential development for many years.

The enforcement of floodproofing requirements including the requirement that the lowest floor of all new homes be elevated to 100-year flood elevations, is expected to slow rapid residential growth in this area. Stringent standards imposed by Erie County for new construction may also be a problem in certain areas. Soils in many areas in the town of Clarence, both in and out of the flood plain, are unsuitable, as determined by soil percolation tests required by the Erie County Health Department for installation of individual septic tank systems. Consequently, the extent and timing of growth in residential development in Clarence will depend upon the extension of lateral sewer lines from major collector lines which lie parallel to Transit Road (Route 78). The current philosophy of town residents in Clarence is not oriented towards rapid residential development. Expansion of municipal services or extensions of lateral sewer or water lines into various parts of this town will be ultimately contingent upon approval by town residents of their elected officials. Social factors in this town may be as important as limitations imposed on northern portions of this area by flooding. Table B36 presents estimates of future incremental land use demands by activity under with and without project conditions.

Most anticipated land use demands in and out of the flood plains are attributable to future regional growth and population shifts within the Buffalo SMSA. The mature manufacturing economy in the Buffalo Metropolitan Area, coupled with the region's reliance upon heavy industries (steel, automotive parts, and chemicals) have created serious problems which could have strong adverse impacts upon growth in outlying suburban areas. The loss of 38 large manufacturing plants in the Buffalo area between 1970 and 1975 has reduced area manufacturing employment by nearly 10,000 jobs and \$125,976,830 in payroll earnings. Also, in 1976 Western Electric Corporation announced the closing of a large manufacturing and assembly plant and the elimination of more than 2,000 jobs. Another area characteristic deterring rapid employment growth is the relatively high cost for industrial labor. The wages for unskilled factory workers in Buffalo are eight percent higher than the national average. Skilled factory workers earn wages that are five percent higher than the national norm. Many of the plants in this area were constructed during World War II and are not as efficient in terms of physical layout and production processes as newer plants in other parts of the country. Also several large firms in the metropolitan area are operated under a system of absentee ownership. This absence of direct social ties to the community by corporate managers or administrators does not create a strong commitment to this region during periods of excess plant capacity or during an economic downturn. Absentee ownership often produces disruptive social impacts to an area when business decisions made outside the area are based solely upon economic considerations.

Projections of future incremental land use demand in the flood plains, presented in Table B31, reflect these basic economic problems in addition to physical constraints such as soil limitations and existing flood hazards. Potential users of the greatest acreage in the flood plains are farmers who plant a variety of grains and forage crops for consumption on the many dairy farms in the watershed. The most significant impact of flood management on agricultural activities within the watershed would be that potential cropland, now too wet, could be transferred from pasture into croplands.

Table B31 - Projected Incremental Land Use Demand
Use Demand in the 100-Year Flood Plain (1)
1980-2030 (in acres)

	:1980-1990:		:1990-2000:		:2000-2010:		:2010-2020:		:2020-2030:		Total
	A	B	A	B	A	B	A	B	A	B	
Residential	:	:	:	:	:	:	:	:	:	:	:
single family	:	:	:	:	:	:	:	:	:	:	:
without project	50	10	100	20	150	30	200	40	300	50	950
multi-family	:	:	:	:	:	:	:	:	:	:	:
without project	25	0	50	0	100	0	225	0	450	0	850
Commercial	:	:	:	:	:	:	:	:	:	:	:
without project	5	0	10	0	15	0	20	0	25	0	75
Industrial	:	:	:	:	:	:	:	:	:	:	:
without project	0	0	0	0	0	0	50	0	75	0	125
Recreation & Open Space	:	:	:	:	:	:	:	:	:	:	:
without project	50	0	100	0	150	0	200	0	250	0	750
Active Agricultural	:	:	:	:	:	:	:	:	:	:	:
without project	*	*	*	*	*	*	*	*	*	*	*

(1) Incremental land use demand is assumed to proceed from the flood fringe area towards the more frequently flooded areas over the project planning period.

A - includes area downstream from Reach T-9 (includes Erie and Niagara Counties). Development projected to occur downstream of New York State Barge Canal is not included.

B - includes T-10 and all other areas upstream (Genesee and Wyoming Counties).

* - no net land demand based upon historical decline in total acreage farmed in New York State.

NOTE: Future long-term land demands are based upon public, local, and regional land use plans for floodprone communities and portions of all counties that lie partially within the limits of the watershed. Table B31 is based upon interpretation of the potential for future development during the project life based upon published estimates of future development likely to occur in the absence of a water resource project.

Much of the idle land could be used for agriculture if the threat of flooding could be significantly reduced. Most farmers could also benefit by reductions in costs of land preparation (i.e., ditching, contouring, and installation of drain tiles) or by a shift in the distribution of crops which would have the effect of increasing the cash flow to the agricultural sector.

Only minimal amounts of neighborhood commercial activity are expected downstream from Reach T10. Growth in multi-family housing units is expected in the vicinity of Ransom Oaks. Development of an industrial park in the town of Amherst, adjacent to Tonawanda Creek was projected to begin in 2010. This complex, however, would be contingent upon completion of the proposed Lockport Expressway. Future commercial, industrial, and residential development in this area was assumed to comply with current Flood Insurance Administration guidelines concerning structures to be built in flood hazard areas.

B6. FLOOD DAMAGES AND MANAGEMENT BENEFITS

The type and distribution of flood plain utilization in the watershed under existing conditions is expected to change very little between 1976 and 1980. Economic activity should increase slightly in those towns and villages adjacent to centers of growth (Buffalo, Niagara Falls, Lockport, and Batavia). However, benefits from the proposed plans of improvements would result in substantial benefits to existing and future flood plain occupants. The benefits accrue from flood inundation reduction, residential affluence, site development benefits, and intensified land use within the agricultural sector.

a. Flood Damage Reduction.

The inundation reduction benefit is the value of reducing flood losses to existing and future activities which would use the flood plain without a plan of improvement. This benefit is measured by calculating the amount of reduction in flood damage and/or related costs. Related costs are those expenditures which would be voluntarily undertaken by rational individual activities to reduce flood damages and include such items as expenditures for floodproofing or elevating the building site by the use of landfill above the existing 100-year flood stages.

(1) Damage Reaches

Flood plains along Tonawanda, Mud, Ransom, and Black Creeks were composed of 31 damage reaches. Limits of these reaches were selected based on hydrologic characteristics and land use. In this way, changes in stage or discharge at an index point of a given reach would be representative of such changes throughout the reach. The locations of the index points, brief descriptions of the damage reaches, initial damaging stages, and recurrence intervals under existing conditions are shown in Table B32. The locations of the index points, limits of the damage reaches, and the March 1960 flood are also shown on Plates B3 through B5.

(2) Damage Surveys

Damage surveys were conducted by the Buffalo District at five separate times to determine damages caused by various floods in the Tonawanda Creek Watershed. In 1954, a thorough damage survey was carried out on the predominantly agricultural areas in the Huron Plain floodland, using the 1954 high water occurrence as a base. In 1959-1960, a damage survey was conducted in the town of Batavia in the areas flooded by the March 1942 and March 1956 floods. In 1962, the 1954 damage survey in the Huron Plain floodland was updated to reflect additional development and changes in land use that had taken place since the 1954 survey. Damages in the villages of Alexander and Attica were determined by a survey in August 1972, using the March 1960 flood as a base. In November and December 1975, a detailed damage survey was conducted in the Tonawanda Creek Watershed from the Niagara River upstream to Alexander using the Intermediate Regional Flood (IRF) as a base and considering the damage that would result from a flood of Standard Project Flood (SPF) magnitude. This latest damage survey is the basis for the existing

Table B32 - Damage Reaches

Reach No.	Location of Index Point	Damaging Elevation	Approximate Recurrence Interval in Years	Limits of Damage Reach
HURON PLAIN FLOODLAND				
<u>TONAWANDA CREEK VALLEY</u>				
T-1	2.4 Stream miles from mouth	568.0	1	:Stream mile 0.0 to 6.0
T-2	8.9 Stream miles from mouth	572.0	1	:Stream mile 6.0 to 10.2
T-3	12.8 Stream miles from mouth	578.0	1	:Stream mile 10.2 to 12.8
T-4	15.2 Stream miles from mouth	584.6	2	:Stream mile 12.8 to 17.4
T-5	17.4 Stream miles from mouth	582.0	1	:Stream mile 17.4 to 22.8
T-6	22.8 Stream miles from mouth	584.0	1	:Stream mile 22.8 to 28.0
T-7	28.0 Stream miles from mouth	593.0	1	:Stream mile 28.0 to 32.3
T-8	32.3 Stream miles from mouth	597.0	2	:Stream mile 32.3 to 34.9
T-9	34.9 Stream miles from mouth	598.0	1	:Stream mile 34.9 to 38.9
T-10	41.5 at Alabama gage location	616.0	1	:Stream mile 38.9 to 41.5
<u>MUD CREEK WATERSHED</u>				
M-1	1.6 Stream miles from mouth	580.0	1	:Stream mile 0.0 to 3.5
M-2	3.5 Stream miles from mouth	583.0	2	:Stream mile 3.5 to 7.0
M-3	7.0 Stream miles from mouth	590.3	4	:Stream mile 7.0 to 10.8
M-4	10.8 Stream miles from mouth	596.0	2	:Stream mile 10.8 to 12.3
M-5	12.5 Stream miles from mouth	596.0	1	:Stream mile 12.3 to 15.0
M-6	15.1 Stream miles from mouth	603.5	2	:Stream mile 15.0 to Ditch Road
<u>RANSOM AND BLACK CREEK WATERSHEDS</u>				
RB-1	2.4 Stream miles from mouth	577.0	1	:Stream mile 0.0 to 2.4
RB-2	4.9 Stream miles from mouth	579.0	1	:Stream mile 2.4 to 4.9
RB-3	7.2 Stream miles from mouth	584.0	1	:Stream mile 4.9 to 8.6
RB-4	8.6 Stream miles from mouth	586.7	2	:Stream mile 8.6 to Salt Road
HOPKINS ROAD TO BATAVIA-TONAWANDA CREEK				
<u>TONAWANDA CREEK VALLEY - MEADVILLE ROAD TO VICINITY OF ROUTE 5</u>				
T-11	52.5 Stream miles from mouth	847.0	3	:Stream mile 41.5 to 59.5
T-12	60.3 Stream miles from mouth	876.5	3	:Stream mile 59.9 to 62.8

Table B32 (Cont'd)

Reach No.	Location of Index Point	Damaging Elevation	Approximate Recurrence Interval in Years	Limits of Damage Reach
ERIE PLAIN FLOODLAND				
<u>CITY OF BATAVIA AND VICINITY</u>				
B-1	Upstream Side of South Lyon Street Bridge	886.0	12	West City Limit to Walnut Street
B-2	Kibbe Park Between Elmwood and Jackson Avenues	893.2	18	Walnut Street to Lower P.C.R.R. Bridge
B-3	Kibbe Park Between Elmwood and Jackson Avenue	893.2	18	Lower P.C.R.R. Bridge to upper P.C.R.R. Bridge, right bank
B-4	Downstream side of Chestnut Street Bridge	889.0	2	Lower P.C.R.R. Bridge to southern city limit left bank
B-5	Downstream side of Chestnut Street Bridge	891.5	12	Lower P.C.R.R. Bridge to Chestnut Street, right bank
<u>CITY OF BATAVIA TO VILLAGE OF ALEXANDER</u>				
T-13	65.5 Stream miles from mouth	890.4	1	Stream mile 65.4 to 77.5
<u>VILLAGE OF ALEXANDER</u>				
A-1	Upstream side of Railroad Ave.	925.0	2	State Rte. 20 to 500 feet upstream from Railroad Avenue
<u>VILLAGE OF ATTICA</u>				
A-2	Upstream side of Prospect St. Bridge	952.0	1	Prospect Avenue upstream to Main Street
A-3	Upstream side of Main Street Bridge	964.0	2	Main Street upstream to Dunbar Road

average annual damage estimates. Results of the 1962 damage survey for the villages of Alexander and Attica are updated to December 1975 prices. Table B33 lists the approximate number of residential, commercial and industrial, and public units that would be affected by the IRF and SPF floods. Also shown are the acreages that would be inundated by these two floods.

Table B33 - Approximate Number of Units and Acres Affected,
1975 Conditions of Development

Reach	Units Affected									
	Commercial									
			&		Public &		Acres			
	Residential		Industrial		Other		Inundated			
	SPF	IRF	SPF	IRF	SPF	IRF	SPF	IRF	SPF	IRF
T-1 through T-10	2,690	890	98	60	21	7	29,200	16,500		
RB-1 through RB-4	419	386	6	5	2	2	9,850	8,770		
M-1 through M-6	210	185	0	0	4	4	7,590	5,430		
T-11 and T-12	213	138	24	21	1	0	7,460	6,710		
B-1 through B-5	2,021	1,815	140	106	17	9	840	710		
T-13	72	69	0	0	0	0	5,470	5,190		
A-1 through A-3	40	8	15	10	0	0	280	250		
Total	5,665	3,491	283	202	45	22	60,690	43,560		

(3) Flood Damage

(a) Methodology

Surface profiles for the IRF and SPF were used as the base for determining flood damage along Tonawanda Creek and its affected tributaries. The stage-damage relationship was established for each reach for the residential, commercial and industrial, and public and other damage categories. Damages were estimated for the Standard Project, Intermediate Regional, and lesser floods by the following method, the results of which are shown in Table B34.

(b) Residential

The value, type of structure, and first floor elevation of each affected unit was established from field observations. The value of contents was determined based upon the estimated value of the structure. Consideration was also given to the proximity of each neighborhood to commercial development, schools and churches, the comparative appearance of each structure, and the extent of landscaping or other improvements around each

**Table B34 - Estimated Damages for Floods of Various Frequencies
Total Residential Damage**

[illegible]

structure. Damages were calculated for various flood depths by use of depth-percent-damage tables for the structure and contents. The tables were developed by sampling residences of all structural types and formulating individual depth-damage curves. The curves were then averaged to establish depth-percent-damage relationships for the structure and contents of each structural type. Initial damage elevations were established as those at which sewer backup would begin or at which floodwater would begin to enter the lowest openings of structures.

(c) Commercial and Industrial

The majority of commercial establishments include service stations, grocery stores, restaurants, motels, and automobile dealerships. The commercial damages used in this study were based on the results of previous damage surveys brought up to December 1975 prices by the application of the appropriate price indices. A sample survey of various commercial establishments in the city of Batavia verified the updating procedure. All industrial damages were established through personal interviews. Industrial damages include damage to machinery and lost production time, inventory and wages, as well as structural damages and anticipated cleanup costs. Most industry subject to flooding is in the vicinity of Batavia.

(d) Public and Other

Damages to public facilities such as buildings, roads, bridges, and utilities were determined based on calculated flood depths and field observations. Emergency operations and cleanup costs incurred by local, State, and Federal agencies were estimated based on actual expenditures incurred in June 1972 after the Hurricane "Agnes" flood which inundated the Upper Genesee River Basin. Generally, bridges were assumed destroyed by floods exceeding their low steel by two or more feet. Detour costs around flooded areas were based on traffic counts obtained from each county and the New York State Department of Transportation. Estimates of detour traffic flows were then used in conjunction with operating costs per mile for commercial and private vehicles to determine total detour costs for various flood events.

(4) Stage-Damage Relationships

The estimated damages that would be caused by the Standard Project and Intermediate Regional floods were plotted against the corresponding stages for each index point. Also, lesser flood stages and corresponding damages were calculated and plotted at each index point. The elevation of zero damage in each reach was established from data obtained from interviews and field observations. These points were then used to develop stage-damage relationships for each activity in each reach. Curves depicting these relationships are shown on Plates B9 through B39. These stage-damage curves are based on December 1975 price levels and conditions of development.

(5) Existing Average Annual Damages

The stage-damage curves referenced in the previous section were used in conjunction with the stage-frequency curves (Plates A32 through A51 and A63 through A68) to determine the damage-frequency relationship for each reach.

The actual calculation of existing average annual damages was done using the Hydrologic Engineering Center's Expected Average Annual Damage computer program. For purposes of computing average annual damages, the Standard Project Flood was assigned a frequency of 1,000 years. The average annual urban damages for each reach, by activity, excluding agricultural damages, based upon December 1975 prices and development are listed in Table B35 and in June 1981 prices in Table B36.

Table B35 - Estimated Average Annual Damages, Existing Conditions
by Reach (December 1975 Development Conditions and Prices)

Reach	Residential	Commercial and Industrial	Public and Other	Total
	\$	\$	\$	\$
T-1	30,210	60	3,500	33,770
T-2	12,480	10	8,940	21,430
T-3	8,750	2,380	11,800	22,930
T-4	380	0	1,080	1,460
T-5	98,360	10	13,910	112,280
T-6	200,740	0	11,400	212,140
T-7	60,620	0	15,680	76,300
T-8	96,860	50	14,110	111,020
T-9	63,720	0	14,880	78,600
T-10	2,920	0	1,220	4,140
RB-1	24,410	0	660	25,070
RB-2	83,410	1,380	11,210	96,000
RB-3	116,930	0	57,020	173,950
RB-4	53,660	670	4,970	59,300
M-1	580	0	3,280	3,860
M-2	800	0	0	800
M-3	2,490	0	210	2,700
M-4	3,180	0	190	3,370
M-5	18,940	0	770	19,710
M-6	17,120	0	1,740	18,860
T-11	7,170	0	9,340	16,510
T-12	15,020	2,670	18,710	36,400
B-1	26,360	6,250	23,500	56,110
B-2	2,120	0	4,450	6,570
B-3	53,920	57,000	10,870	121,790
B-4	19,170	380	1,410	20,960
B-5	540	18,590	2,180	21,310
T-13	22,220	0	7,690	29,910
A-1	15,150	(1)	(1)	15,150
A-2	14,130	(1)	(1)	14,130
A-3	6,520	(1)	(1)	6,520
Total	1,078,880	89,450	254,720	1,423,050

(1) Included in residential.

Table B36 - Estimated Average Annual Damages, Existing Conditions
by Reach, June 1981 Prices and December 1975 Conditions
of Development

Reach	Residential	Commercial and Industrial	Public and Other	Total
	\$	\$	\$	\$
T-1	46,590	100	5,460	52,150
T-2	19,250	20	13,940	33,210
T-3	13,490	3,790	18,400	35,680
T-4	590	0	1,680	2,270
T-5	151,690	20	21,690	173,400
T-6	309,580	0	17,780	327,360
T-7	93,480	0	24,450	117,930
T-8	149,380	80	22,000	171,460
T-9	98,270	0	23,210	121,480
T-10	4,500	0	1,900	6,400
RB-1	37,650	0	1,030	38,680
RB-2	128,630	2,200	17,480	148,310
RB-3	180,330	0	88,920	269,250
RB-4	82,750	1,070	7,750	91,570
M-1	890	0	5,120	6,010
M-2	1,230	0	0	1,230
M-3	3,840	0	330	4,170
M-4	4,900	0	300	5,200
M-5	29,210	0	1,200	30,410
M-6	26,400	0	2,710	29,110
T-11	11,060	0	14,570	25,630
T-12	23,160	4,260	29,180	56,600
B-1	40,650	9,960	36,650	87,260
B-2	3,270	0	6,940	10,210
B-3	83,160	90,880	16,950	190,990
B-4	29,560	610	2,200	32,370
B-5	830	940	3,400	5,170
T-13	34,270	0	11,990	46,260
A-1	23,360	(1)	(1)	23,360
A-2	21,790	(1)	(1)	21,790
A-3	10,060	(1)	(1)	10,060
Total	1,663,830	113,930	397,230	2,174,990

(1) Included in residential.

NOTE: Totals may not add due to rounding.

(6) Average Annual Damages, Improved Conditions

Residual average annual damages have been computed for the recommended plan of improvement. Stage-frequency curves under improved conditions were used in conjunction with the appropriate stage-damage relationships to determine the damage-frequency relationship for each reach. These data were also processed using the Expected Average Annual Damage Program. These damage estimates assume a 1,000-year return period for the SPF, 1975 development conditions and prices. Residual average annual damages are summarized in December 1975 prices in Table B37 and June 1981 prices in Table B38.

(7) Average Annual Inundation Reduction Benefits

The inundation reduction benefit is the value of reduced flood damages under 1975 development conditions. It is calculated by subtracting the estimated residual average annual damages under improved conditions from the average annual damages under existing conditions. Average annual inundation benefits are summarized in December 1975 prices in Table B37 and June 1981 prices in Table B38.

Table B37 - Estimated Existing Average Annual Damages and Benefits
(December 1975 Development Conditions and Prices)

Reach Number	Reach Name	Existing Average Annual Damages	BRCM	
			Residual Average Annual Damages	Existing Average Annual Benefits
		\$	\$	\$
T1-T10	<u>Lower Tonawanda Creek</u>			
	Residential	575,040	165,890	409,150
	Commercial and			
	Industrial	2,510	310	2,200
	Public and Other	<u>96,520</u>	<u>20,340</u>	<u>76,180</u>
	Subtotal	674,070	186,540	487,530
RB1-RB4	<u>Ransom and Black Creek</u>			
	Residential	278,410	83,940	194,470
	Commercial and			
	Industrial	2,050	640	1,410
	Public and Other	<u>73,860</u>	<u>25,470</u>	<u>48,390</u>
	Subtotal	354,320	110,050	244,270
M1-M6	<u>Mud Creek</u>			
	Residential	43,110	13,050	30,060
	Commercial and			
	Industrial	0	0	0
	Public and Other	<u>6,190</u>	<u>520</u>	<u>5,670</u>
	Subtotal	49,300	13,570	35,730
	<u>Total Huron Plain</u>	1,077,690	310,160	767,530
T11-T12	<u>Tonawanda Creek:</u> <u>Meadville Road to</u> <u>City of Batavia</u>			
	Residential	22,190	1,560	20,630
	Commercial and			
	Industrial	2,670	260	2,410
	Public and Other	<u>28,050</u>	<u>830</u>	<u>27,220</u>
	Subtotal	52,910	2,650	50,260
B1-B5	<u>City of Batavia</u>			
	Residential	102,110	6,280	95,830
	Commercial and			
	Industrial	82,220	150	82,070
	Public and Other	<u>42,410</u>	<u>840</u>	<u>41,570</u>
	Subtotal	226,740	7,270	219,470

Table B37 - Estimated Existing Average Annual Damages and Benefits
(December 1975 Development Conditions and Prices) (Cont'd)

Reach Number	Reach Name	Existing Average Annual Damages	BRCM	
			Residual Average Annual Damages	Existing Average Annual Benefits
		\$	\$	\$
T-13	<u>Batavia to Alexander</u>			
	Residential	22,220	0	22,220
	Commercial and			
	Industrial	0	0	0
	Public and Other	<u>7,690</u>	<u>0</u>	<u>7,690</u>
	Subtotal	29,910	0	29,910
A-1	<u>Alexander</u>			
	Residential	15,150	15,150	0
	Commercial and			
	Industrial	(1)	(1)	(1)
	Public and Other	<u>(1)</u>	<u>(1)</u>	<u>(1)</u>
	Subtotal	15,150	15,150	0
A2-A3	<u>Attica</u>			
	Residential	20,650	20,650	0
	Commercial and			
	Industrial	(1)	(1)	(1)
	Public and Other	<u>(1)</u>	<u>(1)</u>	<u>(1)</u>
	Subtotal	<u>20,650</u>	<u>20,650</u>	<u>0</u>
	<u>Total Erie Plain</u>	345,360	45,720	299,640
	<u>Total Tonawanda Creek</u>			
	<u>Watershed</u>			
	Residential	1,078,880	306,520	772,360
	Commercial and			
	Industrial	89,450	1,360	88,090
	Public and Other	<u>254,720</u>	<u>48,000</u>	<u>206,720</u>
	Grand Total	1,423,050	355,880	1,067,170

(1) Included in residential.

Table B38 - Estimated Existing Average Annual Damages and Benefits
(December 1975 Development Conditions and June 1981 Prices)

Reach Number	Reach Name	Existing Average Annual Damages	BRCM	
			Residual Average Annual Damages	Existing Average Annual Benefits
		\$	\$	\$
T1-T10	<u>Lower Tonawanda Creek</u>			
	Residential	886,830	255,840	630,990
	Commercial and			
	Industrial	4,010	490	3,520
	Public and Other	<u>150,510</u>	<u>31,720</u>	<u>118,790</u>
	Subtotal	1,041,350	288,050	753,300
RB 1-4	<u>Ransom and Black Creek</u>			
	Residential	429,360	129,450	299,910
	Commercial and			
	Industrial	3,270	1,020	2,250
	Public and Other	<u>115,180</u>	<u>39,720</u>	<u>75,460</u>
	Subtotal	547,810	170,190	377,620
M1-M6	<u>Mud Creek</u>			
	Residential	66,470	20,130	46,340
	Commercial and			
	Industrial	0	0	0
	Public and Other	<u>9,660</u>	<u>810</u>	<u>8,850</u>
	Subtotal	76,130	20,940	55,190
	<u>Total Huron Plain</u>	1,665,290	479,180	1,186,110
T11-T12	<u>Tonawanda Creek:</u>			
	<u>Meadville Road to</u>			
	<u>City of Batavia</u>			
	Residential	34,220	2,410	31,810
	Commercial and			
	Industrial	4,260	410	3,850
	Public and Other	<u>43,750</u>	<u>1,290</u>	<u>42,460</u>
	Subtotal	82,230	4,110	78,120
B1-B5	<u>City of Batavia</u>			
	Residential	157,470	9,690	147,780
	Commercial and			
	Industrial	102,390	240	102,150
	Public and Other	<u>66,140</u>	<u>1,310</u>	<u>64,830</u>
	Subtotal	326,000	11,240	314,760

Table B38 - Estimated Existing Average Annual Damages and Benefits
(December 1975 Development Conditions and June 1981 Prices)
(Cont'd)

Reach Number	Reach Name	Existing Average Annual Damages	BRCM	
			Residual Average Annual Damages	Existing Average Annual Benefits
		\$	\$	\$
T-13	<u>Batavia to Alexander</u>			
	Residential	34,270	0	34,270
	Commercial and			
	Industrial	0	0	0
	Public and Other	<u>11,990</u>	<u>0</u>	<u>11,990</u>
	Subtotal	46,260	0	46,260
A-1	<u>Alexander</u>			
	Residential	23,360	23,360	0
	Commercial and			
	Industrial	(1)	(1)	(1)
	Public and Other	<u>(1)</u>	<u>(1)</u>	<u>(1)</u>
	Subtotal	23,360	23,360	0
A2-A3	<u>Attica</u>			
	Residential	31,850	31,850	0
	Commercial and			
	Industrial	(1)	(1)	(1)
	Public and Other	<u>(1)</u>	<u>(1)</u>	<u>(1)</u>
	Subtotal	31,850	31,850	0
	<u>Total Erie Plain</u>	509,700	70,560	439,140
	<u>Total Tonawanda Creek Watershed</u>			
	Residential	1,663,830	472,730	1,191,100
	Commercial and			
	Industrial	113,930	2,160	111,770
	Public and Other	<u>397,230</u>	<u>74,850</u>	<u>322,380</u>
	Grand Total	2,174,990	549,740	1,625,250

(1) Included in residential.

b. Area Redevelopment Benefits.

In accordance with current guidance from WRC, no counties in Western New York qualify for Area Redevelopment Benefits. Cattaraugus and Allegany Indian Reservations located in Western New York are areas designated qualified for area redevelopment benefits. The Tonawanda Indian Reservation is not a qualified area.

It is not reasonable to assume that the labor pool employed in the construction of this project will include previously unemployed contract construction workers from either the Cattaraugus or Allegany Indian Reservations. This assumption is reasonable because the commuting distance between each reservation and the Batavia, New York area, where actual construction will take place, is in excess of 50 miles. Also, there is no reliable means of public transportation between either Indian Reservation and the Batavia, New York project construction area.

c. Project Year One (1985) Development Conditions.

Estimating damages and benefits at Project Year One (1985), and also for future years, raises the problem of relating Executive Order 11988 and the Corps regulation ER 1165-2-26, which sets forth Corps policy on implementing this Executive Order, to this analysis. ER 1165-2-26 specifies:

"The Executive Order has an objective the avoidance, to the extent possible of long- and short-term adverse impacts associated with the occupancy and modification of the base flood plain and the avoidance of direct and indirect support of development in the base flood plain wherever there is a practicable alternative."

In order to apply the Executive Order to this analysis, it is necessary to evaluate urban development within the Tonawanda Creek Watershed.

(1) Urban Development in the Tonawanda Creek Watershed

For purposes of evaluating urban development, the Tonawanda Creek Watershed may be divided into two components: the eastern end of the lower watershed, hereafter referred to as the EELW, and the remainder of the watershed. In Niagara County, the EELW includes all or most of the towns of Lockport and Pendleton, and significant portions of the town of Wheatfield and the city of North Tonawanda. In Erie County, it includes nearly all of the town of Clarence, significant portions of the towns of Amherst and Tonawanda, and the city of Tonawanda.

The EELW is strategically situated in a major growth corridor in the Buffalo SMSA, Erie and Niagara Counties. Most suburban development in the SMSA has been directed northward, onto the EELW and portions of the tributary Ellicott Creek Watershed, and eastward onto the Scajaquada and Cayuga Creek Watersheds. While Ellicott Creek is a tributary of Tonawanda Creek, it has been treated as a separate watershed, and a recommended plan of action for flood damage management is now under preparation. At present, most suburban growth is directed north onto the Ellicott Creek Watershed in the town of Amherst. The more distant towns in the EELW - Wheatfield, Pendleton, and Lockport in Niagara County, and Clarence in Erie County - are already

experiencing significant amount of exurban, and in some cases, suburban development.

There are three reasons for assuming that future suburban development will continue to move into the northern growth corridor and eventually into the EELW itself during the project evaluation period.

First, four industrial communities bordering the Niagara River - the city of Buffalo, the industrialized eastern edge of the town of Tonawanda, the city of Tonawanda and its neighbor across Tonawanda Creek, the city of North Tonawanda, plus the city of Niagara Falls contain most of the employment opportunities within the Western New York Region. This employment, in turn, has generated substantial residential development in adjacent and nearby nonindustrial communities, including those comprising the EELW. Though this is not a rapidly growing industrial complex, it continues to generate residential housing demand, through replacement of aging housing stock and new family formation, a significant proportion of which will be met by residential construction on the nearby EELW.

Second, the EELW and adjacent areas have a municipal infrastructure which have been designed to accommodate substantial future development. This is particularly true for sanitary sewerage facilities, processing plants, and sewer lines, which probably are the single most important factor affecting the direction of future urban development in the Western New York Region. New sewer processing plants have recently been completed in the towns of Tonawanda and Wheatfield, and in the cities of Niagara Falls and North Tonawanda. New sewer lines are being or have recently been laid in the city of North Tonawanda, and in the towns of Amherst, Clarence, and Wheatfield. Further, expansion of the local highway network has made the EELW much more accessible to the industrial complex along its eastern edge than was the case a decade or more ago. This expansion includes development of: Williams Road, from I-190 at Niagara Falls to the Summit Mall in the town of Wheatfield; the Division Street Arterial connecting Colvin Boulevard in the town of Tonawanda to Division Street in North Tonawanda; and current improvement of Millersport Highway, which connects I-290 with Transit Road, the major commercial strip development in the region. Finally, expanded services, exemplified by establishment of Summit Mall, commercial development along Transit Road (New York State 78), and establishment of Eastern Hills Mall, the largest regional shopping center in Western New York, have made the EELW an even more desirable location for future urban development. In fact, the developer of Summit Mall has recently initiated construction of a large-scale residential development adjacent to the Mall. Also, significant development continues to take place near Eastern Hills Mall.

Third, though not necessarily prohibited, growth in other directions is more restricted. Growth to the south has been severely restricted by the lack of adequate sewerage facilities. It is also inhibited by topography, the hilliness of the Alleghany Plateau, and the presence of the Lake Erie snowbelt. The snowbelt is an area of seasonal heavy snow storms located south of the city of Buffalo extending inland from Lake Erie to beyond East Aurora. Growth to the east, into the towns of Cheektowaga, Lancaster, and West Seneca has already been extensive, particularly in Cheektowaga and West Seneca.

Growth in this direction must necessarily occur at ever increasing distances from downtown Buffalo. Growth to the west is impossible, given the presence of Lake Erie and the Canadian boundary.

Net impacts of the urban growth trends stated above assure that the EELW will experience urban development in the future, whether or not a flood plain management project is implemented on Tonawanda Creek. The pertinent questions are: (1) how much development will occur without the project; and (2) how much additional development, induced development, will occur as a result of implementation of the Selected Plan?

Table B36, which was originally prepared for the 1976 Interim Feasibility Report, is a summary of the land use requirements in the future. These estimates were developed after evaluating a number of factors which would significantly affect future development such as regional population and employment trends; intraregional shifts in employment and population; local zoning ordinances and development philosophies; enforcement of floodproofing requirements; projected development of future municipal facilities; availability and projected development of sewer facilities and water supplies; soil conditions; and existing flood hazards. The evaluation included consultation with local officials and planners, including the Erie and Niagara Counties Regional Planning Board.

Since 1976, there have been some notable changes in the national situation which might change the projections of future land use patterns, particularly for the residential land demand component as it existed in 1976. Foremost among these have been the pronounced increase in new home prices and the sharp rise in home mortgage rates. Equally important has been the increase in gasoline costs and the shortages in supply. All of these factors have interacted to reduce the estimated demand for residential land on the flood plain of the EELW. For these reasons, the projected growth of residential development utilized in this analysis for the "without-project-condition" has been scaled down by 25 percent from earlier (1976) estimates.

It must be emphasized that all future development is based upon informed projections of future land use requirements under without project conditions. In other words, no induced development has been included in this analysis. The assumption that there will be no induced demand for land as a result of implementation of the Selected Plan is unrealistic when local geographic and land use trends within the watershed are considered, but complies with current policy in Executive Order 11988 and ER 1165-2-26. This conclusion is based on several observations: (1) short-term development since 1976 has already occurred on the flood plain without a project; (2) the Selected Plan, if implemented, will increase the attractiveness of the flood plain by substantially reducing the flood hazard and associated damages; and (3) there are no effective controls on economic growth within the watershed or New York State, other than enforcement of flood plain insurance (FIA) requirements, which can effectively prevent development from occurring. Flood plain insurance (FIA) requirements are not effective in restricting growth along Tonawanda Creek due to the character of the flood hazard. The existing and improved IRF on the EELW is only approximately 1 foot above the bankfull stage. Compliance

with FIA requirements, either through landfill of residential property or floodproofing of other structures, is a relatively inexpensive process. Therefore, while this analysis assumes no induced development, it is to be expected that such development will occur. The only way to prevent induced development would be not to implement a project. However, not to implement this project would clearly not "reduce the hazard and risk associated with floods," and it would not "minimize the impact of floods on human safety, health and welfare" (ER 1165-2-26, 15 May 1979, par. 6b. and 6c.).

A final comment about the effect of future urban land use projections upon this analysis is warranted. Given the assumption of no induced development, the future urban development component of the analysis provides very limited benefits. As will be seen, total average annual future urban benefits account for less than 6 percent of the estimated total benefits for the BRCM plan. Therefore, project feasibility is not dependent upon future urban benefits.

(2) Inundation Reduction Damages and Benefits

Urban development has been projected to occur in the residential, commercial, and industrial sectors during the 1976-85 period. No growth has been projected in the public and other use sector for this period. Residential development has been projected to occur at a rate of 80 residential units per year with a total of 720 additional units to be constructed during this period. Commercial development is projected to occur at a rate of three units per year, and industrial development is projected at one unit every two years; this produces 27 commercial and 4.5 industrial units to be developed in the period. Though damages and benefits are presented for the aggregated category of commercial and industrial use, they were developed separately, due to the differing character of each category.

All development has been assumed to be in compliance with FIA regulations which require the lowest building opening to be at or above the IRF stage. Since short-term development will occur prior to Project Year One (1985), it has been situated at the existing condition, without project, IRF stage. All development has been located in the EELW portion of the flood plain since this area is presently under the greatest short-term developmental pressures.

Damages were calculated by using a hypothetical but typical standard unit type within each category: residential, commercial, and industrial. Damages were separately estimated for contents and structures, and a stage damage relationship was developed for each structure type. For residential structures, the Buffalo District depth-damage curves were used to estimate structure and content damages. Tennessee Valley Authority depth-damage curves were used to develop structure and content damages for commercial and industrial structures. In this case, the same curve, a commercial depth-damage curve, was used for both structures. This was required since: (1) no industrial depth-damage curve was available locally; and (2) it was judged that a typical suburban industrial structure was very similar to the typical suburban commercial structure, though the former is usually larger. The relationship between structure and content values was verified based upon discussions with local building associations and contractors.

The damages described above are per unit damages. Incremental damages for each category were calculated by multiplying the appropriate per unit damage value by the number of units projected to be constructed on the flood plain during the 1976-85 period.

Incremental residual damages were estimated by calculating the amount of damages each unit would incur from floods above the IRF stage under improved conditions. In most, but not in all reaches of the EELW, there would be some damage to structures built at the existing IRF elevation during the 1976-85 period after implementation of the project in 1985. Incremental residual damages for each category were obtained by multiplying the appropriate residual damages value per unit by the number of units projected to be developed on the flood plain in the interim period. These remaining damages were then subtracted to estimate incremental inundation reduction benefits for the period 1976-1985.

Table B39 summarizes the 1976-85 inundation damages, incremental residual damages, and incremental benefits. Estimates are presented for all three variables for three time periods: 1975, 1976-85, and 1985. The flood plain has been subdivided into three components: Lower Tonawanda Creek, Ransom and Black Creeks, and the remainder of the basin. All development in this period is projected to occur within the first two subdivisions.

Short-term development (1976-85) makes a minor contribution to project benefits. Construction of the BRCM would result in incremental benefits of \$51,330 (Table B39) and results primarily from growth of the residential sector.

(3) Urban Damages and Benefits for 1985 Development Conditions

Short-term development has been forecasted for the lower portion of the watershed during the interval 1976-1985. Damages and benefits have been adjusted to reflect a greater number of units within the SPF zone. A summary of urban damages and benefits for 1985 conditions of development has also been developed and is summarized in Table B40. Short-term benefits are relatively small and do not significantly alter the 1975 level of economic feasibility.

d. Future Development Conditions.

(1) Inundation Reduction Effects

Future urban development has been anticipated to occur on the flood plain without implementation of a plan. For the 50-year forecast period, 1985-2035, development has been projected for all three urban sectors: residential, commercial and industrial, and public and other use. Acreage, number of units, and timing of this development by decade are presented in Table B41.

Future urban growth is expected to locate in the lower reaches of the watershed, primarily in T1-T4 and RB1-RB4. This growth is a result of developmental pressures originating along the northern perimeter of the Buffalo Metropolitan Area. All units to be constructed in the flood plain are assumed to have their lowest opening at or above the improved IRF elevation.

Table B39 - Average Annual Urban Damages and Benefits, 1976-1985, June 1981 Prices

Reach Number:	Residential			Commercial and Industrial			Public and Other			Total		
	1975	1976-1985	1985	1975	1976-1985	1985	1975	1976-1985	1985	1975	1976-1985	1985
	\$	\$	\$	\$	\$	\$	\$	\$	\$	\$	\$	\$
<u>BRCH</u>												
<u>T1-10 : Lower Tonawanda Creek</u>												
: Damages	886,830	65,840	952,670	4,010	5,900	9,910	150,510	0	150,510	1,041,350	71,740	1,113,090
: Residual Damages	255,840	19,450	275,290	490	2,870	3,360	31,720	0	31,720	288,050	22,320	310,370
: Benefits	630,990	46,390	677,380	3,520	3,030	6,550	118,790	0	118,790	753,300	49,420	802,720
<u>RBI-4 : Ransom and Black Creek</u>												
: Damages	429,360	0	429,360	3,270	1,910	5,180	115,180	0	115,180	547,810	1,910	549,720
: Residual Damages	129,450	0	129,450	1,020	0	1,020	39,720	0	39,720	170,190	0	170,190
: Benefits	299,910	0	299,910	2,250	1,910	4,160	75,460	0	75,460	377,620	1,910	379,530
<u>Rest of Flood Plain</u>												
: Damages	347,640	0	347,640	106,650	0	106,650	131,540	0	131,540	585,830	0	585,830
: Residual Damages	87,440	0	87,440	650	0	650	3,410	0	3,410	91,500	0	91,500
: Benefits	260,200	0	260,200	106,000	0	106,000	128,130	0	128,130	494,330	0	494,330
<u>Total Tonawanda Creek Flood Plain</u>												
: Damages	1,663,830	65,840	1,729,670	113,930	7,810	121,740	397,230	0	397,230	2,174,990	73,650	2,248,640
: Residual Damages	472,730	19,450	492,180	2,160	2,870	5,030	74,850	0	74,850	549,740	22,320	572,060
: Benefits	1,191,100	46,390	1,237,490	111,770	4,940	116,710	322,380	0	322,380	1,625,250	51,330	1,676,580

Table B40 - Summary of Urban Damages and Benefits for 1985
Conditions of Development (June 1981 Prices)

	Conditions of Development		
	1975	1976 - 1985	1985
Existing Damages	2,174,990	73,650	2,248,640
Residual Damages	549,740	22,320	572,060
Benefits	1,625,250	51,330	1,676,580

Table B41 - Projected Demand for Urban Lands

	1985-1995		1995-2005		2005-2015		2015-2025		2025-2035		Future Change	
	Acres	Units	Acres	Units	Acres	Units	Acres	Units	Acres	Units	Acres(1)	Units
Residential	267	800	267	800	267	800	267	800	267	800	1,335	4,000
Commercial	5	10	10	20	15	30	20	40	25	50	75	150
Industrial	10	2	20	4	31	6	31	6	31	6	125	25
Public and Other:	20	2	20	2	20	2	20	2	20	2	100	10
Total	302		317		333		338		343		1,635	

(1) Change in acreage for 1985-2035 does not equal the sum of acreage across the five decades due to rounding errors.

One acre of residentially zoned land will support three residential units with 80 units per year having been projected for residential development. Public and other use development is also projected to occur at a constant rate. Assuming one public and other use structure per 10 acres of such land use, two units are projected to be developed in each decade of the planning period. Since suburbanization of commercial and industrial activities has characteristically lagged behind population growth, a deferred rate of development has been adopted for this sector. Though aggregated into one sector, projections were independently prepared for commercial and for industrial use. For commercial development, two units are projected for each acre of land; thus the 75 acres projected will allow an additional 150 commercial units. For industrial development, one unit is projected for each 5 acres; thus the 125 acres of industrial land will support 25 industrial units.

All future urban development is assumed to be in compliance with FIA regulations. Since all future development will by definition occur after Project Year One, all structures are assumed to have their lowest openings floodproofed to or built above the improved IRF stage.

(2) Affluence Factor Benefits

Residential Affluence - The dollar value of residential contents has been projected to grow at a rate equal to the projected average annual growth of personal income per capita in the Buffalo Economic Area (BEA-009). Growth in residential contents was terminated when the value of contents equaled 75 percent of the value of residential structures; this constraint occurs at Project Year 27 (2012). Beyond this date, the value of residential contents were held constant throughout the remainder of the planning period.

To provide a base for projecting growth in residential contents, it was necessary to allocate existing inundation reduction benefits between residential structures and contents. Using information obtained from the 1975 damage survey, it has been estimated that damage reduction of residential contents are approximately \$274,000 (Table B42). Assuming a 2.7 percent annual compound growth rate for personal income per capita, the rate at which OBERS forecasts personal income per capita to grow in the nonmetropolitan portion of the Buffalo Economic Area, benefits attributable to contents increases to \$357,600 in Project Year One. Residential content benefits are projected to increase for 27 years reference economic base year at which point content value reaches 75 percent of structural value. In Project Year 27 (2012) residential content benefits will increase to \$734,300. This produces an undiscounted growth of content benefits of \$376,700. Discounting these values by the appropriate average annual equivalent factor (project interest rate of 7.625 percent, 100-year project life, and straight line growth for 27 years) produces discounted average annual residential affluence benefits of \$169,700 based on June 1981 prices (Table B42).

Commercial Affluence - Commercial activity is most commonly measured by retail sales.

Table B42 - Average Annual Residential Affluence Factor Benefits (June 1981 Prices)

	Average Annual Benefits (1975)	Compound Annual Rate of Growth(1)	Undiscounted Benefits at P ₁	Undiscounted Benefits at P ₂₇	Incremental Benefits P ₁ - P ₂₇	Average Annual Equivalent Factor (2)	Average Annual Residential Affluence Factor Benefits
	\$		\$	\$	\$		\$
<u>BRCM</u>							
Structures	917,100	0	917,100	917,100	0	-	-
Contents	274,000	2.7	357,600	734,300	376,700	.4505	169,700
Total	1,191,100		1,274,700	1,651,400	376,700		169,700

(1) The rate at which personal income per capita has been projected to grow in the nonmetropolitan part of BEA Economic Area 004. OBERS, Table 1, Vol. 6, p. 14.

(2) 100 percent project interest rate and 27 years of straight line growth.

The constant dollar value of retail sales in Genesee County, which contains the bulk of commercial activity in the watershed, has stagnated in recent years. In constant dollars, the volume of retail sales increased at an annual rate of only .3 percent per year between the last two Census of Business dates, 1967 and 1972. Since the level of growth in retail sales has been so low, and since future levels of commercial sales cannot be projected with any certainty, no commercial affluence benefits were credited to the proposed project. Industrial affluence - because regulations do not authorize industrial affluence benefits, none have been claimed.

Total Affluence Factor Benefits - Affluence factor benefits for the BRCM plan are summarized in Table B43.

Table B43 - Summary of Affluence Factor Benefits
(June 1981 prices)

	:	BRCM
	:	\$
Residential	:	169,700
Industrial	:	0
Commercial	:	0
Total	:	169,700

(3) Site Development Benefits

Site development benefits are savings in floodproofing costs, net of the increase in residual damages, that would have been incurred by future development but which would be avoided as a result of a plan of improvement. For commercial, industrial, and public and other use facilities, the floodproofing costs saved are generally the cost of floodproofing the structure to its lowest opening above the 100-year (IRF) flood elevation. For residential structures, the floodproofing costs saved are generally landfill savings as residential construction materials and techniques cannot usually withstand significant horizontal pressures exerted by moving flood waters.

(1) Landfill Savings - Landfill savings have been defined as the difference between the cost of landfill required without a project and the cost of landfill material required if a plan of improvement is implemented. Under existing Flood Insurance Administration regulations, new construction or substantial improvements to existing structures within the limits of the designated 100-year flood plain are required to have their lowest structural opening elevated to or above the 100-year flood stage, or, together with attendant utility or sanitary facilities, be floodproofed up to the level of the elevation of the 100-year flood.

It has been estimated that materials excavated from an average residential basement, 38 by 40 by 6 feet in depth, would provide approximately the first foot of required fill on the average residential lot. For this reason, it has been assumed that landfill savings will occur only in those reaches where the IRF stage under improved conditions is projected to decrease by more than

1 foot in comparison to the IRF stage under existing conditions. An examination of the stage frequency curves for existing and improved conditions for each reach indicates this condition would be met in only seven reaches (Table B44). In all other reaches, the decrease in the IRF stage is 1.0 foot or less. Since almost no residential and related development has been projected for these upstream reaches, no landfill savings were credited to the plan of improvement.

Table B44 - IRF Stage Reduction for Selected Reaches

Reach (1)	:Stage Reduction in Feet	
	:	BRCM
T-3	:	1.8
T-11	:	2.4
T-12	:	2.3
B-1	:	2.5
B-2 and 3	:	2.2
B-4 and 5	:	2.1
T-13	:	(2)

(1) Includes only those reaches that have more than 1.0-foot reduction in IRF stage.

(2) Improved flood water elevations are above existing due to storage effect of reservoir compound.

(2) Floodproofing Costs Avoided - Further investigation into these future urban benefits indicated that the equivalent annual discounted values were small when discounted at the project interest rate and converted to an average annual series. Projections of future flood plain development (Table S⁴⁶) and the small reduction in flood stage between the existing and improved IRF elevations in the lower watershed combine to limit discounted annual future site development savings to about \$10,000.

Residual damages were also estimated to rise over time as a result of the susceptibility of future units to floods above the improved IRF. These damages per unit were estimated by constructing stage damage relationships for structures considered to be representative of future flood plain units in terms of value, physical size, and construction materials for residential, commercial and industrial, and public and other units. Damages per unit were based upon that portion of the improved stage frequency curve for floods beyond the 1.0 percent exceedence frequency and depth-damage curves. The damage frequency relationship was integrated to obtain average annual damages per unit and this estimate was multiplied by the number of units anticipated by the end of the forecast period (2030). This absolute increase was converted to its equivalent annual value and summed for all three urban categories.

Future incremental discounted average residual damages are relatively small due to the effect of the project interest rate and the low rate of growth of floodprone structures. Future incremental average annual residual damages were approximately the same as the site development savings.

Site development savings for future urban development are offset by the increase in residual damages, therefore, no net future site development benefits have been credited to the BRCM plan.

e. Summary of Total Urban Benefits.

Residential affluence benefits are the only category of future urban benefits credited to project feasibility. A summary of project benefits is included in Table B45.

Table B45 - Summary of Total Urban Benefits
(June 1981 Prices)

	:	\$
1. <u>Existing Conditions</u>	:	
(a) Inundation Reduction (1)	:	<u>1,676,600</u>
	:	
Subtotal Existing Conditions	:	1,676,600
	:	
2. <u>Future Conditions</u>	:	
(a) Affluence Benefits	:	179,700
(b) Landfill Savings	:	<u>10,000</u>
	:	
Subtotal Future Conditions	:	169,700
	:	
3. <u>Total Urban Benefits</u>	:	1,856,300
	:	

(1) 1985 conditions of development.

B7. AGRICULTURAL FLOOD DAMAGE AND MANAGEMENT BENEFITS

Major changes have been made to the 1976 Final Feasibility Report, primarily in the areas of the recommended operating plan of the Batavia Reservoir Compound Modified. Benefits have been updated to June 1981 price levels and the project interest rate has increased to 7.625 percent since the preparation of the initial feasibility study in November 1976.

The Selected Plan from the 1976 report in this Economic Supplement is referred to as the Batavia Reservoir Compound - Modified (BRCM). Reach T-13 has been subdivided into an upper portion, which includes the area above the upper reservoir alignment (T-13U) upstream to Railroad Avenue in Alexander, NY, and a lower portion (T-13L) which includes the area between the two reservoirs.

a. Sources.

Agricultural information in this Economic Supplement has been collected from flood plain farmers, local agricultural authorities, and N.Y.S. College of Agriculture and Life Sciences at Cornell University. Local agricultural authorities include: District Manager, Genesee County Soil and Water Conservation District; SCS District Conservationists for Genesee and Erie County; New York State Cooperative Extension Regional field crop specialists.

b. General Agricultural Characteristics.

(1) Agricultural Land Use

Agricultural land use within the SPF flood plain was estimated from field surveys and interviews conducted in August 1978. The resulting pattern of crop distributions within this flood zone is presented in tabular form in Table B46. It is estimated that 19,065 acres were devoted to agriculture on the flood plain in 1978. Of this total, 23 percent (4,425 acres) was not cropped. The remaining 77 percent (14,640 acres) was distributed among seven major crop categories: corn for silage, corn for grain, wheat (winter), oats, buckwheat, hay, and miscellaneous cash crops.

Agricultural land on the flood plain has been distributed between (1) those reaches located in Erie and Niagara Counties and (2) those reaches located in Genesee County. Each area is characterized by distinct soil types with distinct capabilities. While there is significant variation among flood plain soils, the following soils predominate: the Genesee Silt Loam in Genesee County; and Hamlin, Canandaigua, Raynham Silt Loam and Rhineback Silty Clay Loam in Erie and Niagara Counties. Seventy-five percent of flood plain agricultural land is located in Niagara and Erie Counties and 25 percent of flood plain agricultural land is located in Genesee County.

(2) Crop Yields

Table B47 presents estimated crop yields for the principal crops grown on the flood plain in 1978. These yields are weighted average yields for the entire flood plain given the yields and the spatial distribution of the principal soils on the flood plain.

Table B46 - Distribution of Crops, by Acre

Crop Reach	:Corn- :Silage	:Corn-: :Grain	:Wheat: :Wheat	:Oats :Oats	:Buck-: :Wheat	:Hay :Hay	:Pas- :ture	:Misc(1) :Misc(1)	:Idle :Idle	Total
T-3	70	:	:	25	10	10	:	215	30	360
T-4	60	15	30	60	:	270	70	:	:	505
T-5	620	30	20	60	180	210	50	70	150	1,390
T-6	700	10	230	520	:	470	50	:	100	2,080
T-7	390	:	70	150	70	375	:	:	370	1,425
T-8	540	:	:	400	340	270	:	:	320	1,870
T-9	350	:	250	50	40	105	:	:	300	1,095
T-10	N E G L I G I B L E									
RB-1	40	:	:	:	20	:	:	20	60	140
RB-2	90	:	30	:	20	40	:	80	50	310
RB-3	60	:	30	:	:	340	100	345	:	875
RB-4	10	:	:	60	:	110	:	70	:	250
M-1	100	:	:	:	:	:	50	:	:	150
M-2	200	:	:	:	170	50	:	:	:	420
M-3	550	:	:	300	:	200	20	:	:	1,070
M-4	200	:	60	:	:	:	30	:	:	290
M-5	450	:	150	100	100	250	:	:	:	1,050
M-6	450	:	400	:	:	150	:	:	:	1,000
T-11	120	80	40	NEG	20	20	170	NEG	195	645
T-12	40	15	NEG	:	:	:	40	80	45	220
T-13	:	:	:	:	:	:	:	:	:	:
Lower	765	190	160	40	70	110	825	NEG	950	3,110
T-13	:	:	:	:	:	:	:	:	:	:
Upper	220	40	15	NEG	10	25	70	NEG	320	700
A-1,	:	:	:	:	:	:	:	:	:	:
2, 3	40	10	NEG	-	-	-	-	-	60	110
Total	6,065	390	1,485	1,765	1,050	3,005	1,475	880	2,950	19,065
Per-	:	:	:	:	:	:	:	:	:	:
cent	32	2	8	9	5	16	8	5	15	100

(1) Negligible amounts of other crops are indicated for each reach where appropriate.

SOURCE: Table III-1, Tonawanda Creek Watershed Agricultural Activity Study Supplemental Report prepared by RECRA Research, Inc. & Wendel Engineers.

Current yields are weighted average yields obtained by flood plain farmers. The extent to which current yields are depressed due to flooding conditions in comparison to floodfree yields represents a cost to the farm owners and operators. Flood free yields are weighted average yields which could be obtained by flood plain farmers with elimination of the flood hazard. Intensified yields are weighted average yields which could be obtained by flood plain farmers with elimination of the flood hazard and intensified management practices (additional production inputs). In accordance with Principles and Standards, flood free yields have been used as the base to calculate agricultural inundation reduction benefits. Intensified yields only affect the calculation of future agricultural benefits under project conditions.

Table B47 - Crop Yields of Principal Crops Grown
on the Flood Plain

Crop	Average Yield Per Acre (Units/Acre) (1)		
	Current	Flood Free	Intensified
Corn, Silage	11.9 Tons	17.3 Tons	21.3 Tons
Corn, Grain	61.9 Bu.	92.5 Bu.	127.5 Bu.
Mixed Hay	2.5 Tons	3.3 Tons	3.75 Tons
Winter Wheat	32.5 Bu.	46.3 Bu.	57.5 Bu.
Oats	49.4 Bu.	82.5 Bu.	102.5 Bu.
Buckwheat	10.5 Hundred Weight	10.5 Hundred Weight	10.5 Hundred Weight

(1) Weighted average yields reflect distribution of and crop yields for flood plain agricultural land in Erie, Niagara, and Genesee Counties based on predominate soil types on the flood plain in these counties.

(3) Crop Prices

In accordance with Principles and Standards, prices used in this report are the 1976 normalized values provided by the Water Resources Council. Crops not surveyed by the WRC, corn for silage, buckwheat, and winter wheat, are based upon an average price received by local farmers in the 1973-1976 period. All prices are provided in Table B48.

Table B48 - Prices of Principal Crops Grown
on the Tonawanda Creek Flood Plain

Crop	:	1976 Prices
	:	\$
Corn, silage	:	19.00 per Ton
Corn, grain	:	2.52 per Bushel
Hay, mixed	:	48.78 per Ton
Wheat, winter	:	3.15 per Bushel
Oats	:	1.65 per Bushel
Buckwheat	:	8.00 per Hundred Weight

SOURCE: Table III-3 - Unit Prices, Tonawanda Creek Watershed Agricultural Activity Study Supplemental Report prepared by RECRA Research, Inc. and Wendel Engineers (1978), and Agricultural Price Standards, U.S. Water Resource Council, Guideline 2 October 1977.

(4) Farm Schedules

The monthly flood free schedules of farm operations (Tables B49 through B55) present data on variable production costs for agriculture on the flood plain for each of the principal crops grown on the flood plain: corn for silage, corn for grain, mixed hay, winter wheat, oats, miscellaneous crops, and buckwheat. These costs were obtained through interviews of flood plain farmers and local agricultural authorities.

The monthly schedules of farm operations show monthly crop loss with consideration given to profit from a catch crop. If a crop is not totally destroyed by a damaging flood, crop loss is a percent decline in yield as specified on the individual crop schedules. For crops totally destroyed by a damaging flood, crop loss is gross revenue minus unexpended variable production cost minus profit from catch crop. Monthly crop loss values have been weighted by the percent distribution of historical floods recorded at the Alabama, NY gage on Tonawanda Creek. The resulting monthly damages summed represent potential annual damage for an acre of each crop.

Table B49 - Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: CORN SILAGE (1976 dollars per acre)

	:Jan	:Feb	:Mar	:Apr	:May	:Jun	:Jul	:Aug	:Sep	:Oct	:Nov	:Dec	:Total				
<u>Variable Production Costs</u>																	
Land Rent													20				
Land Preparation													13				
Seed				20:	3:	6:	4:						10				
Fertilizer						19:	19:						38				
Planting						2:	2:						4				
Weed/Pest Control						6:	7:						13				
Drainage																	
Irrigation																	
Cultivation							5:						5				
Harvest									12:	12:			24				
Monthly Increment					23:	38:	42:			12:	12:						
Accumulated Cost						23:	61:	103:		115:	127:						
<u>Total Variable Production Costs:</u>						127:	127:	127:	127:	127:	127:		127				
Expended																	
Unexpended						23:	61:	103:	103:	115:	127:						
							104:	66:	24:	24:	12:	0:					
<u>Gross Revenue</u>													329				
						329:	329:	329:	329:	329:	329:						
<u>Crop Loss</u>																	
						225:	263:	305:	305:	317:	329:						
<u>Profit from Catch Crop</u>																	
						169:	152:	103:	20:	0:	0:						
<u>Adjusted Crop Loss</u>																	
						56:	111:	202:	285:	305:	317:	329:					
<u>Damage Factor</u>													100.0				
						13.7:	18.6:	31.0:	18.0:	3.1:	2.5:	0:	0.6:	1.9:	0:2.5	8.1	100.0
<u>Damages</u>																	58

SOURCE: Flood plain farm owners and operators and agricultural authorities identified in Section SI of this supplement.

Table B50 - Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: CORN GRAIN (1976 dollars per acre)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
<u>Variable Production Costs</u>													
Land Rent													20
Land Preparation													13
Seed					20:								10
Fertilizer					3:	6:	4:						38
Planting						5:	5:						4
Weed/Pest Control						19:	19:						13
Drainage						2:	2:						
Irrigation						6:	7:						
Cultivation													5
Harvest										12:	6:		18
Monthly Increment						23:	38:	42:			12:	6:	
Accumulated Cost						23:	71:	103:			115:	121:	
<u>Total Variable Production Costs:</u>						121:	121:	121:	121:	121:	121:	121:	121
Expended						23:	71:	103:	103:	103:	115:	121:	
Unexpended						98:	50:	18:	18:	18:	6:	0:	
<u>Gross Revenue</u>						233:	233:	233:	233:	233:	233:	233:	233
<u>Crop Loss</u>						135:	183:	215:	215:	215:	227:	233:	
<u>Profit from Catch Crop</u>						84:	77:	42:	20:	0:	0:	0:	
<u>Adjusted Crop Loss</u>						51:	106:	173:	195:	215:	215:	227:	233:
<u>Damage Factor</u>						13.7:	18.6:	31.0:	18.0:	3.1:	2.5:	0:	2.5:8.1
<u>Damages</u>						16:	19:	5:	5:	0:	2:	4:	0:
													57

SOURCE: Flood plain farm owners and operators and agricultural authorities identified in Section S1 of this supplement.

Table B51 - Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: MIXED HAY (1976 dollars per acre)

	:Jan	:Feb	:Mar	:Apr	:May	:Jun	:Jul	:Aug	:Sep	:Oct	:Nov	:Dec	:Total
<u>Variable Production Costs</u>	:	:	:	:	:	:	:	:	:	:	:	:	:
Land Rent	:	:	:	:	:	:	:	:	:	:	:	:	:
Land Preparation	:	:	:	:	20:	:	:	:	:	:	:	:	20
Seed	:	:	:	:	4:	:	:	:	:	:	:	:	4
Fertilizer	:	:	:	:	8:	:	:	:	:	:	:	:	8
Planting	:	:	:	:	8:	:	:	:	:	:	:	:	8
Weed/Pest Control	:	:	:	:	:	:	:	:	:	:	:	:	:
Drainage	:	:	:	:	:	:	:	:	:	:	:	:	:
Irrigation	:	:	:	:	:	:	:	:	:	:	:	:	:
Cultivation	:	:	:	:	:	:	:	:	:	:	:	:	:
Harvest	:	:	:	:	:	25:	21:	17:	:	:	:	:	63
Monthly Increment	:	:	:	:	40:	25:	21:	17:	:	:	:	:	:
Accumulated Cost	:	:	:	:	40:	65:	86:	103:	:	:	:	:	:
<u>Total Variable Production Costs:</u>	103:	103:	103:	103:	103:	103:	103:	103:	103:	103:	103:	103:	103
Expended	103:	103:	103:	40:	65:	86:	103:	103:	103:	103:	103:	103:	:
Unexpended	0:	0:	0:	63:	38:	17:	17:	0:	0:	0:	0:	0:	:
<u>Gross Revenue</u>	161:	161:	161:	161:	161:	161:	161:	161:	161:	161:	161:	161:	161
<u>Crop Loss (1)</u>	64:	64:	64:	64:	64:	64:	64:	64:	64:	64:	64:	64:	64:
<u>Profit from Catch Crop</u>	0:	0:	0:	0:	0:	0:	0:	0:	0:	0:	0:	0:	0:
<u>Adjusted Crop Loss</u>	64:	64:	64:	64:	64:	64:	64:	64:	64:	64:	64:	64:	64:
<u>Damage Factor</u>	13.7:	18.6:	31.0:	18.0:	3.1:	2.5:	0:	0.6:	1.9:	0:	2.5:	8.1:	100.0
<u>Damages</u>	9:	12:	20:	11:	2:	2:	0:	0:	1:	0:	2:	5:	64

(1) Mixed hay is not replanted; it is a perennial crop in the ground for 4 years. A flood in any month will result in a 40 percent decline in yield (40 percent of gross revenue in any month equals crop loss).

SOURCE: Flood plain farm owners and operators and agricultural authorities identified in

Table B52 - Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: WINTER WHEAT (1976 dollars per acre)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
<u>Variable Production Costs</u>													
Land Rent													20
Land Preparation									20				15
Seed									15				12
Fertilizer									6				14
Planting									7				8
Weed/Pest Control									4				5
Drainage				5									
Irrigation													
Cultivation													
Harvest							6	12					18
Monthly Increment							6	12	52	17			
Accumulated Cost	69	69	69	74	74	74	80	92	52	69	69	69	
<u>Total Variable Production Costs:</u>	92	92	92	92	92	92	92	92	92	92	92	92	92
Expended	69	69	69	74	74	74	80	92	52	69	69	69	
Unexpended	23	23	23	18	18	18	12	0	40	23	23	23	
Gross Revenue	146	146	146	146	146	146	146	146	146	146	146	146	146
Crop Loss	(1)	(1)	123	128	128	128	134	146	106	123	123	(1)	
Profit from Catch Crop			20	20	20	20	0	0	10	20	20		
Adjusted Crop Loss	44	44	103	108	108	108	134	146	96	103	103	44	
Damage Factor	13.7	18.6	31.0	18.0	3.1	2.5	0	0.6	1.9	0	2.5	8.1	100.0
Damages	6	8	32	19	3	3	0	1	2	0	3	4	81

(1) Winter flood results in a 30 percent decline in yield. The plant is dormant during the winter months.

SOURCE: Flood plain farm owners and operators and agricultural authorities identified in Section S1 of this supplement.

Table B53 - Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue and Crop Loss Values: OATS (1976 dollars per acre)

	:Jan	:Feb	:Mar	:Apr	:May	:Jun	:Jul	:Aug	:Sep	:Oct	:Nov	:Dec	:Total
<u>Variable Production Costs</u>													
Land Rent													
Land Preparation				20:									20
Seed				6:	4:								10
Fertilizer				4:	6:								10
Planting					14:								14
Weed/Pest Control				4:	4:								8
Drainage						5:							5
Irrigation													
Cultivation													
Harvest								18:					18
Monthly Increment				34:	28:	5:			18:				
Accumulated Cost				34:	62:	67:		85:					
Total Variable Production Costs:				85:	85:	85:	85:	85:					85
Expended				34:	62:	67:	67:	85:					
Unexpended				51:	23:	18:	18:	0:					
Gross Revenue				136:	136:	136:	136:	136:					136
Crop Loss				85:	113:	118:	118:	136:					
Profit from Catch Crop				31:	10:	103:	20:	0:					
Adjusted Crop Loss				54:	103:	15:	98:	118:	136:				
Damage Factor				13.7:	18.6:	31.0:	18.0:	3.1:	2.5:	0:	0.6:	1.9:	8.1:
Damages				17:	19:	1:	2:	0:	1:				40

SOURCE: Flood plain farm owners and operators and agricultural authorities identified in Section SI of this supplement.

Table B54 - Monthly Flood Free Schedule of Farm Activities, Production Costs
Revenue and Crop Loss Values: BUCKWHEAT (1976 dollars per acre)

	:Jan	:Feb	:Mar	:Apr	:May	:Jun	:Jul	:Aug	:Sep	:Oct	:Nov	:Dec	:Total
<u>Variable Production Costs</u>	:	:	:	:	:	:	:	:	:	:	:	:	:
Land Rent	:	:	:	:	:	:	:	:	:	:	:	:	:
Land Preparation	:	:	:	:	:	20:	:	:	:	:	:	:	20
Seed	:	:	:	:	:	10:	:	:	:	:	:	:	10
Fertilizer	:	:	:	:	:	:	7:	:	:	:	:	:	7
Planting	:	:	:	:	:	:	7:	:	:	:	:	:	7
Weed/Pest Control	:	:	:	:	:	5:	:	:	:	:	:	:	5
Drainage	:	:	:	:	:	:	:	:	:	:	:	:	:
Irrigation	:	:	:	:	:	:	:	:	:	:	:	:	:
Cultivation	:	:	:	:	:	:	:	:	:	:	:	:	:
Harvest	:	:	:	:	:	:	:	:	:	15:	:	:	15
Monthly Increment	:	:	:	:	:	35:	14:	:	:	15:	:	:	:
Accumulated Cost	:	:	:	:	:	35:	49:	49:	49:	64:	:	:	:
<u>Total Variable Production Costs:</u>	:	:	:	:	:	64:	64:	64:	64:	64:	:	:	64
Expended	:	:	:	:	:	35:	49:	49:	49:	64:	:	:	:
Unexpended	:	:	:	:	:	29:	15:	15:	15:	0:	:	:	:
<u>Gross Revenue</u>	:	:	:	:	:	:	84:	84:	84:	84:	:	:	84
<u>Crop Loss</u>	:	:	:	:	:	55:	69:	69:	69:	84:	:	:	:
<u>Damage Factor</u>	:	:	:	:	:	:	:	:	:	:	:	:	:
	:13.7:	18.6:	31.0:	18.0:	3.1:	2.5:	0:	0.6:	1.9:	0:	2.5:	8.1:	100.0
<u>Damages</u>	:	:	:	:	:	1:	0:	1:	1:	0:	:	:	3

SOURCE: Flood plain farm owners and operators and agricultural authorities identified in
Section S1 of this supplement.

Table B55 - Monthly Flood Free Schedule of Farm Activities, Production Costs, Revenue
and Crop Loss Values: MISCELLANEOUS CROPS (1976 dollars per acre)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
<u>Total Variable Production Costs:</u>	550	550	550	550	550	550	550	550	550	550	550	550	550
<u>Gross Revenue</u>	1,050	1,050	1,050	1,050	1,050	1,050	1,050	1,050	1,050	1,050	1,050	1,050	1,050
<u>Crop Loss</u>	200	200	200	500	500	500	500	500	500	200	200	200	200
<u>Profit from Catch Crop</u>				400	200								
<u>Adjusted Crop Loss</u>	200	200	200	100	300	500	500	500	500	200	200	200	200
<u>Damage Factor</u>	13.7	18.6	31.0	18.0	3.1	2.5	0	.6	1.9	0	2.5	8.1	100.0
<u>Damages</u>	27	37	62	18	9	13	0	3	10	0	5	16	200

SOURCE: Flood plain farm owners and operators and agricultural authorities identified in Section SI of this supplement.

c. Existing Agricultural Damages and Benefits.

Agricultural inundation damages presented in this report are based on the concept of agricultural loss as previously defined. A weighted annual agricultural loss value per composite acre of sown cropland for each reach was calculated, with the weights being the percentage each crop is of total sown cropland in the reach. A stage area curve for agricultural land, which is defined as areas of sown cropland inundated from zero damage to SPF stage, was developed for each reach. These relationships were developed from the analysis of agriculture on the flood plain and by planimetering affected areas on USGS topographic maps for the SPF and IRF, the 1960 flood, and bank-full stage.

(1) Projected Growth of Agricultural Inundation Damages

The value of agricultural output on the flood plain has been rising and it is projected to continue to rise over time. This represents a regional component of a national secular trend of rising agricultural productivity and output in the future, acknowledged by Cornell University School of Agriculture and by the U. S. Water Resources Council OBERS projections, Regional Economic Activity in the U. S.

The without project agricultural damages as well as the residual damages have been estimated to grow at a rate of 2 percent per year from 1981-1985 in accordance with Cornell University estimates. Both without and with project damages have been appropriately discounted and are thus referred to as equivalent average annual damages.

(2) Average Annual Agricultural Damages, Existing Conditions

Approximate agricultural damages for existing conditions by reach were calculated by multiplying the area of affected cropland at each stage, by the weighted annual loss value per composite acre of sown cropland in the reach. An example of this calculation is presented in Tables B56 and B57. Other agricultural damages, which include damages to fences, to farm access roads and to machinery and equipment, have been estimated to be 15 percent of crop damage beginning at 1 foot above the zero damage stage. Other agricultural damages are included in the agricultural stage-damage curves. The resulting products were then computer processed using the March 1979 version of Expected Average Annual Damage Program from the Hydrologic Engineering Center (HEC) to estimate "approximate" damage-frequency relationships for each reach. For purposes of computing damages, the Standard Project Flood was assigned an occurrence frequency of once in 1,000 years. The resulting equivalent average annual damage with secular growth for each reach are presented in Table B58.

The agricultural damages produced by this process are termed "approximate" because they underestimate agricultural damage. This is because the stage-frequency curves are based on annual peaks. Field inspection indicates that these curves understate frequency of growing season agricultural damage.

(3) Average Annual Agricultural Damages, Improved Conditions

Residual average annual equivalent damages have been computed for the Batavia Reservoir Compound Modified (BRCM) using improved stage-frequency values. Computations are based upon the March 1979 version of the Expected Average Damage Program of the Hydrologic Engineering Center (HEC). Table B58 presents the residual equivalent average annual agricultural inundation damages for each reach in 1976 prices and updated to 1981 prices based upon 1978 agricultural land use.

(4) Average Annual Equivalent Agricultural Benefits, Existing Conditions

Existing equivalent average annual agricultural benefits (agricultural inundation reduction benefits) are summarized in Table B58. The BRCM is estimated to reduce average annual losses by \$443,870 at June 1981 prices.

Table B56 - Annual Agricultural Loss Calculation, Reach T-5

Crop	Existing Sown Cropland Acres	Percent	Weighted Annual Damage For Each Crop (1)	Weighted Annual Damage for One Composite Acre Reach T-5
Corn, Silage	620	52.1	58	30.2
Corn, Grain	30	2.5	57	1.4
Winter Wheat	20	1.7	81	1.4
Oats	60	5.0	40	2.0
Buckwheat	180	15.2	3	0.5
Hay, Mixed	210	17.6	64	11.3
Misc. Crops	<u>70</u>	<u>5.9</u>	200	<u>11.8</u>
Total	1,190	100.0		58.6

(1) Dollars per acre from Tables S4 - S10

Annual Damage for One Composite Acre of Cropland, Reach T-5 = 58.6

Table B57 - Calculation of Average Annual Agricultural Damages, Reach T-5

Stage	: Weighted Annual : Damage for One : Composite Acre : Cropland, Reach T-5:	:	Crop Land (Acres)	:	Total Agricultural Damage
589.0 (1)	: 58.6	:	1,190	:	69,700
588.5	: 58.6	:	1,140	:	66,800
588.4	: 58.6	:	1,125	:	65,900
587.8	: 58.6	:	1,038	:	60,800
587.4	: 58.6	:	985	:	57,700
587.0	: 58.6	:	915	:	53,600
586.4	: 58.6	:	800	:	46,900
586.0	: 58.6	:	725	:	42,500
585.4	: 58.6	:	585	:	34,300
585.0	: 58.6	:	490	:	28,700
584.4	: 58.6	:	350	:	20,500
584.0	: 58.6	:	250	:	14,700
583.4	: 58.6	:	100	:	5,900
583.0	: 58.6	:	0	:	0

(1) The SPF Stage

Table B58 - Summary of Existing Average Annual Equivalent Agricultural Damages and Benefits (1978 Land Use Patterns)

Reach	Existing Damages	BRCM		Benefits June 1981 Prices
		Residual Damages	Benefits 1976 Prices	
T-1	(1)	(1)	(1)	(1)
T-2	(1)	(1)	(1)	(1)
T-3	2,580	210	2,370	3,400
T-4	140	20	130	190
T-5	29,580	6,480	23,090	33,160
T-6	112,340	41,630	70,710	101,540
T-7	32,670	7,370	25,300	36,330
T-8	79,770	22,390	57,380	82,400
T-9	53,910	13,110	40,790	58,570
T-10		Negligible Amount of Cropland:		
RB-1	1,340	490	860	1,230
RB-2	2,510	750	1,760	2,530
RB-3	47,940	15,640	32,300	46,380
RB-4	23,390	6,440	16,960	24,360
M-1	140	40	100	140
M-2	4,240	1,630	2,610	3,750
M-3	5,370	1,390	3,980	5,720
M-4	1,480	460	1,020	1,470
M-5	20,740	7,670	13,070	18,770
M-6	17,800	5,920	11,880	17,060
T-11	2,170	170	2,000	2,870
T-12	4,340	570	3,770	5,410
T-13L	28,590	29,580	-980	-1,410
T-13U	(2)	(2)	(2)	(2)
A-1	(2)	(2)	(2)	(2)
A-2	(2)	(2)	(2)	(2)
A-3	(2)	(2)	(2)	(2)
Total	471,050	161,960	309,090	443,870

(1) Nonagricultural reaches

(2) These reaches are upstream of the upper dam.

NOTE: Totals may not add due to rounding.

d. Future Agricultural Land Use and Benefits.

(1) Future Land Use

Analysis of cropping patterns in the Tonawanda Creek flood plain under existing flooding conditions (Table B46) indicates that land subject to flooding once in 3 years or more frequently, currently is used as pasture or for production of buckwheat; both are low value uses. Land which is subject to flooding less frequently is used for high value field and vegetable crops. Flood plain farm owners, farm operators, and related regional agricultural authorities (Soil Conservation Service personnel, local conservation district personnel, and New York State Agricultural Extension Service field crop specialists) indicate this land use pattern will be maintained under project conditions.

Future land use patterns have been estimated using the reduction in flood frequency as well as information collected from the above named agricultural authorities. Table B59 presents a reach by reach illustration of: flood event where damage begins under project conditions; total acres in pasture, idle, and buckwheat; acres pasture, idle, and buckwheat shifted to higher use. Future land use in the flood plain is shown in Table B60. It has been projected that 80 percent of flood free (existing condition) buckwheat, idle, and pasture will be shifted to a higher use under project (improved) conditions. This shift in land use is estimated to occur at a linear rate over the 10-year period, 1985 through 1994.

(2) Intensified Management

Based on information from flood plain farm owners and operators and the above named agricultural authorities, land projected to shift upward in use from pasture and buckwheat to high value crops has been projected to be managed more intensively under project (improved) conditions. Additional drainage measure, fertilizer, herbicides, and seed expenditures will result in higher returns (profit per acre). Like the upward shift in land use, the intensified management practices are projected to be implemented over the 10-year period 1985-1994 under project conditions.

(3) Intensified Farm Schedules

Monthly schedules of intensified operation (Tables B61 through B65) present data on gross revenue, total variable production costs and crop loss for each of the principal crops grown on the flood plain which are subject to intensified management - corn for silage, corn for grain, mixed hay, winter wheat and oats; buckwheat and miscellaneous crops have not been intensified.

Table B59 - Shift of Flood Plain Land to Higher Use

Reach	Flood Event Where Damage Begins (Project Conditions)	Total Acres Pasture, Idle, Buckwheat (Without Project Conditions)	Acres, Pasture, Idle, and Buckwheat Shifted to Higher Use
T-1	(1)	(1)	(1)
T-2	(1)	(1)	(1)
T-3	18.0 year	40	0
T-4	180.0 year	70	0
T-5	4.4 year	380	304
T-6	1.4 year	150	82
T-7	3.2 year	440	352
T-8	1.8 year	660	418
T-9	2.6 year	340	250
RB-1	4.8 year	80	64
RB-2	3.7 year	70	56
RB-3	3.2 year	100	80
RB-4	3.8 year	0	0
M-1	7.5 year	50	40
M-2	6.7 year	170	136
M-3	19.0 year	20	16
M-4	6.5 year	30	24
M-5	4.7 year	100	80
M-6	9.5 year	0	0
T-11	33.0 year	385	308
T-12	13.0 year	85	68
T-13L	(2)	1,845	1,476
T-13U	(3)	(3)	(3)
A-1	(3)	(3)	(3)
A-2	(3)	(3)	(3)
A-3	(3)	(3)	(3)
Total		5,015	3,754

(1) Nonagricultural reaches

(2) The clearing and snagging operation needed to assure safe operation of the lower reservoir will increase channel capacity in reach T13-L from about 500 cfs to 2,000 cfs under project conditions significantly reducing flooding during the growing season.

(3) These reaches are located upstream of the upper dam.

Table B60 - Future (Shifted) Distribution of Crops, by Acre

Crop Reach	:Corn-Silage	:Corn-Grain	:Wheat	:Oats	:Buck-Wheat	:Mixed Hay	:Misc. Crops	:Pasture and Idle	:Total
T-3	70	0	0	25	10	10	215	30	360
T-4	60	15	30	60	0	270	0	70	505
T-5	806	42	55	95	36	246	70	40	1,390
T-6	749	13	240	530	0	480	0	68	2,080
T-7	604	14	112	191	14	416	0	74	1,425
T-8	796	16	49	449	125	318	0	117	1,870
T-9	502	10	280	79	10	134	0	80	1,095
T-10	N E G L I G I B L E								
RB-1	78	2	8	8	4	8	20	12	140
RB-2	124	2	37	7	4	46	80	10	310
RB-3	109	3	40	9	0	349	345	20	875
RB-4	10	0	0	60	0	110	70	0	250
M-1	124	2	5	5	0	4	0	10	150
M-2	283	5	16	16	34	66	0	0	420
M-3	559	1	2	302	0	202	0	4	1,070
M-4	215	1	63	3	0	2	0	6	290
M-5	499	3	160	109	20	259	0	0	1,050
M-6	450	0	400	0	0	150	0	0	1,000
T-11	250	88	66	26	4	46	92	73	645
T-12	68	17	6	6	0	6	100	17	220
T-13									
Lower T-13	1,389	230	183	163	14	333	443	355	3,110
Upper A-1, 2, 3	220	40	15	NEG	10	25	NEG	390	700
	40	10	NEG	-	-	-	-	60	110
Total	8,005	514	1,767	2,143	285	3,480	1,435	1,436	19,065
Percent	42	3	9	11	1	18	8	8	100

Table B61 - Monthly Schedule of Intensified Farm Activities, Production Costs, Revenue and Crop Loss Values: CORN SILAGE (1976 dollars per acre)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
<u>Variable Production Costs</u>													
Land Rent													20
Land Preparation			20										13
Seed			3	6	4								10
Fertilizer (1)				5	5								48
Planting				24	24								4
Weed/Pest Control (2)				2	2								17
Drainage (3)			22	8	9								22
Irrigation													5
Cultivation					5								24
Harvest									12	12			
Monthly Increment			45	45	49				12	12			
Accumulated Cost			45	90	139	139	139	139	151	163			163
<u>Total Variable Production Costs:</u>			163	163	163	163	163	163	163	163			
Expended			45	90	139	139	139	139	151	163			
Unexpended			118	73	24	24	24	24	12	0			
<u>Gross Revenue</u>			405	405	405	405	405	405	405	405			405
<u>Crop Loss</u>			287	332	381	381	381	381	393	405			
<u>Profit from Catch Crop</u>			201	181	120	20	0	0	0	0			
<u>Adjusted Crop Loss</u>			86	151	261	361	381	381	393	405			
<u>Damage Factor</u>	13.7	18.6	31.0	18.0	3.1	2.5	0	0.6	1.9	0	2.5	8.1	
<u>Damages</u>			27	27	8	9	0	2	7	0			80

(1) 25 percent increase in fertilizer expenditures.

(2) 30 percent increase in weed/pest control expenditures.

(3) \$300/acre for drainage tiles, amortized at prime rate charged by banks average effective rate for the year 1976 (Source: Economic Report of the President, p. 278).

Table B62 - Monthly Schedule of Intensified Farm Activities, Production Costs, Revenue and Crop Loss Values: CORN SILAGE (1976 dollars per acre)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
<u>Variable Production Costs</u>													
Land Rent													20
Land Preparation			20										13
Seed			3	6	4								10
Fertilizer (1)				5	5								48
Planting				24	24								4
Weed/Pest Control (2)				2	2								17
Drainage (3)			22	8	9								22
Irrigation													
Cultivation					5								5
Harvest										12	6		18
Monthly Increment			45	45	49					12	6		
Accumulated Cost			45	90	139	139	139	139	139	151	157		157
<u>Total Variable Production Costs:</u>			157	157	157	157	157	157	157	157	157		
Expended			45	90	139	139	139	139	139	151	157		
Unexpended			112	67	18	18	18	18	18	6	0		
Gross Revenue			321	321	321	321	321	321	321	321	321		321
Crop Loss													
Profit from Catch Crop			209	254	303	303	303	303	303	315	321		
Adjusted Crop Loss			132	116	68	20	0	0	0	0	0		
Damage Factor			77	138	235	283	303	303	303	315	321		
Damages													
	13.7	18.6	31.0	18.0	3.1	2.5	0	0.6	1.9	0	2.5	8.1	100.0
			24	25	7	7	0	2	6	0	8		79

(1) 25 percent increase in fertilizer expenditures.

(2) 30 percent increase in weed/pest control expenditures.

(3) \$300/acre for drainage tiles, amortized at prime rate charged by banks average effective rate for the year 1976 (Source: Economic Report of the President, p. 278).

Table B63 - Monthly Schedule of Intensified Farm Activities, Production Costs, Revenue and Crop Loss Values: MIXED HAY (1976 dollars per acre)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
<u>Variable Production Costs</u>													
Land Rent													
Land Preparation				20									20
Seed (1)				4									4
Fertilizer (2)				12									12
Planting				10									10
Weed/Pest Control													
Drainage (3)				22									22
Irrigation													
Cultivation													
Harvest					25		21		17				63
Monthly Increment				68	25		21		17				
Accumulated Cost				68	93	93	114	114	131				131
<u>Total Variable Production Costs:</u>	131	131	131	131	131	131	131	131	131	131	131	131	
Expended	131	131	131	68	93	93	114	114	131	131	131	131	
Unexpended	0	0	0	63	38	38	17	17	0	0	0	0	
Gross Revenue	183	183	183	183	183	183	183	183	183	183	183	183	183
<u>Crop Loss</u>	73	73	73	73	73	73	73	73	73	73	73	73	
Profit from Catch Crop	0	0	0	0	0	0	0	0	0	0	0	0	
<u>Adjusted Crop Loss</u>	73	73	73	73	73	73	73	73	73	73	73	73	
<u>Damage Factor</u>	13.7	18.6	31.0	18.0	3.1	2.5	0	0.6	1.9	0	2.5	8.1	
<u>Damages</u>	10	14	23	13	2	2	0	0	1	0	2	6	73

(1) 50 percent increase in seed cost.

(2) 25 percent increase in fertilizer expenditures.

(3) \$300/acre for drainage tiles.

Amortized at prime rate charged by banks average effective rate for the year 1976.

(Source: Economic Report of the President, p. 278)

NOTE: A flood in any month will result in a 40 percent decline in yield.

Table B64 - Monthly Schedule of Intensified Farm Activities, Production Costs,
Loss Values: MIXED HAY (1976 dollars per acre)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
<u>Variable Production Costs</u>													
Land Rent													20
Land Preparation									20				15
Seed									15				12
Fertilizer (1)									6	6			18
Planting									9	9			8
Weed/Pest Control (2)					7				4	4			7
Drainage (3)									22				22
Irrigation													
Cultivation													
Harvest							6	12					18
Monthly Increment					7		6	12	76	19			
Accumulated Cost	95	95	95	102	102	102	108	120	76	95	95	95	120
<u>Total Variable Production Costs:</u>	120	120	120	120	120	120	120	120	120	120	120	120	
Expended	95	95	95	102	102	102	108	120	76	95	95	95	
Unexpended	25	25	25	18	18	18	12	0	44	25	25	25	
<u>Gross Revenue</u>	181	181	181	181	181	181	181	181	181	181	181	181	181
<u>Crop Loss</u>													
	54	54	54	156	163	163	169	181	137	156	156	54	
<u>Profit from Catch Crop</u>													
	0	0	0	20	20	20	0	0	7	20	20	0	
<u>Adjusted Crop Loss</u>													
	54	54	54	136	143	143	169	181	130	136	136	54	
<u>Damage Factor</u>													
	13.7	18.6	31.0	18.0	3.1	2.5	0	0.6	1.9	0	2.5	8.1	100.0
<u>Damages</u>													
	7	10	42	26	4	4	0	1	2	0	3	4	103

(1) 25 percent increase in fertilizer expenditures.

(2) 30 percent increase in weed/pest control expenditures.

(3) \$300/acre for drainage tiles, amortized at prime rate charged by banks average effective rate for the year 1976 (Source: Economic Report of the President, p. 278)

NOTE: A flood in the months of December-February will result in a 30 percent decline in yield.

Table B65 - Monthly Schedule of Intensified Farm Activities, Production Costs, Revenue and Crop Loss Values: OATS (1976 dollars per acre)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
<u>Variable Production Costs</u>													
Land Rent													20
Land Preparation													10
Seed				4									10
Fertilizer (1)				6									18
Planting				9									8
Weed/Pest Control (2)				4									7
Drainage (3)					7								22
Irrigation				22									
Cultivation													
Harvest								18					18
Monthly Increment													
Accumulated Cost				65	23	7		18					113
<u>Total Variable Production Costs:</u>				65	88	95	95	113					
Expended				113	113	113	113	113					
Unexpended				65	88	95	95	113					
Gross Revenue				48	25	18	18	0					
Crop Loss				169	169	169	169	169					169
Profit from Catch Crop				121	144	151	151	169					
Adjusted Crop Loss				31	5	110	20	0					
Damage Factor				90	139	41	131	151	169				
Damages													
	13.7	18.6	31.0	18.0	3.1	2.5	0	0.6	1.9	0	2.5	8.1	100.0
				28	25	1	3	0	1				58

(1) 25 percent increase in fertilizer expenditures.

(2) 30 percent increase in weed/pest control expenditures.

(3) \$300/acre for drainage tiles, amortized at prime rate charged by banks average effective rate for the year 1976 (Source: Economic Report of the President, p. 278).

(4) Future Agricultural Benefits

Future agricultural benefits attributed to the Tonawanda Creek are increased profits less the increase in residual damages attributed to the shift in land use and intensified farm management. Table B66 presents the increase in gross profit, the increase in residual damages and the resulting benefit attributed to the project in the future. The increase in gross profit as well as the increase in residual damages presented in Table B66 have been estimated to grow at a rate of 2 percent per year for the period 1981-1995 in accordance with trend of rising agricultural output and productivity previously documented (p. B-96, Projected Growth of Agricultural Inundation Damages). These benefits, as presented in Table B66, are projected to accrue at a linear rate over a 10-year period ($P_0 - P_{10}$) and are appropriately discounted at the project interest rate. The discounted average annual benefits at 1981 price levels amount to \$1,000,280.

Table B66 - Future Agricultural Benefits (June 1981 Prices)

Reach	: Discounted : Increase in : Gross Profit : (1976 Prices):	: Discounted : Increase in : Residual Damages: : (1976 Prices):	: Future : Agricultural : Benefits : (1976 Prices):	: Future : Agricultural : Benefits : (1981 Prices)
	: \$: \$: \$: \$
T1-10	: 228,050	: 24,190	: 203,860	: 292,740
RB1-4	: 32,280	: 1,210	: 31,070	: 44,620
M1-6	: 45,460	: 2,090	: 43,370	: 62,280
T11-13	: <u>484,150</u>	: <u>65,880</u>	: <u>418,270</u>	: <u>600,640</u>
Total	: 789,940	: 93,370	: 696,570	: 1,000,280

e. Summary of Agricultural Benefits.

Table B67 summarizes estimated average annual agricultural benefits. Construction of the BRCM would result in total agricultural benefits of \$1,444,200.

**Table B67 - Summary of Average Annual Agricultural Benefits
(June 1981 Prices)**

	:	BRCM
	:	\$
<u>Existing Conditions</u>	:	
Inundation Reduction Benefits	:	443,900
<u>Future Benefits</u>	:	
Shift in Land Use and Intensification Benefits	:	1,000,300
<u>Total Agricultural Benefits</u>	:	1,444,200

For purposes of comparison equivalent average annual damage, annual net income, and annual gross revenue per composite acre are presented in Table B68.

Table B68 - Summary Values for Composite Acre

	:	June 1981 Prices
	:	\$
<u>Existing (Flood Free) Conditions</u>	:	
Equivalent Average Annual Existing Damages/Acre	:	47
Annual Net Income per Acre	:	201
Annual Gross Revenue per Acre	:	396
<u>Future (Intensified) Conditions</u>	:	
Average Annual Future Benefits/Acre (Gross Profit/Acre - Residual Damage/Acre):	:	58
Annual Net Income per Acre	:	254
Annual Gross Revenue per Acre	:	507

f. Sensitivity Analysis.

As a sensitivity test, the without project agricultural damages, as well as the residual damages, have been estimated to grow at a rate of 1.53 percent per year from 1981-1985. The 1.53 percent annual growth rate used to approximate secular growth was derived from OBERS (1972), Vol. I, Tables C2 and C7. Both without and with project damages have been appropriately discounted and thus are equivalent average annual damages. Table B69 presents a comparison of agricultural benefits with 2 percent and 1.53 percent secular growth rates. Use of the latter would reduce total average annual benefits by \$84,300 or 2.6 percent of the original estimate.

Table B69 - Comparison of Agricultural Benefits Varying Secular Growth
(June 1981 Prices, 7-5/8 Percent Interest Rate)

	: Two Percent	: 1.53 Percent
	: Growth Rate	: Growth Rate
	: \$: \$
Existing Inundation Reduction Benefits	: 443,900	: 421,700
Future Agricultural Benefits	: 1,000,300	: 938,200
Total Agricultural Benefits	: 1,444,200	: 1,359,900
Total Average Annual Benefits for BRCM	: 3,290,500	: 3,206,200
Total Average Annual Costs for BRCM	: 2,490,000	: 2,490,000
Net Benefits	: 800,500	: 716,200
Benefit/Cost Ratio	: 1.32	: 1.29


B8. ECONOMIC EFFICIENCY


Table B70 presents a summary of average annual benefits, average annual costs, net benefits and the benefit-cost ratio. Net benefits are \$810,500, and the benefit-cost ratio is 1.33.

Table B70 - Summary of Total Benefits
June 1981 Prices, 7-5/8 Percent Interest Rate
1985 Conditions of Development

	:	\$
1. <u>Existing Conditions</u>	:	
a. Agriculture Damage Reduction (1):	:	443,900
b. Urban Damage Reduction	:	1,676,600
c. Area Redevelopment	:	-
d. Subtotal Existing Benefits	:	2,120,500
2. <u>Future Conditions</u>	:	
a. Future Agricultural Benefits (1):	:	1,000,300
b. Future Urban	:	179,700
c. Subtotal Future Benefits	:	1,180,000
3. <u>Total Benefits for BRCM</u>	:	3,300,500
4. <u>Average Annual Costs</u>	:	2,490,000
5. <u>Net Benefits</u>	:	810,500
6. <u>Benefit-Cost Ratio</u>	:	1.33

(1) Agricultural benefits reflect 1978 land use patterns and June 1981 prices.





LEGEND


- URBAN
- RURAL
- FARM
- OPEN SPACE
- INDIAN RESERVATION
- STATE WILDLIFE LANDS


TONAWANDA CREEK WATERSHED, NEW YORK


EXISTING LAND USE

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED 10-79

PLATE 62








AD-A133 910


BUFFALO METROPOLITAN AREA NEW YORK WATER RESOURCES
MANAGEMENT INTERIM REP. (U) CORPS OF ENGINEERS BUFFALO
NY BUFFALO DISTRICT JUL 83

5/9


UNCLASSIFIED

F/G 13/2 NL






MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A




TONAWANDA CREEK WATERSHED, NEW YORK
 ERIE PLAIN FLOODLAND
 (UPPER WATERSHED)
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 IN ACCORDANCE WITH REPORT
 OF 12-1972

ALEXANDER TO ATTICA
 SCALE OF 1:50,000

BATAVIA TO ALEXANDER
 SCALE OF 1:50,000








TONAWANDA CREEK WATERSHED, NEW YORK


PROPOSED CON RAIL AND CHESSIE LINES


U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979


















































ELEVATION IN FEET - U.S. DATUM

1960

DAMAGE IN MILLIONS OF DOLLARS

NOTES:

ALL DAMAGES ARE BASED ON DECEMBER 1975
PRICE LEVELS AND CONDITIONS OF DEVELOPMENT.
REACH LIMITS, MILE 2.4 TO 4.9

LEGEND:

- RESIDENTIAL
- PUBLIC AND OTHER
- COMMERCIAL


TONAWANDA CREEK WATERSHED, NEW YORK


STAGE - DAMAGE CURVES


RANSOM AND BLACK CREEKS


INDEX POINT RB-2 AT MILE 4.9


U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979















NOTES:


ALL DAMAGES ARE BASED ON DECEMBER 1975
PRICE LEVELS AND CONDITIONS OF DEVELOPMENT.
REACH LIMITS, WALNUT STREET TO LOWER
PENN CENTRAL RAILROAD BRIDGE.


LEGEND:

- RESIDENTIAL
- - - PUBLIC AND OTHER
- ... COMMERCIAL

TONAWANDA CREEK WATERSHED, NEW YORK
STAGE - DAMAGE CURVES
TONAWANDA CREEK
INDEX POINT B-2 AT MILE 65.1
KIBBE PARK BETWEEN
ELMWOOD AND JACKSON AVES.
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: 1979







NOTES:

ALL DAMAGES ARE BASED ON DECEMBER 1975
PRICE LEVELS AND CONDITIONS OF DEVELOPMENT.
REACH LIMITS, LOWER PENN CENTRAL RAIL-
ROAD BRIDGE TO CHESTNUT STREET, RIGHT BANK.

LEGEND:

--- RESIDENTIAL
— PUBLIC AND OTHER
... COMMERCIAL

TONAWANDA CREEK WATERSHED, NEW YORK

STAGE - DAMAGE CURVES

TONAWANDA CREEK

INDEX POINT B-5 AT MILE 64.5


DOWNSTREAM FACE OF CHESTNUT ST. BR.


U.S. ARMY ENGINEER DISTRICT, BUFFALO


TO ACCOMPANY REPORT DATED: 1979

ELEVATION IN FEET - U.S.C. & G.S. DATUM

PLATE 53B








NOTES:

ALL DAMAGES ARE BASED ON DECEMBER 1976
 PRICE LEVELS AND CONDITIONS OF DEVELOPMENT.
 REACH LIMITS, PROSPECT AVENUE UPSTREAM
 TO MAIN STREET.

TONAWANDA CREEK WATERSHED, NEW YORK

STAGE - DAMAGE CURVES

TONAWANDA CREEK
 INDEX POINT A-2 AT MILE 81.6
 UPSTREAM FACE OF PROSPECT ST. BR.
 U.S. ARMY ENGINEER DISTRICT, BUFFALO
 TO ACCOMPANY REPORT DATED: 1979



NOTES:

ALL DAMAGES ARE BASED ON DECEMBER 1976
PRICE LEVELS AND CONDITIONS OF DEVELOPMENT.
REACH LIMITS, MAIN STREET UPSTREAM TO
DUNBAR ROAD.

TONAWANDA CREEK WATERSHED, NEW YORK

STAGE - DAMAGE CURVES

TONAWANDA CREEK

INDEX POINT A-3 AT MILE 82.4

UPSTREAM FACE OF MAIN ST. BRIDGE

U.S. ARMY ENGINEER DISTRICT, BUFFALO

TO ACCOMPANY REPORT DATES: 1976

BUFFALO METROPOLITAN AREA, NEW YORK
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

APPENDIX C

COST ESTIMATES

FOR

ALTERNATIVE PLANS

U. S. Army Corps of Engineers
Buffalo District
Buffalo, New York

FOREWORD

All estimates of costs presented in this appendix are based on December 1975 prices. All estimates of average annual costs are based on 100-year economic life and an interest rate of 6-1/8 percent per annum.

TABLE OF CONTENTS

<u>Item</u>	<u>Page</u>
C1. NON-STRUCTURAL BASE PLAN	
1. N.-S. Property Cost	C1
2. N.-S. Construction Cost	C1
3. Summary of First Cost of N.-S. Base Plan	C2
4. Average Annual Cost of N.-S. Base Plan	C2
C2. SIERKS RESERVOIR - LINDEN RESERVOIR	
1. S.R.-L.R. Property Cost	
a. Sierks Reservoir	C3
b. Linden Reservoir	C3
c. S.R.-L.R. Plan	C3
2. S.R.-L.R. Construction Cost	
a. Sierks Reservoir	C4
b. Linden Reservoir	C4
c. S.R.-L.R. Plan	C5
3. Summary of First Cost of S.R.-L.R. Plan	C5
4. Average Annual Cost of S.R.-L.R. Plan	C5
C3. SIERKS RESERVOIR - ALABAMA RESERVOIR COMPOUND	
1. S.R.-A.R.C. Property Cost	
a. Sierks Reservoir	C6
b. Alabama Reservoir Compound	C6
c. S.R.-A.R.C. Plan	C6
2. S.R.-A.R.C. Construction Cost	
a. Sierks Reservoir	C7
b. Alabama Reservoir Compound	C7
c. S.R.-A.R.C. Plan	C8
3. Summary of First Cost of S.R.-A.R.C. Plan	C8
4. Average Annual Cost of S.R.-A.R.C. Plan	C8

TABLE OF CONTENTS (Cont'd)

<u>Item</u>	<u>Page</u>
C4. ALEXANDER RESERVOIR	
1. A.R. Property Cost	C9
2. A.R. Construction Cost	C9
3. Summary of First Cost of A.R. Plan	C11
4. Average Annual Cost of A.R. Plan	C11
C5. BATAVIA RESERVOIR COMPOUND	
1. B.R.C. Property Cost	
a. Upper Reservoir	C12
b. Lower Reservoir	C12
c. B.R.C. Plan	C12
2. B.R.C. Construction Cost	
a. Upper Reservoir	C13
b. Lower Reservoir	C14
c. B.R.C. Plan	C16
3. Summary of First Cost for B.R.C. Plan	C17
4. Average Annual Cost for B.R.C. Plan	C17
C6. BATAVIA RESERVOIR	
1. B.R. Property Cost	C18
2. B.R. Construction Cost	C18
3. Summary of First Cost for B.R. Plan	C20
4. Average Annual Cost for B.R. Plan	C21
C7. BATAVIA RESERVOIR - ALABAMA RESERVOIR COMPOUND	
1. B.R.-A.R.C. Property Cost	
a. Batavia Reservoir	C22
b. Alabama Reservoir Compound	C22
c. B.R.-A.R.C. Plan	C23
2. B.R.-A.R.C. Construction Cost	
a. Batavia Reservoir	C23
b. Alabama Reservoir Compound	C25
c. B.R.-A.R.C. Plan	C26

TABLE OF CONTENTS (Cont'd)

<u>Item</u>	<u>Page</u>
3. Summary of First Cost of B.R.-A.R.C. Plan	C26
4. Average Annual Cost of B.R.-A.R.C. Plan	C26
C8. BATAVIA PROJECT MODIFICATION	
1. B.P.M. Property Cost	C27
2. B.P.M. Construction Cost	C27
3. Summary of First Cost for B.P.M. Plan	C28
4. Average Annual Cost for B.P.M. Plan	C29

C1. NON-STRUCTURAL BASE PLAN

1. N.-S. Property Cost.

Item	Estimated Quantity	Unit	Estimated Cost
Purchase of Residential Buildings (fee simple)			
Attica through Alexander	0	each	\$ 0
Batavia through Bushville	74	each	2,960,000
Bushville to Hopkins Road	15	each	450,000
Hopkins Road to Sweet Home Road	47	each	1,880,000
Sweet Home Road to Con- fluence with Ellicott Creek	0	each	0
Ransom and Black Creek	4	each	180,000
Mud Creek	0	each	0
PLAN SUBTOTAL			\$5,470,000
Property Acquisition (10% of Property Cost)			547,000
PLAN TOTAL			\$6,017,000

2. N.-S. Construction Cost.

Item	Estimated Quantity	Unit	Estimated Cost
Floodproofing (residential)			
Attica through Alexander	20	each	\$ 63,100
Batavia through Bushville	1891	each	4,352,500
Bushville to Hopkins Road	85	each	265,400
Hopkins Road to Sweet Home Road	358	each	923,000
Sweet Home to Confluence with Ellicott Creek	1738	each	3,654,000
Ransom and Black Creek	345	each	796,300
Mud Creek	70	each	182,400
PLAN SUBTOTAL			\$10,236,700

2. N.-S. Construction Cost. (Cont'd)

Item	: Estimated	: Unit	: Estimated
	: Quantity		: Cost
Contingencies (25%)	:	:	: <u>2,559,200</u>
PLAN SUBTOTAL	:	:	: \$12,795,900
Engineering & Design (10%)	:	:	: 1,279,600
Supervision & Admin. (8.5%)	:	:	: <u>1,087,600</u>
PLAN TOTAL	:	:	: \$15,163,100

3. Summary of First Cost of N.-S. Base Plan.

Item	: Amount
Total Property Cost	: \$ 6,017,000
Total Construction Cost	: <u>15,163,100</u>
GRAND TOTAL	: \$21,180,100

4. Average Annual Cost of N.-S. Base Plan.

Item	: Amount
Amortization (.0614)	: \$ 1,300,500
Operation and Maintenance	: <u>115,000</u>
GRAND TOTAL	: \$ 1,415,500

C2. SIERKS RESERVOIR - LINDEN RESERVOIR

1. S.R.-L.R. Property Cost.

a. Sierks Reservoir.

Item	: Estimated : : Quantity :	: Unit :	: Estimated Cost
Land (fee simple)	: 1,100	: acre	: \$ 550,000
Buildings (residential)	: 26	: job	: 910,000
Farms (plant and equip.)	: 7	: job	: <u>700,000</u>
COMPONENT TOTAL	:	:	: \$ 2,160,000

b. Linden Reservoir.

Item	: Estimated : : Quantity :	: Unit :	: Estimated Cost
Land (fee simple)	: 1,200	: acre	: \$ 600,000
Buildings (residential)	: 23	: job	: 805,000
Buildings (public and other)	: 1	: job	: 100,000
Farms (plant and equip.)	: 4	: job	: <u>400,000</u>
COMPONENT TOTAL	:	:	: \$ 1,905,000

c. S.R.-L.R. Plan.

Item	: Amount
S.R. Component Total	: \$2,160,000
L.R. Component Total	: <u>1,905,000</u>
PLAN SUBTOTAL	: \$4,065,000
Property Acquisition (10% of Property Cost)	: <u>406,500</u>
PLAN TOTAL	: \$4,471,500

2. S.R.-L.R. Construction Cost.

a. Sierks Reservoir.

Item	: Estimated : Quantity	: Unit	: Unit : Cost	: Estimated : Cost
Care of Water	: 1	: l.s.	: \$ 158,000	: \$ 158,000
Clearing and Grubbing	: 1	: l.s.	: 31,600	: 31,600
Relocations (Rte. 98)	: 4.5	: mile	: 526,500	: 2,369,250
Common Excavation	: 181,500	: c.y.	: 2.50	: 453,750
Stripping	: 33,000	: s.y.	: 0.65	: 21,450
Line Drilling	: 20,500	: c.y.	: 5.25	: 107,625
Rock Excavation	: 173,000	: c.y.	: 7.40	: 1,280,200
Compacted Random Fill	: 697,000	: c.y.	: 2.50	: 1,742,500
Compacted Filter and Transition Material	: 24,000	: c.y.	: 10.00	: 240,000
Rock Fill	: 34,000	: c.y.	: 26.30	: 894,200
Unreinforced Concrete	: 94,000	: c.y.	: 100.00	: 9,400,000
Reinforced Concrete	: 16,300	: c.y.	: 125.00	: 2,037,500
Tainter Gates	: 4	: each	: 131,625	: 526,500
Slide Gates	: 10	: each	: 63,180	: 631,800
Service Bridge	: 1	: each	: 94,770	: 94,770
Miscellaneous Items	: 1	: l.s.	: \$1,474,200	: \$ 1,474,200
Mobilization and Demobilization	: 1	: l.s.	: 1,092,000	: 1,092,000
COMPONENT TOTAL	:	:	:	: \$22,939,345

b. Linden Reservoir.

Item	: Estimated : Quantity	: Unit	: Unit : Cost	: Estimated : Cost
Relocation (cemetery)	: 1	: l.s.	: 36,800	: \$ 36,800
Relocation (county roads)	: 1	: mile	: 579,000	: 579,100
Relocations (phone and power)	: 1	: mile	: 7,400	: 7,400
Clearing and Grubbing	: 103	: acre	: 2,000	: 206,000
Compacted Impervious Fill	: 350,000	: c.y.	: 4.00	: 1,400,000
Principal Spillway	: 1	: l.s.	: 4,393,000	: 4,393,000
Mobilization and Demobilization	: 1	: l.s.	: 331,000	: 331,000
COMPONENT TOTAL	:	:	:	: \$6,953,300

2. S.R.-L.R. Construction Cost. (Cont'd)

c. S.R.-L.R. Plan.

Item	:	Amount
S.R. Component Total	:	\$22,939,345
L.R. Component Total	:	<u>6,953,300</u>
PLAN SUBTOTAL	:	\$29,892,600
Contingencies (15%)	:	<u>4,483,900</u>
PLAN SUBTOTAL	:	\$34,376,500
Engineering & Design (10%)	:	3,437,700
Supervision & Administration (7.5%)	:	2,578,200
Interest During Construction (6-1/8%)	:	<u>2,105,600</u>
PLAN TOTAL	:	\$42,498,000

3. Summary of First Cost for S.R.-L.R. Plan.

Item	:	Amount
Total Property Cost	:	\$ 4,471,500
Total Construction Cost	:	<u>42,498,000</u>
GRAND TOTAL	:	\$46,969,500

4. Average Annual Cost for S.R.-L.R. Plan.

Item	:	Amount
Amortization (.0614)	:	\$ 2,883,900
Operation and Maintenance	:	<u>100,000</u>
GRAND TOTAL	:	\$ 2,983,900

C3. SIERKS RESERVOIR - ALABAMA RESERVOIR COMPOUND

1. S.R.-A.R.C. Property Cost.

a. Sierks Reservoir.

Item	: Estimated : : Quantity :	: Unit :	: Estimated : Cost :
Land (fee simple)	: 1,100	: acre	: \$ 550,000
Buildings (residential)	: 26	: job	: 910,000
Farms (plant and equipment)	: 7	: job	: <u>700,000</u>
COMPONENT TOTAL	:	:	: \$2,160,000

b. Alabama Reservoir Compound.

Item	: Estimated : : Quantity :	: Unit :	: Estimated : Cost :
Land (fee simple)	: 45	: acre	: \$ 22,500
Land (easements)	: 5,500	: acre	: 550,000
Buildings (residential)	: 9	: job	: 315,000
Buildings (public and other)	: 1	: job	: <u>50,000</u>
COMPONENT TOTAL	:	:	: \$ 937,500

c. S.R.-A.R.C. Plan.

Item	: Amount
S.R. Component Total	: \$2,160,000
A.R.C. Component Total	: <u>937,500</u>
PLAN SUBTOTAL	: \$3,097,500
Property Acquisition (10% of Property Cost)	: <u>309,800</u>
PLAN TOTAL	: \$3,407,300

2. S.R.-A.R.C. Construction Cost.

a. Sierks Reservoir.

Item	: Estimated : Quantity	: Unit	: Unit : Cost	: Estimated : Cost
Care of Water	: 1	: l.s.	: \$ 158,000	: \$ 158,000
Clearing and Grubbing	: 1	: l.s.	: 31,600	: 31,600
Relocations (Rte. 98)	: 4.5	: mile	: 526,500	: 2,369,250
Common Excavation	: 181,500	: c.y.	: 2.50	: 453,750
Stripping	: 33,000	: s.y.	: 0.65	: 21,450
Line Drilling	: 20,500	: c.y.	: 5.25	: 107,625
Rock Excavation	: 173,000	: c.y.	: 7.40	: 1,280,200
Compacted Random Fill	: 697,000	: c.y.	: 2.50	: 1,742,500
Compacted Filter and Transition Material	: 24,000	: c.y.	: 10.00	: 240,000
Rock Fill	: 34,000	: c.y.	: 26.30	: 894,200
Unreinforced Concrete	: 94,000	: c.y.	: 100.00	: 9,400,000
Reinforced Concrete	: 16,300	: c.y.	: 125.00	: 2,037,500
Tainter Gates	: 4	: each	: 131,625	: 526,500
Slide Gates	: 10	: each	: 63,180	: 631,800
Service Bridge	: 1	: each	: 94,770	: 94,770
Miscellaneous Items	: 1	: l.s.	: 1,474,200	: 1,474,200
Mobilization and Demobilization	: 1	: l.s.	: 1,092,000	: 1,092,000
COMPONENT TOTAL	:	:	:	: \$22,939,345

b. Alabama Reservoir Compound.

Item	: Estimated : Quantity	: Unit	: Unit : Cost	: Estimated : Cost
Relocations (highways)	:	: l.s.	: \$ 613,000	: \$ 613,000
Clearing and Grubbing	: 107	: l.s.	: 2,000	: 214,000
Stripping	: 256,500	: s.y.	: 0.65	: 166,725
Compacted Random Fill	: 2,143,000	: c.y.	: 2.50	: 5,357,500
Reinforced Concrete for Inlet and Principal Spillways Structure	:	: l.s.	: 1,118,900	: 1,118,900
Seeding, Fertilizing and Mulching	: 108	: acre	: 1,100	: 118,800
Common Excavation	: 812,000	: c.y.	: 2.50	: 2,030,000
Mobilization and Demobilization	:	: l.s.	: 481,000	: 481,000
COMPONENT TOTAL	:	:	:	: \$10,099,925

c. S.R.-A.R.C. Plan.

Item	:	Amount
S.R. Component Total	:	\$22,939,300
A.R.C. Component Total	:	<u>10,099,900</u>
PLAN SUBTOTAL	:	\$33,039,200
Contingencies (15%)	:	<u>4,955,900</u>
PLAN SUBTOTAL	:	\$37,995,100
Engineering & Design (10%)	:	3,799,500
Supervision & Administration (7.5%)	:	2,849,600
Interest During Construction (6-1/8%)	:	<u>2,327,200</u>
PLAN TOTAL	:	\$46,971,400

3. Summary of First Cost for S.R.-A.R.C. Plan.

Item	:	Amount
Total Property Cost	:	\$ 3,407,300
Total Construction Cost	:	<u>46,971,400</u>
GRAND TOTAL	:	\$ 50,378,700

4. Average Annual Cost for S.R.-A.R.C. Plan.

Item	:	Amount
Amortization (.0614)	:	\$ 3,093,300
Operation and Maintenance	:	<u>100,000</u>
GRAND TOTAL	:	\$ 3,193,300

C4. ALEXANDER RESERVOIR

1. A.R. Property Cost.

Item	: Estimated : Quantity	: Unit	: Estimated : Cost
Land (fee simple)	: 945	: acre	: \$ 472,500
Building (residential)	: 8	: job	: <u>280,000</u>
PLAN SUBTOTAL	:	:	: \$ 752,500
Property Aquisition (10% of Property Cost)	:	:	: <u>75,300</u>
PLAN TOTAL	:	:	: \$ 827,800

2. A.R. Construction Cost.

Item	: Estimated: : Quantity	: Unit	: Unit : Cost	: Estimated : Cost
<u>Earth Dam</u>	:	:	:	:
Clearing & Grubbing	: 25	: acre	: \$2,000.00	: \$ 50,000
Stripping	: 106,000	: s.y.	: 0.65	: 68,900
Common Excavation	: 104,000	: c.y.	: 2.50	: 260,000
Compacted Random Fill	: 342,700	: c.y.	: 2.50	: 856,750
Compacted Impervious Fill	: 143,200	: c.y.	: 4.00	: 572,800
Compacted Filter and Transition Material	: 80,500	: c.y.	: 10.00	: 805,000
Seeding, Fertilizing and Mulching	: 117,200	: s.y.	: 0.23	: 26,956
Access Roadway (top of dam)	: 11,200	: s.y.	: 7.85	: 87,920
Access Roadway (guard rail)	: 11,000	: l.f.	: 7.50	: <u>82,500</u>
SUBTOTAL	:	:	:	: \$2,810,826
<u>Principal Outlet Works</u>	:	:	:	:
Common Excavation	: 30,000	: c.y.	: \$ 2.50	: \$ 75,000
Compacted Select Fill	: 9,825	: c.y.	: 4.00	: 39,300
Concrete (structural)	: 7,514	: c.y.	: 150.00	: 1,127,100

2. A.R. Construction Cost. (Cont'd)

Item	: Estimated: : Quantity :	Unit	: Unit : Cost :	: Estimated : Cost :
Concrete (reinforced)	: 381 :	c.y.	: 125.00 :	: 47,625
Concrete (unreinforced)	: 3,868 :	c.y.	: 100.00 :	: 386,800
Tainter Gates & Anchorage	: 365,387 :	lbs.	: 1.50 :	: 548,080
Tainter Gate Machinery	: 5 :	ea.	: 30,000.00 :	: 150,000
Tainter Gate Housing	: 6 :	ea.	: 7,200.00 :	: 43,200
Stop Logs (One Set)	: :	l.s.	: :	: 95,000
Steel Sheet Piling	: 5,935 :	s.f.	: 8.00 :	: 47,480
Electrical Facilities	: :	l.s.	: :	: 185,000
Service Bridge	: 5 :	ea.	: 4,350.00 :	: 21,750
SUBTOTAL	: :	:	: :	: \$2,766,335
<u>Channels</u>	: :	:	: :	: :
Common Excavation	: 35,900 :	c.y.	: 2.50 :	: 89,750
24" Riprap with Bedding	: 5,500 :	s.y.	: 35.30 :	: 194,150
SUBTOTAL	: :	:	: :	: \$ 283,900
<u>Railroad Floodgate</u>	: :	:	: :	: :
Common Excavation	: 3,260 :	c.y.	: 2.50 :	: 8,150
Compacted Select Fill	: 1,430 :	c.y.	: 4.00 :	: 5,720
Concrete (reinforced)	: 1,920 :	c.y.	: 125.00 :	: 240,000
Floodgate & Guides	: 25,650 :	lbs.	: 1.50 :	: 38,475
Floodgate Machinery	: :	l.s.	: :	: 20,000
Machinery Housing	: :	l.s.	: :	: 10,000
Steel Sheet Piling	: 3,290 :	s.f.	: 8.00 :	: 26,320
Track Relocation	: :	:	: :	: 6,000
Electrical Facilities	: :	l.s.	: :	: 50,000
Service Bridge	: :	l.s.	: :	: 2,500
SUBTOTAL	: :	:	: :	: \$ 407,165
Highway Relocation	: 2,700 :	s.y.	: 7.85 :	: 21,165
Bridge Relocation	: :	l.s.	: :	: 34,400
Care of Water	: :	l.s.	: :	: 100,000
Mobilization and Preparatory Work	: :	l.s.	: :	: 325,000
PLAN SUBTOTAL	: :	:	: :	: \$6,748,821
Contingencies (20%)	: :	:	: :	: 1,349,800
PLAN SUBTOTAL	: :	:	: :	: \$8,098,600

2. A.R. Construction Cost. (Cont'd)

Item	: Estimated: : Quantity :	Unit	: Unit : Cost	: Estimated : Cost
Engineering & Design (10%)	:	:	:	: 809,900
Supervision & Adminis- tration (9.5%)	:	:	:	: <u>769,400</u>
PLAN TOTAL	:	:	:	: \$9,677,900

3. Summary of First Cost for A.R. Plan.

Item	:	Amount
Total Property Cost	:	\$ 827,800
Total Construction Cost	:	<u>9,677,900</u>
GRAND TOTAL	:	\$10,505,700

4. Average Annual Cost for A.R. Plan.

Item	:	Amount
Amortization (.0614)	:	\$ 645,600
Operation and Maintenance	:	<u>50,000</u>
GRAND TOTAL	:	\$ 695,000

C5. BATAVIA RESERVOIR COMPOUND

1. B.R.C. Property Cost.

a. Upper Reservoir.

Item	: Estimated : : Quantity :	Unit	: Estimated : Cost
Land (fee simple)	: 945 :	acre	: \$ 472,500
Buildings (residential)	: 8 :	job	: <u>280,000</u>
COMPONENT TOTAL	: : :		: \$ 752,500

b. Lower Reservoir.

Item	: Estimated : : Quantity :	Unit	: Estimated : Cost
Land (easements for reservoir)	: 3,900 :	acre	: \$ 390,000
Land (easements for emergency spillway)	: 1,730 :	acre	: 173,000
Buildings (residential)	: 32 :	job	: 1,120,000
Farms (plant and equip.)	: 3 :	job	: 300,000
Sand and Gravel Operations: (plant and equipment)	: 1 :	job	: <u>100,000</u>
COMPONENT TOTAL	: : :		: \$2,083,000

c. B.R.C. Plan.

Item	: Amount
U.R. Component Total	: \$ 752,500
L.R. Component Total	: <u>2,083,000</u>
COMPONENT TOTAL	: \$2,835,500
Property Acquisition (10% of Property Cost)	: <u>283,600</u>
PLAN TOTAL	: \$3,119,100

2. B.R.C. Construction Cost.

a. Upper Reservoir.

Item	:Estimated: :Quantity :	Unit	: Unit : Cost	:Estimated : Cost
<u>Earth Dam and Emergency</u>	:	:	:	:
<u>Spillway</u>	:	:	:	:
Clearing & Grubbing	: 25 :	acre	:\$2,000.00	:\$ 50,000
Stripping	: 83,300 :	s.y.	: .65	: 54,145
Common Excavation	: 94,800 :	c.y.	: 2.50	: 237,000
Compacted Random Fill	: 156,500 :	c.y.	: 2.50	: 391,250
Compacted Impervious Fill	: 118,200 :	c.y.	: 4.00	: 472,800
Compacted Filter and Transition Material	: 87,500 :	c.y.	: 10.00	: 875,000
18" Riprap	: 91,100 :	s.y.	: 17.00	: 1,548,700
Seeding, Fertilizing, Mulching	: 57,300 :	s.y.	: .23	: 13,179
Access Roadway (top of dam)	: 11,560 :	s.y.	: 7.85	: 90,746
Access Roadway (guard rail)	: 10,000 :	l.f.	: 7.50	: <u>75,000</u>
SUBTOTAL	:	:	:	:\$3,807,820
<u>Principal Outlet Works</u>	:	:	:	:
Common Excavation	: 8,625 :	c.y.	: 2.50	:\$ 21,562
Compacted Select Fill	: 1,175 :	c.y.	: 4.00	: 4,700
Concrete (reinforced)	: 1,839 :	c.y.	: 125.00	: 229,875
Fixed Wheel Sluice Gates and Misc. Fabrications	: 45,000 :	lbs.	:\$ 1.50	:\$ 68,250
Sluice Gate Electric Lift	: 5 :	ea.	: 5,000.00	: 25,000
Stop Logs (one set)	:	l.s.	:	: 10,000
Steel Sheet Piling	: 2,780 :	s.f.	: 8.00	: 22,240
24" Riprap with Bedding	: 1,105 :	s.y.	: 35.30	: 39,007
Electrical Facilities	:	l.s.	:	: 85,000
Common Excavation (outlet channel)	: 19,800 :	c.y.	: 2.50	: <u>49,500</u>
SUBTOTAL	:	:	:	: \$555,134

2. B.R.C. Construction Cost. (Cont'd)

a. Upper Reservoir (Cont'd)

Item	:Estimated: :Quantity :	Unit	: Unit : Cost	:Estimated : Cost
<u>Railroad Floodgate</u>	:	:	:	:
Common Excavation	: 2,370 :	c.y.	: 2.50	: 5,925
Compacted Select Fill	: 1,023 :	c.y.	: 4.00	: 4,092
Concrete (reinforced)	: 1,304 :	c.y.	: 125.00	: 163,000
Floodgate & Guides	: 19,000 :	lbs.	: 1.50	: 28,500
Floodgate Machinery	:	: 1.s.	:	: 20,000
Machinery Housing	:	: 1.s.	:	: 10,000
Steel Sheet Piling	: 3,290 :	s.f.	: 8.00	: 26,320
Track Relocation	:	: 1.s.	:	: 6,000
Electrical Facilities	:	: 1.s.	:	: 50,000
Service Bridge	:	: 1.s.	:	: 2,500
SUBTOTAL	:	:	:	: \$ 316,337
Highway Relocation	: 2,700 :	s.y.	: 7.85	: 21,195
Bridge Relocation	:	: 1.s.	:	: 34,400
Care of Water	:	: 1.s.	:	: 100,000
Mobilization and Preparatory Work	:	: 1.s.	:	: 250,000
COMPONENT TOTAL	:	:	:	: \$5,084,886

b. Lower Reservoir.

Item	:Estimated: :Quantity :	Unit	: Unit : Cost	:Estimated : Cost
<u>Earth Dam</u>	:	:	:	:
Clearing & Grubbing	: 29 :	acre	: \$2,000.00	: \$ 58,000
Stripping	: 187,000 :	s.y.	: .65	: 121,550
Common Excavation	: 219,000 :	c.y.	: 2.50	: 547,500
Compacted Random Fill	: 350,000 :	c.y.	: 2.50	: 875,000
Compacted Impervious Fill	: 284,000 :	c.y.	: 4.00	: 1,136,000
Compacted Filter and Transition Material	: 160,000 :	c.y.	: 10.00	: 1,600,000

2. B.R.C. Construction Cost. (Cont'd)

b. Lower Reservoir. (Cont'd)

Item	:Estimated: :Quantity :	Unit :	Unit Cost	:Estimated : Cost
Seeding, Fertilizing and Mulching	: 197,000 :	s.y. :	\$ 0.23	:\$ 45,310
Access Roadway (top of dam)	: 13,400 :	s.y. :	7.85	: 105,190
Access Roadway (guard rail)	: 12,000 :	l.f. :	7.50	: <u>90,000</u>
SUBTOTAL	:	:	:	:\$4,578,550
<u>Emergency Spillway</u>	:	:	:	:
Common Excavation	: 195,000 :	c.y. :	2.50	: 487,500
Compacted Random Fill	: 10,000 :	c.y. :	2.50	: 25,000
Seeding, Fertilizing and Mulching	: 224,000 :	s.y. :	0.23	: 51,520
Highway Relocation	: 3,320 :	l.f. :	50.00	: <u>166,000</u>
SUBTOTAL	:	:	:	:\$ 730,020
<u>Ellicott St. Culvert</u>	:	:	:	:
Common Excavation	: 2,650 :	c.y. :	2.50	: 6,625
Concrete (reinforced)	: 30 :	c.y. :	125.00	: 3,750
Concrete Pipe (72" diam.)	: 97 :	l.f. :	140.00	: 13,580
Sluice Gate	:	l.s. :	:	: <u>17,000</u>
SUBTOTAL	:	:	:	:\$ 40,955
<u>Principal Outlet Works</u>	:	:	:	:
Common Excavation	: 2,900 :	c.y. :	2.50	: 7,250
Compacted Select Fill	: 860 :	c.y. :	4.00	: 3,440
Concrete (reinforced)	: 1,391 :	c.y. :	125.00	: 173,875
Fixed Wheel Sluice Gates and Misc. Fabrications	: 37,400 :	lbs. :	1.50	: 56,100
Sluice Gate Electric Lift	: 4 :	ea. :	5,000.00	: 20,000
Stop Logs (one set)	:	l.s. :	:	: 10,000
Steel Sheet Piling	: 4,400 :	s.f. :	8.00	: 35,200
	:	:	:	:

2. B.R.C. Construction Cost. (Cont'd)

b. Lower Reservoir. (Cont'd)

Item	:Estimated: :Quantity :	Unit :	Unit Cost :	:Estimated : Cost :
24" Riprap with Bedding	: 1,222 :	s.y. :	35.30 :	: 43,136
Electrical Facilities	: : :	l.s. :	: : :	: <u>50,000</u>
SUBTOTAL	: : :	: : :	: : :	: \$ 399,001
<u>Railroad Floodgate</u>	: : :	: : :	: : :	: : :
Common Excavation	: 2,370 :	c.y. :	2.50 :	: 5,925
Compacted Select Fill	: 1,023 :	c.y. :	4.00 :	: 4,092
Concrete (reinforced)	: 1,304 :	c.y. :	125.00 :	: 163,000
Floodgate & Guides	: 19,000 :	lbs. :	1.50 :	: 28,500
Floodgate Machinery	: : :	l.s. :	: : :	: 20,000
Machinery Housing	: : :	l.s. :	: : :	: 10,000
Steel Sheet Piling	: 3,290 :	s.f. :	8.00 :	: 26,320
Track Relocation	: : :	l.s. :	: : :	: 6,000
Electrical Facilities	: : :	l.s. :	: : :	: 84,000
Service Bridge	: : :	l.s. :	: : :	: <u>2,500</u>
SUBTOTAL	: : :	: : :	: : :	: \$ 350,337
Care of Water	: : :	l.s. :	: : :	: 200,000
Mobilization and Preparatory Work	: : :	l.s. :	: : :	: 325,000
Clearing and Snagging	: 8 :	mile :	13,500.00 :	: <u>108,000</u>
COMPONENT TOTAL	: 8 :	mile :	13,500.00 :	: \$6,731,863

c. B.R.C. Plan.

Item	: Amount
U.R. Component Total	: \$ 5,084,900
L.R. Component Total	: <u>6,731,900</u>
PLAN SUBTOTAL	: \$11,816,800

2. B.R.C. Construction Cost. (Cont'd)

c. B.R.C. Plan (Cont'd)

Item	:	Amount
Contingencies (15%)	:	\$ <u>1,772,500</u>
PLAN SUBTOTAL	:	\$13,589,300
Engineering and Design (10%)	:	1,358,900
Supervision and Administration (8.5%)	:	1,155,100
Interest During Construction (6-1/8%)	:	<u>832,300</u>
PLAN TOTAL	:	\$16,935,600

3. Summary of First Cost for B.R.C. Plan.

Item	:	Amount
Total Property Cost	:	\$ 3,119,100
Total Construction Cost	:	<u>16,935,600</u>
GRAND TOTAL	:	\$20,054,700

4. Average Annual Cost for B.R.C. Plan.

Item	:	Amount
Amortization (.0614)	:	\$ 1,232,000
Operation and Maintenance	:	<u>100,000</u>
GRAND TOTAL	:	\$ 1,332,000

C6. BATAVIA RESERVOIR

1. B.R. Property Cost.

Item	: Estimated : : Quantity :	: Unit :	: Estimated Cost
Land (fee simple)	: 6,460	: acres	: \$3,230,000
Land (easements)	: 1,730	: acres	: 173,000
Land (extinguishment of mineral rights)	: 100	: acres	: 350,000
Buildings (residential)	: 82	: job	: 2,870,000
Structures (radio station)	: 1	: job	: 50,000
Structures (pipeline sta.)	: 1	: job	: 100,000
Farms (Plant & Equipment)	: 7	: job	: 700,000
Sand and Gravel Operations (plant equipment)	: 4	: job	: 400,000
Relocations	:	:	:
Power Line (9,000 ft.)	: 1	: job	: 735,300
Settling Lagoon Compound	: 1	: job	: 50,000
Private Recreation Facility	: 1	: job	: 40,000
Elevation of 3 miles of County Roads (includes 24 ft. culvert)	: 1	: job	: <u>100,000</u>
PLAN SUBTOTAL	:	:	: \$8,798,300
Property Acquisition (10% of Property Cost)	:	:	: <u>879,800</u>
PLAN TOTAL	:	:	: \$9,678,100

2. B.R. Construction Cost.

Item	: Estimated : : Quantity :	: Unit :	: Unit : Estimated Cost : Cost
<u>Earth Dam</u>	:	:	:
Clearing & Grubbing	: 40	: acre	: \$ 2,000.00: \$ 80,000
Stripping	: 390,200	: s.y.	: 0.65: 253,630
Common Excavation	: 434,600	: c.y.	: 2.50: 1,086,500
Compacted Random Fill	: 1,066,100	: c.y.	: 2.50: 2,665,250
Compacted Impervious Fill	: 583,600	: c.y.	: 4.00: 2,334,400

2. B.R. Construction Cost. (Cont'd)

Item	Estimated Quantity	Unit	Unit Cost	Estimated Cost
Compacted Filter and Transition Material	326,500	c.y.	10.00:	3,265,000
Seeding, Fertilizing and Mulching	585,400	s.y.	0.23:	134,642
Access Roadway (top of dam)	13,400	s.y.	7.85:	105,190
Access Roadway (top of rail)	14,000	l.f.	1.50:	<u>105,000</u>
SUBTOTAL				\$10,029,612
<u>Emergency Spillway</u>				
Common Excavation	256,900	c.y.	2.50:	642,250
Compacted Impervious Fill	44,400	c.y.	4.00:	177,600
Compacted Filter and Transition Material	18,400	c.y.	10.00:	184,000
18" Riprap	35,900	c.y.	17.00:	610,300
Seeding, Fertilizing and Mulching	81,500	s.y.	0.23:	18,745
Highway Relocation	2,700	l.f.	50.00:	<u>135,000</u>
SUBTOTAL				\$ 1,767,895
<u>Ellicott St. Culvert</u>				
Common Excavation		c.y.	2.50:	
Concrete (reinforced)		c.y.	125.00:	
Concrete Pipe (72" diam.)		l.f.	140.00:	
Sluice Gate		l.s.		
SUBTOTAL				\$ 49,800
<u>Principal Outlet Works</u>				
Common Excavation		c.y.	2.50:	
Compacted Select Fill		c.y.	4.00:	
Concrete (reinforced)		c.y.	125.00:	
Fixed Wheel Sluice Gates and Misc. Fabrications		lbs.	1.50:	
Sluice Gate Electric Lift		ea.	5,000.00:	
Stop Logs (one set)		l.s.		
Steel Sheet Piling		s.f.	8.00:	
24" Riprap with Bedding		s.y.	35.30:	
Electrical Facilities		l.s.		
SUBTOTAL				\$ 454,000

2. B.R. Construction Cost. (Cont'd)

Item	: Estimated : : Quantity :	: Unit :	: Unit : : Cost :	: Estimated : : Cost :
<u>Railroad Floodgate</u>	:	:	:	:
Common Excavation	:	: c.y. :	\$ 2.50 :	:
Compacted Select Fill	:	: c.y. :	4.00 :	:
Concrete (reinforced)	:	: c.y. :	125.00 :	:
Floodgate & Guides	:	: lbs. :	1.50 :	:
Floodgate Machinery	:	: l.s. :	:	:
Machinery Housing	:	: l.s. :	:	:
Steel Sheet Piling	:	: s.f. :	8.00 :	:
Track Relocation	:	: l.s. :	:	:
Electrical Facilities	:	: l.s. :	:	:
Service Bridge	:	:	:	:
SUBTOTAL	:	:	:	\$ 564,000
Care of Water	:	: l.s. :	:	200,000
Mobilization and Preparatory Work	:	: l.s. :	:	<u>650,000</u>
PLAN SUBTOTAL	:	:	:	\$13,715,300
Contingencies (15%)	:	:	:	<u>2,057,300</u>
PLAN SUBTOTAL	:	:	:	\$15,772,600
Engineering & Design (10%)	:	:	:	1,577,300
Supervision & Administration: (8.25%)	:	:	:	1,301,200
Interest During Construction: (6-1/8%)	:	:	:	<u>966,100</u>
PLAN TOTAL	:	:	:	\$19,617,200

3. Summary of First Cost for B.R. Plan.

Item	: Amount
Total Property Cost	\$ 9,678,100
Total Construction Cost	<u>19,617,200</u>
GRAND TOTAL	\$29,295,300

4. Average Annual Cost for B.R. Plan.

Item	:	Amount
	:	
Amortization (.0614)	:	\$1,798,700
Operation & Maintenance	:	<u>50,000</u>
	:	
GRAND TOTAL	:	\$1,848,700
	:	

C7. BATAVIA RESERVOIR - ALABAMA RESERVOIR COMPOUND

1. B.R.-A.R.C. Property Cost.

a. Batavia Reservoir.

Item	: Estimated : Quantity	: Unit	: Estimated : Cost
Land (fee simple)	: 6,460	: acre	: \$ 3,230,000
Land (easements)	: 1,730	: acre	: 173,000
Land (extinguishment of mineral rights)	: 100	: acre	: 350,000
Buildings (residential)	: 82	: job	: 3,870,000
Structures (radio station)	: 1	: job	: 50,000
Structures (pipeline station)	: 1	: job	: 100,000
Farms (plant & equip.)	: 7	: job	: 700,000
Sand & Gravel Operations: (plant & equipment)	: 4	: job	: 400,000
Relocations	:	:	:
Power Line (9,000 ft.)	: 1	: job	: 735,300
Settling Lagoon Compound	: 1	: job	: 50,000
Private Recreation Facility	: 1	: job	: 40,000
Elevation of 3 miles of County Roads includes 24 ft. culvert)	:	:	: <u>100,000</u>
COMPONENT TOTAL	:	:	: \$8,798,300

b. Alabama Reservoir Compound.

Item	: Estimated : Quantity	: Unit	: Estimated : Cost
Land (fee simple)	: 45	: acre	: \$ 22,500
Land (easement)	: 5500	: acre	: 550,000
Buildings (residential)	: 9	: job	: 315,000
Buildings (public & other)	: 1	:	: <u>50,000</u>
COMPONENT SUBTOTAL	:	:	: \$ 937,500

c. B.R.-A.R.C. Plan.

Item	:	Amount
B.R. Component Total	:	\$ 8,798,300
A.R.C. Component Total	:	<u>937,500</u>
COMPONENT SUBTOTAL	:	\$ 9,735,800
Property Acquisition (10% of Property Cost)	:	<u>973,600</u>
PLAN TOTAL	:	\$10,709,400

2. B.R.-A.R.C. Construction Cost.

a. Batavia Reservoir.

Item	:	Estimated Quantity	:	Unit	:	Unit Cost	:	Estimated Cost
<u>Earth Dam</u>	:	:	:	:	:	:	:	:
Clearing & Grubbing	:	40	:	acre	:	\$2,000.00	:	\$ 80,000
Stripping	:	390,200	:	s.y.	:	0.65	:	253,630
Common Excavation	:	434,600	:	c.y.	:	2.50	:	1,086,500
Compacted Random Fill	:	1,066,100	:	c.y.	:	2.50	:	2,665,250
Compacted Impervious Fill	:	583,600	:	c.y.	:	4.00	:	2,334,400
Compacted Filter and Transition Material	:	326,500	:	c.y.	:	10.00	:	3,265,000
Seeding, Fertilizing and Mulching	:	585,400	:	s.y.	:	0.23	:	134,642
Access Roadway (top of dam)	:	13,400	:	s.y.	:	7.85	:	105,190
Access Roadway (guard rail)	:	14,000	:	l.f.	:	1.50	:	<u>105,000</u>
SUBTOTAL	:	:	:	:	:	:	:	\$10,029,612
<u>Emergency Spillway</u>	:	:	:	:	:	:	:	:
Common Excavation	:	256,900	:	c.y.	:	2.50	:	642,250
Compacted Impervious Fill	:	44,400	:	c.y.	:	4.00	:	177,600

2. B.R.-A.R.C. Construction Cost. (Cont'd)

a. Batavia Reservoir. (Cont'd)

Item	Estimated Quantity	Unit	Unit Cost	Estimated Cost
Compacted Filter and Transition Material	18,400	c.y.	10.00:	184,000
18" Riprap	35,900	s.y.	17.00:	610,300
Seeding, Fertilizing and Mulching	81,500	s.y.	0.23:	18,745
Highway Relocation	2,700	l.f.	50.00:	135,000
SUBTOTAL				\$ 1,767,895
<u>Ellicott St. Culvert</u>				
Common Excavation		c.y.	2.50:	
Common (reinforced)		c.y.	125.00:	
Concrete Pipe (72")		l.f.	140.00:	
Sluice Gate		l.s.		
SUBTOTAL				\$ 49,800
<u>Principal Outlet Works</u>				
Common Excavation		c.y.	2.50:	
Compacted Select Fill		c.y.	4.00:	
Concrete (reinforced)		c.y.	125.00:	
Fixed Wheel Sluice Gates & Misc. Fabrications		lbs.	1.50:	
Sluice Gate				
Electric Lift				
Stop Logs (one set)		l.s.		
Steel Sheet Piling		s.f.	8.00:	
24" Riprap with Bedding		s.y.	35.30:	
Electrical Facilities		l.s.		
SUBTOTAL				\$ 454,400
<u>Railroad Floodgate</u>				
Common Excavation		c.y.	2.50:	
Compacted Select Fill		c.y.	4.00:	

2. B.R.-A.R.C. Construction Cost. (Cont'd)

a. Batavia Reservoir. (Cont'd)

Item	Estimated Quantity	Unit	Unit Cost	Estimated Cost
Concrete				
(reinforced)		c.y.	125.00:	
Floodgate & Guides		lbs.	1.50:	
Floodgate Machinery		l.s.		
Machinery Housing		l.s.		
Steel Sheet Piling		s.f.	8.00:	
Track Relocation		l.s.		
Electrical				
Facilities		l.s.		
Service Bridge		l.s.		
SUBTOTAL				\$ 564,000
Care of Water		l.s.		200,000
Mobilization and Preparatory Work		l.s.		<u>650,000</u>
COMPONENT TOTAL				\$13,715,700

b. Alabama Reservoir Compound.

Item	Estimated Quantity	Unit	Unit Cost	Estimated Cost
Relocations (highway)		l.s.	\$ 613,000:	\$ 613,000
Clearing and Grubbing	107	acre	2,000:	214,000
Stripping	256,500	s.y.	0.65:	166,725
Compacted Random Fill	2,143,000	c.y.	2.50:	5,357,500
Reinforced Concrete for Inlet and Outlet:				
Structures		l.s.	1,118,900:	1,118,900
Seeding, Fertilizing & Mulching	108	acre	1,100:	118,800
Common Excavation	812,000	c.y.	2.50:	2,030,000
Mobilization and Demobilization		l.s.	481,000:	<u>481,000</u>
COMPONENT TOTAL				\$10,099,925

c. B.R. - A.R.C. Plan.

Item	:	Amount
B.R. Component Total	:	\$13,715,700
A.R.C. Component Total	:	<u>10,099,900</u>
PLAN SUBTOTAL	:	\$23,815,600
Contingencies (15%)	:	<u>3,572,300</u>
PLAN SUBTOTAL	:	\$27,387,900
Engineering & Design (10%)	:	2,738,800
Supervision & Administration (7.5%)	:	2,054,100
Interest During Construction (6-1/8%)	:	<u>1,677,500</u>
PLAN TOTAL	:	\$33,858,300

3. Summary of First Cost of B.R.-A.R.C. Plan.

Item	:	Amount
Total Property Cost	:	\$10,709,400
Total Construction Cost	:	<u>33,858,300</u>
GRAND TOTAL	:	\$44,567,700

4. Average Annual Cost of B.R.-A.R.C. Plan.

Item	:	Amount
Amortization (.0614)	:	\$ 2,736,500
Operation & Maintenance	:	<u>100,000</u>
GRAND TOTAL	:	\$ 2,836,500

C8. BATAVIA PROJECT MODIFICATION

1. B.P.M. Property Cost.

Item	: Estimated : : Quantity :	: Unit :	: Estimated : Cost :
Land (fee simple)	:	: job	: \$ 300,000
PLAN SUBTOTAL	:	:	: 300,000
Property Acquisition 10% of Property Cost)	:	:	: <u>30,000</u>
PLAN TOTAL	:	:	: \$ 330,000

2. B.P.M. Construction Cost.

Item	: Estimated : : Quantity :	: Unit :	: Unit : : Cost :	: Estimated : Cost :
<u>Relocations</u>	:	:	:	:
Removal of Existing Pavement	: 1,500	: s.y.	: 1.30	: \$ 1,950
Headwalls	: 10	: c.y.	: 1.00	: 1,000
Manholes	: 2	: each	: 1,050	: 2,100
12-inch Sluice Gate	: 3	: each	: 315	: 945
15-inch Sluice Gate	: 1	: each	: 525	: 525
36-inch Sluice Gate	: 1	: each	: 950	: 950
36-inch Culvert	: 150	: l.f.	: 18.40	: 2,760
36-inch Automatic Drain- age Gate	: 3	: each	: 525	: 1,575
Gravel Base	: 520	: c.y.	: 5.25	: 2,730
Asphalt Concrete	: 170	: ton	: 13.20	: 2,244
Raise Manhole	: 1	: each	: 315	: 315
Manhole	: 2	: each	: 525	: 1,050
Manhole	: 1	: each	: 1,050	: <u>1,050</u>
SUBTOTAL	:	:	:	: \$19,194
<u>Channels</u>	:	:	:	:
Clearing and Grubbing	:	: l.s.	:	: 84,000
Excavation	: 140,000	: c.y.	: 2.50	: 350,000
Compacted Fill	: 2,300	: c.y.	: 2.50	: 5,750

2. B.P.M. Construction Cost.

Item	Estimated Quantity	Unit	Unit Cost	Estimated Cost
Dumped Riprap	19,100	c.y.	14.20	271,200
Gravel Bedding Course	8,050	c.y.	10.00	<u>80,500</u>
SUBTOTAL				\$791,450
<u>Levees</u>				
Excavation for Embankment:	4,400	c.y.	2.50	11,000
Embankment	23,600	c.y.	2.50	59,000
Dumped Riprap	1,470	c.y.	13.20	19,404
Gravel Bedding Course	550	c.y.	10.00	5,500
Seeding and Fertilizing	3	acre	1,100	<u>3,300</u>
SUBTOTAL				\$ 98,204
Mobilization and Demobilization				50,000
PLAN SUBTOTAL				958,848
Contingencies (20%)				<u>191,800</u>
PLAN SUBTOTAL				1,150,600
Engineering & Design(10%):				115,000
Supervision & Administra- tion (10%)				<u>115,000</u>
PLAN TOTAL				1,380,600

3. Summary of First Cost for B.P.M. Plan.

Item	Amount
Total Property Costs	\$ 330,000
Total Construction Costs	<u>1,380,600</u>
GRAND TOTAL	\$ 1,710,600

4. Average Annual Cost for B.P.M. Plan.

Item	:	Amount
Amortization (.0614)	:	\$ 105,000
Operation and Maintenance	:	<u>25,000</u>
GRAND TOTAL	:	\$ 130,000

BUFFALO METROPOLITAN AREA, NEW YORK
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

1983

APPENDIX D

DESIGN AND COST ESTIMATE

U. S. Army Engineer District, Buffalo
1776 Niagara Street
Buffalo, NY 14207

APPENDIX D

DESIGN AND COST ESTIMATE

TABLE OF CONTENTS

<u>Paragraph</u>	<u>Description</u>	<u>Page</u>
<u>SECTION I - GENERAL</u>		
D1	INTRODUCTION	D-1
<u>SECTION II - UPPER RESERVOIR</u>		
D2	UPPER RESERVIOR EMBANKMENT AND EMERGENCY SPILLWAY	D-2
D3	PRINCIPAL OUTLET WORKS	D-2
D3.1	Control Structure	D-2
D3.2	Stilling Basin	D-3
D3.3	Outlet Channel	D-3
D4	APPURTENANCES	D-4
D4.1	Access Roadway	D-4
D4.2	Miscellaneous Facilities	D-4
D4.3	Clearing and Snagging	D-4
D5	RELOCATIONS	D-4
<u>SECTION III - LOWER RESERVOIR</u>		
D6	LOWER RESERVIOR EMBANKMENT AND EMERGENCY SPILLWAY	D-6
D7	PRINCIPAL OUTLET WORKS	D-6
D7.1	Control Structure	D-6
D7.2	Stilling Basin and Outlet Channel	D-7
D7.3	Inlet Channel	D-7
D8	APPURTENANCES	D-8
D8.1	Training Dikes	D-8
D8.2	Access Roadway	D-8
D8.3	Miscellaneous Facilities	D-8
D8.4	Clearing and Snagging	D-9
D8.5	Bridge Removal	D-9
D9	RELOCATIONS	D-9

TABLE OF CONTENTS (Cont'd)

<u>Paragraph</u>	<u>Description</u>	<u>Page</u>
<u>SECTION IV - ESTIMATE OF COST</u>		
D10	ESTIMATE OF COST	D-10
D11	ANNUAL OPERATION, MAINTENANCE, AND MAJOR REPAIR	D-10
D12	ANNUAL COSTS	D-10

TABLES

<u>Table No.</u>		
D1	ESTIMATED PROPERTY COSTS FOR BATAVIA RESERVOIR COMPOUND (MODIFIED)	D-11
	1. Upper Reservoir	D-11
	2. Lower Reservoir	D-11
	3. Summary	D-11
D2	ESTIMATED CONSTRUCTION COSTS FOR BATAVIA RESERVOIR COMPOUND (MODIFIED)	D-12
	1. Upper Reservoir	D-12
	2. Lower Reservoir	D-14
	3. Summary	D-16
D3	SUMMARY OF ESTIMATED COSTS FOR BATAVIA RESERVOIR COMPOUND (MODIFIED)	D-17
	1. First Cost	D-17
	2. Investment Cost	D-17
	3. Average Annual Cost	D-17

PLATES

<u>Plate No.</u>	
D1	Batavia Reservoir Compound (Modified)
D2	Upper Reservoir Embankment - Cross Section
D3	Lower Reservoir Embankment - Cross Section
D4	Principal Outlet Works

SECTION I - GENERAL

D1. INTRODUCTION

Several multiple purpose and/or flood management reservoirs and a local protection project were considered for reduction of flood damages in Tonawanda Creek Watershed. Several reservoir sites and combinations of sites were studied and the most promising one, the Batavia Reservoir Compound (Modified), is discussed in detail in this appendix. The location of each considered improvement is shown on Plate 5 of the Main Report.

The Batavia Reservoir Compound (Modified), the Recommended Plan, would consist of a combination of two shallow detention reservoirs arranged in series. The reservoirs would be located within the flood plain between the village of Alexander and the city of Batavia. They are referred to as the upper reservoir and lower reservoir in this appendix. A detailed description of each reservoir and a plan of operation are contained in Section 4 of the Main Report. The location of each reservoir is shown on Plate D1. All elevations shown in this appendix are referred to United States Coast and Geodetic Survey datum. The selected plan is a regional protection plan that would reduce existing tangible average annual flood damages by approximately 74 percent; 20 percent in the Erie Plain that includes the city of Batavia and 54 percent in the Huron Plain.

SECTION II - UPPER RESERVOIR

D2. UPPER RESERVOIR EMBANKMENT AND EMERGENCY SPILLWAY

The upper embankment would be located approximately 200 feet downstream of the Conrail Railroad embankment, formerly the Erie-Lackawanna embankment. The embankment would stretch 5,450 feet across the Tonawanda Creek valley to within a short distance from the hamlet of North Alexander. The location selected for the embankment has two advantages: the area to be occupied by the embankment is presently cleared of substantial vegetation and its nearness to the existing railroad embankment allows this embankment to blend in with the surrounding area, providing minimum disruption of transportation facilities and land utilization. The location for the upper reservoir embankment is shown on Plate D1.

The embankment would be designed to function as an emergency spillway with a top elevation of 922.5 in order to satisfy hydraulic requirements for the reservoir. Approximately 3.2 feet of water would flow over the embankment during a Probable Maximum Flood assuming a maximum pool elevation of 925.7.

A typical cross section for the upper embankment is shown on Plate D2. The section was conservatively developed with 1 vertical on 3 horizontal side-slopes. A conservative development process was followed because of the lack of geotechnical information pertaining to the site. The design of the cross section will be modified when more is known of the existing conditions. A 10-foot top width was utilized for most of the upper embankment in an effort to develop the most cost effective recommendation. The geotechnical design of the upper embankment is discussed in Appendix E, paragraph E5.2.

A principal outlet works, consisting of several gated conduits, would be constructed through the upper embankment. The outlet works are discussed in detail under paragraph D3.

A 16-foot wide access roadway would be provided along a portion of the top of the upper embankment. A 20-foot top width would be necessary to accommodate the access road. The access roadway is discussed in more detail under paragraph D4.1.

D3. PRINCIPAL OUTLET WORKS

D3.1 Control Structure

The principal outlet works for the upper reservoir would consist of a control structure, stilling basin, and outlet channel located at or near the intersection of the upper embankment and Tonawanda Creek.

The control structure would be a five-conduit reinforced concrete box culvert with adjacent inlet flume. The culvert would have capacity to pass flows of approximately 2,000 cubic feet per second under natural flow conditions and up to approximately 10,700 cubic feet per second under the 100-year flood condition when the upper pool reaches El. 922.5. The structure would be founded on a 3-foot layer of compacted select fill placed over the natural

subsoil. Each conduit would be 11 feet wide by 11 feet high and equipped with an electrically operable fixed wheel control gate. Each gate would be operated from controls mounted on the electric gate lift and/or from controls located in the equipment building at the west abutment. Each conduit would be provided with upstream and downstream bulkhead slots for maintenance dewatering during nonflood periods. One set of stoplogs would be provided to permit dewatering one conduit at a time. A steel sheet pile cutoff wall would be provided under the control structure to reduce groundwater seepage.

An upstream inlet flume would funnel water into the gated conduits. The inlet flume would consist of a reinforced concrete section, located adjacent to the control gates, and steel sheet pile wingwalls. The reinforced concrete section would be designed as a U-frame with an integral concrete floor slab. The short-height sheet pile windwalls would be designed as freestanding cantilevered walls. The channel bottom between the wingwalls would be protected with 24-inch riprap placed on a 12-inch bedding layer. The riprap would extend from the concrete floor slab to a line 10 feet upstream of the wingwalls. Center piers and wingwalls would be designed to reduce contraction losses. A centerline profile through the principal outlet works, with approximate dimensions, is shown on Plate D4.

D3.2 Stilling Basin

The stilling basin would be a reinforced concrete structure 61 feet wide and 62 feet long. The basin would be designed to reduce the energy of water discharged from the control structure to within tolerable limits. Baffle blocks and a raised end sill would be utilized for this purpose. Gravity-type training walls would be provided for the entire length of the stilling basin. The entire structure would be founded on a 3-foot layer of compacted select fill placed over the natural subsoil. A profile through the stilling basin is shown on Plate D3.

D3.3 Outlet Channel

The meandering Tonawanda Creek channel immediately downstream from the upper embankment would be abandoned. A new outlet channel, starting at the stilling basin, would be excavated normal to the embankment in order to provide a gradual transition to natural channel conditions. The outlet channel bottom, flaring from a width of 71 feet at the stilling basin to 91 feet, would be protected with 24-inch riprap placed on a 12-inch bedding layer for a distance of approximately 100 feet. Thence, the channel would be narrowed to 50 feet to form a pilot channel for low flows. The 50-foot wide pilot channel with 1 vertical on 2.5 horizontal sideslopes would extend downstream and additional 1,100 feet to a junction with the existing creek channel. The abandoned creek channel would be utilized as a spoil area for waste material from clearing and stripping operations associated with the construction of the upper embankment and from clearing and snagging operations along the existing creek channel within the upper and lower reservoir.

D4. APPURTENANCES

D4.1 Access Roadway

A 16-foot wide access road would be provided across the top of the upper embankment. The roadway would run from State Route 98 to Tonawanda Creek, a distance of approximately 1,800 feet. The roadway would have light-duty bituminous pavement. Guardrails would be installed on both sides of the roadway along the emergency spillway, a distance of approximately 1,550 feet. The access road would provide for operation and maintenance of the principal outlet works.

D4.2 Miscellaneous Facilities

Electrical service to the principal outlet works would be provided by existing transmission lines along State Route 98 and underground cables laid in conduit along the top of the upper embankment. A 15-foot by 20-foot equipment building of simple design would be located along the access road at the west abutment. A standby electrical generator, capable of operating the principal outlet works, would be located in the equipment building. Appropriate heating, lighting, and communications equipment would be provided.

D4.3 Clearing and Snagging

The existing Tonawanda Creek channel between Railroad Avenue and the upper embankment would be cleared of snags and debris jams. Dead trees along the channel banks and overhanging, partially uprooted trees would also be removed. This work is expected to restore the creek to a natural channel capacity of approximately 2,000 cubic feet per second near the upper dam, thereby reducing the frequency of minor flooding. The debris removed from the creek channel would be buried in the abandoned sections of the creek channel downstream from the upper embankment.

D5. RELOCATIONS

The Conrail Railroad and roadways within the boundaries of the upper reservoir would be maintained in their present condition with the following exception: thru traffic on Old Creek Road would terminate at the upper embankment. Minor washouts, requiring post flood maintenance, could be anticipated along the railroad right-of-way and Old Creek Road. The local region near the upper reservoir has sufficient alternate roadways so that only minimal inconvenience to local residents would occur. Existing power and telephone lines within the reservoir would remain in place and are not expected to experience any adverse effects due to the anticipated short duration flooding. Real estate requirements and the relocation of several buildings within the upper reservoir are discussed in Section 4 of the Main Report.

Downstream from the upper reservoir a section of Peaviner Road and the existing bridge over Tonawanda Creek would require relocation due to the realignment of the creek channel in the vicinity of the principal outlet works. Approximately 2,000 feet of roadway would be realigned and

reconstructed with a light-duty bituminous pavement. A 24-foot wide road with 10-foot shoulders would be provided. A 60-foot span highway bridge would be provided over the new outlet channel from the principal outlet works. The bridge would have reinforced concrete abutments and wingwalls and a precast concrete deck with a bituminous wearing surface.

SECTION III - LOWER RESERVOIR

D6. LOWER RESERVOIR EMBANKMENT AND EMERGENCY SPILLWAY

The lower embankment would be located between 500 feet and 3,100 feet south of the abandoned Conrail Railroad embankment, formerly the Lehigh Valley embankment. The embankment would stretch 5,600 feet across the Tonawanda Creek valley to within a short distance from the intersection of Route 98 and the abandoned railroad embankment. This represents a major change from the location previously proposed for the Batavia Reservoir Compound. The revised location, selected for the lower embankment, was chosen because of its minimal length and improved foundation conditions. The location for the lower reservoir embankment is shown on Plate D1.

The embankment would be designed to function as an emergency spillway with a top elevation of 900 from Creek Road westward for approximately 4,000 feet. The emergency spillway is required to satisfy hydraulic requirements for the reservoir. Approximately 5.9 feet (0.9 feet if the downstream railroad embankments are out) of water would flow over the embankment during a Probable Maximum Flood assuming a maximum pool elevation of 905.9 (or 900.9 without the railroad embankments). From Creek Road to the east abutment, and for a short distance at the west abutment, the embankment would be designed as a nonoverflow section with a top elevation of 910.0 and grassed slopes.

Two typical cross sections for the emergency spillway of the lower embankment are shown on Plate D3. Both cross sections have 1 vertical on 3 horizontal sideslopes that were conservatively selected to compensate for the lack of geotechnical information for the site. The design of these cross sections will be modified when more information becomes available. A 10-foot top width was utilized for most of the spillway section and for the nonoverflow sections of the lower embankment for economic reasons. The geotechnical design of the lower embankment is discussed in Appendix E, paragraph E5.3.

A principal outlet works, consisting of several gated conduits, would be constructed through the emergency spillway section of the lower embankment. The outlet works are discussed in detail under paragraph D7.

A 16-foot wide access roadway would be provided along a portion of the top of the emergency spillway section of the lower embankment. The top width would be increased to 20 feet to accommodate the access road. The access roadway is discussed in more detail under paragraph D8.2.

D7. PRINCIPAL OUTLET WORKS

D7.1 Control Structure

The principal outlet works for the lower reservoir would consist of a control structure, stilling basin, outlet channel, and inlet channel located approximately 900 feet east of the intersection of the lower embankment and Tonawanda Creek.

The control structure would be a four-conduit reinforced concrete box culvert with adjacent inlet flume. The culvert would have capacity to pass up to approximately 6,000 cubic feet per second under the 500-year flood condition when the lower pool reaches El. 900. This corresponds to the maximum allowable channel discharge through the city of Batavia. The structure would be founded on a 3-foot layer of compacted select fill placed over the natural subsoil. Each conduit would be 11 feet wide by 11 feet high and equipped with an electrically operable fixed wheel control gate. Each gate would be operated from controls mounted on the electric gate lift and/or from controls located in the equipment building near Route 98. Each conduit would be provided with upstream and downstream bulkhead slots for maintenance dewatering during nonflood periods. One set of stoplogs would be provided to permit dewatering one conduit at a time. A steel sheet pile cutoff wall would be provided under the control structure to reduce groundwater seepage.

An upstream inlet flume would funnel water into the gated conduits. The inlet flume would consist of a reinforced concrete section, located adjacent to the control gates, and steel sheet pile wingwalls. The reinforced concrete section would be designed as a U-frame with an integral concrete floor slab. The short-height sheet pile wingwalls would be designed as freestanding cantilevered walls. The channel bottom between the wingwalls would be protected with 24-inch riprap placed on a 12-inch bedding layer. The riprap would extend from the concrete floor slab to a line 10 feet upstream of the wingwalls. Center piers and wingwalls would be designed to reduce contraction losses. A centerline profile through the principal outlet works, with approximate dimensions, is shown on Plate D4.

D7.2 Stilling Basin and Outlet Channel

The stilling basin would be a reinforced concrete structure 48.5 feet wide and 62 feet long. The basin would be designed to reduce the energy of water discharged from the control structure to within tolerable limits. Baffle blocks and a raised end sill would be utilized for this purpose. Gravity-type training walls would be provided for the entire length of the stilling basin. The entire structure would be founded on a 3-foot layer of compacted select fill placed over the natural subsoil. A new outlet channel, starting at the stilling basin, would be excavated normal to the lower embankment. The 70-foot wide channel with 1 vertical on 2 horizontal sideslopes would extend downstream for approximately 100 feet to a junction with the existing creek channel. The outlet channel bottom, flaring from a width of 48.5 feet at the stilling basin to 70 feet, would be protected with 24-inch riprap placed on a 12-inch bedding layer for its total length. A profile through the stilling basin and outlet channel is shown on Plate D4.

D7.3 Inlet Channel

The meandering Tonawanda Creek channel immediately upstream from the lower embankment and west of the principal outlet works would be abandoned. A new inlet channel, starting at the inlet flume, would be excavated normal to the embankment in order to provide a gradual transition to natural channel conditions. The 70-foot wide channel with 1 vertical on 2 horizontal sideslopes would extend upstream for approximately 500 feet to a junction with the

existing creek channel. The abandoned creek channel would be utilized as a spoil area for waste material from clearing and stripping operations associated with the construction of the lower embankment and from clearing and snagging operations along the existing creek channel within the upper and lower reservoir.

D8. APPURTENANCES

D8.1 Training Dikes

Several training dikes would be located along the east and west sides of the Tonawanda Creek valley. Along the east side, a dike would stretch 1,650 feet across a natural saddle located approximately 1,000 feet south of East Road. Along the west side, three dikes would be located approximately 500 feet east of Route 98 in the reach between Cookson Road and the former Lehigh Valley Railroad embankment. These dikes would stretch 3,670 feet, 840 feet, and 200 feet across low areas in order to prevent possible overtopping of Route 98. The locations for the training dikes are shown on Plate D1.

Each dike would be designed as a nonoverflow section with a top elevation of 910.0 and grassed slopes. A cross section with 1 vertical on 3 horizontal sideslopes was conservatively selected to compensate for the lack of geotechnical information for the sites. The design will be modified when more information becomes available. A 10-foot top width was utilized for economic reasons. The maximum height of these dikes varies from 5.5 feet to 9 feet. The geotechnical design of the training dikes is discussed in Appendix E, paragraph E5.5

Natural drainage from small areas adjacent to the lower reservoir would be cut off by the training dikes. A gated culvert would be constructed through each dike to provide the required interior drainage. During periods of flooding, the culverts would function in reverse to prevent a flood pool from inundating the area adjacent to the reservoir. The culverts would consist of 24-inch to 36-inch diameter reinforced concrete pipe, reinforced concrete headwalls and wingwalls, and automatic flap gates mounted on the reservoir side of each dike.

D8.2 Access Roadway

A 16-foot wide access road would be provided across the top of the lower reservoir embankment. The roadway would run from Creek Road to Tonawanda Creek, a distance of approximately 820 feet. The roadway would have light-duty bituminous pavement. Guardrails would be installed on both sides of the roadway along the emergency spillway. The access road would provide for operation and maintenance of the principal outlet works.

D8.3 Miscellaneous Facilities

Electrical service to the principal outlet works would be provided by existing transmission lines along State Route 98 and underground cables laid in conduit along the top of the lower embankment. A 15-foot by 20-foot equipment building of simple design would be located near Route 98. A

standby electrical generator, capable of operating the principal outlet works, would be located in the equipment building. Appropriate heating, lighting, and communications equipment would be provided.

D8.4 Clearing and Snagging

The existing Tonawanda Creek channel within the lower reservoir would be cleared of snags and debris jams. Dead trees along the channel banks and overhanging, partially uprooted trees would also be removed. This work is expected to restore the creek to a natural channel capacity of approximately 2,000 cubic feet per second near the upper dam, thereby reducing the frequency of minor flooding. The debris removed from the creek channel would be buried in the abandoned sections of the creek channel downstream from the upper embankment and upstream from the lower embankment.

D8.5 Bridge Removal

The abandoned Conrail Railroad bridge, formerly the Lehigh Valley bridge, over Tonawanda Creek would be removed in order to improve hydraulic conditions downstream of the lower reservoir. The bridge superstructure and abutments would be demolished. In addition, the creek banks adjacent to the abutments would be excavated to stable 1 vertical on 2 horizontal sideslopes.

D9. RELOCATIONS

Roadways within the boundaries of the lower reservoir would be maintained in their present condition. Minor washouts, requiring post flood maintenance, could be anticipated along several of the light-duty roadways within the reservoir. The local region near the lower reservoir is considered to have sufficient alternate roadways so that only minimal inconveniences to local residents would occur. No major east-west highways cross the lower reservoir. Existing power and telephone lines within the reservoir would remain in place and are not expected to experience any adverse effects due to the anticipated short-duration flooding. However, sections of these lines and a remote controlled radio transmitter may require relocation after more detailed analysis and consultation with the affected utilities during advanced engineering and design. Real estate requirements and the relocation of residences, farms, and businesses situated within the lower reservoir are discussed in Section 4 of the Main Report.

A section of Creek Road in the vicinity of its intersection with the lower embankment would require relocation due to embankment construction. Approximately 500 feet of roadway would be realigned vertically in order to cross over the lower embankments. A 24-foot wide road with 10-foot shoulders and guardrails on both sides would be provided. The roadway would have light-duty bituminous pavement.

SECTION IV - ESTIMATE OF COST

D10. ESTIMATE OF COST

A detailed estimate of property costs for the Batavia Reservoir Compound (Modified) is shown in Table D1. Estimates of costs for lands, easements, and structures are based on current market values as determined from consultations with local realtors and tax assessors as calculated by Division personnel. Property acquisition costs and contingency allowances were estimated and added to obtain the total first cost of property.

A detailed estimate of construction costs for the Batavia Reservoir Compound (Modified) is shown in Table D2. The estimate is based on current costs of similar construction projects, adjusted to October 1982 prices. An estimate of approximately 15 percent was applied as an allowance for contingencies to obtain the total direct cost of required work. Indirect costs for engineering and design, and construction, supervision and administration were estimated to be 15 percent and 10.5 percent respectively, of total direct cost and added to obtain the total first cost of construction assuming that both reservoirs were advertised, bid, and constructed concurrently.

A summary of first costs and investment costs for the Batavia Reservoir Compound (Modified) is shown on Table D3. Total investment includes simple interest of 7-7/8 percent applied for 1 year on initial property requirements and total first cost of required construction. Initial property requirements include land (fee simple) and total acquisition costs.

D11. ANNUAL OPERATION, MAINTENANCE, AND MAJOR REPAIR

The annual operation, maintenance, and major repair (OM&R) costs for the Batavia Reservoir Compound (Modified) were estimated by considering similar data developed for other Corps of Engineers projects. The OM&R costs include the services of a permanent staff and temporary seasonal employees, and also the costs of land management, fish and wildlife management, necessary equipment, normal repairs, periodic major repair, and engineering services. A detailed discussion of OM&R activities is given in Section VII of the Main Report. The average annual OM&R costs for the Batavia Reservoir Compound are estimated to be \$420,000.

D12. ANNUAL COSTS

The average annual costs for the Batavia Reservoir Compound (Modified) are shown in Table D3. Annual costs include 7-7/8 percent interest on investment, amortization of investment over an economic life of 100 years, and operation, maintenance, and major repair costs. The average annual cost of the Batavia Reservoir Compound is estimated to be \$2,878,000.

Table D1 - Estimated Property Costs for Batavia Reservoir
Compound (Modified)

1. Upper Reservoir.

Item	:Estimated Quantity	: Unit	:Estimated Cost
	:	:	\$
Land, Damsite, Fee Title	: 65	: Acre	: 38,000
Land, Reservoir, Perm. Easement	: 1,158	: Acre	: 386,000
Land, Mitigation, Fee Title	: -	: Acre	: -
Buildings, Residential	: 8	: Each	: 241,000(1)
Buildings, Comm. & Farms	: -	: Each	: -
COMPONENT TOTAL	:	:	: 665,000

2. Lower Reservoir.

Item	:Estimated Quantity	: Unit	:Estimated Cost
	:	:	\$
Land, Damsite, Fee Title	: 45	: Acre	: 33,000
Land, Reservoir, Perm. Easement	: 2,474	: Acre	: 571,000
Land, Spillway, Perm. Easement	: 1,616	: Acre	: 455,000
Land, Mitigation, Fee Title	: -	: Acre	: -
Buildings, Residential	: 14	: Each	: 304,000(2)
Buildings, Comm. & Farms	: -	: Each	: -
COMPONENT TOTAL	:	:	: 1,363,000

3. Summary.

Item	: Amount
	: \$
U. R. Component Total	: 665,000
L. R. Component Total	: <u>1,363,000</u>
SUBTOTAL	: 2,028,000
Damages (5 percent)	: <u>102,000</u>
Subtotal	: 2,130,000
Contingencies (20 percent)	: <u>473,000</u>
Subtotal	: 2,603,000
Property Acquisition	: 1,530,000(3)
Relocation	: <u>267,000(4)</u>
TOTAL PROPERTY COST	: 4,400,000

(1) \$32,000 Residence deducted from Nov 1981 Gross Appraisal by NCD.

(2) Assume 12 homes at \$20,000 and 2 homes at \$32,000 = \$304,000.

(3) Per NCD Appraisal.

(4) Relocation (per NCD appraisal) 22 homes at \$12,000=\$266,000 say \$267,000.

Table D2 - Estimated Construction Costs for Batavia Reservoir
Compound (Modified)

1. Upper Reservoir.

Item	:Estimated: :Quantity :	: Unit :	: Unit : Cost :	: Estimated : Cost
	:	:	\$	\$
<u>Earth Dam and Emergency Spillway</u>	:	:	:	:
Clearing and Grubbing	: 65 :	: Acre :	: 2,350.00:	: 152,750
Stripping	: 117,000 :	: S.Y. :	: 1.10:	: 128,700
Common Excavation	: 55,000 :	: C.Y. :	: 4.20:	: 231,000
Compacted Impervious Fill	: 137,100 :	: C.Y. :	: 10.00:	: 1,371,000
Compacted Pervious Fill	: 209,700 :	: C.Y. :	: 4.20:	: 880,740
Compacted Filter Material	: 33,000 :	: C.Y. :	: 14.45:	: 476,850
18-inch Riprap with Bedding	: 10,100 :	: S.Y. :	: 41.20:	: 416,120
36-inch Riprap with Bedding	: 39,200 :	: S.Y. :	: 60.00:	: 2,352,000
Spillway Grout Plug	: 350 :	: C.Y. :	: 77.80:	: 27,230
Topsoil	: 10,800 :	: C.Y. :	: 11.60:	: 125,280
Seed (Crownvetch), Fertilize, and Mulch	: 64,300 :	: S.Y. :	: 0.80:	: 51,440
Access Roadway - Top of Dam	: 3,400 :	: S.Y. :	: 14.90:	: 50,660
Access Roadway - Guard Rail	: 3,400 :	: L.F. :	: 16.95:	: 57,630
Subtotal	:	:	:	: 6,321,400
<u>Principal Outlet Works</u>	:	:	:	:
Common Excavation	: 13,500 :	: C.Y. :	: 4.20:	: 56,700
Compacted Select Fill	: 2,100 :	: C.Y. :	: 12.80:	: 26,880
Concrete (reinforced)	: 2,550 :	: C.Y. :	: 210.00:	: 535,500
Fixed Wheel Sluice Gates and Miscellaneous Fabrications	: 46,750 :	: LBS. :	: 2.55:	: 119,213
Sluice Gate Electric Lift	: 5 :	: Each :	: 8,400.00:	: 42,000
Stop Logs (one set)	: - :	: L.S. :	: 16,900.00:	: 16,900
Steel Sheet Piling	: 2,800 :	: S.F. :	: 13.50:	: 37,800
24-inch Riprap with Bedding	: 1,150 :	: S.Y. :	: 54.65:	: 62,847
Electrical Facilities	: - :	: L.S. :	: 163,000.00:	: 163,000
Common Excavation (Outlet Channel)	: 22,000 :	: C.Y. :	: 4.20:	: 92,400
Compacted Impervious Fill	: 950 :	: C.Y. :	: 10.00:	: 9,500
Compacted Pervious Fill	: 1,850 :	: C.Y. :	: 4.20:	: 7,770
Compacted Filter Material	: 120 :	: C.Y. :	: 14.45:	: 1,734
Topsoil	: 110 :	: C.Y. :	: 11.60:	: 1,276
Seed (Crownvetch), Fertilize, and Mulch	: 600 :	: S.Y. :	: 0.80:	: 480
Subtotal	:	:	:	: 1,174,000

Table D2 - Estimated Construction Costs for Batavia Reservoir
Compound (Modified) (Cont'd)

1. Upper Reservoir. (Cont'd)

Item	:Estimated: :Quantity :	: Unit :	: Unit : Cost :	: Estimated : Cost :
	:	:	\$	\$
<u>Hydro-Meteorologic Data Network</u>	:	:	:	:
<u>System</u>	:	:	:	:
Installation of Radio Telemetric	:	:	:	:
River Gages	: 2 :	: Each :	: 14,600.00:	: 29,200
Converting Existing River	:	:	:	:
Gages to Radio Telemetry	: 4 :	: Each :	: 6,000.00:	: 24,000
Move Alabama Gage Downstream	:	:	:	:
to Foote Road	: - :	: L.S. :	: 4,000.00:	: 4,000
Reservoir Stage Gage	: 1 :	: Each :	: 8,000.00:	: 8,000
Radio Telemetric Rain Gages	: 4 :	: Each :	: 2,700.00:	: 10,800
Mini-Data Analysis and	:	:	:	:
Computation Equipment	: - :	: L.S. :	: 36,000.00:	: <u>36,000</u>
Subtotal	:	:	:	: 112,000
<u>Miscellaneous Work</u>	:	:	:	:
Highway Relocation	: 16,000 :	: S.Y. :	: 14.90:	: 238,400
Bridge Relocation	: - :	: L.S. :	: 189,000.00:	: 89,000
Seed, Fertilize, and Mulch	: 195,000 :	: S.Y. :	: 0.55:	: 107,250
Log Boom Around Principal	:	:	:	:
Outlet Works	: 500 :	: L.F. :	: 110.00:	: 55,000
Downstream Debris Collector	:	:	:	:
(timber piles)	: 13,500 :	: L.F. :	: 9.40:	: 126,900
Care of Water	: - :	: L.S. :	: 72,000.00:	: 72,000
Clearing and Snagging	: 5 :	: Mile :	: 20,800.00:	: 114,000
Mobilization and Preparatory	:	:	:	:
Work	: - :	: L.S. :	: 256,000.00:	: <u>256,000</u>
Subtotal	:	:	:	: 1,058,550
COMPONENT TOTAL	:	:	:	: <u>8,665,950</u>

Table D2 - Estimated Construction Costs for Batavia Reservoir
Compound (Modified) (Cont'd)

2. Lower Reservoir.

Item	:Estimated: :Quantity	: Unit :	: Unit : Cost :	: Estimated : Cost
	:	:	\$	\$
<u>Earth Dam and Emergency Spillway</u>	:	:	:	:
Clearing and Grubbing	: 45	: Acre	: 2,350.00:	105,750
Stripping	: 59,000	: S.Y.	: 1.00:	59,000
Common Excavation	: 143,300	: C.Y.	: 4.20:	601,860
Compacted Impervious Fill	: 42,800	: C.Y.	: 10.00:	428,000
Compacted Pervious Fill	: 45,400	: C.Y.	: 4.20:	190,680
Compacted Filter Material	: 14,100	: C.Y.	: 14.45:	203,745
18-inch Riprap with Bedding	: 41,900	: S.Y.	: 41.20:	1,726,280
Spillway Grout Plug	: 320	: C.Y.	: 77.80:	24,896
Topsoil	: 4,200	: C.Y.	: 11.60:	48,720
Seed (Crownvetch), Fertilize, and Mulch	: 24,600	: S.Y.	: 0.80:	19,680
Access Roadway - Top of Dam	: 400	: S.Y.	: 14.90:	5,960
Access Roadway - Guard Rail	: 440	: L.F.	: 16.95:	7,458
Subtotal	:	:	:	3,422,029
<u>Principal Outlet Works</u>	:	:	:	:
Common Excavation	: 15,000	: C.Y.	: 4.20:	63,000
Compacted Select Fill	: 1,800	: C.Y.	: 12.80:	23,040
Concrete (reinforced)	: 2,150	: C.Y.	: 210.00:	451,500
Fixed Wheel Sluice Gates and Miscellaneous Fabrications	: 37,400	: LBS.	: 2.55:	95,370
Sluice Gate Electric Lift	: 4	: Each	: 8,400.00:	33,600
Stop Logs (one set)	: -	: L.S.	: 16,900.00:	16,900
Steel Sheet Piling	: 2,600	: S.F.	: 13.50:	35,100
24-inch Riprap with Bedding	: 1,050	: S.Y.	: 54.65:	57,383
Electrical Facilities	: -	: L.S.	: 267,000.00:	267,000
Common Excavation (Inlet and Outlet Channels)	: 48,000	: C.Y.	: 4.20:	201,600
Compacted Impervious Fill	: 770	: C.Y.	: 10.00:	7,700
Compacted Pervious Fill	: 1,470	: C.Y.	: 4.20:	6,174
Compacted Filter Material	: 100	: C.Y.	: 14.45:	1,445
Topsoil	: 90	: C.Y.	: 11.60:	1,044
Seed (Crownvetch), Fertilize, and Mulch	: 500	: S.Y.	: 0.80:	400
Subtotal	:	:	:	1,261,256

Table D2 - Estimated Construction Costs for Batavia Reservoir
Compound (Modified) (Cont'd)

2. Lower Reservoir. (Cont'd)

Item	:Estimated: :Quantity :	: Unit :	: Unit : Cost :	: Estimated : Cost
			\$	\$
<u>Training Dikes</u>				
Clearing and Grubbing	: 30	: Acre	: 2,350.00:	70,500
Stripping	: 49,000	: S.Y.	: 1.10:	53,900
Common Excavation	: 6,700	: C.Y.	: 4.20:	28,140
Compacted Impervious Fill	: 50,300	: C.Y.	: 10.00:	503,000
Compacted Pervious Fill	: 45,900	: C.Y.	: 4.20:	192,780
Topsoil	: 9,600	: C.Y.	: 11.60:	111,360
Concrete Pipe (24-inch diam.)	: 235	: L.F.	: 42.00:	9,870
Concrete Pipe (36-inch diam.)	: 60	: L.F.	: 79.00:	4,740
Concrete (reinforced)	: 45	: C.Y.	: 210.00:	9,450
Flap Gate (24-inch diam.)	: 3	: Each	: 2,600.00:	7,800
Flap Gate (36-inch diam.)	: 1	: Each	: 4,300.00:	4,300
Seed, Fertilize, and Mulch	: 145,200	: S.Y.	: 0.55:	79,860
Subtotal				1,075,700
<u>Highway Relocation</u>				
Raise Highways 3'	: 10,000	: L.F.	: 80.00:	800,000
Compacted Pervious Fill	: 22,850	: C.Y.	: 4.20:	95,970
Highway Relocation	: 3,200	: S.Y.	: 14.90:	47,680
Guard Rail	: 2,000	: L.F.	: 16.95:	33,900
Subtotal				977,550
<u>LVRR Bridge Removal</u>				
Demolition - Abutments	: 870	: C.Y.	: 34.30:	29,841
Demolition - Superstructure	: -	: L.S.	: 130,000.00:	130,000
Common Excavation	: 5,100	: C.Y.	: 4.20:	21,420
Subtotal				181,261
<u>Miscellaneous Work</u>				
Seed, Fertilize, and Mulch	: 141,000	: S.Y.	: 0.55:	77,550
Log Boom Around Principal Outlet Works	: 500	: L.F.	: 110.00:	55,000
Care of Water	: -	: L.S.	: 122,000.00:	122,000
Clearing and Snagging	: 8	: Mile	: 22,800.00:	182,400
Reservoir Stage Gage	: 1	: Each	: 8,000.00:	8,000
Mobilization and Preparatory Work	: -	: L.S.	: 189,000.00:	189,000
Subtotal				633,950
COMPONENT TOTAL				7,551,746
			say	7,551,750

Table D2 - Estimated Construction Costs for Batavia Reservoir
Compound (Modified) (Cont'd)

3. Summary.

Item	:	Amount
	:	\$
U. R. Component Total	:	8,665,950
	:	
L. R. Component Total	:	<u>7,551,750</u>
	:	
Plan Subtotal	:	16,217,700
	:	
Contingencies (20 percent)	:	<u>3,243,300</u>
	:	
TOTAL DIRECT COST	:	19,460,000
	:	
Engineering and Design (+15 percent) <u>1/</u>	:	3,070,000
	:	
Supervision and Administration (10.5 percent)	:	<u>2,070,000</u>
	:	
TOTAL CONSTRUCTION COST	:	24,600,000

1/ Includes E+D and hydraulic model testing at \$150,000

Table D3 - Summary of Estimated Costs for Batavia Reservoir
Compound (Modified)

1. First Cost.

Item	:	Amount
	:	\$
Property	:	4,400,000
Construction	:	<u>24,600,000</u>
	:	
TOTAL	:	29,000,000

2. Investment Cost.

Item	:	Amount
	:	\$
Property	:	4,400,000
Construction	:	<u>24,600,000</u>
Subtotal	:	<u>29,000,000</u>
Interest During Construction (7-7/8 percent) <u>1/</u> <u>2/</u>	:	<u>2,200,000</u>
	:	
TOTAL	:	31,200,000

1/ Includes land (fee title for dam sites) and total property acquisition costs, equal to \$1,601,000 and construction cost.

Incremental First Cost:

\$ 538,000 Upper
1,063,000 Lower
\$1,601,000 Total

\$24,600,000 Construction
1,600,000 Property
\$26,200,000 Total

2/ Assume 2-year construction period. .


6 months \$13,100,000 X .0400 (6 mo. factor) = \$ 524,000.
18 months \$13,100,000 X .1249 (18 mo. factor) = \$1,636,190.
\$2,160,190 say \$2,200,000


3. Average Annual Cost.

Item	:	Amount
	:	\$
Interest (7-7/8 percent)	:	2,457,000
Amortization (0.00004)	:	1,000
Operation and Maintenance	:	<u>420,000</u>
	:	
TOTAL	:	2,878,000

4. Benefit-Cost Ratio.

Average Annual Benefits = \$3,419,000 = 1.19
Average Annual Cost \$2,878,000






TONAWANDA CREEK WATERSHED, N.Y.

UPPER DAM
CROSS SECTION
PMF DESIGN


U.S. ARMY ENGINEER DISTRICT, BUFFALO



TONAWANDA CREEK WATERSHED, N.Y.

LOWER DAM
CROSS SECTION
PMF DESIGN

U.S. ARMY ENGINEER DISTRICT, BUFFALO



PRINCIPAL OUTLET WORKS
(CENTERLINE PROFILE OF TYPICAL CONDUIT)

NOT TO SCALE

UPPER RESERVOIR (UR): 5 - 11' X 11' GATED CONDUITS
LOWER RESERVOIR (LR): 4 - 11' X 11' GATED CONDUITS

TONAWANDA CREEK WATERSHED, NEW YORK
BATAVIA RESERVOIR COMPOUND
(MODIFIED)

PRINCIPAL OUTLET WORKS

U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED, 1960

**BUFFALO METROPOLITAN AREA, NEW YORK
WATER RESOURCES MANAGEMENT STUDY**

**TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY**

FINAL FEASIBILITY REPORT

APPENDIX E

GEOTECHNICAL DESIGN

**U. S. Army Engineer District, Buffalo
1776 Niagara Street
Buffalo, NY 14207**

APPENDIX E
GEOTECHNICAL DESIGN
TABLE OF CONTENTS

<u>Paragraph</u>	<u>Description</u>	<u>Page</u>
	<u>SECTION I - GENERAL</u>	E-1
E1	INTRODUCTION	E-1
	<u>SECTION II - GEOLOGY AND SOILS</u>	E-2
E2	REGIONAL GEOLOGY	E-2
E2.1	Physiography	E-2
E2.2	Surficial Geology	E-2
E2.3	Bedrock Geology	E-2
E2.4	Structural Geology	E-2
E2.5	Ground Water	E-3
E2.6	Seismicity	E-3
E3	LOCAL GEOLOGY	E-3
E3.1	Surficial Geology	E-3
E3.2	Bedrock	E-4
E3.3	Ground Water	E-4
E3.4	Structural Geology	E-4
E3.5	Fluvial Processes	E-4
E4	SUBSURFACE EXPLORATIONS	E-5
E4.1	General	E-5
E4.2	1979 Program	E-5
E4.3	Vicinity Program	E-5
E4.4	Laboratory Testing	E-6
E4.5	Soils Stratigraphy	E-6
E5	GEOTECHNICAL DESIGN	E-6
E5.1	General	E-6
E5.2	Upper Reservoir Embankment	E-6
E5.3	Lower Reservoir Embankment	E-8
E5.4	Underseepage Analysis	E-8
E5.5	Training Dikes	E-8a
E5.6	Further Studies	E-9
E6	MATERIALS SURVEY	E-9
E7	CALCULATIONS	E-9

TABLE OF CONTENTS (Cont'd)

FIGURES

Number

- | | |
|----|------------------------|
| E1 | Structural Contour Map |
| E2 | Seismic Zone Map |
| E3 | Vicinity Epicenter Map |

PLATES

Plate No.

- | | |
|----|--|
| E1 | Regional and Local Geology |
| E2 | Soil Laboratory Test Data |
| E3 | Geological Section A-A, Upper Dam |
| E4 | Geological Section B-B, Lower Dam |
| E5 | Possible Material Sources |
| E6 | Centerline Profile Upper Dam |
| E7 | Centerline Profile, Lower Dam |
| E8 | Geological Sections, C-C West Training Dike,
D-D East Training Dike |


NO-A133 910


BUFFALO METROPOLITAN AREA NEW YORK WATER RESOURCES
MANAGEMENT INTERIM REP. (U) CORPS OF ENGINEERS BUFFALO
NY BUFFALO DISTRICT JUL 83

6/9

UNCLASSIFIED

F/G 13/2 NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

APPENDIX E
GEOTECHNICAL DESIGN

SECTION I - GENERAL

E1. INTRODUCTION

The Batavia Reservoir Compound (Modified), the selected plan, is a combination of two shallow detention reservoirs arranged in series. The reservoirs are located within the flood plain between the village of Alexander and the city of Batavia. They are referred to as the upper reservoir and lower reservoir in this appendix. The location of each reservoir is shown on Plate E1. All elevations shown in this appendix are referred to United States Coast and Geodetic Survey datum.

SECTION II - GEOLOGY AND SOILS

E2. REGIONAL GEOLOGY

E.2.1 Physiography

The proposed dam sites are located in the towns of Batavia and Alexander, Genesee County, NY. This area is within the Erie-Ontario Plain of the Central Lowlands physiographic province (Plate E1). Topography is relatively flat to gently rolling except for linear features such as moraines, beach ridges, and bedrock outcrops. The Onondaga escarpment is the most prominent of the latter, and crosses just north of the project. The moraines in the area are late Wisconsinan in age and are generally composed of till. Glacial Lake Warren formed the most outstanding beach ridges at an elevation of 850 to 900 feet above sea level.

Tonawanda Creek, a tributary to the Niagara River, provides the major drainage through the area. Its upper reach, south of the project area, drains a narrow, glacially-filled valley. Its lower portion flows through the bed of a former lake, Lake Tonawanda, which existed up until about 700 years ago. In the project vicinity it flows through a relatively wide alluvial plain.

E2.2 Surficial Geology

Surficial deposits in the area are greatly influenced by glacial processes of the Late Wisconsinan Stage, particularly those activities which occurred about 13,000 years ago. Advance and retreat of ice directly deposited till, morainal ridges, and gravelly kames and outwash. Preglacial lakes in the narrow valleys were filled with clay and silt and gravelly deltas. The glacial Great Lakes such as Lakes Whittlesey and Warren left remnants of their beaches. Lake Tonawanda, which occupied a shallow depression north of the Onondaga escarpment is now swampy and filled with fine-grained and organic deposits.

Alluvium in the form of gravel bars and silt overbank deposits is common.

E2.3 Bedrock Geology

Western New York is underlain by Paleozoic sandstone, siltstone, shale, and carbonate rocks. The general stratigraphy is shown on Plate E1. The Silurian Lockport Dolomite and Devonian Onondaga Limestone are the major ridge formers. These, along with the Medina Sandstone, are primary sources of quarried stone. The Silurian Salina Formation is also of economic importance. The nearby Retsof Salt Mine, located within the Salina Formation is one of the world's largest producers of salt. Several formations, especially the Medina and Lockport, provide reservoirs for natural gas production.

E2.4 Structural Geology

Bedrock forms a south-southwestward dipping homocline. Small scale folds related to gravity creep may be found. Joints are common usually occurring

as two diagonal sets trending N45°W and N75°E (Sutton, 1950). The major structure in the area is the Clarendon-Lindon Fault System (Figure E1). According to Fakundiny and Others (1978), this system forms a 3 to 9.3 mile wide zone of complexly arranged steeply dipping reverse and normal faults in Precambrian and Paleozoic rock. They measured about 300 feet of vertical displacement and consider it to be possibly the longest and oldest active fault in the eastern United States.

E2.5 Ground Water

Large quantities of ground water are available in the region. The carbonate bedrock and glacially deposited gravel form large aquifers. Many municipalities, as well as single homeowners, use ground water as their primary source of water.

E2.6 Seismicity

Northwestern New York is located in an area classified as a Seismic Risk Zone 3 (Figure E2). This is defined as an area where major damage could occur due to seismic activity. The greatest recorded earthquake occurring at Attica, NY, in 1929, had an intensity of VIII on the Modified Mercalli Scale. According to published reports, 251 house chimneys were thrown down and walls were cracked. In a small cemetery east of town, practically every monument went down. Westward of Attica Reservoir, a number of wells went dry and in the reservoir there was a sudden increase of about 1,000,000 gallons per day without any rain; this flow continued for some days. In Batavia, several house chimneys fell and a small lake overflowed a highway. Figure E3 shows the location of earthquake epicenters in the Attica, NY, area. In addition to those shown, there was another earthquake at Dale, NY, in 1973 which has been related to well injection (Fakundiny and Others, 1978).

E3. LOCAL GEOLOGY

E3.1 Surficial Geology

The Tonawanda Creek valley between Batavia and Alexander, NY, is largely filled with stratified gravel, sand, and silt. Poorly drained, low-lying areas are typically filled with organic silty alluvium. Some of these organic deposits are more than 3 feet thick (U. S. Soil Conservation Service, 1969) and probably developed in depressions left in glacial outwash.

The topography of the valley north of Alexander is low except for several kames (Plate E1). These knobby ridges were deposited by glacial ice and are composed of stratified, well-sorted sand and gravel. Some kames are overlain by sandy silt till. The kames have as much as 100 feet of relief and are utilized as borrow areas for sand and gravel (Plate E1).

Many low areas adjacent to the kames are also composed of sand and gravel. These deposits are glacial outwash, inwash to glacial Great Lakes, and alluvium.

The lower dam site (Plate E7) is located on outwash and beach deposits. The beach deposit (Boring D79-3) is composed of well sorted medium sand and is about 21.5 feet thick.

The upland adjacent to the valley is blanketed with sandy silt till. This material appears to be uniformly distributed to the south and east of the valley but is in the form of hummocky end moraine to the west. Low areas between hummocks are poorly drained causing swampy conditions.

E3.2 Bedrock

Bedrock underlying the project area consists of the Levanna Shale member of the Middle Devonian Skaneateles Formation. Grossman (1938) reports a thickness of 128 feet for this member in the Batavia, NY, area. Sutton (1950) describes the basal part of the member as a black, bituminous shale containing the brachiopod Orbiculoidea minuta in great numbers. Twenty-three feet from the base is a brownish-gray, crystalline, fossiliferous limestone, 1-3/10 of a foot thick. Above the limestone is a dark to medium gray shale; upper portions of which are characterized by dark gray, irregularly bedded, fossiliferous shale.

No outcrops were observed in the project area but bedrock was encountered at borings taken along the lower dam alignment.

E3.3 Ground Water

Ground water is relatively close to the surface and is generally encountered within 5 feet of the surface. Water levels are probably controlled mostly by the stage of Tonawanda Creek. Most soils are very permeable. This may result in the need for considering dewatering techniques in excavations. Observation wells were installed in the vicinity of the center of both proposed dams so that ground water processes can be studied.

E3.4 Structural Geology

Bedrock underlying the project site is assumed to follow the regional dip of about 3° to the south. Conners (1969) notes that as one approaches the Clarendon-Linden fault structure, which he maps about 2,000 feet east of the lower dam site and 3 miles from the upper dam site, the dip may change to as much as 3-5° to the west. The effects of this geological structure and its associated seismicity have been considered in the preliminary designs for the embankments.

E3.5 Fluvial Processes

Tonawanda Creek is the major drainage way through the area. In its upstream reaches where it flows through a valley filled with glacial deposits it carries some bedload. In its lower reaches, particularly south of Alexander, it carries mostly washload. This material is deposited at times when the stream overflows its banks. Archer and La Sala (1968) shows the gradation of two suspended sediment samples taken in 1963 to be 58 and 78 percent clay, 41 and 15 percent silt, and 1 and 7 percent sand.

The banks of Tonawanda Creek in the project vicinity are low, relatively stable, and composed of fine sand. Their relative stability is probably due to low velocities of the stream.

La Sala (1968), calculates that 60,000 tons of sediment, mostly clay, is annually discharged at Tonawanda Creek in Batavia. He observed that reservoirs constructed on the creek may experience problems due to the sediment load. The anticipated volume and distribution of sediment accumulation at the upper and lower dams are unknown.

To evaluate the magnitude of sedimentation problems which may occur during periods of extended storage, samples will be taken during detail design at appropriate intervals to determine its concentration and gradation. The volume of sediment and distribution of deposits will be calculated so the maintenance requirements may be determined.

We will also consider the effects that sediment storage and controlling of stream stage will have on the bed and banks downstream of the proposed structures. Some erosion of banks, especially those composed of silts, probably would occur.

E4. SUBSURFACE EXPLORATIONS

E4.1 General

A subsurface exploration program was conducted in 1979 to obtain the soils information necessary to perform a preliminary design for the proposed flood control project.

E4.2 1979 Program

A subsurface exploration program for the Batavia Reservoir Compound was conducted in May 1979. The borings and their locations are shown on Plate E1. The primary purpose of this drilling program was to estimate the liquefaction potential of the soils by their relative density as determined by the Standard Penetration Test (Seed and Idriss, 1971). This method provided us with data to evaluate the suitability of the proposed sites.

The soil borings were conducted using a 3.5-inch outer diameter (O.D.) sampler driven 18 inches by a 375 pound hammer free falling 18 inches. Blow counts were recorded every 6 inches of penetration. When gravel was encountered in the sampler, the amount of penetration per blow was recorded for each drive. This was done to eliminate any resistance due to gravel during driving of the Split Spoon Sampler. Continuous Split Spoon Samples were obtained at each borehole location.

E4.3 Vicinity Programs

Previous subsurface explorations were made in 1974 by the New York State Department of Transportation, in 1950 and 1959 by the New York State Department of Public Works, and in 1971 by the Niagara Mohawk Power Company in the general vicinity of the project. The maximum depth of these borings

is 76 feet. Bedrock was encountered at a depth of approximately 70 feet, just east of the city of Batavia at the crossing of the Conrail railroad line and State Route 63. Rock was encountered at a depth of approximately 20 feet just west of Batavia at the crossing of the Conrail railroad line and State Route 98. Logs of rock samples obtained there indicated that the bedrock consists of a shaley limestone.

E.4.4 Laboratory Testing

Laboratory tests were performed on the disturbed soil samples obtained in the 1979 program. These tests consisted of Atterberg Limits, Gradation Analysis, and Moisture Content. Classification of the soil samples was performed using the Unified Classification System (see Plate E2). Data obtained from the testing program was used for a preliminary determination of the liquefaction potential of the soil and preliminary design of the structures.

E4.5 Soils Stratigraphy

The material underneath the axis of the upper dam consists mainly of sandy silt underlain by gravelly sand. Underlying the gravelly sand is a layer of clayey silt which grades into gravelly fine sand. No bedrock was encountered. The east abutment of the upper dam generally consists of a gravelly sand underlain by a clayey silt. No bedrock was encountered at this location (Plate E4).

The material beneath the axis of the lower dam consists of gravelly silty sand underlain by shale. Shale was encountered at approximately 30 feet below ground surface (Plate E3).

The material underneath the west training dike is a sorted glacial outwash consisting of sandy to silty gravels. The water table was encountered at approximately 6 feet below ground surface and had a distinct sulphur odor. No bedrock was encountered. Underneath the east training dike the material consists of glacial outwash of stratified layers of sand and gravel overlying till. The water table was approximately 8 feet below ground surface and no bedrock was encountered.

E5. GEOTECHNICAL DESIGN

E5.1 General

A preliminary design for the Batavia Reservoir Compound (Modified), was performed for the upper and lower reservoir embankments as well as for the training dikes located on both the east and west side of the valley. Seepage through the embankments was not analyzed nor were the various cases for stability. This will be accomplished in the next phase as well as a detailed seismic analysis of the embankments and foundation materials.

E5.2 Upper Reservoir Embankment

The upper embankment will be located approximately 200 feet downstream of the Conrail railroad embankment. The reservoir embankment will stretch

approximately 5,450 feet across the Tonawanda Creek Valley. The location for the upper reservoir embankment is shown on Plate E1. The embankment has been designed to function as an emergency spillway with a top elevation of 922.5 feet.

The embankment (Plates E3 and E6) was developed with a one vertical on three horizontal side slopes and a top width of 20 feet from the west abutment to Tonawanda Creek. From Tonawanda Creek to the east abutment, the top width is 10 feet. A 16-foot wide access road would be provided across the top of the upper embankment section with the 20-foot top width. This would allow maintenance access from State Route 98 to the control gates.

The abandoned Conrail railroad embankment was not considered for use in the plan of development as there is no available information as to its stability or content. In future studies, the railroad embankment would be investigated for possible use as a source of borrow material.

The foundation preparation would consist of clearing and grubbing, stripping and excavating for an inspection trench, riprap toes, and filter blanket. A preliminary underseepage analysis was performed and a positive cutoff is not considered necessary.

The impervious core will be built up to the top of the embankment with a filter zone to separate it from the pervious fill. On the downstream side of the core material, a filter blanket will extend out to the toe of the embankment. This filter will end in the toe for the riprap section.

Since the location of the flood control project is in the general vicinity of the Clarendon-Linden Fault, certain seismic design considerations were followed. These include the use of a thicker core of impervious material, graded filters in a zone located just downstream from the core, pervious downstream zones and cohesionless material upstream of the core. The correlation of the Standard Penetration Test and gradation of the foundation materials to the liquefaction potential of the material indicates that liquefaction may not be a problem. A detailed seismic analysis of both the dam and foundation material will be performed during the next phase of the project. The probability of a full pool and a seismic event occurring at the same time will be investigated in the detailed design stage.

Riprap with a bedding layer would cover the exposed portion of the embankment. The riprap placed on the upstream face of the embankment will be 12 inches with a 6-inch bedding layer. This is necessary to protect it from wave action that might occur as a result of water ponding in the reservoir.

The top and downstream face of the embankment will be riprapped with 18-inch stone with a 6-inch bedding layer for use as an emergency spillway. The riprap will be chinked with 6 inches of topsoil and seeded with crown vetch. This is necessary to prevent migration of the riprap down the embankment slope due to the flow of water over the spillway. The velocity of the water over the spillway is relatively low, approximately 5 fps, thus 18-inch riprap should be satisfactory as noted in WES Report, T.R. 2-650 (see calculations in Section E7).

E5.3 Lower Reservoir Embankment

The lower embankment lies approximately one-half mile south of the city of Batavia (Plate E1). The total length of the embankment is approximately 5,600 feet. The embankment is designed to function as an emergency spillway with a top elevation of 900 feet from Creek Road westward for approximately 4,000 feet. From Creek Road to the east abutment, and for a short distance at the west abutment, the embankment is designed as a nonoverflow section with a top elevation of 905.5 and grassed slopes (Plates E4 and E7).

The embankment was developed with a one vertical to three horizontal side slope and a top width varying from 10 to 20 feet. The 20-foot wide top width section would extend from Creek Road west for approximately 800 feet to the control gates. This section would have a 16-foot wide access road to allow maintenance access to the gates from Creek Road.

The foundation preparation and construction of this embankment would be essentially the same as those for the upper reservoir embankment as discussed earlier.

E5.4 Underseepage Analysis

A preliminary underseepage analysis was performed for the Lower Reservoir. The Lower Reservoir was considered to be the more critical case since the foundation soils directly underlying the dam (gravelly sands) are considered to be more pervious than the foundation soils directly beneath the Upper Reservoir (sandy silts). The foundation soils of the Lower Reservoir are considered more pervious than those in the structure (impervious core); thus only seepage through the foundation soils is considered.

A presumptive value for permeability was determined based on the diameter of the foundation material which is 10 percent finer by weight (D_{10}). The permeability in the vertical direction was determined to be $K_v = 8.20 \times 10^{-5}$ ft/sec and is considered to have good drainage characteristics (ref: Seepage Drainage and Flow Nets, Cedergren Fig. 2.8). This is based on an average D_{10} of .05 mm for the foundation material taken from 15 gradation tests performed on the samples obtained from subsurface explorations at the dam area; four from boring D79-1, five from boring D79-2, and six from D79-3. The permeability in the horizontal direction K_H was presumed to be four times greater than the permeability in the vertical direction or $K_H = 3.28 \times 10^{-4}$ ft/sec. A ratio of $K_H = 4K_v$ was considered to be a reasonable assumption in taking into account any horizontal stratification of the foundation soil that might exist. A transformed section of the Lower Reservoir was prepared based on this ratio and a flow net was drawn (see Section E-7). An effective permeability $K_e = 1.64 \times 10^{-4}$ ft/sec and a flow $Q = 5.86 \times 10^{-4}$ ft³/sec was determined using the transformed section. The flow net was redrawn on the natural section. An exit gradient of 0.071 and a critical gradient of 0.894 was determined using the natural section. The ratio of the critical gradient to the exit gradient was determined to be equal to 12.56.

Ratios of critical gradients to exit gradients greater than 1.5 are required to prevent piping from occurring, thus a positive cut-off is not considered

necessary. In-situ soil permeability will be determined in the next phase so that a more exact underseepage analysis can be performed.

E5.5 Training Dikes

Nonoverflow training dikes are proposed for both the east and west sides of the Tonawanda Creek Valley. The total length of these embankments is approximately 5,030 feet (see Plate E1).

The foundation preparation and construction of the dikes is essentially the same as those for the upper and lower embankments. The noticeable difference in the dikes is the side slopes are grassed rather than riprapped as the embankments are designed as nonoverflow sections (see Plate E8).

E5.6 Further Studies

Additional subsurface investigations will be performed for the final design, Phase II GDM. These will include obtaining undisturbed and disturbed samples and possibly "Dutch Cone" penetrometer tests to determine, with a great degree of confidence, the liquefaction potential of the soil. Field pumping tests to determine the permeability of the soil and a general comprehensive investigation to determine the locations of buried channels and location of required materials will also be performed.

E6. MATERIALS SURVEY

The construction materials required to build the embankments are:

- riprap
- riprap bedding material
- transition zone and filter material
- impervious fill
- pervious fill
- concrete aggregates

These materials would be used as shown in the cross sections that appear on Plates E3 and E4. A paper materials survey was prepared for the required quarried materials and appears on Plate E5.

The impervious fill consisting of soil with high clay and silt content will form the core of the dam. A review of the surficial geology of the area indicates that suitable impervious material may be found within 15 miles of the project site. Test pits and borings will be utilized to identify sources available for this purpose.

Pervious fill will be utilized to fill in the remainder of the cross section. It will consist of gravel and sand with some silt and clay. The material will have varying amounts of different size particles. The only requirements for the material is that it be free of spoil (that is, cinders, bricks, garbage, and other such material), organic material, and have a maximum size of 6 inches.

The pervious fill will also be utilized to form a bedding layer under the principal outlet works. This will consist of granular material having a maximum size of 3 inches. Material suitable for this purpose is available near the project site.

The stone for the riprap, filter, bedding, and transition materials is available from nine quarry operations within 30 miles of Batavia.

Coarse aggregate for concrete is available from five sources within 30 miles of Batavia. In addition, fine aggregate is available from two sources within 30 miles of Batavia.

The disposal of spoil materials from stripping, clearing and grubbing, and excavation will be accomplished by their removal to landfills or by burial at the project site.

E7. CALCULATIONS

Subject Tonawanda Creek F.C.PComputation of Riprap for wave actionComputed by JAG

Checked by _____

Date 6/28/79

From EM 1110-2-2300, Fig 5-5:

Assumed Wave height = 2 ft.Sp Gr Stone = 2.5

From EM 1110-2-2300, Fig 5-6

With side slopes 1V:3Hwave height = 4 ft.Sp gr Stone = 2.5Riprap req'd = 12"

Subject Tonawanda Creek F.C.P

Computation of Riprap for wave action

Computed by JAG

Checked by _____


Date 6/28/77

EM 1110-2-2300
1 Mar 1971

- GIVEN: ① EMBANKMENT SLOPE, $COT \alpha = 3$
 ② , ⑥ SPECIFIC GRAVITY OF ROCK, $G = 2.5$
 ④ WAVE HEIGHT, $H = 2$ FT

ENTERING THESE VALUES IN THE NOMOGRAPH IN THE ORDER SHOWN,
 THE FOLLOWING VALUES ARE OBTAINED:

- ⑤ MEDIAN ROCK SIZE, $W_A = 35$ lbs.
 ⑦ RIPRAP THICKNESS, $T = 12$ in





Slope protection nomograph for dumped
 riprap for earth dams

Subject Tonawanda Creek F.C.P

Computation of Riprap for overflow

Computed by JAG

Checked by _____

Date 9/4/8-


Given: 10 ft High Embankment
velocity 7.5 fps

Use Test Series 1

Assume Tailwater Elevation 1' above crest

∴ ok to use 28" riprap

LEGEND

SYMBOL	GRADATION
○	A - 24" max
△	A - 36" max
□	B - 16" max
●	C - 24" max

LIMITS OF STABILITY
ACCESS TYPE EMBANKMENTS
From TR. NO 2-650

Subject TONAWANDA CREEK F.C.P.
 Computation of Seepage Analysis, Lower Reservoir
 Computed by JAG Checked by CJL Date 3/20/81

Assumptions: No Flow thru embankment is considered since foundation soils many times more pervious than those in structure - EM 1110-2-1901
 $K_H = 4 K_V$ - Anisotropic Soil

Given: $H = \text{Head } H_2O = 10 \text{ Ft}$
 K_V = permeability in vertical direction =
 $C D_{10}^2$ where $C = 10.0$ and
 $D_{10}^2 = .05 \text{ mm}$ - From grad test
 $K_V = .0025 \text{ cm/sec} = 8.2 \times 10^{-5} \text{ Ft/sec}$
 $K_H = 4 K_V = 3.28 \times 10^{-4} \text{ Ft/sec}$
 $n_F = \# \text{ Flow lines} = 5$
 $n_E = \# \text{ equipotential lines} = 14$

FIND:

$$Q = \text{Flow} = \frac{n_F}{n_E} K_e H$$

Where $K_e = \sqrt{K_H K_V}$ - From transformed section

$$K_e = 1.64 \times 10^{-4} \text{ Ft/sec}$$

$$Q = \frac{5}{14} (1.64 \times 10^{-4}) (10)$$

$$Q = 5.86 \times 10^{-5} \text{ Ft}^3/\text{sec}$$

Determine Exit Gradient & using natural section

$$i = \frac{\Delta h}{l}$$

where $\Delta h = H/n_E$

$$\Delta h = 10/14$$

$$\Delta h = .71$$

$l = \text{length of seepage path to}$

exit - from natural section

$$l = 10 \text{ Ft}$$

$$E = 12$$

R 12/81

Subject Tonawanda Creek F.C.P.
 Computation of Ser-Pass Analysis Lower Bag, No. 1
 Computed by JAG Checked by CWL Date 3/20/81

$$L = 17/10$$

$k = 1.07 < 5$ OK Ref NCD comment Dec 1980
 Where 5 is the critical value for cohesionless soils.

Determination of Critical gradient

$$i_c = \frac{G_s - 1}{1 + e} \cdot \text{R.F. EM 110-2-1913 pg. B-12}$$

where $G_s = \text{Specific gravity} = 2.65$
 $e = \text{Void ratio} = 0.85$ - assumed
 from Basic Soils Eng. - B.K. Hough

$$i_c = \frac{2.65 - 1}{1 + 0.85}$$

$$i_c = 1.89 = \frac{2.65 - 1}{1 + 0.85}$$


Ratio of Critical to Exit Gradients


$$i_c/i_e \geq 1.5 \quad \text{Ref NCD comment Dec 80}$$

$$i_c/i_e = 1.89 / 1.07$$

$$i_c/i_e = 1.76 > 1.5 \quad \text{OK}$$

BY WLB DATE 18 DEC 81 SUBJECT TOMAWANNA CREEK FCP SHEET NO. 1 OF 2
 CHKD. BY DATE SEEPAGE ANALYSIS JOB NO.
 LOWER RESERVOIR





References

- Archer, R. J. and A. M. LaSala, Jr., 1968, A Reconnaissance of Stream Sediment in the Erie-Niagara Basin, NY, Basin Planning Report ENB-5. Prepared for the Erie-Niagara Basin Regional Water Resources Planning Board by State of New York Conservation Dept. Water Resources Comm, p. 34.
- Calkin, Parker E., 1970. Strand Lines and Chronology of the Glacial Great Lakes in Northwestern New York, Ohio Journal of Science 70 (2): 78, p. 79-96.
- Connors, S.D. 1969, Seismic Activity in Western New York. Unpublished. p. 48.
- Environmental Impact Statement for Western New York Nuclear Service Center, 1973, Prepared by Dames and Moore, Inc.
- Fakundiny, Robert H., John T. Myers, Paul W. Pomeroy, Jeffrey W. Pferd, Thaddeus A. Nowak, Jr., 1978, Structural Instability Features in the Vicinity of the Clarendon-Linden Fault System, Western New York and Lake Ontario, in Advances in Analysis of Geotechnical Instabilities, University of Waterloo Press, p. 121-178.
- Fakundiny, Robert H., Jeffrey W. Pferd, Paul W. Pomeroy, 1978, Clarendon-Linden Fault System of Western New York: Longest (?) and Oldest (?) Active Fault in Eastern United States, Geol. Soc. of Am., Abs. with Prgms. 1978, p. 42.
- Geology of Western New York Guide Book, NY State Geol. Assn., 38th Annual Mtg, 1968, E. J. Buehler, Ed, Pub. by NY State Geological Assn., p. 116.
- Grossman, William L., 1938, Geology of the Caledonia Quadrangle, M. A. Thesis University of Rochester.
- Kindle, E. M., and F. B. Taylor, 1913. Description of the Niagara Quadrangle, U. S. Geol. Survey Geol. Atlas Folio 190, p. 25.
- Seed, H. Bolton and Izzat M. Idriss, 1971. Simplified procedure for Evaluating Soil Liquefaction Potential, J. Soil Mechanics and Foundations Div., Proc. ASCE, Vol. 97, No. SM 9, p. 1249-1273.
- Soil Survey of Genesee County, NY, 1969, USDA, Soil Conservation Service, Washington, DC, p. 182.
- Stability of Riprap and Discharge Characteristics, Overflow Embankments, Arkansas River, Arkansas, Technical Report No. 2-650, June 1964. U. S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi.
- Sutton, Robert G., 1950. Stratigraphy and Structure of the Batavia Quadrangle, M. S. Thesis, University of Rochester, NY, p. 141.






FIGURE E 1






PROJECT SITES

LEGEND:

THESE SYMBOLS REPRESENT THE RELATIVE SIZES OF THE EARTHQUAKES AND THEIR APPROXIMATE EPICENTERS. THEY DO NOT DEFINE THE LIMITS OF THE EPICENTRAL AREAS OR FELT AREAS OF THE SHOCKS.

SOURCE: TAKEN FROM WEST VALLEY NUCLEAR PROCESSING PLANT ENVIRONMENTAL IMPACT STATEMENT, PREPARED BY DAMES AND MOORE, 1973.



TONAWANDA CREEK
BATAVIA RESERVOIR COMPOUND
(MODIFIED)
VICINITY EPICENTER MAP
U.S. ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED NOV. 1979

TEST DATA SUMMARY

PROJECT BATAVIA RESERVOIR COMPOUND (MODIFIED)

SHEET 1 OF 2

TEST DATA SUMMARY																				SHEET 1 OF 2					
PROJECT BATAVIA RESERVOIR COMPOUND (MODIFIED)																									
BORING NO.	SAMP NO	DEPTH OF SAMPLE (FEET)	LABORATORY CLASSIFICATION	MECHANICAL ANALYSIS		ATTENDING LIMITS		SPECIFIC GRAVITY G	NAT. UNIT WEIGHT LB/FT ³	CORRECTION DATA		INITIAL	DRY DENSITY LB/FT ³	W _p %	a ₁	TYPE TEST	SPECIMEN SIZE INCHES	TEST	e _{max} / (IN/FT) 100 G	e _{min} / (IN/FT) 100 G	PERMEABILITY K / (IN/FT) 100 G	CONSOLIDATION DATA			REMARKS
				GRAVITY	WATER	LL	PL			GRAVITY	WATER											GRAVITY	WATER	GRAVITY	
B72-1	1	3'-1.8"	CL	1	10	25	10.5	25.0																	
	2	3'-2.5"	CL	1	10	25	10.5	25.0																	
	3	3'-3.2"	CL	1	10	25	10.5	25.0																	
	4	3'-3.9"	CL	1	10	25	10.5	25.0																	
B72-2	1	3'-4.6"	CL	1	10	25	10.5	25.0																	
	2	3'-5.3"	CL	1	10	25	10.5	25.0																	
	3	3'-6.0"	CL	1	10	25	10.5	25.0																	
	4	3'-6.7"	CL	1	10	25	10.5	25.0																	
B72-3	1	3'-7.4"	CL	1	10	25	10.5	25.0																	
	2	3'-8.1"	CL	1	10	25	10.5	25.0																	
	3	3'-8.8"	CL	1	10	25	10.5	25.0																	
	4	3'-9.5"	CL	1	10	25	10.5	25.0																	
B72-4	1	3'-10.2"	CL	1	10	25	10.5	25.0																	
	2	3'-10.9"	CL	1	10	25	10.5	25.0																	
	3	3'-11.6"	CL	1	10	25	10.5	25.0																	
	4	3'-12.3"	CL	1	10	25	10.5	25.0																	
B72-5	1	3'-13.0"	CL	1	10	25	10.5	25.0																	
	2	3'-13.7"	CL	1	10	25	10.5	25.0																	
	3	3'-14.4"	CL	1	10	25	10.5	25.0																	
	4	3'-15.1"	CL	1	10	25	10.5	25.0																	
B72-6	1	3'-15.8"	CL	1	10	25	10.5	25.0																	
	2	3'-16.5"	CL	1	10	25	10.5	25.0																	
	3	3'-17.2"	CL	1	10	25	10.5	25.0																	
	4	3'-17.9"	CL	1	10	25	10.5	25.0																	
B72-7	1	3'-18.6"	CL	1	10	25	10.5	25.0																	
	2	3'-19.3"	CL	1	10	25	10.5	25.0																	
	3	3'-20.0"	CL	1	10	25	10.5	25.0																	
	4	3'-20.7"	CL	1	10	25	10.5	25.0																	
B72-8	1	3'-21.4"	CL	1	10	25	10.5	25.0																	
	2	3'-22.1"	CL	1	10	25	10.5	25.0																	
	3	3'-22.8"	CL	1	10	25	10.5	25.0																	
	4	3'-23.5"	CL	1	10	25	10.5	25.0																	
B72-9	1	3'-24.2"	CL	1	10	25	10.5	25.0																	
	2	3'-24.9"	CL	1	10	25	10.5	25.0																	
	3	3'-25.6"	CL	1	10	25	10.5	25.0																	
	4	3'-26.3"	CL	1	10	25	10.5	25.0																	
B72-10	1	3'-27.0"	CL	1	10	25	10.5	25.0																	
	2	3'-27.7"	CL	1	10	25	10.5	25.0																	
	3	3'-28.4"	CL	1	10	25	10.5	25.0																	
	4	3'-29.1"	CL	1	10	25	10.5	25.0																	
B72-11	1	3'-29.8"	CL	1	10	25	10.5	25.0																	
	2	3'-30.5"	CL	1	10	25	10.5	25.0																	
	3	3'-31.2"	CL	1	10	25	10.5	25.0																	
	4	3'-31.9"	CL	1	10	25	10.5	25.0																	
B72-12	1	3'-32.6"	CL	1	10	25	10.5	25.0																	
	2	3'-33.3"	CL	1	10	25	10.5	25.0																	
	3	3'-34.0"	CL	1	10	25	10.5	25.0																	
	4	3'-34.7"	CL	1	10	25	10.5	25.0																	
B72-13	1	3'-35.4"	CL	1	10	25	10.5	25.0																	
	2	3'-36.1"	CL	1	10	25	10.5	25.0																	
	3	3'-36.8"	CL	1	10	25	10.5	25.0																	
	4	3'-37.5"	CL	1	10	25	10.5	25.0																	
B72-14	1	3'-38.2"	CL	1	10	25	10.5	25.0																	
	2	3'-38.9"	CL	1	10	25	10.5	25.0																	
	3	3'-39.6"	CL	1	10	25	10.5	25.0																	
	4	3'-40.3"	CL	1	10	25	10.5	25.0																	
B72-15	1	3'-41.0"	CL	1	10	25	10.5	25.0																	
	2	3'-41.7"	CL	1	10	25	10.5	25.0																	
	3	3'-42.4"	CL	1	10	25	10.5	25.0																	
	4	3'-43.1"	CL	1	10	25	10.5	25.0																	
B72-16	1	3'-43.8"	CL	1	10	25	10.5	25.0																	
	2	3'-44.5"	CL	1	10	25	10.5	25.0																	
	3	3'-45.2"	CL	1	10	25	10.5	25.0																	
	4	3'-45.9"	CL	1	10	25	10.5	25.0																	
B72-17	1	3'-46.6"	CL	1	10	25	10.5	25.0																	
	2	3'-47.3"	CL	1	10	25	10.5	25.0																	
	3	3'-48.0"	CL	1	10	25	10.5	25.0																	
	4	3'-48.7"	CL	1	10	25	10.5	25.0																	
B72-18	1	3'-49.4"	CL	1	10	25	10.5	25.0																	
	2	3'-50.1"	CL	1	10	25	10.5	25.0																	
	3	3'-50.8"	CL	1	10	25	10.5	25.0																	
	4	3'-51.5"	CL	1	10	25	10.5	25.0																	
B72-19	1	3'-52.2"	CL	1	10	25	10.5	25.0																	
	2	3'-52.9"	CL	1	10	25	10.5	25.0																	
	3	3'-53.6"	CL	1	10	25	10.5	25.0																	
	4	3'-54.3"	CL	1	10	25	10.5	25.0																	
B72-20	1	3'-55.0"	CL	1	10	25	10.5	25.0																	
	2	3'-55.7"	CL	1	10	25	10.5	25.0																	
	3	3'-56.4"	CL	1	10	25	10.5	25.0																	
	4	3'-57.1"	CL	1	10	25	10.5	25.0																	
B72-21	1	3'-57.8"	CL	1	10	25	10.5	25.0																	
	2	3'-58.5"	CL	1	10	25	10.5	25.0																	
	3	3'-59.2"	CL	1	10	25	10.5	25.0																	
	4	3'-59.9"	CL	1	10	25	10.5	25.0																	
B72-22	1	3'-60.6"	CL	1	10	25	10.5	25.0																	
	2	3'-61.3"	CL	1	10	25	10.5	25.0			</														

TEST DATA SUMMARY

PROJECT BATAVIA RESERVOIR COMPOUND (MODIFIED)

SHEET 2 OF 2


BORING NO.	SAND NO.	DEPTH OF SAMPLE (FT)	LABORATORY CLASSIFICATION	MECHANICAL ANALYSIS			ATTENDING LIMITS			SPECIFIC GRAVITY (G _s)	NAT. DRY DENSITY (LB/FT ³)	COMPARATIVE DATA		SHEAR DATA			TEST	Q _u (TSR) (PSI)	C _u (TSR) (PSI)	PERMEABILITY			COMPARATIVE DATA			REMARKS
				W _t (%)	SAND (%)	FINES (%)	D ₁₀	LL (%)	PL (%)			W _t (%)	W _u (%)	W _p (%)	A ₁ (%)	A ₂ (%)				K (1/IN)	K (1/IN)	K (1/IN)	D ₁₀ (FT)	K ₁₅ (FT)	C _u	
BTV-4	7	0'-10.5'	CL	16	84	16	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	8	10.5'-13'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	9	13'-15.5'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	10	15.5'-18'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	11	18'-20.5'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
BTV-7	12	0'-10.5'	CL	16	84	16	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	13	10.5'-13'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	14	13'-15.5'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	15	15.5'-18'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	16	18'-20.5'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
BTV-8	17	0'-10.5'	CL	16	84	16	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	18	10.5'-13'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	19	13'-15.5'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	20	15.5'-18'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										
	21	18'-20.5'	CL	0	100	0	0.075	24.0	17.6	16.2	118.2	100	100	100	100	100										

FORM 2000 (OPTION OF 1 MAY 88) OF CORROSION

Y - TYPICAL COMPRESSION
UC - UNCOMPRESSED COMPRESSION
NP - NON PLASTIC

Q - DIRECT SHEAR
Q - UNCOMPOUND UNDRAMED

S - COMPOUND DRAINED
N - COMPOUND UNDRAMED
(REV 2/82) PLATE 22




TONAWANDA CREEK WATERBOD., NEW YORK
BATAVIA RESERVOIR COMPOUND
(MODIFIED)

GEOLOGIC SECTION ON D-D
UPPER DAM

U S ARMY (W/ WITH C.S. - BUFFALO
O A. COMPANY. RECD. N.Y. 98C

NOTES
FOR LOCATION OF SECTION - SEE PLATE E.
FOR DESCRIPTION OF GEOLOGIC UNITS - SEE PLATE F.
FOR LEGEND FOR BORINGS AND ABBREVIATIONS -
SEE PLATE D.
FOR OTHER GEOLOGIC SECTION SEE PLATE E1



SITE NO.	SOURCE AND ADDRESS	PROPOSED USE	RADIAL DIST.
1.	GENESSEE STONE PRODUCTS CO. QUARRY AT STAFFORD, N.Y.	RIPRAP, BEDDING COARSE AGGREGATE	8 MI.
2.	COUNTY LIME STONE CO. QUARRY AT AKRON, N.Y.	RIPRAP, BEDDING	12 MI.
3.	MEDINA SANDSTONE CO. QUARRY AT MEDINA, N.Y.	RIPRAP	18 MI.
4.	B.R. DEWITT PIT AT OAK ORCHARD, N.Y.	FINE AGGREGATE	21 MI.
5.	HOUDAILLE CONSTRUCTION MAT'S QUARRY AT LANCASTER, N.Y.	RIPRAP, BEDDING	21 MI.
6.	ROYALTON STONE PRODUCTS, INC. QUARRY AT GASPORT, N.Y.	RIPRAP, BEDDING	24 MI.
7.	FRONTIER STONE PRODUCTS, INC. QUARRY AT LOCKPORT, N.Y.	RIPRAP, BEDDING COARSE AGGREGATE	27 MI.
8.	GENERAL CRUSHED STONE, CO. QUARRY AT LEROY, N.Y.	RIPRAP, BEDDING	14 MI.
9.	GENERAL CRUSHED STONE, CO. QUARRY AT HONEOYE FALLS, N.Y.	RIPRAP, BEDDING	30 MI.
10.	CONCRETE MATERIALS, INC. QUARRY AT MANCHESTER, N.Y.	BEDDING COARSE AGGREGATE	50 MI.
11.	DOLomite PRODUCTS, INC. QUARRY AT GATES CENTER, N.Y.	RIPRAP, BEDDING COARSE AGGREGATE	28 MI.
12.	SPENCER AND HALEY INC. PIT AT DELEVAN, N.Y.	FINE AGGREGATE COARSE AGGREGATE	30 MI.

▲ QUARRY OR PIT LOCATION


⊗ PROJECT SITES

SCALE OF MILES
0 10 20

TONAWANDA CREEK WATERSHED, N. Y.
BATAVIA RESERVOIR COMPOUND
(MODIFIED)

POSSIBLE MATERIAL SOURCES

U S ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED: NOVEMBER 1979





TONAWANDA CREEK WATER-SHED, NEW YORK
BATAVIA RESERVOIR COMPOUND
(MODIFIED)
CENTERLINE PROFILE
UPPER DAM

U S ARMY ENGINEER DISTRICT, BUFFALO
TO ACCOMPANY REPORT DATED NOV 1980

NOTES:

SCALE 1" = 300' HOR.
1" = 5' VER.



NOTES:
1. FOR LOCATION OF BORINGS - SEE PLATE 81.
2. FOR DESCRIPTION OF GEOLOGIC UNITS - SEE PLATE 81.
3. FOR LEGEND FOR BORINGS AND ASSOCIATIONS - SEE PLATE 82.

TONAWANDA CREEK WATERSHED, NEW YORK
BATAVIA RESERVOIR COMPOUND
(MODIFIED)
CENTERLINE PROFILE
LOWER DAM
U.S. ARMY ENGINEER DISTRICT BUFFALO
TO ACCOMPANY REPORT DATED NOV 1980

BUFFALO METROPOLITAN AREA, NEW YORK
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

APPENDIX F

NONSTRUCTURAL

BASE PLAN

U. S. Army Corps of Engineers
Buffalo District
Buffalo, New York

TABLE OF CONTENTS

<u>Paragraph</u>	<u>Description</u>	<u>Page</u>
F1	INTRODUCTION	F-1
F2	FLOOD WARNING AND EMERGENCY ACTION	F-1
F3	FLOODPROOFING AND PERMANENT EVACUATION	F-1
F4	FLOOD INSURANCE	F-2
F5	FLOODPLAIN MANAGEMENT (Land Use Regulation)	F-4
F6	PERMANENT EVACUATION	F-4
F7	NON-STRUCTURAL BASE PLAN	F-4

TABLE

<u>Item</u>		<u>Page</u>
F1	ECONOMIC EVALUATION OF FLOODPROOFING AND PERMANENT EVACUATION MEASURES OF THE N-SBP	F-3

APPENDIX F

NON-STRUCTURAL BASE PLAN

F1. INTRODUCTION

Hundreds of structures, additional building sites, and hundreds of acres of farmland are susceptible to periodic flooding. Structural projects have been constructed in the Tonawanda Creek Watershed to diminish flooding somewhat. While all these efforts have contributed to flood damage reduction, a significant flood threat remains for unprotected areas as well as those areas with marginal protection. The existing flood threat could be alleviated by non-structural measures.

Non-structural measures are of a damage management nature. They include flood warning and emergency action, floodproofing, flood insurance, flood plain management (land use regulation), and permanent evacuation.

F2. FLOOD WARNING AND EMERGENCY ACTION

Whether an area is protected by one or a combination of flood protective measures, the possibility of flooding still exists. This may occur as a result of unanticipated storms producing flood flows and/or volumes exceeding design capacities of structural measures or natural capacities of channels. If, in June 1972, Tropical Storm Agnes had followed its northward path instead of turning out to sea, it would have surely resulted in considerable, if not disastrous, flood damage in the watershed.

To reduce damages and, especially, to prevent loss of life, emergency actions must be carefully planned so that they may be implemented promptly when an emergency situation arises.

Efficient evacuation depends upon an effective flood warning system. Most communities in the Tonawanda Creek Watershed do not have a formal flood warning system; however, general flood forecasting is provided by the National Weather Service. It is possible for residents of the lower Tonawanda Creek Watershed to receive flood warnings 24 to 36 hours in advance. With such warning time, orderly and efficient evacuation is possible provided there has been advance planning for it and an organization for carrying it out is ready. An important part of emergency action is the care of flood victims after they have been evacuated from the flood threatened area.

F3. FLOODPROOFING AND PERMANENT EVACUATION

Floodproofing consists of modifying individual buildings or providing external protection measures to reduce flood damage. While floodproofing can reduce interior damages substantially, exterior damages to individual buildings and the overall flooded area are usually not affected. Also, floodproofing can bring about a false sense of security and discourage the development of needed flood protection works. It can also tend to increase

the use of floodplains. Most important of all, if applied to a structurally inadequate building it can result in more damage than would occur if the building were not floodproofed. A structurally inadequate building should be modified to obtain soundness or removed from the flood vulnerable area.

Floodproofing and evacuation were evaluated for areas of like character throughout the watershed. The areas considered include:

- the village of Attica through the village of Alexander;
- the city of Batavia through the hamlet of Bushville;
- the hamlet of Bushville to Hopkins Road in the town of Royalton;
- the Hopkins Road to Sweet Home Road in the town of Amherst;
- the Sweet Home Road to the mouth of Tonawanda Creek;
- the floodplains of Ransom and Black Creeks; and
- the floodplains of Mud Creek.

It was assumed that residential units could be floodproofed against flooding to depths of two feet above their first floors and that units not structurally adaptable to floodproofing measures would be permanently evacuated. Commercial units were assumed to be adaptable to floodproofing measures for all flood depths considered.

The floodproofing and permanent evacuation measures were considered for three levels of protection: Standard Project, 200-year and 100-year. The average annual benefit and costs of providing each level were estimated and compared. An economic evaluation of 100-year protection, found to be most cost-effective for all areas considered, is shown in Table F1.

The floodproofing and permanent evacuation measures are justified for all three levels of protection for the areas between Hopkins Road and Sweet Home Road and the area affected by Ransom and Black Creeks, and for the 100-year level of protection for the area affected by Mud Creek. However, relatively large amounts of residual damage remain with floodproofing measures in place. These residual damages are primarily related to problems of access, surveillance, building exterior and landscape damage. Also, sanitation and isolation problems would persist to affect the social well-being of residents in the Huron Plain.

F4. FLOOD INSURANCE

Flood insurance does not reduce flood damages and is not a true non-structural measure for flood damage reduction. It only compensates for flood damages suffered. Federally subsidized flood insurance is available under the National Flood Insurance Program provided adequate land use regulations are implemented. The Flood Insurance Program is designed to provide economic relief to owners of existing structures vulnerable to flood damage but on the condition that the community take steps to insure that new development be constructed or floodproofed to at least the 100-year flood level. All identified flood vulnerable communities are required to join the Program in order to receive Federal or Federally-related financial assistance.

F5. FLOODPLAIN MANAGEMENT (Land Use Regulation)

The regulation of land use has an important place in any plan to reduce flood damage. It must be understood that the flood plain is an integral part of a stream system even if it is used only intermittently for the discharge of floodwaters. The purpose of flood plain regulation is to limit use of the flood plain so that damages suffered during inevitable periods of flooding will be minimal. Regulation of use of flood plains requires that a map outlining the areas affected by floods of different magnitudes be developed. With this data, regulations prescribing the best use of the flood plain can be developed. These regulations might include zoning, elevation of new residential development, or building codes requiring construction resistive to flood damage.

F6. PERMANENT EVACUATION

Permanent evacuation is another means of preventing flood damage. It consists of the permanent removal of buildings and other structures from flood vulnerable area and relocation of affected people to an area which is free from flooding. This generally involves purchasing the flood vulnerable land, demolishing or otherwise removing the buildings and other structures, cleaning up the debris, and landscaping the area. New sites are provided for buildings relocated. This is a high-cost method of flood damage reduction attractive only under unusual conditions or where the flood risks cannot be reduced by other means.

Application of this method alone for flood damage reduction in the Tonawanda Creek Watershed was deemed infeasible for all areas considered.

F7. NON-STRUCTURAL BASE PLAN

Communities in the Tonawanda Creek Watershed could deal effectively with the flood situation by implementing a combination of non-structural measures. The Non-structural Base Plan would provide for floodproofing to at least the 100-year level for the area between Hopkins Road and Sweet Home Road and for the areas affected by Ransom, Black and Mud Creeks. Pertinent data for this alternative is shown on Table N-SBP.

In addition to floodproofing, the N.-S. Base Plan would provide that flood plain management and a system for flood warning and emergency action be integrated to effectively complete the non-structural approach to the flood problem. A rigorous, well coordinated effort by local, State and Federal agencies, with the basis for decisions coming from the general public, would be made to plan for use of the flood plain in advance of development. The instruments for controlling future land use include: zoning ordinances; open-space and public land acquisition programs; and public policy discouraging the extension of streets and water and sewer lines into floodprone areas.

No matter what flood damage management plan is ultimately accepted, wise use of the flood plain is important. This usually calls for regulation. Also, because of the possibility that the capacities of flood protection works may be exceeded, a plan for evacuating all flood vulnerable areas should be developed.

BUFFALO METROPOLITAN AREA, NEW YORK
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

APPENDIX G

U. S. Army Corps of Engineers
Buffalo District
Buffalo, New York

TABLE OF CONTENTS

Input From Federal Agencies

Input From State Agencies

Input From Local Interests

BUFFALO METROPOLITAN AREA, NEW YORK
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

INPUT FROM FEDERAL AGENCIES

U. S. Army Corps of Engineers
Buffalo District
Buffalo, New York



DEPARTMENT OF THE ARMY
BUFFALO DISTRICT, CORPS OF ENGINEERS
1776 NIAGARA STREET
BUFFALO, NEW YORK 14207

NCBPD-PF

SUBJECT: Tonawanda Creek Watershed, NY - Mitigation

23 SEP 1983

Mr. Paul P. Hamilton
Field Supervisor
US Fish and Wildlife Service
100 Grange Place
Room 202
Cortland, NY 13045

Dear Mr. Hamilton:

I have received your letter dated 13 September 1983 addressing mitigation for the proposed flood damage reduction project in the Tonawanda Creek Watershed. A copy of your letter has been forwarded to the Corps North Central Division (NCD) office in Chicago, Illinois, and to the Board of Engineers for Rivers and Harbors (BERH) in Washington, DC. In addition, all previous correspondence between my District, USFWS, and NYS Department of Environmental Conservation (NYSDEC) regarding this matter has been forwarded to NCD and BERH.

Your position and the position of NYSDEC, regarding mitigation for project construction impacts and idle land conversion impacts, has been acknowledged by BERH staff and has been presented to the Board members.

To mitigate for project construction impacts, I am recommending as part of the project that structural improvements be implemented to increase the management of the Oak Orchard Wildlife Management Area (WMA) and that an additional 30 acres of land be purchased adjacent to the Oak Orchard WMA. I am recommending no mitigation for the impacts of idle land conversion.

In summary, your position has been provided to BERH members both by copy of your letters and through reiteration by the board staff. The point of contact for this study is Mr. David R. MacPherson, P.E. at (716)876-5454, extension 2263 of my District's Planning Division.

Sincerely,

Robert R. Hardiman
ROBERT R. HARDIMAN
Colonel, Corps of Engineers
District Engineer



UNITED STATES
DEPARTMENT OF THE INTERIOR
FISH AND WILDLIFE SERVICE
100 Grange Place
Room 202
Cortland, New York 13045

September 13, 1983

Colonel Robert R. Hardiman
District Engineer, Buffalo District
U.S. Army Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

SEP 13 1983
FWS-015

Dear Colonel Hardiman:

This letter is intended to provide technical assistance in addition to that provided in our letter of February 23, 1983 on the Tonawanda Creek flood control project. It has been coordinated with the Division of Fish and Wildlife of the New York State Department of Environmental Conservation (NYSDEC) and personnel of that agency generally agree with it's contents. We request that you provide it to the Board of Rivers and Harbors for their use during deliberations concerning this project and for eventual submission to Congress along with our previous reports on this project.

Our on-site meeting of August 25, 1983 with members of your staff and NYSDEC did not dispel our concerns regarding the "idle lands" in the project area of influence. We still firmly believe that significant wildlife losses will result from reduced habitat interspersed that is the almost inevitable outcome of flood control projects in agricultural areas. That this will occur here seemed evident to me as we toured the area. The agricultural fields that were removed from the river and, therefore, not subject to flooding appeared larger with much less interspersed than those that were close to the river. In addition, NYSDEC personnel indicated that farming practices on flood protected areas in the Genesee River basin have resulted in reduced interspersed and have even caused erosion problems.

We therefore, hold to the recommendation in our February 23 letter that habitat evaluation procedures be conducted on the idle lands in the near future. Personnel from CE, DEC, and FWS should compose the HEP team. We will no longer insist that the figures in our October 1980 report be used as estimates of the land acquisition required provided that the

Corps agrees to support and carry forward whatever mitigation measure is mutually agreed upon by members of the team.

As to mitigating the losses resulting from the direct impacts of dam construction and snagging and clearing we now consider acceptable the improvements proposed for the Oak Orchard Management Area plus the acquisition and management of an additional 30 acres. We strongly support DEC's position on the need for the 30 acres since structural and management improvements alone on State lands already under management cannot be considered true mitigation.

We appreciate your continuing coordination on this matter.

Sincerely yours,



Paul P. Hamilton
Field Supervisor

XC:
NYSDEC, Albany, NY
NYSDEC, Avon, NY

NCBED-PE

17 October 1980

Dr. Bennie Keel
Departmental Consulting Archaeologist
Heritage Conservation and
Recreation Service
U. S. Department of the Interior
Washington, DC 20243

Dear Dr. Keel:

Enclosed for your information is a Final Cultural Resources Report entitled,
Batavia Reservoir Compound: Phase I Archaeological Summary and Appendicies.

If you have any questions regarding this report, please contact Mr. Richard H.
Lewis, Staff Archaeologist, at (716) 876-5454, extension 2175.

Sincerely,

2 Incl
as stated

DONALD M. LIDDELL
Chief, Engineering Division

CF:
NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

NCBED-PE

17 October 1980

Mrs. Myra Harrison
Division of Archaeology
Heritage Conservation and
Recreation Service
William J. Green Federal Building
600 Arch Street
Room 9310
Philadelphia, PA 19106

Dear Ms. Harrison:

Enclosed for your information is a Final Cultural Resources Report entitled,
Batavia Reservoir Compound: Phase I Archaeological Summary and Appendicies.

If you have any questions regarding this report, please contact Mr. Richard U.
Lewis, Staff Archaeologist, at (716) 376-5454, extension 2175.

Sincerely,

2 Incl
as stated

DONALD M. LIDDELL
Chief, Engineering Division

CF:
✓ NCBED-PE

Lewis_____
Berkeley_____
Bennett_____
Pieczynski_____
Hallock_____
Liddell_____

NCBED-PE

17 October 1980

SUBJECT: Transmittal of the Batavia Reservoir Compound: Phase I
Archaeological Summary

THRU: Division Engineer, North Central
ATTN: WCDPD-EE

TO: HQDA (DAEN-ASI-L)
WASH, DC 20413

1. References: ER 1105-2-460, Identification and Administration of Cultural Resources.

2. The subject report and appendices are transmitted in accordance with paragraph 460.14(d) of the referenced regulation.

FOR THE DISTRICT ENGINEER:

2 Incl
as

DONALD M. LIDDELL
Chief, Engineering Division

CF:
✓ NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

NCBED-PE

17 October 1980

Defense Technical Information Center
ATTN: DTIS/DDA-2/Paul F. Cooper
Alexandria, VA 22314

Dear Mr. Cooper:

Enclosed are 12 copies of the report entitled, "Batavia Reservoir Compound Archaeological Summary," and appendices. Please make the necessary arrangements to have this report and appendices available from the National Technical Information Service, Springfield, VA.

If you require any further input, please feel free to contact me at the above address.

Sincerely,

1 Incl (12 cys)
as stated

THOMAS VAN WART
District Librarian

CF:
✓ NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
VanWart _____



IN REPLY REFER TO:

W540

United States Department of the Interior
HERITAGE CONSERVATION AND RECREATION SERVICE
SOUTHEAST REGIONAL OFFICE
75 Spring Street S.W., Suite 1176
Atlanta, Georgia 30303

JUL 15 1980

Mr. Richard H. Lewis
Buffalo District, Corps
of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Mr. Lewis:

Due to staff reductions within the Office of Interagency Archeological Services-Atlanta, we are unable to review the report "Batavia Reservoir Compound, Phase I Archeological Survey." We will be happy to continue to receive reports for review from your office and will notify you on an as received basis which ones we will review. If you have any questions, please contact Mr. James Thomson at (404) 221-2633.

Sincerely,


Victor A. Carbone
Acting Chief

NCBED-PE

9 June 1980

Dr. Stephanie H. Rodeffer, Acting Chief
Interagency Archaeological Services - Atlanta
Heritage Conservation and Recreation Service
Richard B. Russel Federal Building
75 Spring Street
Atlanta, GA 30303

Dear Dr. Rodeffer:

Enclosed for your review and comment is a cultural resources reconnaissance report entitled "Batavia Reservoir Compound, Phase I Archaeological Summary" prepared for the Buffalo District by the State University of New York at Binghamton. This report is an update (which was required by project changes) of the cultural resources report provided for your review in November 1979.

If we do not receive your comments within 30 days of your receipt of this letter, we will assume you are in agreement with the contents of the report. Comments received after the expiration of the comment period cannot be considered in the preparation of the final report.

If you have any questions regarding this matter, please contact my staff Archaeologist, Mr. Richard H. Lewis at (716) 876-5454, extension 2171.


Sincerely,

DONALD M. LIDDELL
Chief, Engineering Division

CF:
NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

New York State Department of Environmental Conservation
50 Wolf Road, Albany, New York 12233



Robert F. Flac
Commissioner

February 20, 1980

Mr. Paul P. Hamilton
Field Supervisor
United States Department of
the Interior
Fish and Wildlife Service
100 Grange Place, Room 202
Cortland, New York 13045

Dear Mr. Hamilton:

The Division of Fish and Wildlife is in general accord with the findings and recommendations of the report on the proposed flood control project along Tonawanda Creek in the towns of Batavia and Alexander, Genesee County, New York. But we do feel that instead of using the term "selective snagging", you should indicate that stumps embedded in the bank should be cut rather than pulled, and where they would not materially affect the roughness of the bottom, deeply embedded logs are to remain in the bottom. We also believe that instead of building a stairway or path traversing the dams, the Batavia-Alexander Recreational Trail should be re-routed around the structures.


Sincerely,

Kenneth Wich

Kennth F. Wich
Director
Division of Fish and Wildlife

cc: James Kelley

New York State Department of Environmental Conservation
6274 E. Avon-Lima Rd., Avon, New York 14414



Robert F. Flacke
Commissioner

Eric A. Seiffer
Regional Director

September 29, 1980

Mr. Paul B. Hamilton
Field Supervisor
United States Department of the Interior
Fish and Wildlife Service
100 Grange Place, Room 202
Cortland, New York 13045

Dear Mr. Hamilton:

The Division of Fish and Wildlife concurs with the findings and recommendations of the report on the Corps of Engineers Tonawanda Creek Flood Control Project, Towns of Batavia and Alexander, Genesee County, New York prepared under the authority of the Fish and Wildlife Coordination Act (16 USC 661).

We would also like to make some specific recommendations for sites to be considered as mitigation (see attached).

Site #1 - Shallow fresh marsh, deep fresh marsh, wood wetland, gets heavy use by waterfowl and heavy hunting pressure; great potential for enhancement with water control structures.

Sites #2 and #3 - High vulnerability to filling for industrial development, shallow fresh marsh, wooded swamp, has good potential for enhancement.

Sites #4 and 5 - Wooded swamp, low potential for enhancement.

Sites #7, 7 and 8 - Shallow fresh to deep fresh marsh, good potential for enhancement.


Mr. Paul B. Hamilton

-2-

September 29, 1980

If you have any questions concerning these areas, please contact Jack Cooper or Dan Carroll at our Regional Office. Our continued coordination on this project should help to ensure an environmentally acceptable project.

Very truly yours,




Edward D. Holmes
Regional Supervisor
Fish & Wildlife
Region #8



Kenneth Wich
Director
Division of Fish & Wildlife

JC:er
enc.



UNITED STATES DEPARTMENT OF AGRICULTURE

SOIL CONSERVATION SERVICE

700 East Water Street, Syracuse, New York 13210

June 23, 1976

Colonel Bernard C. Hughes
District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hughes:



We have reviewed the Draft Final Feasibility Main Report and Technical Appendix for the Interim Report on Feasibility of Flood Management in Tonawanda Creek Watershed, dated 1976, and have no comments to make on these submissions.

We appreciate the opportunity to review and comment on these reports.

Sincerely yours,


Robert L. Hilliard
State Conservationist

FILE COPY

Checked by 
Filed by 





United States Department of the Interior

NATIONAL PARK SERVICE

NORTH ATLANTIC REGION

150 CAUSEWAY STREET

BOSTON, MA. 02114

June 22, 1976

IN REPLY REFER TO:

L-7619-NAR-(PE)

ER-76/456

Colonel Bernard C. Hughes
District Engineer
Department of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hughes:

This will serve as a multiple response to your request for review and comment of:

- 4 May on - Draft Environmental Statement, Proposed Flood Control, Tonawanda Creek Watershed, Erie, Genesee, Niagara, and Wyoming Counties, New York (originally sent to our Departmental Office of Environmental Project Review which advised our direct response to you).
- 24 May on - Draft Feasibility Report for Tonawanda Creek Watershed New York.
- 3 June on - Reconnaissance Level Literature Search and Records Review (cultural resources report-largely on archeological values) for Tonawanda Creek Watershed, New York. This report was prepared for the Corps by Barbour and Miller of Department of Anthropology, SUNY at Buffalo.

You should understand that our comments on the cultural resources report and the draft feasibility report are provided as technical assistance based solely on the interests, expertise and responsibilities of the National Park Service. The comments on the draft environmental statement are also those of the National Park Service as a portion of the collective expertise of the Department, but a consolidated Departmental commentary will be presented at a later date upon the Chief of Engineer's request to review the proposal.



Cultural Resources Report. Because the findings of this report are basic to the development of an adequate environmental impact statement, we will speak to it first. The report appears adequate as a literature search and records review, and we note that many archeological and potential historical sites were identified. It is also noted that the State Historic Preservation Officer's office contributed a listing of sites on and recommended for listing on the National Register of Historic Places, as well as archeological sites on file with that office.

Draft Environmental Statement. Section 2, paragraphs 2.104 and 2.105 (pages 131-134) makes appropriate use of the information recorded in the cultural resources report. Appendix F-1, summary of that cultural resources report further emphasized the potential and probability of archeological resources in the overall study area. That summary reflects on the project alternative which would cause less effect on such resources and indicates that some alternatives would require much more detailed archeological investigations prior to final project design. Paragraph 2.104 indicates that consultation of the National Register of Historic Places has been accomplished. Up to this point, consideration for the protection of cultural resources would appear satisfactory. However, as this is where the consideration stops, we feel that necessary required considerations are incomplete.

We find this environmental statement deficient as now presented for failure to discuss accomplished or intended efforts to fulfill the requirements of EO 11593 and follow the procedures for compliance with Section 106 of the Historic Preservation Act as presented in 36 CFR Part 800. While it may be the intent to perform such compliance at a later project phase, the level of detail in discussing various alternatives in this draft environmental statement warrants a commensurate consideration for the protection of cultural resources so that the selection of the best alternative can be properly guided.

With the citation of all the National Register sites involved, certainly the alternative project selected is very likely to undergo Section 106 proceedings. Further, until the many archeological sites identified have been evaluated for their significance and eligibility for inclusion on the National Register of Historic Places, compliance with Section 106 requirements remains a potential threat to the accomplishment of the selected project alternative.

Section 4, paragraph 4.11.i (page 150) flatly states that "some cultural resources will be lost" with the mollification that preservation efforts will be considered in the public recreation development areas.

Paragraph 4.27 (page 154) expresses a partial approach to the protection of cultural resources. However, it would seem essential, even as an aspect of mitigation of harmful effects, to first determine where the cultural resources are that require protective measures.

We would remind you that the Director, Office of Archeology and Historic Preservation, National Park Service, Washington, D. C. 20240, will, upon request, provide a determination of eligibility of sites of historical or archeological significance for inclusion in the National Register of Historic Places.

Paragraph 9.04 (page 186) mentions initial coordination with the National Park Service as further identified in our technical assistance letter of January 5 displayed as Appendix B-1-2.

It is not our outlook that detailed archeological investigations should be performed over the entire study area. However, we are concerned that adequate considerations be given at this time for the protection of cultural resources commensurate with the detail of consideration given all other aspects leading to the selection of a project alternative. Certainly, the applicability and necessity for compliance with Section 106 should be discussed which beckons completion of EO 11593 requirements and applicable NEPA provisions already initiated. It would seem possible that the unfinished cultural resource protection consideration work can be satisfactorily completed before finalization of this environmental statement and that the present inadequacies in the treatment of this bona fide aspect of the human environment can be rectified in the final environmental statement.

Draft Feasibility Report. As indicated in our letter of January 5 included in Appendix F, we were pleased to note cultural resources coverage in the Preliminary Feasibility Report and fully expected to see an adequate treatment of cultural resource protection considerations in the following stages of the report. We are now concerned that all cultural resource considerations seem to have been dropped from the feasibility report, particularly when numerous other aspects and criteria, such as biological, climatological, land use, economical, recreational resources, along with population growth, transportation trends, housing needs and industrial activity factors are maintained and treated in significant detail in the main report and technical appendices. In a manner commensurate to the treatment of the many other factors mentioned above, we recommend that cultural resource protection considerations be included in the final report and that all efforts to comply with standing requirements for the protection of cultural resources should be clearly presented.

Again, in summary, it is not our intent to demand an excessive effort to survey, investigate and evaluate the impacts of every alternative.

Moreover, it is our purpose to technically assist the Corps in its responsibility to protect cultural resource values from adverse effects that may or will result from any selected project alternative.

Sincerely yours,

A handwritten signature in cursive script, reading "Gilbert W. Calhoun". The signature is written in dark ink and is positioned above the printed name and title.

Gilbert W. Calhoun
Acting Regional Director

UNITED STATES DEPARTMENT OF AGRICULTURE
FOREST SERVICE
NORTHEASTERN AREA, STATE AND PRIVATE FORESTRY
6816 MARKET STREET, UPPER DARBY, PA. 19082
215-596-1672

8400
June 18, 1976



LTC Byron G. Walker
Deputy District Engineer
Department of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Refer to: NCBED-PE, Draft Environ-
mental Statement
Tonawanda Creek Watershed
NY


Dear Col. Walker:

Of the four plans described in the above Statement, we consider the selected plan -- Batavia Reservoir -- the most environmentally sound. We understand that flood water inundation will not continue beyond a period that would cause damage to elm, ash, and cottonwood.



Loss of habitat and wetland appears unavoidable and to be the minimum compatible with completion of the project.

If possible, at dike and spillway construction areas (p. 153) seeding and mulching should be supplemented by planting trees and shrubs to restore wildlife habitat.

Sincerely,


DALE O. VANDENBURG
Staff Director
Environmental Quality
Evaluation

FILE COPY

Checked by 
Filed by 



UNITED STATES
DEPARTMENT OF THE INTERIOR
FISH AND WILDLIFE SERVICE
Post Office and Courthouse Building
BOSTON MASSACHUSETTS 02109

JUL 12 1976

District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Sir;

The following comments are provided in response to your May 24, 1976 letter to Mr. Willard W. Cole, Jr., field supervisor of the New York Area Office of the U.S. Fish and Wildlife Service, requesting comments on the Draft Final Feasibility Report for Tonawanda Creek Watershed, New York. Our comments are provided as field level review and are not the comments of the Department of the Interior as outlined under Section 2 (b) of the Fish and Wildlife Coordination Act (48 Stat. 401, as amended; 16 U.S.C. 661 et. seq.)

The U.S. Fish and Wildlife Service reviewed the proposed project and provided a January 28, 1976 report to the District Engineer, Buffalo District on the Preliminary Feasibility report and a June 17, 1976 report reviewing your April 1976 draft environmental statement for Flood Control in the Tonawanda Creek Watershed, New York.

We appreciate the Corps of Engineers' selection of the Batavia Reservoir Compound and believe that the project, as presented in your Draft Final Feasibility Report, will have the least environmentally damaging effects on fish and wildlife resources of the area. However, in Section VII E, outlining Data Needs, mention should be made of further need for environmental data. As discussed in our June 17, 1976 report, additional fish survey work, as well as more detailed field observations of vegetation and bird species within the vicinity of the Batavia Reservoir Compound are needed.

We appreciate the opportunity to review the Draft Feasibility Report at this time, and look forward to further coordination on the proposed project.

Sincerely yours,

ACTING Regional Director



FILE COPY

Checked by

Filed by



United States Department of the Interior

NATIONAL PARK SERVICE

NORTH ATLANTIC REGION

150 CAUSEWAY STREET

BOSTON, MA. 02114

January 5, 1976

IN REPLY REFER TO:

L-7619-NAR-(CE)

NCBED-PN

Colonel Byron G. Walker
Deputy District Engineer
Department of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207


Dear Colonel Walker:

This responds to your letter of 15 December requesting our comments on the Preliminary Feasibility Report on Flood Management in the Tonawanda Creek Watershed, New York.

We are pleased to note the report's coverage of cultural resources (pp. 32 and 33) and the commitment to accomplish cultural resource literary studies. Further, we understand that the information found in these literary searches will be used in the identification and development of mitigating measures as necessary to protect cultural resources that may be affected by specific project works of the overall flood management plan.

We also note the report's mention of the Erie (later) Barge Canal in the study area. The further literary searches should help to focus on the recognized resources and probable archeological values related to that historic waterway. While we, at this time, see but one National Historic Landmark in the study area, there are doubtless a number of sites listed or in the process of being considered for inclusion on the National Register of Historic Places that could be affected by project work. Therefore, we would suggest that in addition to checking the National Register of Historic Places, contact should be maintained with the State Historic Preservation Officer (Mr. Orin Lehman, Commissioner, Parks and Recreation, Room 303, South Swan Street Building, Albany, New York 12223) to assure no oversight.

Literary research performed by competent archeologists should provide the necessary basis to determine the location and scope of field surveys and need for excavations to assure the utmost protection for any significant




archeological values that could be destroyed by project works. We would suggest contact with the New York Archeological Council (Dr. Thomas King, 4242 Ridge Lea Road, Buffalo, New York 14226) and/or the State Archeologist (Dr. Robert E. Funk, New York State Museum and Science Service, Albany, New York 12224) for assistance in pursuing the archeological sectors of the literary searches to be performed.

In addition to the above, concerning the protection of significant natural resources, we suggest that the literary search and other continuing investigations include a check of existing and potential National Natural Landmark designations. Assistance for identifying Natural Landmarks can be requested from this office or from our Natural Landmarks Specialist (Mr. Paul Favour, P. O. Box 187, Northeast Harbor, Maine 04662).

We will be most anxious to see and review the final feasibility study inclusive of natural and cultural resource protection considerations, and we appreciate this early opportunity to comment on this preliminary report.

Sincerely yours,


Jerry D. Wagers
Regional Director



UNITED STATES
DEPARTMENT OF THE INTERIOR
FISH AND WILDLIFE SERVICE
100 Grange Place, Room 202
Cortland, New York 13045

January 28, 1976

District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Sir:

This responds to LTC Byron Walker's December 15, 1975 letter requesting our comments on your Preliminary Feasibility Report on Flood Management in the Tonawanda Creek Watershed, New York.

The following comments are provided as a result of informal field review. They are submitted by the U. S. Fish and Wildlife Service as technical assistance for input to your final plan for Flood Management in the Tonawanda Creek Watershed. Further review will be undertaken by this Service during the Departmental review process when the Departmental position will be provided.

The U. S. Fish and Wildlife Service has provided prior reports to the District Engineer, Buffalo District, on several of the flood management measures being considered in the Preliminary Feasibility Report. In our February 2, 1960 report, we discussed the possible effects on fish and wildlife resources of modifications to the existing Corps project at Batavia and of a storage reservoir or reservoirs on the headwaters of Tonawanda Creek. On February 8, 1961, we issued a preliminary report on fish and wildlife resources of the Tonawanda Creek basin and then issued a supplemental to the preliminary report on October 2, 1967.

We have reviewed your Preliminary Feasibility Report and find that four regional measures and one local protection measure are presently being considered for Flood Management in the



OPT
Save Energy and Conserve America!
Checked by
Filed by

Tonawanda Creek Watershed. The four regional measures consist of Sierks Reservoir, Linden Reservoir, Alabama Pools, and the Batavia Reservoir Compound. The local protection measure involves the modification of the existing Corps project at Batavia, New York. These flood management measures have also been considered in combination to form several plans for basin flood management.

We offer the following specific comments on the considered flood management measures:

Batavia Reservoir Compound. This measure involves two shallow detention reservoirs arranged in series designed to intercept all runoff from that part of the Tonawanda Creek Watershed upstream from the city of Batavia, New York. Since these reservoirs will normally be dry, no significant fisheries impact can be expected except during the construction phase when some disturbance of the existing warmwater fishery, consisting of such species as smallmouth bass and northern pike, will occur.

Wildlife resources consist of a variety of species. There are white-tailed deer in the basin and upland game populations of pheasants and ruffed grouse. Muskrats, beavers, racoons, and red foxes as well as an occasional siting of otters are some of the furbearing mammals in the area. Waterfowl hunting occurs along Tonawanda Creek, its tributaries, and associated wetlands. The magnitude of this type of hunting in the proposed project area has not been determined. However, since the proposed reservoirs will normally be dry, no significant impact on wildlife resources is currently expected.

One consideration that must be addressed, is the effect the Batavia Reservoir Compound will have on the present cooperative hunting area leased from local land owners by the New York State Department of Environmental Conservation (NYSDEC).

Modification to the Existing Batavia Project. This local protection measure involves levees, bank protection, and channel enlargement within the city of Batavia and downstream to Bushville, New York. The NYSDEC has no current fisheries data on this portion of the Tonawanda Creek. Expected warm-water species include smallmouth bass, northern pike, and some panfish and bullheads below Batavia. The channel modification's impacts on these fishery resources cannot be accurately determined at present due to the lack of current fishery data.

The Batavia to Bushville section of the Tonawanda Creek is primarily agricultural. Wildlife species that will be affected by the resultant disturbance of stream-bank vegetation from levees, bank protection, and channel enlargement consist of songbirds, some pheasant wintering area, and various furbearers including muskrats and possible otters.

Alabama Pools. This measure is a complex of reservoirs including both storage and detention reservoirs in the vicinity of the NYSDEC Tonawanda Wildlife Management Area (WMA). The Alabama Pools would have no beneficial effect on fisheries resources of the area, however, this alternative would have serious adverse consequences on wildlife resources associated with the state's existing Tonawanda WMA.

Coordination with the NYSDEC has indicated that the Tonawanda WMA habitat conditions are nearly ideal for the production, enhancement, and enjoyment of the waterfowl resource and other marsh-related wildlife species. The NYSDEC has presently spent upwards of \$25,000 on establishing the ideal wetland habitat conditions which according to present data supports waterfowl hunting providing approximately 2500 man-days of recreation annually with an annual harvest of approximately 1500 ducks and geese. The Alabama Pools project would result in the destruction of much of the NYSDEC developmental work in the area. Recent expenditures by the NYSDEC have been made in order to prevent damaging flood waters from entering the Tonawanda WMA impoundments, just the opposite of the Alabama Pools proposal.

The present system of shallow marshlands created by the low dikes of the Tonawanda WMA supports aquatic submerged, emergent, and floating vegetation, together with small pockets of open water. These important wetland habitat conditions attract waterfowl for cover, resting, food, and nesting during the spring, summer, and fall. The storage of spring flood waters at the depths proposed in the Alabama Pools will result in disastrous effects on both aquatic and terrestrial vegetation. Desired growth of aquatic plants that do poorly in deep water, even for short periods of time, will be severely retarded or destroyed. Proposed spring flood water depths will also have serious adverse effects on nesting waterfowl and shorebirds as well as the valuable furbear resource present on the area.

The Alabama pools may also have severe adverse impacts on several rare and endangered bird species sighted around the Iroquois National Wildlife Refuge and Tonawanda Wildlife Management Area. These sightings include golden eagles (rare), bald eagles and the American Perigrine Falcon (endangered) and ospreys (undetermined). Additional studies on this matter are necessary.

Sierks Reservoir. This protection measure is a storage reservoir on Tonawanda Creek in the Cattaraugus Hills, near the hamlet of Sierks, New York. It is proposed as a multi-purpose project for flood management, fishery enhancement, recreation, water quality management and irrigation.

As discussed in our October 2, 1967 Fish and Wildlife Service Supplemental Report, fish and wildlife resources within the area of project influence involve a limited warm water fishery. This fishery is expected to consist of smallmouth bass, northern pike, rock bass, pumpkinseed, and bullhead.

Due to the limited warmwater fishery, Sierks Reservoir may afford substantial opportunities for the development of this type of fishery as well as a possible trout fishery. However, the project area's wildlife resource will be lost through inundation. The project area supports a moderate wildlife population comprised of such species as cottontail rabbit, ruffed grouse, raccoon, and fox. Lack of suitable habitat is responsible for low populations of pheasants, muskrats, and waterfowl. The project area does, however, support a wintering area for white-tailed deer.

The multi-purpose benefits for this measure can only be determined after further detailed studies. The potential recreation and fishery benefits must be weighed against the loss of wildlife resources.

Linden Reservoir. This measure is a storage reservoir on Little Tonawanda Creek in the Cattaraugus Hills, near the hamlet of Linden, New York. It is proposed as a multi-purpose project for flood management, fishery enhancement, recreation, water quality management and irrigation.

This reservoir would probably permit the development of a warm-water fishery superior to the existing stream fishery. Little Tonawanda Creek within the project area is fairly sluggish with erodible, silty banks, and little cover. Although the stream is less than ideal, it is being stocked with brown trout by the NYSDEC in a 3.2 mile stretch extending upstream from just above Linden to Dale, New York. Fishery resources within the project area also include panfish (primarily rockbass), suckers, and common shiners and associated minnows.


The proposed project area supports a moderate population of wildlife including white-tailed deer, cottontail rabbit, ruffed grouse, raccoon, and fox. As found at the proposed Sierks Reservoir area, lack of suitable habitat is responsible for low populations of pheasant, waterfowl and muskrat.

The construction of Linden Reservoir will result in the loss of wildlife resources as well as the present NYSDEC brown trout stream stocking program. These losses must be considered when discussing the potential benefits of recreation and an improved warmwater fishery. The multi-purpose benefits for this measure can only be determined after further detailed studies.

Of the four regional and one local protection measures presented in your Preliminary Feasibility Report, the Batavia Reservoir Compound will have the least impact on fish and wildlife resources. This measure will also benefit the NYSDEC Tonawanda Wildlife Management Area by preventing inundation from floodwaters. The Alabama Pools measure will have the most disastrous impact on fish and wildlife resources. This measure will destroy the already present ideal habitat conditions for production, enhancement, and enjoyment of the waterfowl resource and other marsh-related wildlife species.

We appreciate the opportunity to comment on your Preliminary Feasibility Report at this time and look forward to further coordination on the Tonawanda Creek Watershed Flood Management project.

Sincerely yours,



Willard W. Cole, Jr.
Area Office Supervisor

BUFFALO METROPOLITAN AREA, NEW YORK
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

INPUT FROM STATE AGENCIES

U. S. Army Corps of Engineers
Buffalo District
Buffalo, New York



HENRY G. WILLIAMS
COMMISSIONER

STATE OF NEW YORK
DEPARTMENT OF
ENVIRONMENTAL CONSERVATION
ALBANY, NEW YORK 12233-0001

12 AUG 93 11 07
OFC. MCNT. OAS

00210 1353

Dear Colonel Hardiman:

The purpose of this letter is to provide you with the Department's position regarding the use of the NYSDEC's Oak Orchard Wildlife Management Area in conjunction with your recommendation for Fish and Wildlife mitigation for the Tonawanda Creek Flood Control project.

My regional staff has indicated in previous correspondence and at various meetings that while they prefer on-site mitigation to compensate for wetland and riparian habitat losses they would consider mitigation on the Oak Orchard Wildlife Management Area. Their recommendations involved the additional acquisition of approximately 30 acres of land adjacent to Goose Pond, and various habitat improvement options. We stressed that simple habitat improvements alone was not considered adequate to compensate for the loss of habitat and that the additional acquisition and management of land was vital for our acceptance of the proposed off-site mitigation.


Since our initial discussions concerning mitigation options at Oak Orchard, Bureau of Wildlife has carried out much of the work included in the mitigation proposal of the Corps. These improvements have been accomplished with 1972 Bond Act monies. By the end of this construction season, the storage capacity of Goose Pond will have been increased from 200 acre feet to just over 300 acre feet through dike and control structure improvements. In addition, we are anticipating habitat improvement involving pothole and level ditch construction during the 1984 construction season. At the completion of the work, the benefits of the proposed Corps mitigation will have been reduced by as much as 50%. We do not, at this time, have any plan to acquire the 30 acre parcel referred to above.

It is this Department's position that the Corps' proposal for mitigation at Oak Orchard is an acceptable first element, but that as that work and additional work by the Department, as anticipated over the next several years is completed, acquisition and management of land as previously recommended is necessary for adequate compensation for wetland losses associated with the Tonawanda Creek project.

We hope that through our continued coordination between your staff and the US Fish and Wildlife staff that an environmentally sound mitigation plan is developed. Edward Holmes at our Region 8 office is available to provide assistance in working out problems concerning mitigation. If I can be of any further assistance, please feel free to contact me.

My staff has reviewed your revised report and recommended that this Department continue to support implementation of the project. I concur with the staff recommendation.

Sincerely,

A handwritten signature in dark ink, appearing to read "Henry G. Williams". The signature is written in a cursive style with a large, stylized initial "H".

Henry G. Williams

Colonel Robert R. Hardiman
District Engineer
US Army Engineering District, Buffalo
1776 Niagara Street
Buffalo, New York 14207



STATE OF NEW YORK
DEPARTMENT OF
ENVIRONMENTAL CONSERVATION
ALBANY, NEW YORK 12233-0001

HENRY G. WILLIAMS
COMMISSIONER

APR 20 1983

Dear Colonel Hardiman:

Following receipt of your December 27, 1982 letter requesting a new letter of support for the Batavia Reservoir Compound (Modified) my staff has carefully reviewed your final feasibility report, letters and resolutions of local governments regarding the proposed project and other available information. In addition, this Department held two technical workshops in Batavia on February 8 and March 2, 1983 to obtain the views of local interests in the Basin. Members of your staff participated in the second workshop and answered many questions.

My staff has concluded that, while some of the objections to the project are valid, particularly in the upper portions of the watershed, the benefits to be received from the project far outweigh the negative impacts and the greatest good to the region would be served by construction of the project. Therefore, this agency supports the Batavia Reservoir Compound (Modified) and urges that the project be recommended to the Congress for authorization.

Once the project is authorized and you begin advanced engineering and design, you are requested to coordinate with Regional Fish and Wildlife staff of this agency in planning mitigation measures to offset impacts on fish and wildlife and with the Department of Agriculture and Markets to minimize any negative impacts on agricultural activities in the reservoir areas.

Sincerely,

Henry G. Williams

Colonel Robert R. Hardiman
District Engineer
U.S. Corps of Engineers
Department of the Army
Buffalo District
1776 Niagara Street
Buffalo, New York 14207

25 60 88 APR 22
SVO, WONT, OAS

FLOOD PROTECTION FOR THE
TONAWANDA CREEK WATERSHED
BATAVIA RESERVOIR COMPOUND (MODIFIED)

BACKGROUND

Under resolutions of the Congressional Committees on Public Works passed in 1950 and 1956, the Chief of Engineering, in 1973 authorized study of water resources management in the Buffalo Metropolitan Area and directed that the study include the Buffalo Urban Area (SMSA) and its tributary watersheds including the Tonawanda Creek Watershed. Since that time Buffalo District, Corps of Engineers has been investigating the water management needs of the watershed and has found that a critical need is flood damage reduction. Over a period of nearly ten years of study the Corps has examined a number of potential solutions to water management needs, with an emphasis on flood damage reduction, both individually and in various combinations. These solutions were examined for economic feasibility as well as the degree to which they offered flood damage reductions and environmental and social impacts.

PROJECT DESCRIPTION

In November 1981 the Corps completed a Final Feasibility Study and Report which recommended that an upper watershed project, identified as the Batavia Reservoir Compound (Modified), be authorized for construction by Congress. The project calls for construction of two shallow detention reservoirs (normally dry) south of and upstream from the City of Batavia on the main stem of Tonawanda Creek. The lower (downstream) dam would be only 10 feet high while the upper dam 15 feet high. Each earthfill dam would be equipped with outlet control gates which would be closed only during excessive runoff periods (usually occurring in late winter or early spring) when flows would exceed downstream channel capacity. After the excessive runoff period the gates would be opened to release impounded water at non-damaging levels until the pools were fully drained. In addition, the stream channel within the two reservoir areas would be cleared of snags and debris which would substantially decrease the frequency of flooding of farms in these areas. Because of improved channel capacity in the reservoir areas and the fact that in most years the reservoirs would be fully drained by the time spring land preparation for crop planting begins, it is predicted that there will be a net benefit to agricultural interests.

Land for construction of the two dams, would be acquired in fee and would total some 95 acres. Permanent easements on 20 acres of land would be acquired for construction of training dikes. Flowage easements would be acquired on 3612 acres in the reservoir areas to permit temporary impoundment of excess runoff during flood periods and an additional 1616 acres of flowage easement would be acquired immediately downstream of the lower dam.

Twenty two homes will have to be acquired in the reservoir areas and the families relocated.

PROJECT COSTS AND BENEFITS

The total cost of the project at June 1981 price levels is estimated at \$25.8 million. Based upon an economic life of 100 years and an interest rate of 7 5/8 percent, the average annual cost of the project is \$2.49 million including operation and maintenance costs.

The average annual benefits in flood damages prevented over the life of the project are valued at \$3.29 million. Comparing costs and benefits yields an average annual net benefit of \$805,000 for a benefit to cost ratio of 1.32 to 1.0. One third of the average annual benefits, or \$1.1 million, will accrue to Genesee County and the remaining two thirds of the benefits will accrue to lower basin areas in Erie and Niagara Counties.

State Position

The Erie-Niagara Basin Comprehensive Water Resources Plan, adopted by the Department of Environmental Conservation in 1970, called for the construction of two multi-purpose reservoirs in the upper Tonawanda Creek watershed. Those two sites were considered by the Corps in their studies and were not recommended for various reasons including lack of economic justification, and loss of valuable farm land.

In letters to the Corps in 1976, 1979 and 1982 the Department has indicated support for the Batavia Reservoir Compound.

In light of strong opposition to the Batavia Reservoir Compound (Modified) by several Towns in the watershed and the Genesee County legislature, the Corps, in a letter dated December 27, 1982 to Commissioner Flacke asked that the Department reconsider the project and provide a new letter of support.

PUBLIC INVOLVEMENT

Since authorization of the study of the watershed in 1973 the Buffalo District has held numerous public meetings and workshops to obtain input from the public and local governments and to keep them advised of the status of the investigation. These began in 1975 and have included 12 public meetings and 6 workshops in various locations in the watershed. In addition, Corps personnel participated in a meeting with Town and Village of Alexander representatives and a technical workshop in early March, 1983 which were called for by this Department.

PRESENT CONTROVERSY

Support for the project has been expressed by Erie and Niagara Counties, the City of Batavia and five towns. The reasons for this support include the projected reduction of the frequency of flood damage, the reduction in size of the flood prone area, significant reduction of the area where flood insurance is mandatory in order to

obtain a home mortgage and the perceived advantages in attracting new industry to areas which are not flood prone.

Opposition to the project has been expressed by Genesee County and three towns in the watershed as well as four towns which would not be significantly impacted by the project. The position of the latter should be discounted in weighing support and opposition. The opposition of the Town and Village of Alexander to the project has some validity in that 22 residences to be acquired if the project is constructed would decrease the tax base somewhat and might also reduce income to the school district. The Village of Alexander would receive no benefits from the project.

Regional staff of the Division of Fish and Wildlife have expressed some concern over mitigation of negative impacts. The Department of Agriculture and Markets has expressed concern regarding impacts on local farm operations in the reservoir areas.

STAFF CONCLUSIONS

Staff has reviewed copies of resolutions adopted by local governments, both in support of and in opposition to the project as well as questions raised at the December 1, 1982 public meeting and answers to those questions contained in a Public Information Report dated December 1982 published by the Corps. In addition, Department staff conducted two technical workshops in Batavia in February and March of 1983 to obtain the viewpoints of local government staff and assess the validity of the basis for their positions. Staff have reached the following conclusion:


1. Some of the objections raised by communities within the reservoir areas and upstream are valid. There will be a reduction in tax base in these areas although much less than perceived by opponents of the project. There may be some adverse affects on farm operations although overall these should benefit. There are always some adverse impacts caused by construction of reservoirs.
2. Much of the opposition has no factual basis but is the result of misunderstandings, misinterpretations of information presented by the Corps and outright disbelief of certain aspects of the Corps' report.
3. As with any public works project, the concept of the "greatest good" should be applied. In the professional judgment of flood protection staff of the Division of Water, the overall benefits of construction of the project will outweigh the negative impacts.
4. Whether the Department supports or opposes the project for recommended action to Congress, substantial political pressure to change that position will likely be applied by local governments and possibly by members of the legislature.

Regional Directors of Regions 8 and 9 have indicated their support of the proposed project.

RECOMMENDATIONS

It is the recommendation of Division of Water Staff that the Commissioner sign a letter to Col. Hardiman, Buffalo District Engineering, reaffirming the support of the Department of Environmental Conservation for recommending the Batavia Reservoir Compound (Modified) for authorization by Congress. It is further recommended that the letter of support request the Corps of Engineers to coordinate closely with Regional Fish and Wildlife staff regarding mitigation of negative impacts and with the Department of Agriculture and Markets regarding impacts on farm operation, during post authorization studies.

New York State Department of Environmental Conservation
50 Wolf Road, Albany, New York 12233



Robert F. Flacke
Commissioner

February 17, 1982

Colonel George P. Johnson
District Engineer
U. S. Corps of Engineers
Dept. of the Army
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Johnson:

This is to advise that we are pleased to learn of the favorable feasibility study for a flood management plan of the Tonawanda Creek Watershed. We support this study and urge that a general design memorandum study be initiated as soon as possible.

Assuming that future studies confirm a feasible flood control project, the State of New York through, the Department of Environmental Conservation, is authorized to enter into a contractual agreement with the Corps of Engineers for construction of the project.

Sincerely,



James F. Kelley
Director
Flood Protection Bureau

REW:pt

cc: John Spagnoli, Region 9

NCBED-PE

17 October 1980

Dr. Robert Funk
State Archaeologist
University of the State
of New York
State Education Department
Cultural Education Center
Albany, NY 12230

Dear Dr. Funk:

Enclosed for your information is a Final Cultural Resources Report entitled,
Batavia Reservoir Compound: Phase I Archaeological Summary and Appendicies.

If you have any questions regarding this report, please contact Mr. Richard H.
Lewis, Staff Archaeologist, at (716) 876-5454, extension 2175.

Sincerely,

3 Incl
as stated

DONALD M. LIDDELL
Chief, Engineering Division

✓ CF:
NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

NCBED-PE

17 October 1980

Ms. Ann Webster Smith
Deputy Commissioner for
Historic Preservation
New York State Office of
Parks and Recreation
Agency Building #1
Empire State Plaza
Albany, NY 12338

Dear Ms. Smith:

Enclosed for your information is a Final Cultural Resources Report entitled,
Batavia Reservoir Compound: Phase I Archaeological Summary and Appendicies.

If you have any questions regarding this report, please contact Mr. Richard E.
Lewis, Staff Archaeologist, at (716) 876-5454, extension 2175.

Sincerely,

3 Incl
as stated

DONALD M. LIDDELL
Chief, Engineering Division

CF:
✓ NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____



NEW YORK STATE PARKS & RECREATION Agency Building 1, Empire State Plaza, Albany, New York 12238 Information 518 474 0666
Orin Lehman, Commissioner

June 27, 1980

Mr. Donald Liddell
Chief, Engineering Division
Dept. of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, N.Y. 14207

Dear Mr. Liddell:

Batavia Reservoir Compound
Genesee County, New York

We have reviewed the cultural resource reconnaissance report on this project and wish to make a few comments. The survey seems to be complete and the recommendations are in order. However, the structure survey forms do not provide sufficient information for us to evaluate them. The contact prints are not adequate particularly in cases where the structure may well be eligible for the National Register. Photos should be attached to the form as indicated on the form and in the enclosed manual. Also, an overall map should be included with forms keyed to it. This can be a USGS map if scale is a problem. We suggest you have your consultants follow the instructions in the manual for architectural and historical information as well.

Due to the large number of structures included in this study, it may be beneficial to wait until you know which structures are to be affected before a detail study is made.

Please call Bruce Fullem at 518-474-3176 should you wish to discuss this matter in detail.

Sincerely,

Stephen J. Raiche
Director
Historic Preservation Field
Services

5/2
Checked by

Filed by

BF:mr

Enc.

NCBED-PE

9 June 1980

Dr. Robert Funk, State Archaeologist
New York State Museum and Science Service
Anthropological Survey
Albany, NY 12234

Dear Dr. Funk:

Enclosed for your review and comment is a cultural resources reconnaissance report entitled "Batavia Reservoir Compound, Phase I Archaeological Summary" prepared for the Buffalo District by the State University of New York at Binghamton. This report is an update (which was required by project changes) of the cultural resources report provided for your review in November 1979.

If we do not receive your comments within 30 days of your receipt of this letter, we will assume you are in agreement with the contents of the report. Comments received after the expiration of the comment period cannot be considered in the preparation of the final report.

If you have any questions regarding this matter, please contact my staff Archaeologist, Mr. Richard H. Lewis at (716) 876-5454, extension 2171.

Sincerely,

DONALD M. LIDDELL
Chief, Engineering Division

CF:
✓NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

NCBED-PE

9 June 1980

Dr. Ann Webster-Smith, Deputy Commissioner
for Historic Preservation
Division for Historic Preservation
New York State Office of Parks and
Recreation
Agency Building No. 1
Empire State Plaza
Albany, NY 12238

Dear Dr. Webster-Smith:

Enclosed for your review and comment is a cultural resources reconnaissance report entitled "Batavia Reservoir Compound, Phase I Archaeological Summary" prepared for the Buffalo District by the State University of New York at Binghamton. This report is an update (which was required by project changes) of the cultural resources report provided for your review in November 1979.

If we do not receive your comments within 30 days of your receipt of this letter, we will assume you are in agreement with the contents of the report. Comments received after the expiration of the comment period cannot be considered in the preparation of the final report.


If you have any questions regarding this matter, please contact my staff Archaeologist, Mr. Richard H. Lewis at (716) 876-5454, extension 2171.

Sincerely,

DONALD H. LIDDELL
Chief, Engineering Division

CF:
NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____



Soil and Water Conservation District

5272 Clinton Street Road - Batavia, New York 14020 - Phone (716) 343-2362

October 29, 1979

Mr. Ronald J. Guido
Chief, Economics Section
Department of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Ron:

After reviewing the material sent regarding the BRMC in Genesee County, we offer the following comments:

- 1) The study appears to be well written and based on the materials and data used, a significant benefit should be achieved.
- 2) There is no doubt that some time will elapse before the full "improvement" impact will be seen, but gradually landowners in the area should begin to utilize the abandoned or idle land. However, intensification could occur from more than one direction.

If annual flooding in the lower region is controlled during the growing season, dairy men in the area might utilize more of the idle land for livestock crop production such as oats, corn and hay.

Also cash crop farmers not necessarily in the area, may also begin to renovate the idle land for more intensive crops such as cabbage, dry beans, beets, sunflowers, etc.

A third prospect would be a combination of the two, whereas a dairy man might diversify by adding some acreage of cash crops as he presently produces enough feed and still has extra land now capable of growing and harvesting crops.

- 3) Much of the idle land will need improved internal water management in order to compete in crop production. This is an assumption based on the premise that the land was abandoned due to prolonged wetness after the initial flooding had subsided.

Internal water management can be obtained through the use of land leveling and filling, open drainage channels, subsurface tile installation and diversion of over land flow from adjacent higher land.



Soil and Water Conservation District

5272 Clinton Street Road · Batavia, New York 14020 · Phone (716) 343-2362

Ronald J. Guido
Page 2

- 4) Channel improvement particularly in the area between the upper and lower impoundments, would add an extra dimension to water control in the area. Often high flows (not bankfull) back up at the log jams and flow into adjacent fields causing local flooding and crop loss. The removal of impediments within the channel proper, would reduce the severity of annual summer crop losses along certain sections of the stream.
- 5) In reference to item G on the included disposition form dated Sept. 26, 1979 from R. Waxmonsky to you, we completely agree with this and think it will be one of the points of contention.

However, I also think a similar problem may occur in the lower area with the farms where buildings and facilities will require removal.

In closing, please feel free to call for any additional information you may need. Either Art Hanson or myself are available at 716-343-2362.

Respectfully,

Robert Berkemeier
District Manager

RB/jg

NCBED-PC

5 October 1979

Mr. Robert Berkmeier
Genesee County Soil & Water
Conservation District
5272 Clinton Street Road
Batavia, NY 14020

Dear Mr. Berkmeier:

As agreed in our meeting of 24 September 1979, I am forwarding you some material relating to the agricultural component of the Tonawanda Creek study we are presently concluding. This includes a draft copy of the agricultural section of the Economic Supplement to the Revised Interim Feasibility Report and a copy of an in-house memo from R. Waxmonsky to me dated 26 Sep 79. The latter specifically relates to the impact alternative plans would have upon agriculture in the two reservoir sites.

I would appreciate your reviewing these materials in light of your knowledge and experience with agriculture on the Tonawanda Creek flood plain. I would like to receive your written comments by Monday, 29 October, so that we might consider them before we hold a public information and status meeting on the project in the city of Batavia on 8 November 1979.

Should you have any questions, please feel free to phone me, Area Code (716) 876-5454, extension 2177.

Sincerely,

2 Incl
as stated

RONALD J. GUIDO
Chief, Economics Section

CF:
✓ NCBED-PC
NCBED-PN/J. Hassey

Waxmonsky_____
Guido_____

NCBED-PC
R. Guido

The Effect of Alternative Reservoir Management Plans
Upon Agriculture in Reaches T-13 L and T-13 U
R. Waxmonsky

26 Sep 79
Waxmonsky/ls/2178

After having talked with Brad and Mike this morning, I would restate my 7 Aug 79 memo as follows:

a. Given the historical record of flowage in Tonawanda Creek at the Batavia Gage for the 1945-1970 period, it is estimated that only three floods in the 16 April to 1 July period would have overspilled the bank in T-13 Lower (the area between the two reservoirs) under existing (that is, with natural or without project) conditions.

b. If the Batavia Reservoir Compound-Modified had been in place in 1945, only one of these floods would have impounded water in T-13 Lower. This would have been the 25 April 1961 flood. This assumes "winter operation" of the two reservoirs - the floodgates in each reservoir are partially closed.

c. Under with project and winter operation conditions, an area of 1,250 acres would be inundated in Reach T-13 Lower by this flood. This compares to 870 acres which are estimated to have been inundated under existing (natural) conditions in April 1961. The depth of the pooled water would have been 5.3 feet greater under with project and winter operation conditions than under existing (natural) conditions. Under the improved and winter operation conditions, an area of 350 acres would be inundated in the Upper Reservoir (T-13 Upper); this compares to 45 acres which was estimated to have been unundated under existing (natural) conditions in April 1961. The depth of pooled water in the Upper Reservoir would have been 9.4 feet greater under with project and winter conditions than under existing (natural) conditions in 1961.

d. The 25 April 1961 flood would have been out-of-bank for seven days in T-13 Lower under with project and winter operation conditions; this is four days longer than it has been estimated; it was out-of-bank under existing (natural) conditions in April 1961. The additional four days would not have had a significant affect on spring planting as field preparation could have begun by 15 May; at a minimum, it would not have significantly hindered the planting of corn. The same flood would have been out-of-bank in T-13 Upper for approximately four days under the same conditions. Since it has been estimated that there was no flooding in T-13 Upper under existing (natural) conditions, this is a net and an absolute increase in the duration of flooding in the area. However, for the reason given in the discussion of T-13 Upper above, the flooding would not significantly hinder the planting of corn. It could, however, significantly delay the planting of oats in T-13 Upper. But, as no oats were planted in T-13 Upper in 1978, this may well be insignificant.

e. Since the project would have eliminated all but one flood during the 16 April to 1 July period in the 25 years from 1945 to 1970, there is a four percent risk in any one year of a flood occurring in T-13 Upper during the 16 April to 1 July period. Consequently, at a maximum, there is a four percent risk of agricultural crop damage in the reach from a flood occurring during this period of time. Though the value of the damage could amount to as much as the total agricultural revenue produced in the

NCBED-PC

SUBJECT: The Effect of Alternative Reservoir Management Plans
Upon Agriculture in Reaches T-13 L and T-13 U

reach minus all remaining unexpended variable production costs, the probability that the damage would be this great is relatively small. Most probably, damages associated with a flood in the 16 April to 1 July period would be substantially below the above mentioned maximum value.

f. Operation of the project on a "summer operation" plan (closing the floodgates of the upper reservoir to as great an extent as possibly and as frequently as possible) would reduce the flowage into the lower reservoir site, T-13 Lower. This would greatly reduce the probability of the very slight but very frequent floods (annual floods) which currently inundate low lying areas along the creek. This would increase the productivity of these lands and would produce some agricultural benefits which would tend to offset the increase loss farmers in T-13 Lower would experience from more frequent impounding of water on their land under the project and winter operation conditions. This would further reduce the magnitude of the latter loss.

g. Though "summer operation" of the two reservoirs would increase the utility and productivity of lands in the lower reservoir (T-13 Lower) by reducing the frequency and extent of the slight but frequent (annual) floods, it would do so at the expense of farm operations in the upper reservoir site (T-13 Upper). Here, the effect would be to increase agricultural losses because the area would be flooded more frequently, and a greater area would be flooded to a greater depth, under summer operation than under winter operation or under existing (natural conditions). This increased loss to upper reservoir farmers would be compensated by paying them a relatively high flowage easement price which would presumably compensate them for their increase loss. Since they will still own the land, they will still be able to use it as they choose, and as conditions permit in nonflood periods.

RAYMOND WAXMONSKY
Regional Economist

NEW YORK STATE
DEPARTMENT OF TRANSPORTATION
Raymond T. Schuler, Commissioner



1220 Washington Avenue, State Campus, Albany, New York 12226

December 8, 1975

LTC Byron G. Walker
Corps of Engineers
Deputy District Engineer
Department of the Army
1776 Niagara Street
Buffalo, New York 14207

Dear LTC Walker:

Your letter of December 1 has been received and forwarded to Mr. K. W. Shiatte, Director of our Development Division, for reply. Any future correspondence should be directed to Mr. Shiatte at the following address:

Mr. K. W. Shiatte, Director
Development Division
New York State Department of Transportation
1220 Washington Avenue
State Campus
Albany, New York 12232

Please send a carbon copy of the notification letter, without attachments, to Mr. J. K. Mladinov, Assistant Commissioner for Planning and Development, at the above address. Thank you.

Sincerely yours,

E. Wilson Campbell
E. Wilson Campbell
Director, Planning Division

EWC:BHC

FILE COPY

Checked by

Filed by

New York State Department of Environmental Conservation
Region 9 Fish & Wildlife Office
128 South Street
Olean, New York 14760



Ogden Reid,
Commissioner

December 18, 1975

Mr. Bernard C. Hughes
Colonel, Corps of Engineers
Buffalo District
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hughes,

I did not have an opportunity to attend the public meeting November 20, 1975 concerning flood management along the Tonawanda Creek.

I would like to bring your attention to a matter of interest to the Region 9 Wildlife Unit concerning the study area.

Region 9 Wildlife personnel have identified a major deer wintering area in the Tonawanda Creek valley between the Sierks reservoir dam site and Varysburg in Wyoming County. It is entirely possible that a reservoir in this area would significantly affect this wintering area and consequently the deer herd in a much larger area. I have encircled in red on a map of the study area the approximate location of the area of concern. A detailed analysis of the effects of a reservoir in this area will require considerable time.

Thank you for the opportunity to comment on this proposal.

Very truly yours,


R. L. Cheney
Russell L. Cheney
Regional Wildlife Manager
Region 9

RLC/dm
Encl.
cc: L.S. Nelson
J. Dell


FILE COPY

Checked by
Filed by

fr
RL



New York State Department of Environmental Conservation
50 Wolf Road, Albany, New York 12233



Ogden Reid,
Commissioner

January 7, 1976

Colonel Bernard C. Hughes
District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hughes:

We have reviewed your report entitled Considered Structural Alternatives for Flood Control in the Tonawanda Creek, New York and have the following comments:

1. Alternative #1 - Sierks Reservoir

Although this alternative would be consistent with the State-adopted Erie-Niagara Basin Plan, there are several significant environmental concerns which must be considered. A major deer wintering area in the Tonawanda Creek Valley between the Sierks reservoir dam site and Varysburg has been identified. It appears that a reservoir in this area would significantly affect this wintering area and consequently, the deer herd in a much larger area. In addition, the impacts associated with relocating Route 98, which is presently within the proposed reservoir pool, will have to be carefully evaluated. The impact of the project on wetlands and active agricultural activities must also be considered.

2. Alternative #2 - Linden Reservoir

This measure is also consistent with the State-adopted Erie-Niagara Basin Plan. Although no specific adverse impacts have been identified, the impact of the project on wetlands and active agricultural activities will have to be carefully reviewed as additional information becomes available.

3. Alternative #3 - Alabama Pools

One of our major concerns is the potential loss of wetlands resulting from various alternatives of the watershed project. The Alabama Pools alternative appears to have the greatest potential for adverse impacts on wetlands. It may have an adverse impact on the Tonawanda Wildlife Management Area, which has been developed approximately 80% by this Department, and would negate some of the previously completed development. In addition, this measure may affect portions of two agricultural districts comprising approximately 43,000 acres in the Towns of Batavia, Alabama, Oakfield and Pembroke.

FILE COPY

Checked by

Filed by

January 7, 1976

4. Alternative #4 - Batavia Reservoir Compound

From an environmental viewpoint, this measure would probably have the least amount of adverse impacts when compared to the other alternatives. A major concern in conjunction with this measure would be the loss of productive farmland. However, since both detention reservoirs would normally be dry, provisions could be made to permit existing farming operations to continue as long as such activities do not affect the integrity of the flood protection provided. In addition, the limited period of flood water inundation associated with these types of structures (dry dams) would probably have a minimal impact on wetlands and wildlife habitat within the project area.

5. Alternative #5 - Modification to Existing Corps Project at Batavia

This measure may have a significant impact on Tonawanda Creek in the Batavia area, which could conflict with fishery management plans. The potential for adverse impacts would result primarily from the recommended enlargement of the stream channel for approximately 2½ miles.

Thank you for the opportunity to review the proposed project alternatives. We, of course, would like to receive additional information as it becomes available.

Very truly yours,



Terence P. Curran
Director of Environmental Analysis

BUFFALO METROPOLITAN AREA, NEW YORK
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

INPUT FROM LOCAL INTERESTS

U. S. Army Corps of Engineers
Buffalo District
Buffalo, New York

BENNY POTRZEBOWSKI
Council President

J. ROBERT BUCKLEY
President Pro Tem

IRA M. GATES
City Administrator

REBECCA J. TIEDE
Clerk-Treasurer

GEORGE E. SCHAEFER, JR.
City Attorney

CITY OF BATAVIA



COUNCILMEN AT LARGE
BENNY POTRZEBOWSKI
CATHERINE K. ROTH
JOHN C. BANNISTER

COUNCILMEN
BRUCE R. TEHAN
LOUIS D. CANALE
THOMAS E. HUNTLEY
D. HOWARD COHEN
RICHARD E. O'DONNELL
J. ROBERT BUCKLEY

Batavia, New York 14020

November 30, 1981

Mr. Daniel Kelly
Project Engineer
U.S. Army Corps of Engineers
1776 Niagara Street
Buffalo, N.Y. 14207

Dear Mr. Kelly:

Attached is a resolution adopted by City Council on November 23, 1981 supporting the Corps of Engineers flood control project south of the City of Batavia.

Sincerely,

Ira M. Gates
Ira M. Gates
City Administrator

IMG:ble

Attach.

2. Motion of Councilman O'Donnell

WHEREAS, due to its location and topography, the City of Batavia is frequently subject to floods and the threat of floods from the Tonawanda Creek, and

WHEREAS, these conditions limit development in certain sections of the city and impose additional insurance costs for residents of these areas, and

WHEREAS, the Army Corps of Engineers have studied and recently proposed the construction upstream (south) from the city of impoundment areas to equalize flow of the Tonawanda Creek, especially in periods of high water, as a method of reducing the flood prone area in the city, and

WHEREAS, this project has been approved by the Tonawanda Creek Watershed Committee, now, therefore,

BE IT RESOLVED by the Council of the City of Batavia, that the Council supports this proposed flood control project and requests speedy implementation, as a means to limit the flood hazard problem in the City of Batavia.

Seconded by Councilman Buckley

and on roll call approved unanimously

STATE OF NEW YORK
COUNTY OF GENESEE
CITY OF BATAVIA

I hereby certify that the foregoing is a true and correct
manuscript of a resolution duly adopted by the City Council
of the City of Batavia on the 23rd day of November,
1981, and of the whole thereof.

Dated at Batavia, N. Y.

November 30 1981
Deanna L. Mee
City Clerk, Batavia, N. Y.

November 5, 1981
9079 Creek Road
Batavia, NY 14020

David MacPherson
Planning Study Manager
Corps of Engineers
1776 Niagara Street
Buffalo, NY 14207


Dear Mr. MacPherson:

Damaging floods have been a part of Batavia's history. The Flood of 1942 prompted the construction of channel improvements which lessened the damages of the 1960 Flood. However, these channel improvements do not offer adequate protection against major floods. The area has escaped serious flooding in recent years but the Federal Flood Insurance Maps graphically detail the extent of major flooding which could engulf a large percentage of the City.

This Committee has spent many hours in discussions with Corps of Engineers' representatives and interested citizens. Everyone agrees that flood protection is necessary. The Corps of Engineers have studied and explained many alternatives. The Batavia Reservoir Compound Plan (modified) will greatly benefit Genesee County but as with any drainage protection plan some areas will receive more protection than others. The time for study and debate has passed and we believe the time has come to enthusiastically support this selected plan. We urge everyone to give this project their undivided support.

Attached are copies of the Tonawanda Creek Watershed Minutes of October 22, 1981 recommending support of this important project.

Very truly yours,



Frank Gorecki, Chairman
Tonawanda Creek Watershed

DL:am
Att.

MINUTES OF
TONAWANDA CREEK WATERSHED COMMITTEE
OCTOBER 22, 1981

This Meeting is a carry over of the October 15 meeting which lacked a quorum. Frank Gorecki called the Meeting to order at 7:50 P.M. Present:

Ed Starowicz
Don Woodruff
Ray Chudoba
Jim Kustus
Dennis Larson, Secretary

Mr. Gorecki reported that Maynard Glor was sick and would not be able to attend. Dick Young could not attend because of the press of business, but sent his proxy with Mr. Gorecki.

Motion by Ray Chudoba, seconded by Don Woodruff, that the minutes of August 6, 1981 be approved as received. Unanimous approval.

The following motion by Ray Chudoba, seconded by Jim Kustus. For a period of about 75 years flood control type projects have been under consideration with fragmented interest periodically and only to die out for long periods, even decades. Interest is sparked only when near disaster strikes only to die out again. In the past 2 years several alternatives have been discussed. Each and every time the discussion centers around the best method to accomplish flood control, the main topic seems to get lost, "DO WE NEED A FLOOD CONTROL PROJECT". In our opinion the answer is YES. Recently a new study was completed that places nearly 50% of the City of Batavia in a flood plain. The economic impact of this alone verifies the fact that we need flood control. Hundreds of additional homes and businesses will now be required to buy flood control insurance. These properties will now have the disadvantage of this stigma in their future development, when financing improvements or when attempting to sell such property. In the past few days we have heard the concern of people regarding the loss of our young people leaving the area. They get their education in or around Batavia and find little to offer in the varied job market. Why? Look around and see the various employers who are or have left the area. Blame this on the flooding, no; but if we had a good flood control project in existence that could or would free us some of the land available to be offered

AD-A133 910


BUFFALO METROPOLITAN AREA NEW YORK WATER RESOURCES
MANAGEMENT INTERIM REP. (U) CORPS OF ENGINEERS BUFFALO
NY BUFFALO DISTRICT JUL 83


7/9

UNCLASSIFIED

F/G 13/2

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

to business and industry, this could make a difference in attracting those types of business, and our young people just might decide to stay. We say get in your car and take a tour, in and around the City with a flood plain map and you will see the southeast, south and southwest sections of this area are most bleak compared to their counterparts.

Some of the best people have put their minds together and through their efforts have come up with a sound, safe and mostly financial free solution to this yearly threat in the Batavia Reservoir Compound Flood Control Project and we move that this project be approved forthwith with all the backing and support we can muster.

Discussion followed and Chairman Gorecki pointed out that this is only the preliminary plan and that details will be refined as the project goes through the many steps to construction. Also there would be future public hearings before the project becomes a reality. Roll call vote on the motion:

Jim Kustus, Yes	Frank Gorecki, Yes
Ray Chudoba, Yes	Don Woodruff, No
Ed Starowicz, No	Dick Young, Yes (Proxy Vote)

Summary: 4 Yes Votes, 2 No Votes.

Don Woodruff explained that he voted No but would not work against the proposed project. Don Woodruff made a motion, seconded by Jim Kustus, to send the attached letter to all affected Municipalities.

Roll call vote on the letter:

Jim Kustus, Yes	Frank Gorecki, Yes
Ray Chudoba, Yes	Don Woodruff, Yes
Ed Starowicz, No	


Summary: 4 Yes Votes, 1 No Vote.

It was also suggested that copies of the news article be attached to the letters.

Meeting adjourned at 8:50 P.M.

DL:am

cc: All Members & City Council
J. Woodruff, Co. Leg. Chairman
J. Hume, Co. Leg.
C. Scott, Town Supv.
A. McWilliams, Daily News
H. Kelsey, Chairman, SWCD
C. Meyer, County Mgr.
J. Hiller, Town Mgr.
D. McPherson, Corps Eng.


Dennis Larson, Secretary

Flood Control Plan Ready For Washington Review

By Al McWilliams

Flood control plans calling for the construction of two dams — each over a mile long — on the Tonawanda Creek south of the city are ready to go to Washington.

Corps of Engineers officials Thursday told the Tonawanda Watershed Committee and area residents the survey report and technical review are complete and the next step in submission to the Board of Rivers and Harbors.

The report given at a meeting at City Hall indicates the project that has been several decades in the talking and preliminary planning stages may be on the move again. Several alternatives have been ruled out and the two-dam plan is the one engineers believe will best meet the control needs in the city, the area south of the city and downstream in Erie County.

Total cost estimated on the basis of June 1980 prices is \$22 million. Inflation is expected to push the price tag up about 10 percent a year while the authorization process goes on, Charles Gilbert, planning chief for the corps' Buffalo office, told the gathering of local officials and property owners.

The upper dam, about 5,450 feet long, would be south of Peaviner Road just downstream from the Conrail embankment. It would have five electrically operated gates that would each have a maximum opening of 11-by-11-feet.

Downstream about three miles would be the lower dam — a 5,600-foot-long structure reaching from near Route 98 across the

valley to a point about 1,500 feet east of Creek Road. It would have four electric gates with the same maximum

Map on Page 4

openings as those in the upper dam.

Because it is a project that would solve regional problems, construction and annual maintenance costs would be entirely federally financed, the engineers stated. The

operating expenses are expected to run about \$275,000 a year.

The project is still a long way from becoming a reality. Mr. Gilbert told The News it will take a year for the plan to move through the Washington review process. It could then be five to six years before it will clear Congress and be ready for construction which will take another two years.

Fifty-four houses, farms and farm

buildings are in the immediate reservoir areas and are slated for removal. Robert Dragonette, an official of the corps real estate section, told the 15 area residents present they would be paid fair market value for their homes, receive payment for moving expenses and be eligible for up to \$15,000 for the difference in the cost of

Continued on Page 4

Continued from Page 1

financing a new home.

Farm land would not be purchased by the federal government. The corps would negotiate easements and the farm operators would still be able to farm the land. The engineers claim the farmers would benefit from a longer growing season because the flood control would allow them to get on the fields earlier in the spring.

Debris would be cleared from the creek between the dams to provide a better flow. The gates would be closed only during heavy runoff periods, and most of the year the reservoir areas would be dry, the engineers report.

The new plan is a modified version of a previous proposal. Questions had been raised about the ability of earthen dams to withstand an earthquake — the site is on a fault extending north from Attica.

Engineers moved the lower dam about 2,000 feet upstream from an abandoned Conrail right of way and have proposed inclusion of materials that would pack down with the quake vibrations.

City officials have been concerned over the large sections of the community that have been designated as potential flood zones. The designation requires owners to carry flood insurance and involves more restrictions in the sale.


Corps engineers told County Legislator Sibyl B. Zorn the dam construction would end the flood zone designations. The dams would provide 500-year flood protection in the city.

Frank Gorecki, the watershed committee chairman, told the gathering, "Everyone agrees we need flood

control. To get the people to agree on what type is an impossibility. We've got to depend on the expertise of the engineers. We're not going to have agreement and it will go on forever."

City Engineer Dennis Larson, a committee member, commented that each year the city is "on the brink of disaster" as the creek rises. "I'm afraid, to get the project, we've got to have a disastrous flood."

Residents will have an opportunity to comment on the proposal. In the next step in the process, the corps division office in Chicago will advertise the plan and comments will be received for 30 days before it is sent on to Washington.



FLOOD CONTROL PLANS — Two mile-long dams on the Tonawanda south of the city are included in a Corps of Engineers flood control plan ready for submission to federal officials in Washington.

THE DAILY NEWS

Published Monday through Saturday evenings by
Griswold & McWain, Inc., a subsidiary of Johnson
Newspaper Corporation. Phone 343-8888

2 Apollo Drive, Batavia, New York 14020.

JOHN B. JOHNSON
President

JOHN H. CONNOR
Editor

Flood Control

There thankfully is a glimmer breaking through the area flood control clouds.

It is an issue that has been talked and studied and debated and planned for a couple of decades. Now the Corps of Engineers has a plan in focus that is being submitted to the Board of Rivers and Harbors.

That assertedly is the first step in an authorization process. Observations are that it will take a year to clear the review proceedings and then probably another five or six years to attain funding by Congress, if that comes to pass.

Nonetheless, it is reassuring that there is a positive plan in place and in the proper channels.

At current figures, it is a \$22 million project. Contemplated are two dams — a 5,450-foot upper dam south of Peaviner Road and a 5,600-foot structure about 3 miles downstream on Tonawanda Creek. Each would be equipped with electrically-controlled gates.

Fifty-four houses, farms and farm buildings would have to be acquired to accomplish the undertaking. Because of its regional scope, operating costs would be federally funded.

The area has pretty much escaped major flooding through the years but the margin has been so close many times. Just a little bit more rain on many occasions could have resulted in disaster.

Significant of the peril are the extensive flood zone designations in this sector that require property owners involved to carry flood insurance and involve restrictions on property sales.

MINUTES OF
TONAWANDA CREEK WATERSHED COMMITTEE
OCTOBER 15, 1981

This Meeting lacked a quorum so there was no Committee action.

The following representatives from the Corps of Engineers provided detailed information on the background, alternatives considered and information on the status of the flood control study:

Charles Gilbert, Chief, Planning Division
David MacPherson, Planning Study Manager
Bradford Price, Chief, Hydrologic Invest. Sect.
Joseph Hassey, Planning, Former Study Manager
Jack Carr, Economics Branch
Ray Waxmonsky, Economics Branch
Philip Berkeley, Environmental Resources Br.
Robert Dragonette, Real Estate Office

Summary:


With the project in place, those in the upper reservoir would have some benefit from a reduction in flooding due to clearing and snagging of the upper and lower reservoirs. Those in the lower reservoir would be benefited by extending the planting season most years. This will enable farmers to start planting earlier in the Spring since many of the present frequent Spring floods would be eliminated. Most of the City of Batavia would have 500-year protection from Tonawanda Creek overbank flooding. The existing average annual flood damages in the Tonawanda Creek Watershed would be reduced by about 74 percent. The protection at Rapids, New York, in the Clarence-Amherst area would experience about 1-5 year protection, much less than at Batavia, but the overall saving in damages would be significant with no adverse impact to the area.

The total first cost of the Batavia reservoir compound (modified) plan is \$22,680,000, all Federal expense at June 1980 price levels. The average annual operation and maintenance cost is \$275,000 (all Federal). The benefit/cost ratio is 1.35 based on an economic life of 100 years. There are no Non-Federal costs.

Throughout the previous plan formulation process, we have involved the public in many meetings and workshops to insure that the study responds to the public's needs. Now that a plan has been selected based upon your recommendations, your continued support of the plan is needed. Corps reviewers of higher authority and members of Congress will be asking the question "Does the Public and their Representatives want this project?"

Following the presentation, many questions were asked and thoroughly discussed and answered.

Because the Committee lacked a quorum, they will meet again October 22, 1981.



Dennis Larson, Secretary

DL:am

29 April 1981

MEMORANDUM FOR RECORD

SUBJECT: Agriculture on the Tonawanda Creek Flood Plain

1. On 7 April 1981 (12:30 - 4:00 p.m.) a meeting was held at the Buffalo District Office, U.S. Army Corps of Engineers concerning the Tonawanda Creek flood control study. The specific purpose of this meeting was to obtain further detailed documentation for the projected increase in crop yields that will result directly from our project.

2. Attendees at this meeting included:

Bruce Tillapaugh	Cooperative Extension Service
Nathaniel Herendeen	Cooperative Extension Service
Douglas Dettenrieder	Soil Conservation Service
James Hume	County Legislator, Flood Plain Farmer
Frank Gorecki	Flood Plain Farmer
John Carr	Project Economist, Buffalo District, Corps of Engineers
David MacPherson	Project Manager, Buffalo District, Corps of Engineers
Michael Mohr	Project Hydrologist, Buffalo District, Corps of Engineers
Ronald Guido	Chief, Economics Section, Buffalo District, Corps of Engineers
Kenneth Hallock	Assistant Chief, Engineering Division, Buffalo District, Corps of Engineers
Mark Charlton	Economist, North Central Division, Corps of Engineers

3. Following a thorough discussion of the Tonawanda Creek flood control project and its impact upon agriculture in the flood plain, a consensus among the agricultural authorities in attendance was arrived at regarding current and optimal planting dates on the flood plain. Tables 1 and 2, which follow, illustrate this consensus regarding current and optimal planting dates on the flood plain.

Table 1 - Current Planting Dates

Crop	:	Genesee County	:	Erie and Niagara Counties
Corn, silage	:	25 May	:	25 May
Corn, grain	:	25 May	:	25 May
Oats	:	10 May	:	10 May
Winter Wheat	:	10 September	:	10 September
Mixed Hay	:	10 May	:	10 May

Table 2 - Optimal Planting Dates

Crop	:	Genesee County	:	Erie and Niagara Counties
Corn, silage	:	1 May	:	1 May
Corn, grain	:	1 May	:	1 May
Oats	:	10 April	:	10 April
Winter Wheat	:	20 September	:	20 September
Mixed Hay	:	10 April	:	10 April

These current and optimal planting dates reflect existing flooding and drainage conditions on the Tonawanda Creek flood plain. They represent the average current and optimal planting dates considering: probability of flooding, soil capability, existing drainage tiles, existing fertilizer applied to specific crops, existing precipitation patterns, and specific crops being planted.

4. Agricultural intensification will result from two factors: (1) an extension of the effective growing season, which will enable farmers to plant crops earlier in the spring due to elimination of most April floods and (2) a change in farmers' behavior toward more intensive agriculture.

Agricultural intensification benefits have been claimed for reach T13 lower (the area between the reservoirs) and all agricultural reaches downstream of Batavia, NY (reaches T3-T9, RB1-4, M1-6, T11, T12).

NCBED-PC

SUBJECT: Agriculture on the Tonawanda Creek Flood Plain

Reach T13L

Despite the fact that the lower reservoir (reach T13L) would be filled on the average every 2 years, the time that the reservoir would be filled would be during snowmelt the end of February to early April. In general, for floods after 8 April only pasture and wooded areas near the lower reservoir would be inundated. The clearing and snagging operation will contain most of these late spring floods (after 8 April) in the upstream area of the lower reservoir. The clearing and snagging operation will increase channel capacity in T13L from about 500 cfs to 2,000 cfs under improved conditions. From historical data at the Batavia gage (1945-1970) it has been observed that 10 of 74 floods during this period occurred during the growing season of 8 April - 31 October. If the clearing and snagging operation had been undertaken during this historical period the increased channel capacity would have contained six out of ten of these events.

This represents a sharp reduction in the perceived risk of the farmers operating on the flood plain in reach T13L. The threat of an April flood, with the associated problem of delaying planting beyond the optimal date, would no longer preclude more intensive operations.

Agricultural Reaches Downstream of Batavia -
(Reaches T3-9, RB1-4, M1-6, T11, T12)

It is possible to estimate the probable impact the project would have on the frequency of April floods by comparing the frequency with which April floods would have occurred in the 1922-1977 period, if the project had been in place.

The argument that the project will eliminate most April floods has been developed for the major agricultural reaches, those with more than 800 acres of agricultural land downstream of Batavia. This includes reaches T5-T9, RB-3, M1-3, M-5, and M-6. These reaches include 78 percent of the agricultural land downstream of Batavia.

The data used to support the methodology includes the stage-frequency curves for the above mentioned reaches and historical data of flood levels at the Alabama Gage on Tonawanda Creek. This gage is located on the creek at Hopkins Road; it is the boundary between reaches T-10 and T-11. Observations at this gage site are based on the 56-year period from 1922 to 1977.

It has been assumed that the stage will be reduced in all agricultural reaches downstream of Batavia, NY, by the average reduction in the major agricultural reaches (1.9 feet). It is observed that, had this project been in place during the historical period (1922-1977) the vast majority of April floods, 23 out of 26, would have been eliminated during this period. This would have reduced the historical occurrence of April floods to once in 18.5 years as opposed to once in 2.2 years.

NCBED-PC

SUBJECT: Agriculture on the Tonawanda Creek Flood Plain

This represents a very sharp reduction in the perceived risk of farmers operating on the flood plain. The threat of an April flood with the associated problem of delaying planting beyond the optimal date would no longer preclude more intensive operations.

5. The shift in planting dates (from current to optimal dates) will result in higher yields from the major crops grown on the flood plain.

Tables 3-5 represent a consensus of agricultural experts in attendance at the 7 April 1981 meeting regarding existing yields, "with-project" yields, and the highest possible yields given the soil types found on the flood plain under ideal conditions. Ideal conditions assume elimination of all overbank flooding, all farmers install drainage tiles, and apply additional fertilizer and ideal precipitation patterns.

Table 3 - Existing (Without Project) Yields

Crop	:	Genesee County	:	Erie and Niagara Counties
Corn, silage	:	13 tons/acre	:	11-12 tons acre
Corn, grain	:	65-70 bushels/acre	:	60 bushels/acre
Oats	:	50-60 bushels/acre	:	45-50 bushels/acre
Winter Wheat	:	40 bushels/acre	:	30 bushels/acre
Mixed Hay	:	2.5 tons/acre	:	2.5 tons/acre

Note: Genesee County is characterized by distinct soil types with distinct capability.

Erie and Niagara Counties are characterized by similar soil types with similar capability.

NCBED-PC

SUBJECT: Agriculture on the Tonawanda Creek Flood Plain

Table 4 - Improved (With Project) Yields

Crop	:	Genesee County	:	Erie and Niagara Counties
Corn, silage	:	18 tons/acre	:	17 tons acre
Corn, grain	:	100 bushels/acre	:	90 bushels/acre
Oats	:	90 bushels/acre	:	80 bushels/acre
Winter Wheat	:	50 bushels/acre	:	45 bushels/acre
Mixed Hay	:	4 tons/acre	:	3 tons/acre

Note: Genesee County is characterized by distinct soil types with distinct capability.

Erie and Niagara Counties are characterized by similar soil types with similar capability.

These existing (without project) and improved (with project) yields reflect existing drainage conditions found on the Tonawanda Creek flood plain. No additional investment is required of the farmer to obtain the improved yields cited in Table 4. Only planting crops on the flood plain at optional planting dates is required to obtain the improved yields.

Table 5 - Yields Under Ideal Conditions

Crop	:	Genesee County	:	Erie and Niagara Counties
Corn, silage	:	22 tons/acre	:	21 tons acre
Corn, grain	:	135 bushels/acre	:	125 bushels/acre
Oats	:	110 bushels/acre	:	100 bushels/acre
Winter Wheat	:	65 bushels/acre	:	55 bushels/acre
Mixed Hay	:	4.5 tons/acre	:	3.5 tons/acre

Note: Genesee County is characterized by distinct soil types with distinct capability.

Erie and Niagara Counties are characterized by similar soil types with similar capability.


NCBED-PC

SUBJECT: Agriculture on the Tonawanda Creek Flood Plain

Yields under ideal conditions represent the highest possible yields given the soil types found on the flood plain with elimination of the overbank flooding, adding additional fertilizer, installing additional drain tiles, and with ideal precipitation patterns. These yields represent an upper bound on yields obtainable by the major crops grown on the flood plain.

6. With the implementation of the Tonawanda Creek flood control project the flood plain farmers can be expected to plant crops at optimal dates as shown in Table 2 and obtain "with project" yields shown in Table 4.

Also shifts in acreage planted from lower to higher value crops can be expected with a project in place. It is also expected that idle land will be put into production with a project in place. A very conservative estimate of the change in agricultural land use on the flood plain as a result of this project would be to assume that 50 percent of the idle agricultural land in reaches impacted on by the project will be shifted into production in the same distribution as major crops are currently planted on the flood plain.



RONALD J. GUIDO
Chief, Economics Section

401 North Main Street
Warsaw, N.Y. 14569
Telephone: 716-786-2251

21 South Grove Street
East Aurora, N.Y. 14052
Telephone: 716-652-5453

May 8, 1981

Ronald Guido
Department of the Army
Buffalo District
Corps of Engineers
1776 Niagara Street
Buffalo, NY 14207

Dear Ron:

First I would thank those from the Army Corps of Engineers that invited Cooperative Extension and Soil Conservation Service staff to contribute to the Tonawanda Creek Project. All too often local expertise is not used adequately. I'm sure the farming sector would look to Cooperative and SCS to provide the type of information you have asked for us to contribute.

I have enclosed a copy of your letter dated April 29, 1981 with additions or corrections as I felt were discussed at the April 7, 1981 meeting at the Corps office in Buffalo.

With the addition of improved harvest conditions as I noted on page two, I fully concur with the technical information and accompanying explanation.


In conclusion I feel that Agriculture on the Tonawanda Creek Flood Plain would respond favorably to the project, if completed as presented.

Sincerely,



Bruce P. Tillapaugh
Regional Extension Specialist
Field Crops

BPT:pt
Enclosure



James H. Hume, Jr.

9778 Creek Road
Batavia, New York 14020

May 7 1981

Ronald J. Guido,
Chief, Economics Section

Dear Ron,

I have reviewed the memorandum of Record of the April 7, 1981 meeting. I concur with material in the report and believe the plantings, dates and average yields established for the different situations listed in the report are accurate.

I thank you for your efforts to get this material together.

Sincerely,

James H. Hume, Jr.

420 East Main St.
Batavia, NY 14020
716-343-3040249 Highland Ave.
Rochester, NY 14620
716-461-10004487 Lake Ave.
Lockport, NY 14094
716-433-265120 South Main St.
P.O. Box 150
Albion, NY 14411
716-589-5561

May 14, 1981

Ronald J. Guido
Buffalo District, Corps of Engineers
1776 Niagara St.
Buffalo, N.Y. 14207

Dear Ron,

Thanks for sending a copy of the memorandum for record of the meeting regarding the Tonawanda Creek flood control project at your office on 7 April 1981. I believe the write up is accurate, but there are a couple of small changes which I would suggest. The first of these has to do with the note under table 3 on page 4. As you will note, the yields on the Erie and Niagara County portion of the summary are slightly lower than on the Genesee County portion. The reason we made this difference was because the soils are somewhat different in the Erie and Niagara flood plain of Tonawanda Creek. These soils were formed under shallow glacial lakes during the recession of the glaciers from Western New York, about 12,000 years ago. These lacustine or lake-laid soils are somewhat higher in clay content than the glacial till soils occurring in the Genesee portion of the Tonawanda Creek flood plain. These soils with the higher clay content are somewhat more difficult to manage and have poorer permeability than the soils which occur upstream. I believe that is the reason we made the yield potential slightly lower on the Erie and Niagara portion of the Tonawanda Creek flood plain. For that reason, I would suggest you change the second note to read "Erie and Niagara Counties are characterized by slightly different soil types with somewhat lower capability."

The same change would apply to the second note under table 4 on page 5 and also under 5 on page 5. I hope you understand the difference this makes in the input which we made to your project.

Another small change is in the paragraph between table 4 and table 5 on page 5. In the last sentence of that paragraph the word "optional" should be changed to "optimal". This was probably just a typographical error on the part of your office staff.

I am sending a copy of this to Bruce Tillapaugh and Doug Dettenrieder just to see if they concur with my opinion on the soil type differences.

I know that the Corps has been working on this project for many years. Hopefully sometime in the next few years it will become a reality. If the plan is ever implemented, I know there will be great benefits to the farmers in the flood plain of Tonawanda Creek as well as to many down stream rural and urban residents. Thanks for your continued interest in this project good luck in your efforts to advance it. Please let me know if you want to discuss this further.

Sincerely,

Nathan Herendeen
Nathan Herendeen
Regional Extension Specialist
c/ Bruce Tillapaugh
Doug Dettenrieder
Jack Carr

Cooperatives and Extension Service is an Equal Opportunity Program and Employment Opportunity. New York State College of Agriculture and Life Sciences, New York State College of Human Ecology, and New York State College of Veterinary Medicine at Cornell University. Cooperative Extension Associations, County Governing Bodies, and Under Sponsors Department of Agriculture cooperating.

May 18, 1981

Ronald J. Guido, Chief
Economics Section
Corps of Engineers
1776 Niagara Street
Buffalo, NY 14207


Dear Mr. Guido:

Thank you for your April 29, 1981 letter with the Memorandum for Record. I reviewed the report and find it to be correct. You accurately incorporated my comments into the report.

I am confident that the proposed project will benefit farmers, the City of Batavia and everyone in the area, therefore, I am very much in favor of the project. I am interested both as an area farmer for crop improvement and as Chairman of the Flood Study Committee designated by the Genesee County Legislation and Batavia City Council.

Please keep us informed of progress. We will be pleased to assist you in pushing this worthwhile project to completion.

Very truly yours,



Frank Gorecki, Chairman
Flood Study Committee
9070 Creek Road
Batavia, NY 14020

DL:am

cc: J. Woodruff, Chairman, G. County Leg.
I. Gates, City Admin.

juz 2273

WCBED-PC

3 June 1981

Dr. Shaw Reid
Professor of Soils
155 Emerson Hall
Cornell University
Ithaca, NY 14853

Dear Dr. Reid:

I have enclosed a copy of our evaluation of Agricultural activity on the Tonawanda Creek floodplain. A description of the Tonawanda Creek flood control project, and relevant correspondence used to support our evaluation is also enclosed.

I would appreciate your review of the enclosed portion of the Tonawanda Creek flood control report. The agricultural sector is our primary concern. Your comments in this area would be most appreciated.

A letter reply detailing the results of your independent review is desired. With your permission, your letter will be included in the documentation for the agricultural benefits credited to the Tonawanda Creek flood control project.

Since the economic evaluation is near completion I would appreciate your reply as soon as possible. If you have any questions please do not hesitate to contact Jack Carr, staff economist assigned to the Tonawanda Creek Flood Control project at (716) 876-5454, extension 2265. Thank you for your interest and participation in this study.

Sincerely,

2 Incls
as stated

RONALD J. GUIDO
Chief, Economics Section

WCBED-PC

Carr_____
Guido_____
Pieczynski_____



New York State College of Agriculture and Life Sciences
a Statutory College of the State University
Cornell University

Department of Agronomy
Bradfield and Emerson Halls, Ithaca, N. Y. 14853

June 11, 1981

Mr. Ronald Guido
Chief, Economics Section
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, NY 14207

Dear Mr. Guido:

I have reviewed the Agricultural section of the Tonawanda Creek flood control project. I would like to compliment the group of people who put together the planting dates, present yields, expected yields, (with project) and yields under prudent management conditions.

It is reasonable to expect that average yields of 100 bushels per acre is attainable in the Genesee County area and 90 bushels per acre is attainable in the Erie and Niagara area with flood control. This would be using the average technology as used by farmers today without additional costly inputs.

The values given for yields under ideal conditions are certainly attainable using the best technology that is available today. This would include additional drainage practices, maximizing use of fertilizers, lime, varieties and timing of operations. I would change the title of table 5 to Yields Under Optimal Conditions, because I would consider ideal conditions to be that best year out of 10 to 20 years when everything worked correctly for highest yields. In this case the yields could easily be over 150 bushels.

In your evaluation the yields are projected to 1995. There has been a historic increase in yields at about 2% per year that might be projected into the yields for about this time. The yields estimated for the project are those that a farmer might obtain using average 1980 techniques. It will require time for the farmers of the area to adopt these techniques, but at the same time there will be another increase in yields that will occur as a general increase in productivity which these farmers will adopt as well. In other words, they will gain in productivity faster than the average. The farmers in the flood area could not utilize all of the general increase in productivity without the flood control thus making a greater difference in their productivity.

Mr. Ronald Guido
Page 2
June 11, 1981

I would also predict that more than 50% of the idle agricultural land will move into agricultural production by 1995. Much of the idle land will be used to replace land lost to non-agricultural uses as well as to increase production on the farm. I would estimate that no more than 5% of the area would be as idle agricultural land by 1995 (if the project is completed by 1985).

This appears to be a project that is very beneficial to the economy of the area; therefore, we hope it can be successfully funded.

Sincerely,



W. Shaw Reid
Professor, Soils Science

WSR:ns



The Ohio State University

Department of
Agricultural Economics
and Rural Sociology

2120 Fyffe Road
Columbus, Ohio 43210

Phone 614 422-7911

June 12, 1981

John Carr, Staff Economist
Corps of Engineers, Buffalo District
1776 Niagara St.
Buffalo, New York 14207

Dear Mr. Carr:

Enclosed are some comments concerning the Tonawanda Creek Flood Control Study. Steve Yaksich asked that I review the study. Generally, I found the study to be well done. The methodology used to analyze the costs and benefits is used in an appropriate manner. Any investigator has to use numerous assumptions to complete a project analysis, and your assumptions seem reasonable.

I have the following specific suggestions about the study:

1. Yields (with project) and yields (without project) seem reasonable. The method used to arrive at these estimates is acceptable.
2. Land rent should not be included as a cost. While this is a cash outlay to the tenant, it is not an economic cost for the watershed (Tables S4-S9). This is essentially a transfer payment from operator to owner. Moreover, it is a fixed cost to the watershed.
3. What is included in "variable production costs". Is this equivalent to a custom rate for these operations plus costs of materials? This needs to be more explicit. Some of these costs look questionable. For example, harvest costs at \$24 per acre would seem to approximate a custom rate. This custom rate covers fuel, labor, repairs, insurance, maintenance, depreciation, interest, plus some profit. Some of these costs are fixed costs which are supposedly excluded.
4. Interest on operating capital is not included as a variable cost. This cost is likely to amount to \$3-\$9 per acre depending on the crop grown.


Mr. John Carr
page two
June 12, 1981

5. Another problem seems to be with the concept of "increase in gross profitability". (Table S-18). It assumes that all yield increases are realized at no additional costs. In fact, there are additional fertilizer costs and possibly additional harvesting, transportation, drying and interest costs. These costs would be on the order of \$10 per acre. Similarly, "change in gross profit/acre" (Table S25) is probably overestimated.
6. Your estimated "growth in future agricultural benefits" seems very modest, but I suppose it is best to err on the side of conservation. A minor point is that national "productivity gains" actually result in less agricultural income due to the inelasticity of demand for agricultural products. Any growth in agricultural benefits must be rationalized on the basis on increased foreign and domestic demand rather than increased productivity.

If these changes were made, the net agricultural benefits would probably decrease; however, the change would be small and the benefit - cost ratio would decline only slightly.

If you have any questions concerning these comments, please call me at (614) 422-2641.

Sincerely,



D. Lynn Forster
Associate Professor

DLF:sg

cc: Steve Yaksich

GENESEE COUNTY LEGISLATURE

GENESEE COUNTY BUILDING
Administrative Office

OFFICE OF THE CHAIRMAN
James E. Woodruff



Phone (716) 344-2550

BATAVIA, NEW YORK 14020

November 21, 1979 -

Colonel George P. Johnson
District Engineer
U. S. ARMY CORPS OF ENGINEERS
Buffalo District
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Johnson:

The Buffalo District Army Corps of Engineers held a meeting on November 8, 1979, in Batavia, New York at the Genesee County Building No. 2, for the express purpose of explaining their plan known as "The Batavia Reservoir Compound Modified." This plan appears to meet the approval of persons from the City of Batavia who had concerns about the location of the dam in the earlier proposal.

Approximately one-hundred people attended the meeting at County Building No. 2, of which a few had any objections. It appeared that the majority are in agreement with the proposal.

The meeting was conducted very well by CORPS personnel and most questions were answered.

I would also like to take this opportunity to thank you and your organization for your sincere endeavors to assist the County of Genesee on this project.

Very truly yours,

JAMES E. WOODRUFF
CHAIRMAN, GENESEE COUNTY LEGISLATURE

JEW/apc

November 20, 1979

Mr. Joseph Hassey
Project Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Sir:

As Chairman of the Tonawanda Creek Watershed Committee, I would like this letter to become a part of the record in regard to the planned "Batavia Reservoir Compound Modified" flood control project.

In attending the November 8th meeting in Batavia, which was conducted by the Corps of Engineers, it would seem quite evident that the vast majority were satisfied or in favor of the plans to control flooding along the Tonawanda Creek. I further believe that most people will agree on the need for flood protection today or the need will surely grow greater in the years ahead.

Very truly yours,



FRANK GORECKI
CHAIRMAN
TONAWANDA CREEK WATERSHED COMMITTEE

FG/apc

ERIE & NIAGARA COUNTIES



REGIONAL PLANNING BOARD

Leo J. Vavreck, Jr.
DIRECTOR

November 20, 1979

James L. Hynes
CHAIRMAN

James L. Hynes
CHAIRMAN

Joseph A. Williams
VICE CHAIRMAN

Mr. Joseph Hasey
Department of the Army
U.S. Army Corps of Engineers
Buffalo District
1776 Niagara Street
Buffalo, New York 14207

RE: Tonawanda Creek Watershed Study

Dear Mr. Hasey:

This office has reviewed the proposed Batavia Reservoir Compound Plan of the referenced study and has noted that some limited benefits will result to the Erie and Niagara Region. The Regional Board therefore supports the proposed plan, however, wishes to emphasize that a regional solution to the entire Tonawanda Creek Watershed is required in order to alleviate present and future flood damages. It must also be pointed out that the downstream reaches include the fastest growing areas in the watershed (Town of Amherst and Clarence) and that the present benefit to cost ratio may not be a true barometer of future needs.

The Regional Board therefore respectfully requests that other alternate plans such as diversion channels, channelization and smaller reservoir compound plans be addressed for the Erie and Niagara Region and supplement the Batavia Reservoir thus insuring a regional solution.

Very truly yours,

Henry C. Jawor
Henry C. Jawor, P.E.
Sanitary Engineer

HCJ:sw

TOWN OF BATAVIA
TOWN HALL
4165 WEST MAIN STREET ROAD
BATAVIA, NEW YORK 14020

FOUNDED 1802


January 10, 1976

Mr. Byron G. Walker
LTC. Corps of Engineers
Deputy District Engineer
Department of the Army
Buffalo District
1776 Niagara Street
Buffalo, New York 14207

Dear Mr. Walker:

We enclose herewith our master plan, existing zoning ordinance together with amendments for your information and reference in accordance to your letter sent to me on December 10, 1975.

Sincerely yours,


John T. O'Brien, Chairman
Town of Batavia Planning Board

JTO:w
ence.


2
FILE COPY

Checked by L

Filed by AL

DEPARTMENT OF PLANNING

PLANNING BOARD



3837 WEST MAIN STREET ROAD
BATAVIA, NEW YORK
PHONE (716) 341 1182

Gail Seemans CHM
Dominic Mancuso V. CHM
Dwight Wells DIR

December 16, 1975

Mr. Byron G. Walker
LTC, Corps of Engineers
Deputy District Engineer
1776 Niagara Street
Buffalo, New York 14207

Dear Mr. Walker:

Thank you for the information on the flood management control proposal for the Tonawanda Creek Watershed.

Alternatives 1 and 2 do not directly affect land in Genesee County. However, alternative 2 is important to our county because of its creation of a source of water which could be used in developing a countywide water supply system. We also feel that alternative 2 would provide necessary control of the level of the Tonawanda Creek as it flows north so as to reduce the spring flooding in lands in the Towns of Bethany and Alexander.

Alternative 3, which is on the Tonawanda Game Management Area, does not conflict in any way with land use planning as seen by the county planning department. We favor further development and resource conservation measures in the Tonawanda Game Management Area so as to maximize the opportunity for wildlife management and public utilization of that area for conservation/education activities.


Alternative 4, entitled the Batavia Reservoir Compound, does affect a rather substantial amount of land in the Town of Bethany. Present land use plans call for continuation of this land as agricultural. As examination would show that the creation of these compounds would reduce the annual flooding of the more extensive lands in the Towns of Bethany and Alexander, the county planning board would be supportive of such an approach. We also feel that the creation of these compounds could create a recreational area usable by people from all over Western New York. We feel that from a cost benefit analyses that alternative 4

DEPARTMENT OF PLANNING
should be given priority from the corps.

The proposal outline in alternative 5 would seem to fit nicely with alternative 4 for an overall program of flood control and recreational development for the area along the Tonawanda in the City and Town of Batavia.

We would appreciate receiving any further information as it becomes available and would be more than happy to work with the corps as it nears implementation of one or more of the alternatives.

Sincerely yours,



Dwight M. Wells, Director
Genesee County Dept. of Planning

DMW:vmn



County of Erie

EDWARD V. REGAN
COUNTY EXECUTIVE

DIVISION OF PLANNING

CHARLES O. BROWN
DIRECTOR

PHONE: 716 - 846-831

December 17, 1975

Bryon G. Walker, Deputy District Engineer
Department of the Army
Buffalo District Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Mr. Walker:

This is written in reference to your letter of December 1, 1975 regarding a draft environmental impact statement on a preliminary feasibility report entitled "Buffalo Metropolitan Area, New York, Water Resources Management Interim Report on Feasibility of Flood Management in the Tonawanda Creek Watershed."

You have requested basic information in knowing whether or not the various project alternatives will conform or conflict with the various land use plans, policies, controls, etc. of the indicated area.

In our evaluation of the various town master plans and zoning regulations of the effected towns in Erie County, the project should have no significant control on Erie County. None of the recommended alternates appear to have any detrimental effects upon land use development in this area, and the reduction of possible flood damage and the improvement of water quality will be beneficial.


Sincerely,

CHARLES O. BROWN
Director

sm

RIE & NIAGARA COUNTIES

Leo J. Nowak, Jr.
DIRECTOR



REGIONAL PLANNING BOARD

Donald P. La
CHAIRMAN

Susan R. Gre
VICE-CHAIRMAN

H. William De
SECRETARY

December 18, 1975

Byron G. Walker
LTC, Corps of Engineers
Deputy District Engineer
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Walker:

Thank you for your letter of December 1, 1975 requesting our comments and input to the Environmental Impact Statement on Flood Management in the Tonawanda Creek Watershed.

We are enclosing herewith a copy of the statement submitted by the Utilities Committee of the Regional Planning Board and given at the November 20, 1975 public meeting in Batavia, New York.

On November 18, 1975 Colonel Hughes wrote a letter regarding our presentation of the Tonawanda Creek Watershed Storm Drainage Proposals as recommended in our "Storm Drainage Management Plan", a copy of which the Buffalo District has in its files.

The Utilities Committee is meeting on December 18 at 10:00 a.m. in the Grand Island Town Hall. The committee will be reviewing this letter and has asked Colonel Hughes to attend their meeting to further discuss the differences between the Corps proposals and the RPB proposals and the problems caused through separate presentations. The Utilities Committee holds open meetings and anyone is free to attend. Should you desire to attend along with Colonel Hughes, please feel free to do so.

Very truly yours,

Leo J. Nowak, Jr.
Leo J. Nowak, Jr., Director

LJN:meg
Encs.

**Statement from the Utilities Committee of the Erie and Niagara Counties
Regional Planning Board Regard the U. S. Army Corps of Engineers
Alternative Plans for Flood Control on Tonawanda Creek to be given at
the Public Meeting in Batavia on November 20, 1975**

My name is Robert Floyd and I am here representing the Utilities Committee of the Erie and Niagara Counties Regional Planning Board.

The Board has completed a Storm Drainage Study covering the major watersheds of Erie and Niagara Counties. This study was funded by a grant from the U. S. Dept. of Housing and Urban Development. The region was divided up into 15 major watersheds, one of which is the Tonawanda Creek Watershed which the Corps of Engineers has presented here tonight. We are presently in the process of showing alternative solutions to the flooding problems as determined by the study and requesting public comments thereon.

On completion of the public presentations, the RPB expects to adopt a storm drainage plan and program consisting of a map and a report covering both Erie and Niagara Counties.

The plan and program now being presented by ENCRPB for Tonawanda Creek consists of a recommended plan and 4 alternatives, which identifies areas in need of flood protection in Erie and Niagara Counties along Tonawanda Creek.

The recommended plan calls for a two phase program the 1st phase being the construction of a floodway or diversion channel from the Barge Canal east to Transit Road with levees along Transit Road to divert the Black Creek flow to the diversion channel. Second stage construction will extend the diversion channel from Transit Road east to Tonawanda Creek with another levee in the

construction of the Alabama Pools should the need ever arise. Land use controls are also included in this solution.

Alternative No. 1 consists of individual protection such as construction allowed only above the 100 year flood level and then through the use of detention ponds by the developers to prevent further damages downstream due to the increased runoff generated.

Alternate No. 2

Excavation of Existing Channel: Tonawanda Creek would be deepened upstream from Mud Creek (mile 13.0 to 13.6) and near Rapids (mile 17.6 to 19.4). Low levees would be constructed across the Tonawanda-Black Creek Divide near Beeman Creek.

Alternate No. 3

Excavation of Existing Channel Combined with Alabama Pools: Alternative 2 would be combined with two inches of flood control storage over the upper Tonawanda Creek Watershed in the proposed Alabama Pools. The proposed Alabama Pools are located on the Erie-Genesee County line off-channel north from Tonawanda Creek. Low levees would be constructed across the Tonawanda-Black Creek divide.

Alternate No. 4

Complete Flood Plain Zoning: The entire broad flat flood plain would be used for non-flood vulnerable use.

In reviewing the U. S. Army Corps of Engineers alternative projects, we note the following:

2. The Alabama Pools solution but with modifications to the present Batavia Flood Control Project and without the levee and channelization projects in the Towns of Clarence and Newstead in Erie County.
3. The addition of Sierks and Linden Reservoirs a possible solution but with less protection especially in the downstream reaches.
4. The Alabama Pool solution but with Sierks Reservoir in lieu of the downstream levees and channelizations.
5. The no action and no structural action alternatives have been ruled out because they fail to meet the flood protection needs of the watershed.

The Utilities Committee of the RPB would like to go on record here tonight that the Corps of Engineers include in the next step of the study process the following:

1. Inclusion of the two phase Black Creek Diversion Channel Alternative as recommended in the RPB's Storm Drainage Management Study. This Study shows \$276,000 annual cost versus \$365,000 for the proposed study presented here tonight.
2. Inclusion of the no action alternative as required by the NEPA act.
3. The Alabama Pools alternate with the use of levees and channelization as shown in the RPB's Storm Drainage Study as an alternative to its recommended plan.
4. That the corps define the 100 year flood prone area and indicate through mapping the areas which will be no longer flooded for each of the alternatives studied.

ORLEANS COUNTY PLANNING BOARD

Court House Square
Albion, New York 14411

Mr. Byron G. Walker
LTC, Corps of Engineers
Deputy District Engineer
Buffalo District
1776 Niagara St.
Buffalo, N.Y. 14207

Dear Mr. Walker:

This is in response to your December 1 letter to Mr. Pahura regarding the Tonawanda Creek Watershed Management Feasibility interim report.

We appreciate your willingness to let us respond although this proposed flood mangement program has a relatively minor impact on Orleans County.

The only proposed area of impact involves lands in the extreme southwest corner of our county where Niagara and Genesee Counties abut Orleans.

Most of the land in question is part of the Oak Orchard Swamp and is under federal management. The County Planning Board's Preliminary Land Use Plan calls for continued protection of these lands as a natural wildlife refuge. Other areas, adjacent to Oak Orchard Swamp are designated as resource management areas.

The Shelby Township zoning ordinance designates other adjacent areas as agricultural use districts. However, the residential use district is defined in the ordinance as follows: "...For the purpose of this Ordinance those lands in the Agricultural Use Districts which are adjacent, opposite or within three hundred (300) feet, measured along the road frontages on both sides of the road, to a premise on which a one or two family dwelling, other than a farm dwelling, has been or may in the future be established shall be a Residential Use District and shall be subject to the provisions of this Ordinance applicable to the Residential Use Districts."

In effect this ordinance allows for and encourages the strip development of all roadways in the Town of Shelby. The County Planning Board opposes strip development of any nature. However, it is a fact of which you should be cognizant as it appears there are local roadways which are located in that area of Orleans County which was defined in Plate 1 of your interim report.

To date I have not had the opportunity to involve the Town of Shelby in any of my deliberations on this matter but I feel it proper that you also give the Town an adequate opportunity to respond if you have not already done so.

If I can be of any further assistance feel free to contact me.

Sincerely,

Geoffrey C. Astles
Geoffrey C. Astles
Planner

GCA:J

The Committee is concerned that certain areas are developed and are developing in Erie and Niagara Counties and in order to place sufficient information in the hands of the residents affected that all alternatives possible and their impact be clearly defined so that adequate public opinion can be secured and a final solution justified to the satisfaction of the public.

The Utilities Committee thanks the Corps for the opportunity to present this statement and also expresses a continuing interest in the project and desires to participate to its fullest extent. Thank you Col. Hughes.

DISPOSITION FORM

For use of this form, see AR 340-15; the proponent agency is The Adjutant General's Office.

REFERENCE OR OFFICE SYMBOL

NCBED-PN

SUBJECT

Workshop for Local Officials on Tonawanda Creek Flood
Damage Management

TO

☒ FILES

FROM

P. Markham

DATE

4 May 76

CMT 1

Markham/ds/231

1. Time: 12 April 1976, 1:30 p.m.
2. Place: Legislative Chambers, Genesee County building, Main and Court Streets, Batavia, NY.
3. Participants: Local officials of the county, city, village and towns located in the upstream flood plain. See Inclosure 1 for complete list of invitees and participants. Corps representatives were Don Liddell, Chief, Engineering Division; Jack Jurentkuff, Planner; Charlie Baldi, Project Manager; and Paula Markham, Public Involvement Specialist.
4. The purpose of the workshop was to describe to local officials the impacts, costs and benefits of the Batavia Reservoir Compound, and to hear their comments on the Compound proposal.
5. Don Liddell opened the meeting with a review of the various flood control measures considered by the Corps for the Tonawanda Creek watershed. He explained that some measures, e.g Sierks and Linden reservoirs, were no longer being considered because of their high costs, limited protection and severe environmental problems. Mr. Liddell described the operation of the Batavia Reservoir Compound and then opened the meeting for comments and questions.
6. Mr. Robert Beats, Mayor of the village of Alexander, asked about protection for the village of Alexander and suggested that the Corps consider relocating the creek to the east, in the area just upstream from the Batavia Reservoir Compound, to prevent flooding and erosion damage of property along Rt. 98.
7. No serious objections to the Batavia Reservoir Compound were expressed by local officials.
8. The meeting ended at 2:30 p.m.

Incl
as

Paula T Markham

PAULA MARKHAM
Public Involvement Specialist

Persons Invited
Tonawanda Creek Workshop 12 April 1976

Lewis Del Plata	Genesee County Legislator
James Hume, Jr.	Genesee County Legislator
James Woodruff	Genesee County Legislator
Joseph Amedick, Jr.	County Highway Superintendent
Henry Mosbaugher	Genesee County SCD
Duane Ivison	Chairman, Genesee County Soil & Water Conservation District
Michael Stevens	Genesee County Department of Planning
Dwight M. Wells	Director, Genesee County Department of Planning
Raymond T. Babcock	Supervisor, Town of Batavia
	Town Clerk, Town of Batavia
Robert Smart	Town of Batavia Highway Superintendent
John O'Brien	Chairman, Batavia Town Planning Board
Ira Gates	City Administrator, City of Batavia
Roy Worthington	Supervisor, Town of Alexander
	Town Clerk, Town of Alexander
Donald Shaw	Town of Alexander Highway Superintendent
	Village Clerk, Village of Alexander
Robert Beats	Mayor, Village of Alexander
Gerald D. Post	Town Assessor, Town of Alexander
Norman Nichols	Supervisor, Town of Bethany
	Town of Bethany Highway Superintendent
William Surrey	U. S. Soil Conservation Service

Participants
Tonawanda Creek Workshop 12 April 1976

James Hume, Jr.	County Legislator
James Woodruff	County Legislator
John Carragher	County Legislator
Joseph Amedick, Jr.	County Highway Superintendent
Russ Felski	County Highway Department
Catherine Roth	Councilman, City of Batavia
Dennis Larson	City Engineer, City of Batavia
Donald Shaw	Town of Alexander Highway Superintendent
Robert Beats	Mayor, Village of Alexander
Harold Norton	Town of Bethany Highway Superintendent
William Surrey	District Conservationist, U. S. SCS
Michael Stevens	Genesee County Planning Department
John O'Brien	Town of Batavia Planning Board
Dwight Wells	Genesee County Planning Board
Henry Jawor	Erie & Niagara Counties Regional Planning Board
Gregg McAllister	Batavia Daily News

DISPOSITION FORM

For use of this form, see AR 340-15; the proponent agency is The Adjutant General's Office.

REFERENCE OR OFFICE SYMBOL

NCBED-PN

SUBJECT

Summary: Workshop for Downstream Officials on Tonawanda Creek Flood Damage Management

TO ☒ FILES

FROM P. Markham

DATE 4 May 76
Markham/ds/231

CMT 1

1. Time: 20 April 1976, 7:30 p.m.
2. Place: Pendleton Town Hall, 6570 Campbell Blvd., Town of Pendleton.
3. Participants: Officials and planning board members from the city, towns and villages in the downstream flood-prone area. See Inclosure 1 for complete list of invitees and participants. Corps representatives were Don Liddell, Chief, Engineering Division; Jack Jurentkuff, Planner; and Paula Markham, Public Involvement Specialist.
4. Purposes of the workshop were:
 - a. To describe the Batavia Reservoir Compound to downstream officials and get their reactions to the plan.
 - b. To determine whether there is any local interest in non-structural measures that could reduce flood damages in the downstream area.
5. Don Liddell opened the workshop with a review of the various flood control measures considered by the Corps for the Tonawanda Creek Watershed. He explained why the Batavia Reservoir Compound is the most promising, and described its impacts, costs and benefits. He also mentioned floodproofing, flood-insurance, and other non-structural measures for the downstream area, but emphasized that we don't know what the Federal share of non-structural costs would be.
6. After Mr. Liddell's presentation, the meeting was opened for discussion. The following points were raised:
 - a. One man expressed the opinion that flooding in the lower floodlands has become worse in recent years because the creek is clogged up with brush, and asked if the Corps had considered improving drainage in the area by clearing and improving the creek channel. Mr. Liddell explained that channel ^{improvement} movement had been considered, but rejected as too costly and environmentally unsound.
 - b. Mr. Bob Floyd from the Erie and Niagara Counties Regional Planning Board said that ENCRPB was in favor of the Batavia Reservoir Compound, but would like to see additional measures incorporated into the plan to provide more protection for Erie and Niagara Counties.
 - c. Mr. Floyd suggested a meeting between representatives of ENCRPB and the Corps to discuss plans that ENCRPB has already developed.
 - d. Mr. Floyd stated that he would like the Corps to develop a topographic map showing the reduced flooding in Erie and Niagara Counties that could be expected if the Batavia Reservoir Compound were built.

DA FORM 2496

REPLACES DD FORM 98, EXISTING SUPPLIES OF WHICH WILL BE
ISSUED AND USED UNTIL 1 FEB 03 UNLESS SOONER EXHAUSTED

☆ U.S. GPO: 1974-858-130/9888

NCBED-PN

SUBJECT: Workshop for Downstream Officials on Tonawanda Creek Flood
Damage Management

7. Local officials expressed little interest in floodproofing, flood insurance and other non-structural measures.

8. The workshop broke up into individual discussions that lasted until about 9:15 p.m.

Paula T. Markham

Incl
as

PAULA MARKHAM
Public Involvement Specialist

Persons Invited
Tonawanda Creek Workshop 20 April 1976

James V. Ryan	Supervisor, Town of Tonawanda
William Wittkowsky	Mayor, City of North Tonawanda
Ferdinand Castiglione	City of North Tonawanda Planning Board
Jack Sharp	Supervisor, Town of Amherst
Clifford McDaniel	Town of Amherst Planning Board
Robert V. Maerten	Supervisor, Town of Pendleton
Joseph Bors	Town of Pendleton Planning Board
Floyd Snyder	Supervisor, Town of Lockport
Richard McFarland	Town of Lockport Planning Board
	Supervisor, Town of Clarence
Donald Smith	Town of Clarence Planning Board
George Hyder	Supervisor, Town of Newstead
Dante Marconi	Town of Newstead Planning Board
George E. Steimer, Jr.	Supervisor, Town of Royalton
Louis Gillmeister	Town of Royalton Planning Board
Charles J. Ritecz	Mayor, Village of Akron
Elmer Ottney	Village of Akron Planning Board
John McMahon	NYS Department of Environmental Conservation
Charles Brown	Erie County Planning
Robert Floyd	Erie & Niagara Counties Regional Planning Board
Larry Cartwright	Supervisor, Town of Pembroke
Chief Corbett Sundown	Tonawanda Indian Reservation

Participants
Tonawanda Creek Workshop 20 April 1976

Robert Floyd	Erie & Niagara Counties Regional Planning Board
John Krol	Town of Amherst Planning Department
Margaret Spaulding	Town of Clarence Planning Board
Lawrence Herberger	Town of Clarence Planning Board
Floyd D. Snyder	Town of Lockport Supervisor
G. B. McDowell	Town of Pendleton
Andy Johnson	Town of Pendleton
George Mason	Town of Pendleton
Joe Bors	Town of Pendleton
Bob Wurtenberger	Town of Pendleton
Burton Lenhart	Town of Pendleton
Louis Gillmeister	Town of Royalton Planning Board
Peter Buechi	NYS DEC, Buffalo

BUFFALO METROPOLITAN AREA, NY
WATER RESOURCES MANAGEMENT STUDY

TONAWANDA CREEK WATERSHED
INTERIM FLOOD MANAGEMENT STUDY

FINAL FEASIBILITY REPORT

APPENDIX H

ENVIRONMENTAL

U. S. Army Engineer District, Buffalo
1776 Niagara Street
Buffalo, New York 14207

APPENDIX H

ENVIRONMENTAL APPENDICES

PART 1 - Comment Letters on the 1976 Draft Environmental Impact Statement and Corps of Engineers Responses.

PART 2 - Fish and Wildlife Mitigation Analysis.

PART 3 - Correspondence from the U.S. Fish and Wildlife Service and New York State Department of Environmental Conservation.

PART 4 - Cultural Resources Coordination.

APPENDIX H, PART 1

COMMENT LETTERS ON THE
1976 DRAFT ENVIRONMENTAL IMPACT
STATEMENT AND CORPS OF ENGINEERS
RESPONSES

H.1.1 Draft Environmental Impact Statement Coordination - The Draft Environmental Impact Statement presenting the Batavia Reservoir Compound as the selected plan was distributed to the agencies, individuals, and groups listed below for review and comment on 4 May 1976. At the same time, the DEIS was filed with the Council on Environmental Quality and notice of availability was recorded in the Federal Register dated 14 May 1976 commencing the official 45-day review period.

Federal Energy Administration
U. S. Department of Health, Education and Welfare, Region II
U. S. Environmental Protection Agency
 Region II Office
 Rochester Field Office
U. S. Department of Interior
 Office of Environmental Project Review
 Bureau of Indian Affairs
U. S. Department of Commerce
U. S. Department of Transportation
U. S. Soil Conservation Service
U. S. Forest Service
U. S. Department of Housing and Urban Development
U. S. Bureau of Outdoor Recreation
Great Lakes Basin Commission
Federal Highway Administration, Region I
Honorable J. L. Buckley, U. S. Senator
Honorable B. B. Conable, Jr., U. S. Representative
Honorable Jack Kemp, U. S. Representative
Honorable Henry J. Nowak, U. S. Representative
Advisory Council on Historic Preservation
National Park Service
New York State Department of Transportation
New York State Parks and Recreation Department
 Director of Environment Management
 Bureau of Recreation Planning
New York State Office of Planning Services
New York State Historic Preservation Officer
New York State Department of Commerce
 Program Planning Analyst
 Division of Industrial Services and Technologies
New York State Department of Transportation
 Office of Planning and Development
 Program Analysis Bureau
New York State Urban Development Corporation
 Program Development Division
 Project and Environmental Impact Statement Review
New York State Department of Environmental Conservation
 Office of Environmental Analysis
 Director of Water Resources Planning
New York State Department of Health
Sierra Club - Niagara Group
Trout Unlimited (Western NY Chapter)

Izaak Walton League of America
League of Women Voters (Erie Co.)
League of Women Voters (Genesee Co.)
League of Women Voters (Niagara Co.)
Buffalo Audubon Society
The National Wildlife Federation
Northwestern University (Center for Urban Affairs)
National Audubon Society (Central Midwest Regional Office)
Center for Environmental Management (Cornell University)
Erie-Niagara Counties Regional Planning Board
Erie County Department of Planning
Genesee County Department of Planning
Attica Town Planning Board
Batavia City Planning Board
Batavia Town Planning Board
Pembroke Town Planning Board
Stafford Town Planning Board
Genesee County Health Department
Department of Environmental Quality of Erie County
Erie County Laboratory (Public Health Division)
Tonawanda Indian Reservation
Mr. Koichiro J. Yagi, (SUNY)
Dr. James R. Spotila, (SUC)
Ms. Kathleen Hassan
Dr. Wayne Hadley, (SUNY)

H1.2 Comment - Response - The commenting letters on the Draft Environmental Impact Statement for the Tonawanda Creek study and corresponding Corps response appear on the following pages. Each commenting letter has been separated into specific comments and numbered along the left hand margin of the letter. Corps responses to each comment can be found by referring to the corresponding number to the right of each letter of comment.

H1.3 This FEIS has been completely rewritten and is in a different format than the DEIS. As such, it complies with the Council on Environmental Quality "Regulations for Implementing the Procedural Provisions of the National Environmental Policy Act" 40 CFR 1500-1508 dated 29 November 1978 and Corps of Engineers Regulation ER 200-2-2 dated 25 August 1980. Complying with these new regulations considerably streamlined the amount and content of information and data contained in the Tonawanda Creek FEIS when compared to the DEIS. Most of the following comment letters to the DEIS refer to paragraph numbers and data which no longer exist in the FEIS. Responses have been provided as completely as possible considering this situation.

Great Lakes Basin Commission

Frederick K. D. Rouse
Chairman
3475 Plymouth Road
Post Office Box 999
Ann Arbor, Michigan 48106
313/763-3590 FTS 374-5431

CORPS RESPONSES TO THE GREAT LAKES BASIN COMMISSION
(Letter Dated 13 May 1976)

May 13, 1976

Mr. Byron G. Walker, LTC
Deputy District Engineer
Buffalo District
U.S. Department of the Army
1776 Niagara Street
Buffalo, New York 14207

Dear Mr. Byron Walker:

We appreciate the opportunity to review and comment on the draft Environmental Impact Statement on the proposed project for flood control in the Tonawanda Creek Watershed, New York, as enclosed in your letter of May 4, 1976. We have reviewed the draft Environmental Impact Statement and find that we have no substantive comments to make at this time.

The final report of the Great Lakes Basin Framework Study will be completed around October 1976. While the final Report will contain general recommendations for the Great Lakes Basin, it will not include recommendations for site-specific projects.

Sincerely,

Robert W. Reed
Robert W. Reed
Water Resources Planner

1. No response necessary.

2. No response necessary.

State of Illinois	Department of Health, Education and Welfare	Commonwealth of Pennsylvania	Department of State
State of Indiana	Department of Housing and Urban Development	State of Wisconsin	Department of Transportation
State of Michigan	Department of the Interior	Great Lakes Commission	Energy Research and
State of Minnesota	Department of Justice	Department of Agriculture	Development Administration
State of New York		Department of the Army	Environmental Protection Agency
State of Ohio		Department of Commerce	Federal Power Commission



U. S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION
REGION ONE
New York Division Office
Leo O'Brien Federal Building, Ninth Floor
Albany, New York 12207

CORPS RESPONSES TO THE U. S. DEPARTMENT OF TRANSPORTATION
(Letter dated 27 May 1976)

May 27, 1976
IN REPLY REFER TO:
01-36.2

Mr. Byron G. Walker
Deputy District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Mr. Walker:

We have reviewed the Draft Environmental Impact Statement on Flood Management in the Tonawanda Creek Watershed, transmitted with your May 4, 1976 letter, and offer the following comments:

In general, greater protection will be afforded to the various Federal-aid highways in the project area as a result of the proposed construction. However, two important area routes, State Route 98 and U.S. 20, might be subject to more frequent flooding after the upper reservoir is constructed.

The final environmental impact statement should specifically address the changes in flooding frequency on these two routes if the project is implemented. If the frequency does increase, then the grade of these two routes should be raised to provide the same protection as now exists.

1. The Corps concurs that greater protection will be afforded to the various Federal-aid highways in the project area as a result of the proposed project.

2. Based on available information, the present design of the upper reservoir should decrease the frequency of flooding on State Route 98 and Federal Route 20. However, should the Corps determine during further study that the present design would increase the frequency of flooding on these two highways, then the Corps would change the design or raise the roads, or both, so that the frequency of flooding would be no greater than now.

Sincerely yours,

Victor E. Taylor
Victor E. Taylor
Division Administrator



United States Department of the Interior

BUREAU OF INDIAN AFFAIRS
EASTERN AREA OFFICE
1951 Constitution Avenue NW,
Washington, D.C. 20245

IN REPLY REFER TO:

CORPS RESPONSE TO THE U.S.D.I. - BUREAU OF INDIAN AFFAIRS
(Letter dated 4 June 1976)

JUN 4 1976

Colonel Bernard C. Hughes
District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hughes:

Reference is made to the Draft Environmental Impact Statement on the proposed Project for Flood Control in the Tonawanda Creek Watershed.

This office has determined that the Batavia Reservoir Compound, the selected plan, will have no adverse impact on Indian Trust land.

Sincerely yours,

Harry A. Rainbolt

Harry A. Rainbolt
Area Director, Eastern Area Office

1. No response necessary.





United States Department of the Interior

BUREAU OF MINES

4800 FORBES AVENUE
PITTSBURGH, PENNSYLVANIA 15213

CORPS RESPONSES TO THE U.S.D.I. - BUREAU OF MINES
(Letter dated 4 June 1976)

June 4, 1976

Colonel Bernard C. Hughes
District Engineer
Buffalo District, Corps of Engineers
Department of the Army
1776 Niagara Street
Buffalo, New York 14207

Dear Sir:

Re: Draft Environmental Statement for the Interim
Report on Feasibility of Flood Management in
Tonawanda Creek Watershed; Erie, Genesee, Niagara,
and Wyoming Counties, New York

We have reviewed the draft environmental statement concerning the construction of two detention dams in Genesee County, New York, for the purpose of flood control.

Mineral resources occurring in the project area are sand and gravel, limestone, dolomite, and gypsum, of which only sand and gravel is currently being produced, while limestone, gypsum, and natural gas are produced outside the project area.

The project should have little effect on the recovery of mineral resources or mineral potential of the area. The statement satisfactorily describes impact of the project on minerals. We therefore offer no suggestion for revision or addition to the statement.

1. No response necessary.

2. No response necessary.

Sincerely yours,

Robert D. Thomson, Chief
Eastern Field Operation Center



CORPS RESPONSES TO THE SIERRA CLUB - NIAGARA GROUP
(Letter dated 7 June 1976)

June 7, 1976

LTC. Byron G. Walker
Department of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Walker:

R. Blake Reeves, Chairman of the Sierra Club-Niagara Group, asked me to reply to your letter regarding the Draft Environmental Impact Statement on the proposed project for Flood Control in the Tonawanda Creek Watershed.

Sierra Club-Niagara Group would like to reserve the right to comment and we intend to do so. Thank you for keeping us informed.

Yours truly

Antonia Deepster

Antonia Deepster
Sierra Club-Niagara Group

1. No response necessary.

2. The Corps will continue to coordinate proposed projects with the Sierra Club.



DEPARTMENT OF HEALTH, EDUCATION, AND WELFARE

REGION II
FEDERAL BUILDING
28 FEDERAL PLAZA
NEW YORK, NEW YORK 10009

CORPS RESPONSES TO THE U. S. DEPARTMENT OF
HEALTH, EDUCATION AND WELFARE
(Letter dated 8 June 1976)

OFFICE OF THE
REGIONAL DIRECTOR

June 8, 1976

Mr. Bernard C. Hughes
Department of the Army
Buffalo District, Corps
of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Mr. Hughes:

Subject: EIS #020-05-76
Interim Report on Feasibility of Flood Management
Tonawanda Creek Watershed

On the basis of our review of the above we have determined that the impacts in those areas of concern to this Department have been adequately addressed.

We would however, suggest that since an expected result of this project will be increased development in areas previously designated as flood plain, efforts should be undertaken to initiate local/regional planning to assure that the growth patterns will be orderly.

We appreciate the opportunity to review your Draft EIS.

Sincerely yours,

Luther W. Stringham

Luther W. Stringham
Regional Environmental Officer

1. No response necessary.

2. Those areas within the present 100-year floodplains must be regulated in accordance with the National Flood Insurance Program. Until the Batavia Reservoir Compound is constructed, the status of these lands, under the program, cannot be changed. Development must comply with requirements of the program.

All communities having lands which would be protected from the 100-year flood by the Batavia Reservoir Compound have plans for use of these lands. Although these communities would probably change their plans for lands to be protected, it is not expected that they would do so until design and construction of the Batavia Reservoir Compound is certain. This would not be the case for at least several years.

ROBERT V. MAERTEN

DEPUTY SUPERVISOR
TOWN OF PENDLETON

6576 CAMPBELL BLVD.

LOCKPORT, NEW YORK 14094

CORPS RESPONSES TO THE TOWN OF PENDLETON
(Letter dated 17 June 1976)

June 17, 1976

Department of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Attention: Mr. Bernard C. Hughes
Colonel, Corps of Engineers

Gentlemen:

In re: Tonawanda Creek Watershed

In reply to your letter of May 24, 1976, please be advised
that I am in favor of the construction of the Batavia Reservoir Com-
pound.

I am extremely pleased that something is being done to
alleviate regional flooding problems in the Tonawanda Creek Watershed
and to prevent the possibility of any flooding in our Town.

Very truly yours,

Robert V. Maerten
Robert V. Maerten
Deputy Supervisor

1. No response necessary.

2. The Corps will continue to maintain coordination of the proposed
project with the town of Pendleton.



UNITED STATES
DEPARTMENT OF THE INTERIOR
FISH AND WILDLIFE SERVICE
For Office and Conference Building
BOSTON, MASSACHUSETTS 02108

CORPS RESPONSES TO THE USDI - FISH AND WILDLIFE SERVICE
(Letter dated 17 June 1976)

ER-76/456

JUN 17 1976

Colonel Bernard C. Hughes, District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hughes:

The following comments are provided in response to your letter of May 4, 1976, to Mr. John W. Larson requesting comments on the draft environmental statement for the proposed Flood Control project in the Tonawanda Creek Watershed, New York. Since this document will provide a basis for future congressional action, the Department will be asked to review and comment at a later date by the Chief of Engineers. Our comments are provided as field level review and are not the comments of the Department of the Interior.

The U. S. Fish and Wildlife Service reviewed the proposed project and provided a report to the District Engineer, Buffalo District, on January 28, 1976, recommending the Batavia Reservoir Compound as being the least environmentally damaging alternative. We appreciate the Corps of Engineers' selection of this alternative and find that, in general, the draft environmental statement adequately describes the proposed project's impacts on fish and wildlife resources. The following specific comments on the statement are offered for your consideration.

Paragraphs 1.03-1.04 state that the upper and lower reservoirs of the Batavia Reservoir Compound will involve the removal and purchase of eight residences. These residences are possibly located within the headwater fringe of the upper reservoir flood pool. However, in Section 4, Paragraph 4.02, it is stated that about 32 residences and

1. No response necessary.

2. No response necessary.

3. As the project has been changed slightly since the DEIS was circulated, all references to required relocations of residences have been changed in this FEIS. The project now requires relocation of 22 residences. The costs of relocations have been included in cost estimates for the project. The entire cost of the project is a Federal responsibility.



farsteads within the limits of the maximum probable flood pools of the Batavia Reservoir Compound would be relocated. The disparity between the number of residences being relocated should be clarified. Also, there should be further clarification as to who is responsible for the purchase and relocation costs of the residences. If the federal government is responsible, this should be stated and the costs should be presented in your economic data in Appendix C.

Paragraphs 2.28-2.29 state that cursory on-site field observations of vegetation in the vicinity of the Batavia Reservoir Compound were made during October 28-29, 1975. Further detailed field observations are necessary, particularly in determining the types of vegetation present in areas of the proposed dikes, including the short-height dikes, where existing vegetation removal will occur. This section should also address any effect the proposed project's construction and location of dikes will have on the Christmas Fern (*Aspidium acrostichoides*), a native plant protected pursuant to Section 9-1503 of the Environmental Conservation Law, listed in Table 28. Further, it would be beneficial if a map was included showing the location, extent, and importance of the wetland areas found within the Batavia Reservoir Compound site.

Paragraphs 2.31-2.33 discuss fish samplings taken at various stations along Tonawanda Creek. Except for the early winter fish survey conducted by Corps ecologists on December 4, 1975 when much of the creek was inaccessible, all other fish samplings were taken at areas outside the Batavia Reservoir Compound site. In order to determine the possible effects of the proposed project on the area's fishery, further fish survey work should be conducted on Tonawanda Creek in the proposed Batavia Reservoir Compound site.

Paragraph 2.34 states that bird species presented in Table 2K were the result of observations made on an October 28-29, 1975 field reconnaissance survey. Further surveys conducted during spring and early summer would be beneficial since bird migration on the Niagara Frontier reaches its peak at this time.

Paragraph 2.37 mentions that there are a number of significant wetland areas within the Batavia Reservoir Compound site. As presented in our discussion on Paragraphs 2.28-2.29 a map showing

CORPS RESPONSES TO THE USDI - FISH AND WILDLIFE SERVICE (Cont'd)
(Letter dated 17 June 1976)

4. In response to the need for additional biological field data, the Buffalo District and the Cortland Field Office of the U. S. Fish and Wildlife Service conducted joint field studies of the area during the spring and summer of 1979. The results of these studies are presented in the USFWS Coordination Act Report (Appendix H, Part 3). Copies of other biological field studies (fisheries, wetlands, invertebrates) conducted for the Tonawanda Creek Flood Control Study are available from the Buffalo District. No impacts of the flood control project on the Christmas Fern were identified during the biological field studies.

5. Refer to Response 4 above. Additional field studies on the fisheries of Tonawanda Creek within the proposed project area were conducted during 1979. A report discussing the results of these fishery studies is available from the Buffalo District on request.

6. Additional data has been provided in the USFWS Coordination Act Report (Appendix H, Part 3).

7. A wetland location map (Source: 1950 USGS Batavia South, NY, Quadrangle, series V821) is available from the Buffalo District on request.

Copy available to DTIC does not
permit fully legible reproduction

CORPUS RESPONSES TO THE USDI - FISH AND WILDLIFE SERVICE (Cont'd)
(Letter dated 17 June 1976)

the location of these wetland areas would be very helpful.

Paragraph 2.17 uses the 1973 edition of "Threatened Wildlife of the United States," published by the Fish and Wildlife Service, U. S. Department of the Interior as a reference source. This publication is no longer considered an official list, since it is neither accurate nor current. The present U. S. Department of the Interior, Fish and Wildlife Service official list of "Endangered and Threatened Wildlife and Plants" was published in the Friday, September 26, 1975, Federal Register. It includes the reclassification of the American Alligator and other amendments. Please find a copy attached.

Paragraph 4.20 states that wetlands in the lower reservoir would be subject to less frequent flooding with implementation of the proposed project. This paragraph should discuss in more detail the location and significance of these wetlands, particularly concerning the effects less frequent flooding will have on nesting and breeding areas of waterfowl and avian species, as well as pheasant wintering areas within the lower reservoir compound.

Paragraph 4.21 states that the construction of dikes for the proposed project would involve the filling of approximately eight acres of wetland in the existing floodplain. Does the eight-acre loss of wetlands include any further possible loss that may occur from access roads for movement of materials or equipment? Again, the significance of a loss of eight acres of wetland on the winter cover and nesting habitat for wildlife within the Batavia Reservoir Compound should be addressed in greater detail.

Paragraph 4.24 states that the proposed construction of dikes and the emergency spillway would require stripping about 73 acres. This paragraph should identify whether the stripping of 73 acres includes any possible vegetation removal resulting from access roads for movement of materials or equipment.

Paragraph 4.25 discusses the removal of debris jams and snags from Tonawanda Creek within the Batavia Reservoir Compound. This paragraph should address the probability and extent of removal of bank side vegetation during debris and snag removal. Every effort should be made to preserve vegetation along the banks of Tonawanda Creek within the project area, since removal will reduce shaded stream sections, resulting in increased water temperatures.

Copy available to DTIC does not
permit fully legible reproduction

8. The most recent list of endangered species has been consulted and new information on endangered species has been discussed in this FEIS.

9. Considerable discussion of the impacts on wetlands and wildlife in the lower reservoir is provided in the mitigation analysis (Appendix H, Part 2) and the USFWS Coordination Act Report (Appendix H, Part 3).

10. The present approximate estimate of wetland acreage impacted, which is 75 acres for the modified Batavia Reservoir Compound, includes those lands on which dikes and dams would be proposed for construction and clearing and snagging areas. At this stage of planning in the engineering feasibility study, specific locations of access roads have not been determined. It is reasonable to assume that some further temporary disturbance or loss of land might occur from access roads. Most likely, such access road locations would be over terrestrial land rather than through wetlands. If this proposed project is authorized and funded for detailed design, avoidance of existing wetland areas for access roads would be assured. Additional data on winter cover and resting habitat has been provided in Appendix H, Parts 2 and 3 of this FEIS.


11. Since the sizes and locations of access roads have not been specifically defined in this phase of the Corps planning effort for the proposed project, the stripping estimate (refer to the design appendix) for the modified project, does not include allowance for access roads. The acreage estimate would be updated during advanced engineering design, if and when the project is authorized by Congress.

12. Access to debris jams and snags by construction equipment would unavoidably destroy some natural vegetation along the creek banks. Extent of debris and snag removal has not been specifically determined yet. As suggested by the U. S. Fish and Wildlife Service, every effort will be made to preserve bank vegetation along Tonawanda Creek in the project area. Site specific removal of debris and snags in the creek would probably be done by use of heavy equipment on one side of the bank, where possible. Consideration would be given to planting disturbed bank areas with herbaceous and woody vegetation to help mitigate some of the plant loss caused by construction. In addition, fish and wildlife mitigation has been recommended for 20 acres of streambank vegetation lost by removal of debris jams (Appendix H, Part 2).

13.

We appreciate the opportunity to review the draft environmental statement at this time, and look forward to further coordination on the proposed project.

Sincerely yours,



Acting Regional Director

CORPS RESPONSES TO THE USDI - FISH AND WILDLIFE SERVICES (Cont'd)
(Letter dated 17 June 1976)

13. The Corps will continue to maintain close coordination with the U. S. Fish and Wildlife Service on the proposed Batavia Reservoir Compound project.

Attachment

UNITED STATES DEPARTMENT OF AGRICULTURE

FOREST SERVICE
NORTHEASTERN AREA, STATE AND PRIVATE FORESTRY
6816 MARKET STREET, UPPER MERION, PA. 19082

215-596-1672

8400

June 18, 1976



LTC Byron G. Walker
Deputy District Engineer
Department of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Refer to: NCBED-PE, Draft Environmental Statement
Tonawanda Creek Watershed
NY

Dear Col. Walker:

Of the four plans described in the above Statement, we consider the selected plan -- Batavia Reservoir -- the most environmentally sound. We understand that flood water inundation will not continue beyond a period that would cause damage to elm, ash, and cottonwood.

Loss of habitat and wetland appears unavoidable and to be the minimum compatible with completion of the project.

If possible, at dike and spillway construction areas (p. 153) seeding and mulching should be supplemented by planting trees and shrubs to restore wildlife habitat.

Sincerely,

DALE O. VANDENBURG
DALE O. VANDENBURG

Staff Director
Environmental Quality
Evaluation

CORPS RESPONSES TO THE USDA - FOREST SERVICE
(Letter dated 18 June 1976)

1. No comment necessary.

2. The Corps concurs that some loss of habitat would be unavoidable during project construction as one of the trade-off impacts to provide flood management protection. Disturbed soils would be reseeded with a herbaceous vegetation mixture to provide cover protection against soil loss into downstream areas. Although reseeded areas would not contain the variety of natural woody and herbaceous plant species that were established prior to project construction, the herbaceous plantings would somewhat help to mitigate habitat that was disrupted by construction. In addition, a fish and wildlife mitigation plan has been recommended as part of the project.

3. Although supplemental plantings of trees and shrubs would provide more variety and help restore wildlife habitat to some degree, in addition to enhancing the natural appearance of the proposed project, such woody plantings would not be practical from an engineering standpoint. During periods of flooding, trees and shrubs would tend to act as snags that could trap drift materials coming downstream and obstruct flow that would contribute to overbank flooding. Root system development and snagged debris along dikes could endanger the structural stability of the project. Tree and shrub roots could cause dike seepage pathways to develop, or high winds could upheave entire root systems and weaken earth dikes and dams. The emergency spillway would also require unobstructed flow in the event of a significant flood.

UNITED STATES DEPARTMENT OF AGRICULTURE

SOIL CONSERVATION SERVICE

700 East Water Street, Syracuse, New York 13210

June 22, 1976

LTC Byron G. Walker
Deputy District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Col. Walker:

We have reviewed the Draft Environmental Impact Statement for the Final Feasibility Report on Flood Management in the Tonawanda Creek Watershed prepared by the Buffalo District, Corps of Engineers, dated April 1976.

Our comments are listed below:

1. Page 75 and 76 - Table 2. M

This table could be improved by including the units of BOD, DC, PO₄, etc. at head of each column.

2. Page 80 - Plate 2. 12

Units are not shown.

3. Page 91 - Plate 2. 17

Has the LEGEND been inadvertently rotated 90° on the map?

4. Page 138 and 139 - Table 2. FF

The exact same table appears to be duplicated on each page!

5. Page 151 - Paragraph 4. 16

The first sentence states, "If the Batavia Reservoir Compound were constructed, farmland use within this site would remain essentially the same." It is possible that use might remain the same but very likely, it will not. It is recognized that the lower reservoir area will receive a 10-year protection but the upper

CORPS RESPONSES TO THE USDA - SOIL CONSERVATION SERVICE
(Letter dated 22 June 1976)

1. The entire EIS has been rewritten to comply with the 1978 CEQ Guidelines and most of the information contained in Chapter 2 and other parts of the EIS has been eliminated from the FEIS.

2. See response to Comment 1.

3. See response to Comment 1.

4. See response to Comment 1.

5. The Corps concurs that the upper dry-retention reservoir of the Compound would be flooded more frequently that would in turn have an adverse impact on the intensity of agriculture. This would be an unavoidable trade-off that would make cultivation of farmlands in the upper reservoir impractical.

- 2 -

reservoir area will flood much more frequently. In this area, at least, intensity of agricultural use will be decreased significantly.

CORPS RESPONSES TO THE USDA - SOIL CONSERVATION SERVICE (Cont'd)

6. Page A-1 - Glossary of Terms

BIOCHEMICAL OXYGEN DEMAND (BOD) - Is it proper to assume this is a 5-day BOD? The definition should clarify this point.

6. See response to Comment 1.

We appreciate the opportunity to review and comment on this proposal.

Sincerely yours,



Robert L. Hilliard
State Conservationist

cc: R. M. Davis, Administrator, SCS, Washington, D. C.
Dr. Fowden G. Maxwell, Coordinator, Office of Environmental
Quality Activities, Office of the Sec'y, USDA, Washington, D. C.
Council on Environmental Quality, Washington, D. C., Attention.
General Counsel (5 copies)



United States Department of the Interior

NATIONAL PARK SERVICE

NORTH ATLANTIC REGION
150 CAUSEWAY STREET
BOSTON, MA. 02114

IN REPLY REFER TO:
L-7619-NAR-(PE)
BR-76/456

June 22, 1976

Colonel Bernard C. Hughes
District Engineer
Department of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hughes:

This will serve as a multiple response to your request for review and comment of:

4 May on - Draft Environmental Statement, Proposed Flood Control, Tonawanda Creek Watershed, Erie, Genesee, Niagara, and Wyoming Counties, New York (originally sent to our Departmental Office of Environmental Project Review which advised our direct response to you).

24 May on - Draft Feasibility Report for Tonawanda Creek Watershed New York.

3 June on - Reconnaissance Level Literature Search and Records Review (cultural resources report-largely on archeological values) for Tonawanda Creek Watershed, New York. This report was prepared for the Corps by Barbour and Miller of Department of Anthropology, SUNY at Buffalo.

You should understand that our comments on the cultural resources report and the draft feasibility report are provided as technical assistance based solely on the interests, expertise and responsibilities of the National Park Service. The comments on the draft environmental statement are also those of the National Park Service as a portion of the collective expertise of the Department, but a consolidated Departmental commentary will be presented at a later date upon the Chief of Engineer's request to review the proposal.

CORPS RESPONSES TO THE USDI - NATIONAL PARK SERVICE
(Letter dated 22 June 1976)

1. No response necessary.

2. No response necessary.



CORPS RESPONSES TO THE USDI - NATIONAL PARK SERVICE (Cont'd)
(Letter dated 22 June 1976)

3. No response necessary.
4. In order to more fully address the project impacts on cultural resources a reconnaissance level survey was undertaken. This survey identified a number of cultural resources sites. Refer to Appendix M, Part 4, and the main text of this FEIS for more information.
5. In response to your statements, a new cultural resources report has been prepared and revisions made in this FEIS.
6. See Response No. 4.
7. See Response No. 4.
8. See Response No. 4.

Cultural Resources Report. Because the findings of this report are basic to the development of an adequate environmental impact statement, we will speak to it first. The report appears adequate as a literature search and records review, and we note that many archeological and potential historical sites were identified. It is also noted that the State Historic Preservation Officer's office contributed a listing of sites on and recommended for listing on the National Register of Historic Places, as well as archeological sites on file with that office.

Draft Environmental Statement. Section 2, paragraphs 2.104 and 2.105 (pages 131-134) makes appropriate use of the information recorded in the cultural resources report. Appendix F-1, summary of that cultural resources report further emphasized the potential and probability of archeological resources in the overall study area. That summary reflects on the project alternative which would cause less effect on such resources and indicates that some alternatives would require much more detailed archeological investigations prior to final project design. Paragraph 2.104 indicates that consultation of the National Register of Historic Places has been accomplished. Up to this point, consideration for the protection of cultural resources would appear satisfactory. However, as this is where the consideration stops, we feel that necessary required considerations are incomplete.

We find this environmental statement deficient as now presented for failure to discuss accomplished or intended efforts to fulfill the requirements of EO 11593 and follow the procedures for compliance with Section 106 of the Historic Preservation Act as presented in 36 CFR Part 800. While it may be the intent to perform such compliance at a later project phase, the level of detail in discussing various alternatives in this draft environmental statement warrants a commensurate consideration for the protection of cultural resources so that the selection of the best alternative can be properly guided.

With the citation of all the National Register sites involved, certainly the alternative project selected is very likely to undergo Section 106 proceedings. Further, until the many archeological sites identified have been evaluated for their significance and eligibility for inclusion on the National Register of Historic Places, compliance with Section 106 requirements remains a potential threat to the accomplishment of the selected project alternative.

Section 4, paragraph 4.114 (page 150) flatly states that "some cultural resources will be lost" with the modification that preservation efforts will be considered in the public recreation development areas.

Paragraph 4.27 (page 154) expresses a partial approach to the protection of cultural resources. However, it would seem essential, even as an aspect of mitigation of harmful effects, to first determine where the cultural resources are that require protective measures.

CORPS RESPONSES TO THE USDI - NATIONAL PARK SERVICE
(Letter dated 22 June 1976)

3

9. Neither the project or the cultural resources portion of the project has reached a stage where this is appropriate. At this time, it is envisioned that an archaeological testing program will be necessary prior to submittal of a request for determination of eligibility to the NRHP. This work would be done after the project is authorized.

10. No comment necessary.

11. See Response No. 4.

12. The Final Feasibility Report has been rewritten and gives consideration to cultural resources.

13. No response necessary.

We would remind you that the Director, Office of Archeology and Historic Preservation, National Park Service, Washington, D. C. 20240, will, upon request, provide a determination of eligibility of sites of historical or archeological significance for inclusion in the National Register of Historic Places.

Paragraph 9.04 (page 186) mentions initial coordination with the National Park Service as further identified in our technical assistance letter of January 5 displayed as Appendix 8-1-2.

It is not our outlook that detailed archeological investigations should be performed over the entire study area. However, we are concerned that adequate considerations be given at this time for the protection of cultural resources commensurate with the detail of consideration given all other aspects leading to the selection of a project alternative. Certainly, the applicability and necessity for compliance with Section 106 should be discussed which beckons completion of EO 11593 requirements and applicable NEPA provisions already initiated. It would seem possible that the unfinished cultural resource protection consideration work can be satisfactorily completed before finalization of this environmental statement and that the present inadequacies in the treatment of this broad field aspect of the human environment can be rectified in the final environmental statement.

Draft Feasibility Report. As indicated in our letter of January 5 included in Appendix F, we were pleased to note cultural resources coverage in the Preliminary Feasibility Report and fully expected to see an adequate treatment of cultural resource protection considerations in the following stages of the report. We are now concerned that all cultural resource considerations seem to have been dropped from the feasibility report, particularly when numerous other aspects and criteria, such as biological, climatological, land use, economical, recreational resources, along with population growth, transportation trends, housing needs and industrial activity factors are maintained and treated in significant detail in the main report and technical appendices. In a manner commensurate to the treatment of the many other factors mentioned above, we recommend that cultural resource protection considerations be included in the final report and that all efforts to comply with standing requirements for the protection of cultural resources should be clearly presented.

Again, in summary, it is not our intent to demand an excessive effort to survey, investigate and evaluate the impacts of every alternative.

CORPS RESPONSES TO USDI - NATIONAL PARK SERVICE (Cont'd)
(Letter dated 22 June 1976)

4

Moreover, it is our purpose to technically assist the Corps in its responsibility to protect cultural resource values from adverse effects that may or will result from any selected project alternative.

Sincerely yours,

Gilbert W. Calhoun
Gilbert W. Calhoun
Acting Regional Director

14. No response necessary.



UNITED STATES DEPARTMENT OF COMMERCE
The Assistant Secretary for Science and Technology
Washington, D.C. 20230

June 22, 1976

CORPS RESPONSES TO THE U. S. DEPARTMENT OF COMMERCE - THE
ASSISTANT SECRETARY FOR SCIENCE AND TECHNOLOGY
(Letter dated 22 June 1976)

Colonel Bernard C. Hughes
Buffalo District, Corps of Engineers
Department of the Army
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hughes:

This is in reference to your draft environmental impact statement entitled "General Investigation, Tonawanda Creek Watershed, New York." The enclosed comments from the National Oceanic and Atmospheric Administration are forwarded for your consideration.

Thank you for giving us an opportunity to provide these comments, which we hope will be of assistance to you. We would appreciate receiving eight copies of the final statement.

Sincerely,

Sidney R. Galler
Sidney R. Galler
Deputy Assistant Secretary
for Environmental Affairs

Enclosures Memos from: Mr. Eugene J. Aubert
Director, GLERL, RF24

Dr. Gordon Lill
Deputy Director, NOS

1. No response necessary.

2. Eight copies of the Final Environmental Statement will be sent to the Department of Commerce when the document is completed.





Corbin

U.S. DEPARTMENT OF COMMERCE
National Oceanic and Atmospheric Administration
ENVIRONMENTAL RESEARCH LABORATORIES
Great Lakes Environmental Research Laboratory
2300 Washtenaw Avenue
Ann Arbor, Michigan 48104

CORPS RESPONSES TO THE U. S. DEPARTMENT OF COMMERCE - NATIONAL
OCEANIC AND ATMOSPHERIC ADMINISTRATION - ENVIRONMENTAL
RESEARCH LABORATORIES
(Letter dated 2 June 1976)

May 28, 1976

JUN 2 1976

TO : Director
Office of Ecology and Environmental Conservation, EE

FROM : Eugene J. Kubert
Director, GLERL, RF24

SUBJECT: DEIS 7605.15 - Interim Report on Feasibility of Flood Management
in Tonawanda Creek Watershed

The subject DEIS prepared by the Corps of Engineers, Buffalo District,
on environmental effects of proposed flood management in Tonawanda
Creek watershed has been reviewed and comments herewith submitted.

During the four to five years of construction of Batavia Reservoir Compound
and clearing of Tonawanda Creek, fine soil particles will be suspended and
carried downstream. They will be deposited in slack water of either New
York State barge canal or Tonawanda Nation, or through the Niagara River
in Lake Ontario. It will cause some deterioration of water quality and
silt in these waterways. After project completion, however, some
improvement of quality of flood water can be expected due to reduction of
peak flows.

1. No response necessary.

2. The Corps concurs that during construction of the Batavia Reservoir
Compound, temporary stream siltation into downstream areas would be
unavoidable. The Contractor would be required to mitigate soil loss into
the creek by seeding the mulching disturbed bank soils as soon as possible.



U.S. DEPARTMENT OF COMMERCE
National Oceanic and Atmospheric Administration
NATIONAL OCEAN SURVEY
Rockville, Md 20852

JUN 10 1976

C52/JLR

JUN 11 1976

CORPS RESPONSES TO THE U. S. DEPARTMENT OF COMMERCE - NATIONAL OCEANIC
AND ATMOSPHERIC ADMINISTRATION - NATIONAL OCEAN SURVEY
(Letter dated 11 June 1976)

TO: Dr. William Aron
Director
Office of Ecology and Environmental Conservation
Gordon Lill
FROM: Dr. Gordon Lill
Deputy Director
National Ocean Survey

SUBJECT: DEIS #7605.15 - Interim Report on Feasibility of Flood
Management in Tonawanda Creek Watershed

The subject statement has been reviewed within the areas of NOS
responsibility and expertise, and in terms of the impact of the
proposed action on NOS activities and projects.

The following comment is offered for your consideration.

Geodetic control survey monuments may be located within the
proposed project areas. If there is any planned activity which
will disturb or destroy these monuments, NOS requires not less
than 90 days notification in advance of such activity in order
to plan for their relocation. NOS recommends that funding for
this project includes the cost of any relocation required for
NOS monuments.

1. No response necessary.

2. Construction of the proposed project would be at least five years
away, if it is authorized and funded by Congress. During our precon-
struction planning stage, the Corps would contact the National Oceanic
and Atmospheric Administration to coordinate removal of any monuments
that may be within the construction area, if any exist in the Batavia
Reservoir Compound locale.



New York State Department of Environmental Conservation
5 Road, Albany, New York 12233



CORPS RESPONSES TO THE NYS DEPARTMENT OF ENVIRONMENTAL CONSERVATION
(Letter dated 24 June 1976)

Peter A. A. Berle,
Commissioner

June 24, 1976

LTC. Byron G. Walker
Deputy District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Walker:

Draft Environmental Impact Statement
Tonawanda Creek Watershed, N. Y.
DEC Project No. 089-007

We have reviewed the above noted document and have enclosed our comments.

In summary, the statement is generally accurate, but effects of siltation in the reservoirs should be addressed in the Final E.I.S. In addition, the enhancement of other wetlands in the project area to compensate for the probable impacts on wetlands in the lower detention reservoir should be considered. We believe that adverse environmental effects can be minimized by incorporating adequate measures during construction to control soil erosion, sedimentation, and stream pollution. Finally, the feasibility of employing non-structural measures in the lower basin in conjunction with the selected plan should be addressed.

- 1.
2. Thank you for the opportunity to review this statement. We would like to receive five copies of the Final E.I.S. when it is available.

Very truly yours,

Terence P. Curran
Director of Environmental Analysis

Enclosure

1. Corps responses to the summarized comments in this paragraph from the New York State Department of Environmental Conservation, letter dated 24 June 1976, are provided on the following two pages.

2. Five copies of the Final Environmental Statement will be sent to the NYS Department of Environmental Conservation when the document has been completed.

**COMMENTS ON DRAFT ENVIRONMENTAL IMPACT STATEMENT
TONAWANDA CREEK WATERSHED**

CORPS RESPONSES TO THE NYS DEPARTMENT OF ENVIRONMENTAL CONSERVATION (Cont'd)
(Letter dated 24 June 1976)

3. **Section 1.08** - Disposal of solid wastes generated by construction of the project must be at a site approved by the Department of Environmental Conservation. The Department's Regional Solid Waste Engineer at Avon should be contacted regarding specific requirements.
4. **Section 4** - The statement should discuss effects of siltation in the reservoirs. The impoundment of Tonawanda Creek floodwaters, which carry a high silt load, will probably result in the deposition of silt within the reservoir areas. Some wetlands in the detention reservoirs may be detrimentally altered by the deposition of this silt load. In addition, erosion of silt after the reservoirs are drained may result in the filling of wetlands, drainage ditches and small streams within the reservoirs. This silt deposition may also cause other environmental problems, such as obnoxious odors, which should be addressed.
5. **Section 4.03** - Although soil erosion, stream turbidity and sedimentation are identified as temporary, long range adverse impacts may result. The smothering of aquatic organisms or destruction of their habitat, for even a short period, can still have a permanent effect. Once destroyed, aquatic life may require a considerable time to reestablish itself. Therefore, it is essential that measures be taken during construction to keep soil erosion and water pollution to an absolute minimum.
6. **Section 4.20** - This section indicates that wetlands in the lower reservoir would be subject to less frequent flooding. However, some wetlands in this area may depend on annual flooding for water recharge purposes; annual flooding may even be essential to the existence of some of these wetlands.
7. In view of the actual and potential adverse impacts on the wetland habitat found in the detention reservoir areas, consideration should be given to creating or enhancing a wetland in the project area to mitigate this loss of habitat. A wetland area southwest of Batavia near the intersection of Route 63 and Shepard Road would be suitable for enhancement.
8. **Section 4.28** - Plans to relocate Peaviner Road should include measures to minimize soil erosion, sedimentation and stream pollution.
9. **Section 6.07** - Since the Batavia Reservoir Compound plan would provide only 50-year flood protection in the lower Tonawanda Creek basin (the Huron Plain Floodland), consideration should be given to incorporating non-structural measures in conjunction with the Batavia Reservoir Compound proposal.

3. The Corps will coordinate with the NYS Department of Environmental Conservation with regard to site selection approval, and the Regional Solid Waste Engineer at the Department's office in Avon would be contacted regarding specific requirements, as recommended.
4. If the proposed project were implemented, some deposition of silt onto wetlands by temporary containment of floodwaters in the Batavia Reservoir Compound would occur. But under natural conditions, floodwater deposits silt onto wetlands and drainageways in these areas. The area of more silt accumulation would probably occur near the dam of the upper reservoir. It is reasonable to assume that silt would accumulate on some wetlands in this area and would destroy some vegetation and possibly fill in some low areas. Generally, this would be followed by reestablishment of terrestrial or aquatic vegetation. Wetlands within the lower reservoir would be less subject to silt accumulation because of operation of the upper reservoir. The proposed project would provide various degrees of protection from siltation due to flooding on wetlands located in the floodlands downstream of the Batavia Reservoir Compound. With regard to the possibility of obnoxious odors from silt deposits, such temporary odors may occur after flooding, but wind and reestablishment of plant growth would tend to reduce this potential impact in the rural location of the project. Present land use in the area which includes use by dairy cattle and fertilization of agricultural land with commercial fertilizers and manure, contributes to occasional odor which cannot be avoided in necessary farming operations to keep soils productive.
5. Measures will be taken to mitigate soil erosion, stream turbidity, and sedimentation as much as possible. Consideration would be given to installation of temporary settling basins and interceptor ditches to contain runoff from soils disturbed by construction. Replanting of vegetation and mulching of seeded areas would also be done to conserve soils on disturbed terrain. The Contractor will also be required to minimize temporary environmental impacts which includes noise, dust, and water turbidity, in accordance with the procedures and regulations outlined in the Civil Works Construction Guide Specification for Environmental Protection (CW 01430, 1979).
6. As indicated on the Batavia South, NY, U. S. Geological Survey Quadrangle Map (1950), wetlands in the Batavia Reservoir Compound are fed by local small tributaries. Floodwaters from Tonawanda Creek are not the main source of recharge for wetlands in this area.
7. Most wetlands are found in the lower reservoir. These wetlands would be enhanced to some degree by the reduction in siltation that would be afforded to them by the upper reservoir. A mitigation plan at the Oak Orchard WMA has been recommended to offset the construction impacts on wetlands (Appendix H, Part 2).

CORPS RESPONSE TO THE NYS DEPARTMENT OF ENVIRONMENTAL CONSERVATION (Cont'd)
(Letter dated 24 June 1976)

8. The Corps concurs. Measures to minimize soil erosion, sedimentation, and stream pollution are outlined in a previous Corps response (paragraph 5) and would be part of the Contractor's requirements for construction.
9. Consideration was given to incorporation of nonstructural measures in conjunction with the Batavia Reservoir Compound proposal, however, at this point in time, Federal - non-Federal cost sharing responsibilities are indeterminate. Implementation of the Batavia Reservoir Compound would not preclude consideration of nonstructural measures during General Design Memorandum I study. The Corps has provided flood plain information reports to the towns of Tonawanda, Amherst, and Clarence and would work with these communities upon request to implement nonstructural measures such as flood plain management.



United States Department of the Interior

BUREAU OF OUTDOOR RECREATION

NORTHEAST REGIONAL OFFICE

Federal Building - Room 9110

600 ARCH STREET

Philadelphia, Pennsylvania 19106

IN REPLY REFER TO:

ER-76/456

Colonel Bernard C. Hughes
District Engineer
Buffalo District
Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

JUN 25 1970

Dear Colonel Hughes:

We have reviewed the draft environmental statement for Flood Control in the Tonawanda Creek Watershed; Erie, Genesee, Niagara, and Wyoming Counties, New York.

We commend the District on the consideration and the recommendation of "dry bed" reservoirs to reduce flood damage in the Tonawanda Creek watershed. Dry bed reservoirs have great recreation potential such as for the canoe trail described in the subject statement. However, we suggest that consideration also be given to the purchase of a strip along the entire watercourse within the project limits so that, eventually, walking trails and picnic areas could be developed. Public management of a narrow strip along the creek would assure good public access to the canoe trail and other activities.

We suggest consideration of a special design for the energy dissipation basins below both of the normal flow outlet works so that the basins may be eventually developed into outdoor swimming facilities by local or state recreation agencies. We note only 3 public swimming facilities in your inventory.

The statement would be improved by the inclusion of a map showing the sites of existing recreational facilities, especially those which are likely to be impacted during flood conditions.

CORPS RESPONSES TO THE USDI - BUREAU OF OUTDOOR RECREATION
(Letter dated 25 June 1976)

1. A recreation trail along Tonawanda Creek is currently under consideration by the Genesee County Planning Department.

2. During the Phase I General Design Memorandum, consideration will be given to designing the energy dissipation basins of the principal outlet works, so that the basins might be developed into outdoor swimming facilities by local or State agencies.

3. A recreation map showing the general locale of the Batavia Cooperative Hunting Area is available from the Buffalo District on request.

Copy available to DNR does not
permit full hydrologic investigation




CORPS RESPONSES TO THE USDI - BUREAU OF OUTDOOR RECREATION (Cont'd)
(Letter dated 25 June 1976)

4. The location of the Genesee County Park in the Town of Bethany should be noted and the park should be included in your inventory.

5. I hope that these remarks will be helpful in the development of the final statement.

Sincerely yours,


Regional Director

4. A location map of the Genesee County Park in the town of Bethany is available from the Buffalo District on request.

5. The Corps appreciates comments received from the Bureau of Outdoor Recreation, and will continue to coordinate proposed projects with the Bureau.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION II
26 FEDERAL PLAZA
NEW YORK, NEW YORK 10007

Class. LO-2

JUN 25 1976

Colonel Bernard C. Hughes
District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hughes:

We have reviewed the draft environmental impact statement (EIS) for Flood Control in the Tonawanda Creek Watershed, New York. The following comments are offered for your consideration in preparing the final EIS.

The destructive effect of overbank flooding is mentioned throughout the draft EIS. This destruction takes place when stream banks become saturated and collapse as floodwaters recede faster than the banks can drain. Once farmlands are saturated, drainage is very slow and cultivation is inhibited. We believe that construction of the proposed dam will not improve these conditions. In fact, conditions may worsen in the upper reservoir area. The final EIS should, therefore, describe the measures that will be taken to control erosion and improve drainage after project implementation.

Land currently used for farming could still be used for such a purpose. However, the threat and extent of flooding in the upper dry-retention reservoir would be more severe than at present. The final EIS should indicate if the farmers plan to cultivate their lands after project implementation. If they do, would their losses due to a disastrous flood during the growing season be compensated?

In our letter dated January 28, 1976 on the preliminary feasibility report for this project, we expressed preference for the Alabama Reservoir Compound alternative since the area that would be affected by this alternative is located in an already diked wildlife preserve. However, after reviewing the draft EIS and in light of comments by the New York State Department of Environmental Conservation and the U.S. Fish and Wildlife Service indicating potentially severe impacts to the preserve if the Alabama Reservoir Compound alternative is chosen, we now believe that the Batavia Reservoir Complex, as proposed, would be the lesser environmentally damaging alternative for flood control.

CORPS RESPONSES TO THE U. S. ENVIRONMENTAL
PROTECTION AGENCY - REGION II
(Letter dated 25 June 1976)

1. The Corps concurs that some destructive effects of flooding occur when streambanks become saturated and collapse as floodwaters recede faster than banks can drain; that slow soil drainage from saturated farmlands would impede cultivation, and that implementation of the proposed project would probably not improve these conditions significantly in the upper reservoir area. However, flooding of farmlands even within the upper reservoir would occur less frequently with the project. This is so because part of the proposed project is to clear and snag the channel of Tonawanda Creek through the B.R.C. to improve its capacity. This would improve drainage and lessen the frequency of flooding. Because the frequency of flooding would be less, the frequency of channel banks and adjacent farmland saturation should be lessened. This would serve erosion control and would improve farmlands for cultivation.

2. Since the upper reservoir would be designed to provide about a 10-year degree protection to floodlands in the lower reservoir of the Compound, flooding would occur far less frequently on lands below the upper dam. In order to provide this protection, flooding of the upper reservoir would be necessary. However, improved channel of this Tonawanda Creek through the Compound would lessen the frequency of flooding in both reservoirs.

3. Based on Corps communication with the New York State Department of Environmental Conservation and USDI Fish and Wildlife Service with regard to the Alabama Reservoir Compound, the Corps viewed the potential impacts that this flood management alternative could have on the State-owned Wildlife Management Area as severe enough to eliminate this alternative from further consideration, and concurs with the U. S. Environmental Protection Agency that the Batavia Reservoir Compound would be the lesser environmentally damaging alternative for flood management.

In accordance with EPA policy, this EIS has been classified LO-2, which indicates that EPA lacks objections to the proposed action and that the draft EIS does not contain certain information necessary to fully evaluate environmental impacts.

Two copies of the final EIS are requested for subsequent review. If you have any questions concerning our comments, please feel free to contact us at (212) 264-8556.

Sincerely yours,

Barbara M. Metzger

Barbara M. Metzger
Chief
Environmental Impacts Branch

CORPS RESPONSES TO THE U. S. ENVIRONMENTAL
PROTECTION AGENCY - REGION II (Cont'd)

4. Telephone communication on 7 July 1976 with the EIS Coordinator at the Region II EPA Environmental Impact Branch office, further clarified this comment in that, the "certain information necessary to fully evaluate environmental impacts" refers to the aforementioned comments in this comment letter from EPA dated 25 July 1976.

5. As requested, when completed, two copies of the Final Environmental Statement for this phase of the engineering planning study will be provided to the region II Environmental Protection Agency Office.

APPENDIX H, PART 2

FISH AND WILDLIFE MITIGATION ANALYSIS

TABLE OF CONTENTS

FISH AND WILDLIFE MITIGATION ANALYSIS

<u>Paragraph</u>	<u>Description</u>	<u>Page</u>
1.	INTRODUCTION	H2-1
1.01	Purpose	H2-1
1.02	Introduction	H2-1
2.	U.S. FISH AND WILDLIFE SERVICE AND CORPS OF ENGINEERS POLICIES ON MITIGATION	H2-2
2.01	U.S. Fish and Wildlife Service	H2-2
2.03	Corps of Engineers	H2-2
2.05	Comparison of Policies	H2-3
3	U.S. FISH AND WILDLIFE SERVICE RECOMMENDED MITIGATION	H2-4
3.02	Assumption Used in the HEP Analysis	H2-4
3.07	Changes to Mitigation Recommendation	H2-5
3.15	Coordination of this Mitigation Analysis	H2-7
4.	ANALYSIS OF IMPACTS OF CONSTRUCTION AND OPERATION	H2-8
4.01	Introduction	H2-8
4.02	User Day Analysis	H2-8
	CONSTRUCTION IMPACTS	H2-10
4.09	Construction of Embankments, Outlet Works, and Training Dikes	H2-10
4.10	Impacts of Clearing and Snagging	H2-10
	OPERATIONAL IMPACTS	H2-12
4.13	Introduction	H2-12
4.14	Potential Effects of Flooding on Plants	H2-12
4.15	Time of Year	H2-12
4.16	Flood Frequency	H2-12
4.17	Flood Duration	H2-13
4.18	Water Depth	H2-13
4.19	Siltation	H2-13
4.20	Basis of Analysis	H2-13
4.23	Areas Flooded by Operation	H2-17
4.25	Effects of Sedimentation and Siltation	H2-17
4.28	Areas Effectuated by Operation of the Reservoirs	H2-18
4.30	Impact of Operation	H2-19

TABLE OF CONTENTS (Cont'd)

<u>Paragraph</u>	<u>Description</u>	<u>Page</u>
	IMPACTS OF LAND USE CHANGES WITH THE PROJECT	H2-24
4.34	Introduction	H2-24
4.38	Habitat and Wildlife Value of Idle Agricultural Lands	H2-27
4.40	Habitat Quality Considerations	H2-29
4.41	Impacts of Conversion of Idle Agricultural Lands on the Key Species	H2-34
4.43	Impacts on White-Tailed Deer	H2-34
4.44	Impacts on Cottontail Rabbit	H2-34
4.45	Impacts on Ring-Necked Pheasant	H2-34
4.46	Impacts on Red Fox	H2-36
4.47	Impacts on Raccoon	H2-36
4.48	Impacts on Red-Tailed Hawks	H2-36
4.49	Impacts on Mice (White-Footed Mouse, Meadow Vole, and House Mouse)	H2-36
4.50	Significance of Impact of Land Conversion	H2-37
4.57	Conclusions as Related to Providing Mitigation	H2-38
5.	CONCLUSIONS ON MITIGATION	H2-39
5.01	Introduction	H2-39
5.02	Construction Impacts	H2-39
5.05	Clearing and Snagging	H2-39
5.06	Project Operation	H2-40
5.07	Conversion of Idle Agricultural Lands	H2-40
5.08	Conclusion	H2-40
6.	RECOMMENDATIONS ON MITIGATION	H2-40
6.01	Introduction	H2-40
6.02	U.S Fish and Wildlife Service Recommended Mitigation	H2-40
6.04	New York State Department of Environmental Conservation Recommended Mitigation	H2-41
6.06	The Oak Orchard Wildlife Management Area	H2-41
6.13	Plan of Improvement	H2-44
6.17	Agency Coordination of the Mitigation Plan	H2-46
6.18	Costs and Institutional Arrangements	H2-47

TABLES

<u>Table</u>	<u>Title</u>	<u>Page</u>
4.1	Habitat Loss in Acres from Construction of the Batavia Reservoir Compound (Modified)	H2-11

TABLE OF CONTENTS (Cont'd)

TABLES (Cont'd)

<u>Table</u>	<u>Title</u>	<u>Page</u>
4.2	Lower Reservoir, Pool Elevations, Acreage Flooded and Duration of Pool Flooding Under Natural and Improved Conditions	H2-14
4.3	Upper Reservoir, Pool Elevations, Acreage Flooded and Duration of Pool Flooding Under Natural and Improved Conditions	H2-15
4.4	Changes in Flooding Conditions with the Project	H2-16
4.5	Additional Areas Flooded by Habitat Types, From Operation of the Batavia Reservoir Compound to Control the Two-Year Frequency Flood	H2-18
4.6	Lower Reservoir Sediment Settling Times	H2-18
4.7	Forested Wetlands in the Batavia Reservoir Compound and Relative Flood Tolerance of Dominant Tree Species	H2-23
4.8	Tonawanda Creek Watershed, Total Acreage and Agricultural Acreages Within SPF (Existing Conditions)	H2-24
4.9	Idle Agricultural Lands Located in Various Reaches of the Tonawanda Creek Watershed (Within the limits of the Standard Project Flood)	H2-26
4.10	General Characteristics of Idle Agricultural Areas and Corn Fields	H2-30
4.11	Relative Significance of Habitat Quality Parameters to Key Species	H2-31
4.12	Common Shrubs, Forbs, and Grasses Found in Idle Agricultural Areas Along Tonawanda Creek	H2-33
4.13	Impacts of Conversion of Idle Agricultural Lands to Active Farming (Corn Crops)	H2-35
6.1	Costs of Fish and Wildlife Mitigation Plan at the Oak Orchard Wildlife Management Area	H2-48

TABLE OF CONTENTS (Cont'd)

PLATES

<u>Plate</u>	<u>Title</u>	<u>Page</u>
4.1	Number of Flows, 2,000 CFS or Greater, Jan.-Dec., 1945-1979	H2-20
4.2	Number of Flows, 2,000 CFS or Greater, April-May, 1945-1979	H2-21
6.1	Location of the Oak Orchard Wildlife Management Area	H2-42
6.2	Mitigation Plan at the Oak Orchard Wildlife Management Area	H2-45

TONAWANDA CREEK
FISH AND WILDLIFE MITIGATION ANALYSIS

1. INTRODUCTION

1.01 Purpose - The purpose of this appendix to the Tonawanda Creek Final Feasibility Report (FFR) and Final Environmental Impact Statement (FEIS) is to present an analysis of the Corps of Engineers position on fish and wildlife mitigation for the proposed Tonawanda Creek Flood Control Project, compare it with mitigation recommended by the U. S. Fish and Wildlife Service, and develop a justifiable mitigation plan for the project. The analysis and recommendations presented here have been incorporated into both the FFR and FEIS for Tonawanda Creek.

1.02 Organization - This appendix is divided into six sections for ease of presentation. The first section is this introduction. The second section briefly discusses the Corps of Engineers and U. S. Fish and Wildlife Service's policies on mitigation, particularly as such policies apply to the Tonawanda Creek study. The third section describes the U. S. Fish and Wildlife's recommendation on the proposed project. The fourth section contains a Corps of Engineers analysis of the impacts of project construction and operation on fish and wildlife resources and habitats within the flood-pool boundaries of the project. In addition the fourth section considers the possible wildlife impacts of changed farming practices that are predicted to occur if the project is implemented. This is primarily concerned with agricultural intensification and conversion of idle agricultural areas within the lower floodpool and downstream areas to active agricultural uses. The fifth section summarizes the predicted impacts; and the sixth section compares the mitigation recommendations of the Corps and Fish and Wildlife Service; recommends a mitigation plan; and gives costs and institutional arrangements for the proposed plan.

2. U. S. FISH AND WILDLIFE SERVICE AND CORPS OF ENGINEERS POLICIES ON MITIGATION

2.01 U. S. Fish and Wildlife Service - The purpose of this section is to briefly contrast the U. S. Fish and Wildlife Service and the U. S. Army Corps of Engineers policies on mitigation of adverse effects of water resources development projects on fish and wildlife resources. The U. S. Fish and Wildlife Service's policy on mitigation is described in a notice of final policy entitled "U. S. Fish and Wildlife Mitigation Policy" as published in the Federal Register.^{1/} Section V of the final policy states that "In the interest of serving the public, it is the policy of the U. S. Fish and Wildlife Service to seek to mitigate losses of fish, wildlife, their habitats, and uses thereof from land and water development." Compensation, as a form of mitigation, is defined in the policy statement as "when used in the context of Service mitigation recommendations, means full replacement (underlining added) of project-induced losses to fish and wildlife resources, provided such full replacement has been judged by the Service to be consistent with the appropriate mitigation planning goal."

2.02 With the exception of Resource Category 4, as defined in the policy statement, it is generally the policy of the U. S. Fish and Wildlife Service to recommend ways to minimize losses. If losses are still likely to occur, it is the policy of the U. S. Fish and Wildlife Service to recommend compensation for such losses. For Resource Category 4, where habitats are of medium to low value to evaluation species, it is the policy of the U. S. Fish and Wildlife Service to recommend ways to minimize loss of habitat value. If losses are still likely to occur then the policy states that "... the service may not (underlining added) make a recommendation for compensation depending upon the significance of potential loss." It can generally be stated that the U. S. Fish and Wildlife Services Policy is that all habitat and fish and wildlife resources losses should be mitigated for in one manner or another.

2.03 Corps of Engineers - The Corps of Engineers policy on mitigation is defined in Engineer Regulation 1105-2-50 ^{2/}. The Corps authority for mitigation of fish and wildlife resource losses in water resources projects arises from the Fish and Wildlife Coordination Act. The Act states that "fish and wildlife conservation shall receive equal consideration with other project purposes." The Fish and Wildlife Coordination Act authorizes the inclusion in water resources development plans measures to offset losses or damages to fish and wildlife resources.

2.04 In general, Corps policy is that damages to or losses of significant fish and wildlife resources be avoided or minimized to the extent

^{1/} Federal Register. Notice of Final Policy. U. S. Fish and Wildlife Service Mitigation Policy. 23 January 1981. Vol. 46, No. 15, pages 7644-7663.

^{2/} ER 1105-2-50, dated 29 January 1982, Environmental Resources.

practicable, and that unavoidable damages and losses be compensated to the extent justified. Significant resources include, but are not limited to, those resources identified in the laws, regulations, guidelines, or other institutional standards of national, regional and public agencies, and certain private groups. The extent of, and justification for, mitigation of adverse effects of an alternative plan shall be based upon the significance of the resulting losses, compared to the combined monetary and non-monetary costs required to carry out the mitigation measures.

2.05 Comparison of Policies - In general, Corps of Engineers and U. S. Fish and Wildlife Service policies are quite similar. However, justifying criteria for determining mitigation to be recommended can be quite different depending upon how the various policy statements of the two agencies are interpreted. U.S. Fish and Wildlife Policy for determination of mitigation needs is based primarily, and in most cases almost exclusively, on the value of the resource lost. Corps policy is similar in this respect, but must also consider the costs (monetary, social, and environmental) in making a determination if mitigation is warranted for a water resource development project. Mitigation is, therefore, only a part of the entire project evaluation in Corps projects and when making trade-off decisions for the project cannot be made a separable feature of the project, justifiable in itself, without the consideration of other project aspects.

3. U. S. FISH AND WILDLIFE SERVICE RECOMMENDED MITIGATION

3.01 The U. S. Fish and Wildlife Service provided a final Fish and Wildlife Coordination Act Report for the study on 23 October 1980. The recommendations contained in this report were somewhat modified by a supplement to it dated 23 February 1983.^{1/} The U. S. Fish and Wildlife Service, has recommended mitigation of the predicted adverse fish and wildlife impacts of the project based upon a Habitat Evaluation Procedure (HEP) study of the project area. Field work for the study was conducted by personnel of the U. S. Fish and Wildlife Service, New York State Department of Environmental Conservation and the Buffalo District. The mitigation recommended originally by the U. S. Fish and Wildlife Service was based upon the estimated habitat unit changes that will occur if the Batavia Reservoir Compound (Modified) Plan is constructed.

3.02 Assumptions Used in the HEP Analysis - A number of assumptions were used in the HEP analysis (23 October 1980) which affect the mitigation acreages determined. The most important assumptions were:

a. That 35 percent of the upper floodpool lands and 5 percent of the lower floodpool lands would develop into unstable mudflats under the with-the-project conditions and that all mudflats would form within the first 25 years of project life.

b. That all habitat types would be equally affected by mudflat formation, except that emergent marshland in the lower floodpool would remain unaffected (0 percent loss) and that cropland in the upper floodpool would be severely affected (60 percent loss).

c. That the mudflats would have little or no wildlife value (HSI = 0.000).

3.03 These assumptions were modified in the 23 February 1983 supplement to the following:

a. The assumption that 35 percent of the upper floodpool lands and 5 percent of the lower floodpool lands would convert to unstable mudflats was retained. However, it was predicted that the assumption only applies to three of five habitats present within the floodpool areas.

b. The revised assumption on mudflat formation was applied to emergent marsh, pasture, and cropland. It was assumed that emergent marsh and forested wetland would not be affected by mudflat formation.

c. The assumption of a HSI value of 0.000 for mudflats was changed to 0.300 in the supplement.

3.04 Originally the U. S. Fish and Wildlife Service recommended that several wetland complexes in both the upper and lower floodpools be protected from complete inundation by the construction of lateral dikes and flapgates. Due to the high cost of such a dike in the upper floodpool, the Buffalo District asked U. S. Fish and Wildlife Service to consider the possibility of

^{1/} Both reports are contained in Appendix H3 of the main report.

in-kind compensation for the purported loss of a large wetland area in the upper floodpool. Subsequently, the U. S. Fish and Wildlife Service recommended that another equally valuable wetland complex, outside the maximum floodpool boundaries, be obtained for compensation and managed for fish and wildlife purposes. This area would be about 112 acres in size and would compensate for the loss of 37 acres of emergent marsh and 75 acres of shrub swamp in the upper floodpool. This recommendation was retained in the supplement to the Coordination Act Report.

3.05 Originally, the U. S. Fish and Wildlife Service also recommended that projected habitat unit losses be compensated for by the purchase and management of habitat outside the maximum floodpool boundaries. As much of the projected habitat loss was in high value cropland, U. S. Fish and Wildlife Service and the Buffalo District agreed that projected cropland losses should be converted to out-of-kind (substituting different habitat types for those lost) compensation in the form of shrub swamp and forested wetland. As shrub swamp and forested wetland have a higher habitat suitability index (HSI) than cropland, this conversion reduced both the total amount of compensation acreage required and the cost of obtaining such acreage. The total amount of out-of-kind compensation recommended was 78 acres of shrub swamp and 475 acres of forested wetland.

3.06 Therefore, the total amount of compensation lands recommended by the U. S. Fish and Wildlife Service in the 25 October 1980 Coordination Act Report was 665 acres (475 acres of forested wetland, 153 acres of shrub swamp, and 37 acres of emergent marsh).

3.07 Changes to the Mitigation Recommendation - As a result of the changed assumptions contained in the 23 February 1983 supplement and some changes to HEP procedures since 1980, the U. S. Fish and Wildlife Service recalculated the HEP analysis and provided revised tables and recommendations as a result of the HEP analysis. In summary, the revised analysis concluded that, as a result of project construction and the predicted mudflat formation, the net impact of the project on all habitat types would be close to zero; therefore, no mitigation was recommended in the basis of the HEP analysis.

3.08 The Fish and Wildlife Service also considered the wildlife impacts that would occur on 1,933 acres of idle agricultural land, which is predicted to shift to active agricultural use if the project is implemented. These lands are located within the lower floodpool reservoir and in downstream areas in close proximity to Tonawanda Creek and its tributaries. The Fish and Wildlife Service recommended that a HEP analysis be performed on these lands to determine the amount of mitigation warranted. They further recommended that the total amount of mitigation lands determined in the original Coordination Act Report (about 665 acres) be used as estimates of the land acquisition required for mitigation until such time that a HEP analysis can be performed on the shifted idle agricultural lands.

3.09 In conclusion, the Fish and Wildlife Service recommended that no acquisition of specific habitat types be done at this time. They also

recommended that consideration be given to obtaining a buffer strip along Tonawanda Creek. The buffer strip would preserve riparian wildlife habitat along the creek from agricultural encroachment, revert some cropland to riparian wildlife habitat, protect Tonawanda Creek from bank and sheet erosion, and allow access to the creek for operations and maintenance and public recreation.

3.10 The Corps of Engineers had problems accepting the mitigation recommendations contained in the original (23 October 1980) Fish and Wildlife Coordination Act Report. The problems were related to the assumptions used concerning mudflat formation and the amount of impact on habitats present within the reservoir floodpools. The Corps analysis concludes that sedimentation will be a minor insignificant impact within the reservoir floodpools (see paragraphs 4.25 to 4.27 of this report.) This analysis contradicts the conclusions reached in the original Fish and Wildlife Service Report.

3.11 In the 23 February 1983 supplement, the U. S. Fish and Wildlife Service changed some of the recommendations and basically concluded that no mitigation was needed for the impacts of mudflat formation. However, mitigation was recommended for the 112-acre wetland in the upper floodpool and for presumed, but unquantified downstream conversions of agricultural lands subject to a future HEP analysis of these areas. Based upon telephone conversations with USF+WS personnel on 18 April 1983, it appears that F+WS is recommending separate compensation for the 112 acre wetland over and above what is recommended in the HEP analysis. The USF+WS believes that this shrub swamp and emergent marsh wetland is the most valuable in the compound area and that the impacts of dam construction, changing of water regimes and flooding are severe enough to lower the value of the wetland thereby requiring Fish and Wildlife resource mitigation.

3.12 At this time, the Corps of Engineers cannot accept the Fish and Wildlife Service's recommendations for obtaining mitigation acreage. The results of the Corps of Engineers analysis of the operational impacts of the project (paragraphs 4.28 to 4.32) conclude that wetlands within the floodpool areas will not be adversely affected. Therefore, no impact on the 112-acre wetland in question is expected and no mitigation can be justified.

3.13 The Corps has also concluded that the wildlife impacts associated with the conversion of idle agricultural lands to active farming with the project are not significant, nor are scarce wildlife habitats involved (paragraphs 4.34 to 4.57) and, therefore, mitigation for their changed wildlife value is not warranted.

3.14 The Buffalo District has prepared a separate non-HEP mitigation analysis (Section 4 of this report) and has reached independent conclusions of the fish and wildlife mitigation warranted for the Batavia Reservoir Compound (Modified) Plan.

3.15 Coordination of This Mitigation Analysis - A draft version of this mitigation analysis was coordinated with the U.S. Fish and Wildlife Service (USF+WS) and New York State Department of Environmental Conservation (NYSDEC) on 9 June 1983. In a letter dated 1 July 1983, (see Appendix H3 of the main report) the USF+WS provided comments on the analysis. In general, the USF+WS disagreed with the analysis and "urged" the Corps of Engineers to accept their recommendations contained in their 23 October 1980 and 23 February 1983 reports or to perform a "joint" (USF+WS, NYSDEC, and COE) HEP analysis of the idle lands in question. To date, no response has been received from NYSDEC on the Corps mitigation analysis.

3.16 The Corps of Engineers believes that the fish and wildlife mitigation analysis presented here is correct and that no significant impact on wildlife will occur from the conversion of idle farmlands to active agriculture. Therefore, the Corps will not conduct any additional wildlife mitigation analysis of the lands in question.

4. ANALYSIS OF IMPACTS OF CONSTRUCTION AND OPERATION

4.01 Introduction - This section provides the Buffalo district's analysis of the predicted habitat impacts of the construction and operation of the Batavia Reservoir Compound (Modified) Plan. It is based upon the habitat types described in the U. S. Fish and Wildlife Service Coordination Act Report^{1/} and the construction features and operational plan developed for the reservoirs as described in the Final Feasibility Report for Tonawanda Creek. This evaluation is also concerned with predicted changes in agricultural land use patterns that will occur after the project is constructed. Such changes are predicted to occur both within the boundaries of the lower reservoir floodpool and in downstream agricultural areas near Tonawanda Creek.

4.02 User Day Analysis - The Buffalo District considered doing a User-Day Analysis of the impacted project area. As discussed in Earls (1981)^{2/}, a user-day analysis is a type of analysis that quantifies the economic damage and/or benefits that will occur to fish and wildlife resources if a project is implemented. The ideal user-day analysis should evaluate the economic benefit or damage to consumptive (hunting, trapping) and nonconsumptive (bird watching, hiking, etc.) uses of fish and wildlife resources. This economic data generated can then be converted into costs and benefits and included in the National Economic Development (NED) account for the project. In practice, user-day analyses usually involve the evaluation of consumptive uses of important key recreational species with little attention or best guess estimates of nonconsumptive resource uses.

4.03 The Buffalo District made numerous contacts with the New York State Department of Environmental Conservation (NYSDEC) and the U. S. Fish and Wildlife Service (USF&WS) in attempts to gather all possible consumptive and nonconsumptive fish and wildlife resource data for the project area and in downstream reaches of Tonawanda Creek. Information is available from the NYSDEC on numbers of hunting and fishing licenses issued in the counties of Genesee, Orleans, Niagara, and Erie Counties and yearly data is available on total deer take in these counties. However, data on actual consumptive and nonconsumptive fish and wildlife uses in the project impact areas is essentially nonexistent. NYSDEC has cooperative agreements which allow hunting and fishing on private land within the project floodpool boundaries and in downstream areas, however, no significant hunter and fisherman surveys have been conducted of the actual use of such cooperator areas. In addition, variable, intermittent posting for no-hunting or fishing on private lands within the project impact areas make it impossible to determine how much land is open and available for hunting or fishing.

^{1/} See Appendix H3 of the Main Report.

^{2/} Earls, Gary A. (1981). Traditional Analysis Fish and Wildlife Approaches Used in the Corps. Planning Associates Program: 1980-1981 Board of Engineers for Rivers and Harbors, Fort Belvoir, VA, 71 pp.

4.04 The USFWS are the NYSDEC own and operate a large complex of wetland and upland wildlife habitat in an area about 10 miles to the northwest of Batavia, NY. This wetland complex is historically known as the "Oak Orchard Swamp." These areas are administratively known as the Iroquois National Wildlife Refuge (USF&WS), the Tonawanda Wildlife Management Area (NYSDEC), and the Oak Orchard Wildlife Management Area (NYSDEC). In total, the three areas comprise about 20,000 acres of some of the best waterfowl resting, feeding and breeding areas in the eastern United States. The most westerly area, the Tonawanda Creek Wildlife Management Area, is about 6,300 acres in size and has been developed by the construction of a number of water impoundments, production of annual grains for wildlife use and other public use facilities for hunters and naturalist uses. The Iroquois National Wildlife Refuge, about 10,800 acres in size, is the central of the three areas and has been developed for similar uses as Tonawanda. The most easterly and similarly developed area, the Oak Orchard Wildlife Management Area, is the smallest at about 2,500 acres.

4.05 Large numbers of Canada Geese (50,000+) as well as many other species of waterfowl use the areas as feeding and resting spots during spring northward migration. Lesser numbers of Canada geese stop at the areas during fall southern migration. The varied habitats present also provide excellent areas for production of wood duck, Canada geese, mallard and blue-winged teal. Over 200 species of birds have been sighted at Iroquois NWR since its establishment in 1958.

4.06 Waterfowl hunting is allowed during the fall at all three areas on a controlled permit basis and other consumptive nonconsumptive fish and wildlife uses of the areas are allowed. Therefore, considerable data on man-days of use at these areas are available. For instance, 121,502 total visits were recorded at the Iroquois NWR in 1981. In 1982, 70,596 public use visits were recorded at Iroquois. Of these numbers 5,494 visits in 1981 and 5,519 in 1982 were for all types of hunting allowed (upland game birds, waterfowl, big and small game).

4.07 The Buffalo District gave consideration to the possibility of using the data available (almost all from the refuge and wildlife management areas described) for the preparation of a user-day analysis to determine the amount of economic impact on fish and wildlife resources that might occur if the Tonawanda Creek Flood Control Project is constructed. The problems that would be encountered in using this data are that they are not reflective of the actual areas that will be impacted by the project. That is, the data comes from areas of intensive development and public use for wildlife purposes while the project area is primarily private lands that have been developed for agricultural purposes, rural development purposes, or just have not been developed. In addition, the location of these wildlife areas in relative close proximity to the Tonawanda Creek Project area may actually lessen the hunting and fishing pressures that might normally occur on private lands within the floodpool boundaries and in downstream impacted areas.

4.08 For the various reasons discussed, the Buffalo District has concluded that a user-day type of analysis that attempts to determine the consumptive and nonconsumptive uses of wildlife resources subject to impact

from the Tonawanda Creek Flood Control Project is not applicable or warranted. Therefore, the analysis presented in the following pages will focus primarily on acreages of fish and wildlife habitats that would be affected by the construction and operation of the project as well as by future land use changes that are predicted to occur if the project is implemented.

CONSTRUCTION IMPACTS

4.09 Construction of Embankments, Outlet Works, and Training Dikes - Construction of both the upper dam (embankment and outlet works) and the lower dam (embankment and outlet works) as well as the training dikes for the lower reservoir will result in the outright loss of a number of acres of various habitat types. A compilation of the estimated habitat losses that will result with construction of the project are presented in Table 4.1. As indicated in the table, the total predicted loss is about 138 acres of which about 78 acres (57 percent) is cropland. Lesser amounts of pasture, shrub swamp, forested wetland, and emergent marsh will also be lost with construction of the project.

4.10 Impacts of Clearing and Snagging - The existing Tonawanda Creek channel will be cleared of snags and debris jams along a total length of 13 miles within the reservoir compounds (8 miles in the lower reservoir and 5 miles in the upper reservoirs). The purpose of this action is to provide a debris free channel of 2,000 cfs capacity along the entire channel length within the reservoir floodpools. Dead trees along the streambanks and overhanging partially uprooted trees will be removed. In addition, accumulations of dead trees and other debris will be removed from the creek itself. This clearing and snagging will be a selective operation to remove only what is necessary to clear the channel, however, there will be some unavoidable destruction of live vegetation and trees that will be necessary to allow access of construction equipment to the areas of the creek where snags will be removed.

4.11 Removal of dead trees from the creek banks will affect various wildlife species including birds which use the trees for nesting sites and den sites for small mammals, reptiles, and amphibians. This action will also have some aquatic impacts as debris jams provide habitat for aquatic insects and food sources and cover areas for numerous fish species including northern pike and smallmouth bass. The clearing of streambank trees will be selective, therefore, little impact on the shading and temperature control provided to the creek's waters by the streambank vegetation is expected.

4.12 At the present time it is not known how much clearing and snagging will be needed along the 13-mile stretch of Tonawanda Creek within the limits of the Batavia Reservoir Compound. For the purpose of this analysis it has been estimated that one major clearing and snagging action, about 1.5 acres in size, will be done along each mile of creek. As debris jams typically occur in the same locations along the creek these areas would be cleared out on a continuous operations and maintenance basis. Therefore, the total impacted area of riparian vegetation (forested wetland) would be 13 miles by 1.5 acres or 20 acres.

Table 4.1 - Tonawanda Creek, New York - Habitat Loss in Acres from Construction of the Batavia Reservoir Compound (Modified)

Habitat Type (1)	Habitat Losses (2)		
	Upper Reservoir	Lower Reservoir	Training Dikes : Total
Forested Wetland	4	2	6 : 12
Cropland	33	26	19 : 78
Pasture	-	5	- : 5
Shrub Swamp	18	15	- : 33
Emergent Marsh	10	-	- : 10
Totals	65	48	25 : 138

(1) The habitat types are those described in the U. S. Fish and Wildlife Service Final Fish and Wildlife Coordination Act Report, dated 23 October 1980 (Appendix H3 of the Main Report).

(2) Acreages calculated for the Probable Maximum Flood Design of the Compound.

OPERATIONAL IMPACTS

4.13 Introduction - Operation of the Batavia Reservoir Compound (Modified) will create temporary impoundments of floodwaters in both the upper and lower reservoir pool areas. Such containment of flood waters could create conditions under which the naturally occurring vegetation in both reservoir storage areas could be impacted. The next few pages of this appendix will present the Buffalo District's analysis of the possible operational effects of the Batavia Reservoir Compound (Modified) on the various habitat types present within the reservoir floodpools. Again, the habitat types are those discussed in the U. S. Fish and Wildlife Service Coordination Act Report. The regulation of the reservoirs is as presented in the Hydrology and Hydraulics Appendix of the Final Feasibility Report for Tonawanda Creek.

4.14 Potential Effects of Flooding on Plants - Several recent publications have reviewed considerable literature and research on the responses of vegetation, particularly woody vegetation, to intermittent flooding. Teskey and Hinckley (1977)^{1/} give a good review of both short-term and long-term impacts of flooding on vegetation. Physiological responses of plants to stresses induced by flooding are reviewed in Teskey and Hinckley (1977) and in more detail in Whitlow and Harris (1979)^{2/}. It is not the purpose of this discussion to review this literature on plant physiology. The interested reviewer should refer to the cited publications. However, as described in Teskey and Hinckley (1977), there appears to be five major physical factors which are critical in determining plant responses to changes in water level. These physical factors are described in the following paragraphs.

4.15 Time of Year - The particular time of year a flood occurs appears to be a critical factor in determining the growth and survival of a plant species exposed to flooding. For most bottomland tree species, flooding during the dormant season has few if any adverse effects on mortality. However, flooding or high water tables extending into the growing season can have serious effects. Along with time of the year, water temperature appears to effect the survival of plants exposed to flooding. Warm water is more damaging to tree survival than cool water.

4.16 Flood Frequency - There is no consensus on the effects of flood frequency. However, it appears that as flood frequency decreases, herbaceous understory vegetation increases in diversity. Flood frequency is very important in the establishment of trees, but appears to be less important than the timing and duration of flooding for mature woody vegetation.

^{1/} Teskey, Robert O., and Thomas M. Hinckley, 1977. Impact of Water Level Changes on Woody Riparian and Wetland Communities, Volume 1: Plant and Soil Responses to Flooding, U. S. Fish and Wildlife Service, Office of Biological Services. FWS/OBS-77/58, 30 pp.

^{2/} Whitlow, Thomas H., and Richard W. Harris, 1979. Flood Tolerance in Plants: a State-of-the-Art review, U. S. Department of the Army, Waterways Experiment Station, TR E-79-2. 161 pp. plus Appendix.

4.17 Flood Duration - The duration of flooding is very important in determining the survival of a species exposed to intermittent flooding. Trees flooded for durations of less than 1 month at the beginning of the growing season are often damaged, the amount of damage being related to the flood tolerance of the species. Recovery is often rapid if the tree does not die before the flood waters recede. Long-term flooding, especially during the growing season, causes considerably higher mortality. However, many species are highly flood tolerant and can survive flooding for a period of 1 or more years.

4.18 Water Depth - The depth of flooding is another important factor in determining the responses of woody vegetation to flooding. It is particularly important for seedlings and herbaceous vegetation as they will often be completely covered by water. However, dormant seedlings will often survive flooding, remaining dormant while covered with water, and leaf out after the flood waters recede.

4.19 Siltation - Flood waters depositing heavy loads of silt affect plant growth and survival, however, many species are somewhat resistant to damage from siltation.

4.20 Basis of Analysis - For this purpose of this impact analysis, the operating plans of both the upper and lower reservoirs were considered. As illustrated in Table 4.2 for the lower reservoir, operating the reservoir to control the 2-year frequency flood actually creates the greatest flooding changes (thus impacts) from the flooding that naturally occurs in the reservoir pool area. This discussion concerns only flooding within the reservoir floodpools and not downstream flooding. As indicated in the third column of Table 4.2, for the 2-year flood, the elevation of flooding in the pool would be increased by 6.2 feet, the area flooded by 610 acres, and the duration of flooding by 7.4 days. For the less frequent floods, the elevation and duration of flooding are increased but to a lesser magnitude than for the 2-year flood. The area flooded at maximum pool actually decreases for the more frequent floods as waters that would normally spread into low lying areas near the pool margins are contained within the pool by the dam and lateral dikes.

4.21 Table 4.3 presents similar data for operation of the upper reservoir. Although the differences are not as pronounced as for the lower reservoir, it is still apparent that the 2-year controlled flood actually creates the greatest changes from naturally occurring flooding within the reservoir floodpool. Table 4.4 summarizes the information on changed flood conditions for operation of both the upper and lower reservoirs.

4.22 As the frequency, depth, and duration of flooding are some of the most important factors in determining the effects of intermittent flooding on vegetation and the fact that operating the reservoirs to control the 2-year flood creates the greatest changes from naturally occurring flooding within the floodpools, operating to control the 2-year flood has been selected as the basis of this analysis. This does not imply that operating the reservoirs to control less frequent floods has lesser overall impact. In most cases, flooding is more severe and has a longer duration than for the 2-year flood. However, the changes from naturally occurring flooding is less and the frequency of such floods is much less; therefore, recovery can be assumed.

Table 4.2 - Tonawanda Creek, New York - Lower Reservoir, Pool Elevations, Acreage Flooded, and Duration of Pool Flooding Under Natural and Improved Conditions

Flood Frequency	Natural Conditions				Improved Conditions				Change (From Natural to Improved Conditions)			
	Maximum Pool Elevation (feet)	Area Flooded at Maximum Pool (acres)	Duration of Pool Flooding (days)	Maximum Pool Elevation (feet)	Area Flooded at Maximum Pool (acres)	Duration of Pool Flooding (days)	Maximum Pool Elevation (feet)	Area Flooded at Maximum Pool (acres)	Duration of Pool Flooding (days)	Maximum Pool Elevation (feet)	Area Flooded at Maximum Pool (acres)	Duration of Pool Flooding (days)
2-Year	891.8	1,340	2.4	898.0	1,950	9.8	+6.2	+610	+7.4			
10-Year	893.9	1,850	3.0	895.1	1,220	5.1	+1.2	-630	+2.1			
20-Year	894.6	2,020	3.3	895.9	1,400	6.8	+1.3	-620	+3.5			
50-Year	895.4	2,250	4.3	897.3	1,750	8.1	+1.9	-500	+3.8			
100-Year	895.8	2,350	4.9	898.3	2,020	8.3	+2.5	-330	+3.4			
200-Year	896.2	2,470	7.3	899.2	2,300	9.8	+3.0	-170	+2.5			
500-Year	896.7	2,620	8.6	900.0	2,560	10.8	+3.3	-60	+2.2			
SPF	902.0	5,150	15.5	902.5	3,050	15.5	+0.5	-2,100	0.0			

Table 4.3 - Tonawanda Creek, New York - Upper Reservoir, Pool Elevations, Acreage Flooded, and Duration of Pool Flooding Under Natural and Improved Conditions

Flood Frequency	Natural Conditions				Improved Conditions				Change (From Natural to Improved Conditions)			
	Maximum Pool Elevation (feet)	Area Flooded at Maximum Pool (acres)	Duration of Pool Flooding (days)	Maximum Pool Elevation (feet)	Area Flooded at Maximum Pool (acres)	Duration of Pool Flooding (days)	Maximum Pool Elevation (feet)	Area Flooded at Maximum Pool (acres)	Duration of Pool Flooding (days)	Maximum Pool Elevation (feet)	Area Flooded at Maximum Pool (acres)	Duration of Pool Flooding (days)
2-Year	911.7	240	2.5	920.9	740	5.3	+9.2	+500	+2.8			
10-Year	914.1	320	N/A	922.5	850	N/A	+8.4	+530	N/A			
20-Year	914.9	390	N/A	922.5	850	N/A	+7.6	+460	N/A			
50-Year	915.8	430	4.2	922.5	850	7.4	+6.7	+420	+3.2			
100-Year	916.4	470	N/A	922.5	850	N/A	+6.1	+380	N/A			
200-Year	917.1	500	4.1	922.5	850	8.1	+5.4	+350	+4.0			
500-Year	917.6	520	N/A	922.5	850	N/A	+4.9	+330	N/A			
SPP	923.8	930	N/A	924.5	980	N/A	+0.7	+ 50	N/A			

N/A = Data Not Available.

Table 4.4 - Tonawanda Creek, New York - Changes in Flooding
Conditions with the Project

Flood Frequency	Depth of Flood (feet)	Area Flooded (acres)	Duration (days)
Lower Reservoir			
2-Year	+6.2	+ 610	+7.4
10-Year	+1.2	- 630	+2.1
20-Year	+1.3	- 620	+3.5
50-Year	+1.9	- 500	+3.8
100-Year	+1.5	- 330	+3.4
200-Year	+3.0	- 170	+2.5
500-Year	+3.3	- 60	+2.2
SPF	+0.5	-2,100	+0.0
Upper Reservoir			
2-Year	+9.2	+ 500	+2.8
10-Year	+8.4	+ 530	N/A
20-Year	+7.6	+ 460	N/A
50-Year	+6.7	+ 420	+3.2
100-Year	+6.1	+ 380	N/A
200-Year	+5.4	+ 350	+4.0
500-Year	+4.9	+ 330	N/A
SPF	+0.7	+ 50	N/A

N/A = Data Not Available.

4.23 Areas Flooded by Operation - Table 4.5 indicates the additional area that will be flooded, by habitat types, with operation of the Batavia Reservoir Compound (Modified) to control the 2-year frequency of flood. For the lower reservoir, this area is 610 acres in size and comprises all areas between 891.8 and 898.0 feet in elevation. For the upper reservoir, this area is 500 acres in extent and comprises all areas between 911.7 and 920.0 feet in elevation. This data on elevation was superimposed upon the map of habitat types supplied by the U. S. Fish and Wildlife Service in the Coordination Act Report. From this, the areas of additional flooding with operation of the Batavia Reservoir Compound (Modified) to control the 2-year flood were computed.

4.24 As indicated in Table 4.5, the majority of additionally flooded area is composed of pasture and cropland. For the upper reservoir, this pasture and cropland is 299 of 500 acres (59.8 percent) and for the lower reservoir, it is 324 of 611 acres (53.0 percent).

4.25 Effects of Sedimentation and Siltation - One of the major potential effects of the impoundment of water in reservoirs is the possible settling out of suspended sediments. Such sediments, if deposited in heavy quantities, can have major adverse effects on vegetation present in the area. Table 4.6 presents data on potential settling times for various diameter sediments in the lower reservoir. The reservoir was assumed to be full and the mean depth was assumed to be the volume divided by the surface area.

$$\begin{aligned}\text{Mean Depth Lower Reservoir (when full)} &= \text{volume/area} \\ &= 15,500 \text{ ac-ft}/2,560 \text{ acres} \\ &= 6.05 \text{ feet}\end{aligned}$$

Under natural conditions during the 2-year flood, the lower reservoir area will have water overbank for 2.4 days during which time (assuming quiescent conditions) suspended fine sand and larger diameter particles will settle. With the reservoir in operation, water will be impounded for 9.8 days during which time it is expected that suspended particulate matter with a diameter approximately greater than 0.005 cm (coarse silt) will settle.

4.26 No data currently exists on suspended sediment for Tonawanda Creek. However, visual observations of bank material along Tonawanda Creek indicate that most of the bank material, therefore material that would be suspended in the waters of Tonawanda Creek, are fine silts (roughly with diameters of 0.001 cm to 0.005 cm). As indicated in Table 4.6, these types of silt would take between 10.7 and 267 days to settle 6 feet in the lower reservoir floodpool.

4.27 As indicated in Table 4.3, the duration of pool flooding for the 2-year flood for the upper reservoir is 5.3 days, and for the lower reservoir (Table 4.2) is 9.8 days. These are relatively short time periods when considering settling of fine silts. Therefore, for the purpose of this analysis, it is predicted that there will be minor insignificant settling of suspended sediments from operation of the reservoirs and that any impacts on fish and wildlife habitat within the reservoir floodpools from sedimentation will be insignificant.

Table 4.5 - Tonawanda Creek, NY - Additional Areas Flooded,
By Habitat Types, from Operation of the Batavia
Reservoir Compound (Modified) to Control the
Two-Year Frequency Flood ^{1/}

Habitat Type	Upper Reservoir (acres)	Lower Reservoir (acres)	Total (acres)
Cropland	202	275	477
Pasture	77	49	126
Shrub Swamp	63	72	135
Forested Wetland	83	198	281
Emergent Marsh	75	17	92
Totals	500	611	1,111

^{1/} The acreage in this table only represents additional areas within the reservoir floodpools that will be inundated to control the 2-year flood. Areas less than 891.8 feet (lower reservoir) and 911.7 feet (upper reservoir) in elevation will be flooded whether or not the reservoirs are in place and operating to control the 2-year flood. However, the depth and duration of flooding will be increased in such areas.

Table 4.6 - Tonawanda Creek, NY - Sediment Settling times

Diameter (CM)	Classification	Fall Velocity V_s cm/sec ^{2/}	Time to Settle 6 Feet Days
.001	Silt	8×10^{-6}	267
.002	Silt	3.2×10^{-5}	66.7
.005	Silt	2×10^{-4}	10.7
.01	Fine Sand	8×10^{-4}	2.7
.02	Fine Sand	2.4	1.28 minutes

^{2/} The fall velocity was determined using Stokes' Law, the drag coefficient for spheres at V_s and a value of 2.65 for particle specific gravity.

4.28 Areas Effected by Operation of the Reservoirs - As discussed previously, numerous factors have a part in determining the effects of intermittent flooding on vegetation. One of the most important of these factors is the time of year when flooding occurs. Therefore, for this analysis

instances of flows over 2,000 cfs at the Batavia gauging station for the period 1945 to 1979 were compiled on a monthly basis to determine when flooding most frequently occurs on Tonawanda Creek. From 1945 to 1979 flows of 2,000 cfs or greater were recorded at the Batavia gauging station on 99 different occasions. As illustrated on Plate 4.1, the vast majority of these floods (80 or 80.8 percent) occur during the months of January to April. Late spring and summer floods occur infrequently. For the months of June through September, only six flows (6.1 percent) of 2,000 cfs or greater have been recorded at the Batavia gauging station during the period of record, 1945 to 1979. Probably, the most important factor in determining the impact on plants, particularly woody plants, is whether or not they are inundated during the growing season. Woody vegetation is affected much less severely by flooding during the dormant season than during the growing season. The growing season for most woody vegetation in the area of Batavia Reservoir Compound commences in late April or early May. Therefore, the flow data for the Batavia gauging station for the period of record 1945 to 1979 was compiled on a weekly basis for the months of April and May. This data is presented on Plate 4.2. A total of 27 flows greater than 2,000 cfs have occurred during April and May from 1945 to 1979. Of this total, 20 floods (74.1 percent) occurred during the first 3 weeks of April and the remaining seven occurred during the latter part of April and May.

4.29 During the growing season for woody vegetation within the compound area (roughly the end of April through October), 10 of 99 floods (10 percent) of 2,000 cfs or greater have occurred. This information illustrates that there is a reasonable chance (10 floods in 34 years) that flooding can and does occur during the growing season for mature woody vegetation in the Batavia Reservoir Compound. Therefore, it is apparent that the type of summer flooding that would occur with the project in a summer operational state has occurred in the past and will occur after the project is constructed. Therefore, it is likely that the type of impact that will occur with the project operating to control the 2-year flood has already occurred in the past except that additional areas will be flooded (Table 4.4), and the duration of flooding will be prolonged if the project is constructed.

4.30 Impact of Operation - Due to the fact that flooding could occur during the growing season for mature woody vegetation, in both reservoir pool areas, numerous times during the life of the project, it can be predicted that all the acreage presented in Table 4.5 will be affected by summer operation of the project; cropland (477 acres) and pasture (126 acres) will be flooded, however, they will still be available for farming. It is highly unlikely that these areas will be abandoned as the new channel capacity in Tonawanda Creek, obtained by clearing and snagging, will in most years enhance farming opportunities within the reservoir floodpools. Therefore, for this analysis, the predicted effect on farmlands and pasture is zero acres affected. Operation of the project to control the 2-year flood will result in the inundation of additional areas of shrub swamp (135 acres), emergent marsh (92 acres), and forested wetland (281 acres). This is in addition to areas within the reservoir floodpool boundaries that are already flooded without the project in place. The depth and duration of flooding of these wetland habitats will also be increased (Table 4.5).

AD-A133 918


BUFFALO METROPOLITAN AREA NEW YORK WATER RESOURCES
MANAGEMENT INTERIM REP. (U) CORPS OF ENGINEERS BUFFALO
NY BUFFALO DISTRICT JUL 83


8/9

UNCLASSIFIED

F/G 13/2

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A


TONAWANDA CREEK

JAN/DEC

NUMBER OF FLOWS

2,000 cfs or greater


1945-1979
(99 FLOODS)



TONAWANDA CREEK APRIL / MAY

NUMBER OF FLOWS
2,000 cfs or greater

1945-1979
(27 FLOODS)



PERIOD	NO.	Pct
APR 1-7 (1945-1979)	15	55.6
APR 8-14 (1945-1979)	3	11.1
APR 15-21 (1945-1979)	2	7.4
APR 22-28 (1945-1979)	3	11.1
APR 29-MAY 5 (1945-1979)	2	7.4
MAY 6-12 (1945-1979)	1	3.7
MAY 13-19 (1945-1979)	0	0.0
MAY 20-26 (1945-1979)	1	3.7
MAY 27-30 (1945-1979)	0	0.0
Total	27	100.0

PERIOD

4.31 The following discussion will predict what impacts might occur to the wetland habitats in question if the depth and duration of flooding are increased by operation of the project to control the two-year flood during the summer growing season. Emergent marshes and shrub swamp should not be adversely affected by additional summer flooding as they usually have standing water year round and the vegetative species found in these habitats are highly adapted to or tolerant of standing water. Forested Wetlands occur in greatest abundance along the creek banks and although they require wet soil conditions for best growth year-round, standing water of significant depth and long duration during the growing season might have an adverse effect. To evaluate the potential effect of summer flooding on Forested Wetlands Table 4.7 was developed based upon data and information contained in Teskey and Hinckley (1978) and Whitlow and Harris (1979). Both references contain extensive summaries of research on the effects of prolonged flooding on trees and other woody vegetation. The first column of Table 4.7 lists the most common species of woody shrubs and trees found in Forested Wetlands within the Batavia Reservoir Compound. American beech, shagbark hickory, red oak, and white oak are not common components of the forested wetland areas subject to frequent flooding. They would only be found on dryer, better drained sites. The second, third and fourth columns present flood tolerance information from Whitlow and Harris (1979) for some of the species. Most of this data comes from long-term studies of the effects of flooding on floodplain forests along the Sangamon River in Illinois. The fifth column of the table presents information on the relative tolerance of the species to summer flooding as taken from Teskey and Hinckley (1978). For the most part, the information presented relates to mature trees. Seedlings as previously discussed are much more susceptible to flooding and in most cases have much lower flood tolerance levels than mature individuals, however, many do survive prolonged flooding and as long as mature individuals remain to reseed areas, there should be no significant long term adverse effect on Forested Wetland from any particular flood.

4.32 Careful review of Table 4.7 indicates, with the possible exception of American beech, red oak, and white oak that the tree species found in Forested Wetlands of the reservoir compound are highly tolerant to flooding conditions. Most of the species can survive several months of flooding during the growing season with little or no impact. The data contained in Table 4.2 indicates that flooding duration for the two-year flood in the lower reservoir will increase from 2.4 days under existing conditions to 9.8 days under project conditions. Table 4.3 shows that flooding in the upper reservoir for the two-year flood would increase from 2.5 to 5.3 days with the project. The depth and duration of flooding will also increase as illustrated in Table 4.4.

4.33 Flooding Forested Wetlands for 5.3 days (upper reservoir) and 9.8 days (lower reservoir) under the two-year flood conditions are very short periods of time when compared to the relative flood tolerance of most of the species found in these habitats. It should also be noted that summer floods (flows over 2,000 cfs) represent only about 10% (10 of 99) of the floods recorded for Tonawanda Creek over the 34-year period of record. Therefore, the likelihood of having a summer growing season flood of the 2-year magnitude, with the project in place, is considerably less than once every two

Table 4.7 - Forested Wetlands in the Batavia Reservoir Compound and Relative Flood Tolerance of Dominant Tree Species

Species (1)	From Whitlow and Harris 1979 - Representing			From Teskey and Hinckley 1978 (3)	
	Relative	Maximum Flood duration	Representing a compilation of	studies for the Northern Forest Region	
	Tolerance (2)	Consecutive days	% Survival		
Green Ash*	Somewhat Tolerant	170-189	100		Very Tolerant
Silver Maple*	Tolerant	170-189	100		Tolerant
Red Maple*	-	-	-		Tolerant
Black Willow*	Tolerant	170-189	100		Very Tolerant
Buttonbush*	-	-	-		Very Tolerant
American beech	-	-	-		Intolerant
Shagbark hickory	Somewhat Tolerant	170-189	100		-
Red Oak	Slightly Tolerant	70-89	100		-
White Oak	Slightly Tolerant	110-129	17		Tolerant

(1)* Species listed as common in wetter Forested Wetlands by USF+WS in their 23 October 1980 Coordination Act Report.

(2) Tolerant - most individuals survive 150 or more days of inundation.
Somewhat Tolerant - most individuals survive more than 50 but less than 100 days of flooding.
Slightly Tolerant - some individuals killed in less than 90 days and some survive more than 150 days of flooding.

(3) Tolerant - trees which can withstand flooding for most of one growing season.
Intermediately Tolerant - Species can withstand flooding for one to three months during the growing season.
Intolerant - species which cannot withstand flooding for short periods (1 month or less) during the growing season.

Whitlow Thomas H., and Richard W. Harris, 1979. Flood Tolerance in Plants: A State-of-the-Art review. U.S. Department of the Army, Waterways Experiment Station. TR E-79-2. 161 pp. plus Appendices.

Teskey, Robert O., and Thomas M. Hinckley, 1978. Impact of Water Level Changes on Woody Riparian and Wetland Communities. Vol. V: Northern Forest Region. FWS/OBS - 78/88. 54 pp.

years. From late spring through early summer, the lower reservoir would not impound the higher frequency floods thereby decreasing the chance for a growing season flood. In addition, these areas frequently flood naturally under existing conditions. Based upon data and information contained in the USF+WS reports and numerous observations by Corps of Engineers biologists throughout the course of the study, it does not appear that frequent flooding, under natural conditions, in the Compound area has any significant effect on mature trees and understory vegetation, particularly in forested wetland areas. The conclusion is thereby reached that operation of the project to control the two-year or greater flood will not have any significant impact on wetland habitats within the Batavia Reservoir Compound (Modified).

IMPACTS OF LAND USE CHANGES WITH THE PROJECT

4.34 Introduction - It has been predicted that if the Tonawanda Creek Project is constructed and operated consistent with the operational plan described in the Final Feasibility Report, there will be changes in farming practices both within the lower reservoir area and in downstream reaches of Tonawanda, Ransom, Black and Mud, Creeks. The predicted locations of changed agricultural practices with the project are located in close proximity to the creeks at elevations physically below the flood stage associated with the 3-year flood. Most of the agricultural lands in these areas are idle, used for pasture or for the production of buckwheat. With the project, it is predicted that 3,754 acres of pasture, buckwheat, and idle agricultural lands will be shifted into more profitable, higher intensity agricultural production. These 3,754 acres of lands are located within the Standard Project Flood (SPF) boundaries of Tonawanda Creek and its tributaries. Of the 3,754 shifted acres within the SPF boundary, 2,890 acres are idle agricultural lands and it is predicted that 1,933 of these idle acres will be shifted into active agriculture with the project. Table 4.8 presents various characteristics of the agricultural and non-agricultural acreages for the Tonawanda Creek Watershed.

Table 4.8 - Tonawanda Creek Watershed
Total Acreage and Agricultural Acreages within SPF (Existing Conditions)

Area	Acreage	% of Watershed	% of SPF Boundary
Total Watershed	414,720	100%	N.A.
Agricultural Acreages in Watershed	286,000	69%	N.A.
Within SPF Limits			
- Total Acres	39,667	9.6%	100%
- Agricultural Acres	14,280	3.4%	36%
- Idle Agricultural Acres	2,890	0.7%	7.3%
- Idle Acres Shifted With Project	1,933	0.5%	4.9%

4.35 Idle agricultural lands, within the SPF boundaries and in particular within the limits of the 3-year flood are primarily lands that have been damaged by recent flooding, and to lesser extent lands under crop rotation procedures or out of production due to owner disinterest (removal, retirement or disability). Idle lands also include lands under residential ownership or held by absentee ownership for speculative purposes. Most of the former idle agricultural lands held for speculative or residential purposes are located in the western (downstream) portion of the watershed and are not likely to be shifted into agricultural production with the project. The 2,890 idle agricultural acres are located along various reaches of Tonawanda Creek as described in Table 4.9. Table 4.9 also indicates, by reach, the idle acreages that are predicted to be shifted into active agriculture. Although a breakdown of the 1,933 idle agricultural acres into various component idle categories has not been made, it is assumed for this analysis that the majority of the 1,933 idle acres are lands that are subject to frequent flooding (lands damaged by recent flooding).

4.36 Field surveys by Corps of Engineers personnel to various idle areas have indicated that for the most part these areas have been farmed within the last 5 to 10 years primarily for corn crops. The majority of the areas have been recently plowed and with a minimum of effort on the part of farmers could be returned to active crop production. Most of the idle areas within the SPF boundaries are small (from 5 to 100+ acres) and are interspersed with other farm fields, woodlands, wetlands, wet meadows (pasture) and in many cases border a riparian tree zone on Tonawanda Creek. As Table 4.9 indicates, 1,933 of 2,890 total idle agricultural acres within the SPF boundaries will be shifted into active agricultural use. This represents about 67% of the total idle lands available within the SPF boundaries. The SPF boundaries spread to the north of Tonawanda Creek in reaches T5 to T9 where they interact with overflow from the Mud Creek drainage. To the south in these reaches the SPF boundaries range from 2,000 to 14,000 feet away from Tonawanda Creek. In T13L (Lower Reservoir) the SPF spreads out in the natural basin of the area covering about 5,150 acres of land. In the upper reservoir (T13U) the SPF covers about 930 acres.

4.37 As illustrated in Table 4.9, the overall conversion of idle agricultural lands within the SPF boundaries is rather large (66.9%: 1,933 of 2,890 acres). However, there are large, but unquantified, amounts of idle agricultural acres in the rest of the Tonawanda Creek Watershed. Table 4.8 indicates that 69% of the acreage (286,000 acres) within the Watershed is classified as agricultural. Observations made during the course of the Tonawanda Creek Study indicate that large amounts of these agricultural areas, outside the SPF boundaries, have not been farmed for upwards of 30 to 40 years. Some of these areas are similar to areas within the SPF in that they have been idled during the last 5 to 10 years and have similar habitat value to the 1,933 acres of idle agricultural lands located within the SPF limits. Their primary difference is that they are better drained and are not subject to frequent flood damage. For the purpose of this analysis, it is assumed that the 1,933 acres of idle lands that will convert to agriculture, with the project, represent a minor percentage of recently idled agricultural lands within the entire Tonawanda Creek Watershed.

Table 4.9 - Idle Agricultural Lands Located in Various Reaches
of the Tonawanda Creek Watershed (within the limits
of the Standard Project Flood)

Creek Reach ^{1/}	Idle Agricultural Lands (Acres)	Total Agricultural Lands (Acres)	Idle Agricultural Lands Shifted to Higher Use (Acres)	Percent Idle Agricultural Lands Shifted (Percent)
T-3	30	360	0	0
T-4	0	505	0	0
T-5	150	1,390	120	80
T-6	100	2,080	55	55
T-7	370	1,425	296	80
T-8	320	1,870	202	63
T-9	300	1,095	220	73.5
T-10	NEG.	NEG.	0	0
T-11	195	645	156	80
T-12	45	220	36	80
T-13L	950	3,110	760	80
T-13U	320	700	0	0
RB-1	60	140	48	80
RB-2	50	310	40	80
RB-3	0	875	0	0
RB-4	0	250	0	0
M-1	0	150	0	0
M-2	0	420	0	0
M-3	0	1,070	0	0
M-4	0	290	0	0
M-5	0	1,050	0	0
M-6	0	1,000	0	0
Totals	2,890	18,955	1,933	66.9

^{1/} T-Tonawanda Creek Reaches
RB - Ransom and Black Creek Reaches
M - Mud Creek Reaches

NOTE: The reaches are illustrated on maps contained in Appendix B, Plates B3, B4, and B5 of the Tonawanda Creek Final Feasibility Report.

4.38 Habitat and Wildlife Value of Idle Agricultural Lands - The idle agricultural lands generally provide feeding and cover habitat for various species of birds such as mourning doves, ring-neck pheasants, and numerous small passerine birds. Mammals that frequently use these areas for food and cover include such large game species as white-tail deer and smaller game species such as cottontail rabbit. In addition, other nongame mammals such as woodchucks, raccoons, and numerous small rodents are frequently found in these habitats. The value of the habitat lies not so much in their own intrinsic value, but rather in their interspersions with other habitat types such as wetlands, woodlands, and riverine habitats. Most of the idle agricultural areas are small in size, ranging from a few acres up to about 100 acres in size and are adjacent to undeveloped woodlands, wetlands, or brushy areas along the banks of Tonawanda Creek. In general, most of the idle agricultural areas have not been farmed for 5 to 10 years and were formerly used to produce corn crops. In many cases, the corn was only partially harvested or never harvested due to the wetness of the areas and provides excellent food and cover area for small mammals and birds. In other instances, the crops were harvested, some residue left behind, and the areas were replowed and planted to hay or allowed revegetate naturally. Today, most of the areas consist of degraded (weedy) hay fields or in some cases naturally revegetated fields of grasses, goldenrod, and occasionally some small woody shrubs.

4.39 The remainder of this discussion will present a qualitative biological assessment of the existing habitat quality and wildlife values and uses of the idle agricultural areas in question. It will also describe the changes in the habitat, quality and wildlife values and uses of these areas after conversion to active agricultural use for the production of corn crops. A number of key species (species that are of human use for hunting, fur, meat or are significant for other reasons) will be examined in terms of their use of the habitats and potential damage that might be inflicted on them if the land conversions occur. Brief descriptions of the key species and value of the two habitats follow.

a. White-tailed deer (*Odocoileus virginianus*) - White-tailed deer are the most numerous and widespread species of deer in the United States. They are the major big game species of sportsmen in the eastern U.S. and are most abundant in woodlands. Deer generally prefer areas of dense woods and edge habitat in proximity to open areas where they forage along forest margins and sometimes on farmland. Shrubs and grasses, such as found in the idle agricultural areas, are often eaten in summer. Corn does not usually make up a large proportion of white-tailed deer diet, but they will eat it when available, particularly in winter.

b. Cottontail rabbit (*Sylvilagus floridanus*) - Cottontail rabbits are common species of the fields and brushlands of the eastern U.S. and are hunted extensively for their fur, meat and for sport. In summer, cottontails feed on tender herbaceous plants such as found in idle agricultural lands and elsewhere. Corn does not make up a large proportion of cottontail diet, most of what they eat consists of corn crop residue. Cottontails commonly utilize woodchuck burrows for winter cover and prepare nests, to raise young, in heavily vegetated fields quite often preparing a nest in natural cavities in the ground.

c. Ring-necked pheasant (*Phasianus colchicus*) - Ring-necked pheasants are an important game bird native to Asia that have been successfully introduced into the eastern United States. Their preferred habitat are farmlands, grasslands, and grassy areas adjacent to woodland edges. At times, pheasant can be destructive to grain crops and they often pull up seedling corn. Corn and ragweed are an important part of adult pheasant diets although insects are also eaten. Pheasants are a relatively common game bird of farmfields in the Tonawanda Creek Watershed, although recent years have seen declines in their numbers for unknown reasons. Pheasants commonly nest on the ground in open, heavily vegetated fields and in hedgerows. They do not often nest in cornfields.

d. Red fox (*Vulpes vulpes*) - The red fox is common throughout most of the eastern United States. It occupies diverse habitats, but generally prefers rolling farmlands, mixed with sparsely wooded areas, marshes and streams. They commonly venture into idle farm fields in search of rabbits and mice. The red fox sometimes constructs dens and raises young in open fields although it prefers wooded slopes for den sites. In winter the red fox feeds primarily on mice and rabbits. In summer, it feeds on whatever mammals and birds it can catch. In fall, it eats wild berries, grapes and mice. The Red fox is trapped throughout its range for its fur and is occasionally hunted for sport. About 400 Red fox were trapped in Genesee County, NY during 1981 and 1982. Apart from searching for prey in cornfields, it would not utilize such habitats to any great degree.

e. Raccoon (*Procyon lotor*) - The raccoon is a common animal of the eastern United States and is usually found in areas of woods, swamps, and streams where suitable food and den sites are available. Raccoons forage along streams for crayfish, frogs and fish. They also feed heavily on corn in summer, stripping the ears of growing corn. Excellent raccoon habitat is present along Tonawanda Creek where woodlots are interspersed with cornfields, crop fields, and swampy areas. Raccoons are not frequently hunted for sport but occasionally trapped for their pelts. About 2,000 raccoon were trapped in Genesee County, NY during 1981 and 1982.

f. Red-tailed hawk (*Buteo jamaicensis*) - Red-tailed hawks are common and widespread in the eastern United States. They frequent deciduous forest with adjacent open country. These hawks frequently soar over open country in search of prey or perch in large trees near meadows. These hawks feed primarily on small rodents. They are protected throughout the United States by various State and Federal laws. Red-tailed hawks are quite common in the Tonawanda Creek watershed and excellent habitat is provided with areas of deciduous forest interspersed with idle or abandoned farm fields.

g. Mice: White-footed mouse (*Peromyscus leucopus*); Meadow Vole (*Microtus pennsylvanicus*) and House Mouse (*Mus musculus*) - The three species of mice listed above are the most common and likely to be seen in open field areas of the Tonawanda Creek Watershed. The white-footed mice is a forest dweller that is commonly found in hedgerows and brushy areas and sometimes in open lands near brushy areas. They are omnivorous feeding chiefly on nuts, berries and seeds. Meadow voles, otherwise known as field mice, are common inhabitants of low meadows, swampy areas and fields with protective covers of dead grass and herbs. Their primary food consists of dead grasses and maturing seeds of all kinds. The House mouse has been introduced from Europe and is now widespread in areas inhabited by man. It is found in abundant numbers in cornfields, wheatfields, and grassy areas. These mice provide an abundant food source for raptorial birds and predaceous mammals.

4.40 Habitat Quality Considerations - For this assessment, a number of habitat quality parameters, of variable importance to the key species, have been considered in determining the impact of conversion of idle agricultural areas to active farming for corn crops. The habitat quality parameters include: dependability of winter cover, quality of food, proximity to water; proximity to dense woods; density of vegetation; percent of area in trees; percent of area in shrubs; and percent of area in grasses and forbs. Table 4.10 compares the general characteristics of the habitat quality parameters for idle agricultural areas and actively farmed corn fields in the project impact area. Table 4.11 presents a qualitative assessment of the relative significance of the various habitat quality parameters, irrespective of habitat type, to the key species life requirements.

a. Dependability of Winter Cover - The dependability of winter cover is very important to wildlife for a number of reasons. Winter cover vegetation (heavy bladed grasses, woody shrubs, trees, etc.) provide places of escape and protection from predators; provide relatively safe access to food sources; and provide protection from cold. Idle agricultural areas in general provide fair winter cover. Although most of the grasses will be covered with snow during the height of winter, some woody shrub areas will provide cover. Corn fields provide poor to fairly good winter cover depending upon the completeness of fall corn harvests. In the Tonawanda Creek Watershed and particularly in areas within the poorly drained SPF boundaries, farmers frequently plow their fields after fall harvest. This practice gives farmers a head start on spring planting of crops when plowing is often hard or impossible due to wet soil conditions. Fall plowing is not a universal practice, and often times wet soil conditions prevent fall plowing, but it could be assumed that 25 to 50% of the active fields are fall plowed when possible. In other cases, particularly during wet falls, the corn may not even be harvested in the more saturated areas. Therefore, the dependability of winter cover on actively farmed areas can range from none to a good heavy cover of corn stalks or complete corn plants that provide a good winter cover and food source. Winter cover is of significant importance for mice, ring-necked pheasant and cottontail rabbit among the key species considered.

Table 4.10 - General Characteristics of Idle
Agricultural Areas and Corn Fields

Habitat Quality Parameter	General Characteristics	
	Idle Agricultural Areas	Corn Fields
Dependability of Winter Cover	Fair - Some heavy grasses and a few shrubs not covered by heavy snow.	Negligible to Good - At times, fields fall plowed leaving no cover - at other times, crops left or residue left standing throughout winter providing heavy cover.
Quality of Food	Good - Grasses provide seeds, forbs provide fleshy plants and shrubs provide some fruits.	Excellent - To some degree corn fed on throughout growing season - unharvested or residue provides good although limited food sources.
Proximity to Water	Excellent	Excellent
Proximity to Dense Woods	Good - Areas interspersed with tree stands and gener- ally in close proximity to wooded riparian areas.	Same as for idle agricul- tural areas.
Density of Vegetation	Heavy grass density, some limited areas of woody shrubs.	Good during late summer and early fall - poor during rest of year unless crop is not harvested.
% of area in trees	0%	0%
% of area in shrubs	5-10%	0%
% of area in grasses/forbs	90-95%	0% (1)

(1) Either 100% Corn or some active intrusion of grasses and weedy plants in areas not plowed.

Table 4.11 - Relative Significance of Habitat Quality Parameters to Key Species

	Species							
	W	h	i	t	e	T	a	i
Habitat Quality Parameter	D	l	e	e	d	r	t	e
Dependability of Winter Cover	+	++	++	0	+	0	++	
Quality of Food (Vegetation)	+	++	++	+	+	0	++	
Proximity to Water	0	0	0	+	+	0	0	
Proximity to Dense Woods	++	+	+	+	+	++	0	
Density of Vegetation	+	+	+	+	+	0	++	
Percent of Area in Trees	+	0	0	+	0	++	0	
Percent of Area in Shrubs	+	+	+	++	0	0	+	
Percent of Area in Grasses/Forbs	+	++	++	+	0	0	++	

0 = Little or No Significance
 + = Of Some Significance
 ++ = Of Major Significance

b. Quality of Food. The quality and quantity of food produced by any particular habitat type is of major significance for the survival of any wildlife species. Idle agricultural areas provide good vegetative food sources for all the key species considered except the Red-tailed hawk, and to some degree the Red fox. The variability of seed producing grasses, forbs, and fruit-bearing shrubs provide relatively diverse food sources. Table 4.12 lists some of the common shrubs, forbs, and grasses found in these idle agricultural areas. Conversion of these areas to cornfields will reduce the diversity of vegetation present; however, corn is a widely consumed food of most of the key species. In fact, White-tailed deer, Ring-necked pheasant, raccoon, and mice can cause serious damage to corn crops through their heavy consumption. Any corn left after harvest is used throughout the fall and winter by the same species. The Red-tailed hawk and Red fox are heavy predators on mice and rabbits which are produced in large numbers in both habitat types.

c. Proximity to Water. The proximity to water of the two habitat types and the significance to the key species does not appear to be of major importance. Except, for the raccoon, which typically prefers habitats near creeks and rivers, none of the species appear to have habitat requirements that require close proximity to water. In any event, all the areas considered in this assessment are in close proximity to water.

d. Proximity to Dense Woods. The proximity of habitat types, to wooded areas whether they be idle agricultural areas or actively farmed cornfields is important to several of the key species. White-tailed deer generally spend most of their time in densely wooded areas, coming out to feed in open areas in early morning or late in the afternoon. Red-tailed hawks often perch on large trees, with good vantage points near the edges of fields, searching for prey. Woods provide cover and escape areas for all of the key species. As previously discussed, the idle agricultural areas are small and widely interspersed with other habitat types including dense woods and wooded riparian areas. Conversion of idle areas to active farming will have little or no impact on the proximity of dense woods. It is unlikely that farmers would engage in any clear-cutting of densely wooded areas to increase the size of their fields. To some degree, increasing farming practices in fields adjacent to dense woods will cause disruption to some of the key species that prefer wooded areas for some of their habitat requirements. The narrow shrubby edge habitats located between densely wooded areas and idle agricultural areas that are converted to corn production will occur the greatest disturbance from increased farming activities.

e. Density of Vegetation. The relative density of vegetation is important to wildlife for several reasons. Dense vegetation provides a higher quality cover for some of the smaller species, that are heavily preyed upon, such as mice and Cottontail rabbit. In addition, the greater the density of vegetation, the more food that is usually produced in a given habitat. For the idle agricultural areas, there is a high grass and forb density. For the cornfields there is usually a high late summer and early fall density of vegetation. After harvesting, if fall plowing is not done, there is a high density of cornstalks.

Table 4.12 - Common Shrubs, Forbs, and Grasses Found in Idle
Agricultural Areas Along Tonawanda Creek

Goldenrod
Orchard grass
Raspberry
Blackberry
Elderberry
Ragweed
Virginia creeper
Wild grape
Buckthorn
Nightshade
Chokecherry
Plantain
Vervain (blue)
Wild carrot
Vetch
White and Yellow sweet clover
Cinquefoil
Mustards (Brassica)
Chickweed
Pigweed
Thistle
Sorrel (sheep)
Sedges (in wetter field spots)
Broom sedge
Foxtail
Honeysuckle
Arrow wood vibrunum
Hawthorne
Ground cherries
Beggar ticks
Dandelion
Curly dock

f. Percent of Area in Trees, Shrubs, Grasses, and Forbs. The relative diversity of vegetation in any particular habitat type is of variable importance for the key species, as previously discussed. Neither habitat type has any mature trees, as these agricultural areas have been plowed and farmed within the last 10 years. The idle agricultural areas have a high percentage of grasses and forbs (90-95 percent) and are good habitats for mice, Cotton-tail rabbits, and Ring-necked pheasants.

4.41 Impacts of Conversion of Idle Agricultural Lands on the Key Species. As previously discussed, implementation of the Batavia Reservoir Compound Plan will result in the conversion of 1,933 acres of existing idle agricultural areas in the lower reservoir area and lower watershed to active croplands. The purpose of this section of the analysis is to qualitatively predict the impacts of such conversions on the key species for these habitats. Table 4.13 presents a summary of the predicted adverse and beneficial impacts of the conversions as related to the habitat quality parameters and the ultimate effect on the key species. This table has been developed to take into account the significance of each habitat quality parameter to each key species as indicated in Table 4.11.

4.42 As indicated in Table 4.13, three habitat quality parameters (proximity to water, proximity to dense woods, and percent of area in trees) will not change as a result of the conversion of idle agricultural areas to active farming. Therefore, these factors are not discussed further here.

4.43 Impacts on White-Tailed Deer. Conversion of idle agricultural areas will have both positive and negative impacts on White-tail deer. Winter cover will be slightly reduced for deer, as some of the fields will be fall plowed and left bare of waste corn. However, in fields that are not plowed after harvest or are not harvested at all, large quantities of corn will provide a good late fall and early winter food source for deer. During the summer, deer will occasionally feed on some areas of growing corn, although, at this time, other food sources are readily available for deer. As succession proceeds in idle agricultural areas, if they are abandoned, such areas would become more valuable to deer providing more cover and additional winter food sources. In general terms, the reduction in habitat diversity provided to deer should be somewhat offset by the additional summer and winter food sources provided. There should be limited negative impact on deer populations from the predicted land conversions.

4.44 Impacts on Cottontail Rabbit. Conversion of idle agricultural areas will have some negative impacts on Cottontail rabbit. The dependability of winter cover will be reduced and they will be subject to additional predation in open, plowed fields or they will just avoid these areas. The quality of food provided will be somewhat reduced for cottontails as corn is not widely eaten by rabbits. They prefer soft herbaceous plants in summer and often eat bark and twigs of young trees in winter. Both these food sources are provided in idle agricultural areas. Overall, it appears that there will be some negative impact on cottontail resources from the predicted land conversions.

4.45 Impacts on Ring-Necked Pheasant. It appears that the conversion of idle agricultural areas will have both negative and positive impacts on pheasants. Winter cover, particularly on fall plowed fields will be reduced.

Table 4.13 - Impacts of Conversion of Idle Agricultural Lands to Active Farming (Corn Crops) (1)

	Species						
	W	R	C	P	R	R	T
	h	i	o	t	e	a	i
	i	C	R	N	e	d	c
	t	g	h	R	R	a	T
	e	t	P	h	R	R	T
	T	o	R	N	e	a	T
	a	n	a	e	a	d	c
	i	D	t	b	c	s	c
	l	e	a	b	k	a	F
	e	e	i	i	e	n	o
	d	r	l	t	d	t	x
	:	:	:	:	:	:	:
Habitat Quality Parameter	:	:	:	:	:	:	:
	:	:	:	:	:	:	:
Dependability of Winter Cover	-	--	--	0	0	0	--
Quality of Food (Vegetation)	+	-	++	-	++	0	+
Proximity to Water	NC	NC	NC	NC	NC	NC	NC
Proximity to Dense Woods	NC	NC	NC	NC	NC	NC	NC
Density of Vegetation	0	0	++	0	0	0	+
Percent of Area in Trees	NC	NC	NC	NC	NC	NC	NC
Percent of Area in Shrubs	-	-	-	0	0	0	-
Percent of Area in Grasses/Forbs	0	-	0	0	0	0	-

- = Minor Adverse Impact
 -- = Major Adverse Impact
 0 = Relatively Neutral Impact
 + = Minor Beneficial Impact
 ++ = Major Beneficial Impact
 NC = No change to habitat quality parameter; thus, no impact.

(1) Taken into account in determining the significance of impact is the significance of the habitat quality parameter to the key species as indicated in Table 4.11.

However, pheasants feed heavily on corn and the abundance and quality of food provided to pheasants will be increased. On the negative side, some of the open fields that pheasants nest in will be lost. Hedgerow nesting areas near cornfields will suffer disturbance through the increased agricultural practices in the converted idle areas. Pheasants are creatures of open grassy fields and farmlands. Increasing the amount of utilized farmland if well interspersed with open fields and other habitat types could lead to increase in their numbers. Without the project, it is likely that, some percentage of the 1,933 acres of idle areas would revert through secession, back to wooded areas. This is a general trend for poorer soil agricultural areas throughout the watershed, including the 1,933 acres which suffer damages from flooding or poor drainage. This effect would lead to decreases in preferred pheasant habitat and presumably decreases in their numbers.

4.46 Impacts on Red Fox. The direct impacts of land conversions to the Red fox should be rather minor. Red fox do feed somewhat on wild berries, wild grapes, etc., particularly during the fall. These food sources will be lost with the predicted conversions of idle lands. Indirectly, the impacts have a possibility of being much greater. As previously discussed, Red fox feed heavily on mice (particularly meadow voles) and Cottontail rabbits. Any significant reductions in quantities and availability of such prey species could lead to reductions in Red fox populations. Red fox do on occasion den in open fields, therefore, some denning sites might be lost with the idle land conversions. Discussions in forthcoming paragraphs of this analysis do not predict any major impacts to either prey species; therefore, the conversion of idle agricultural averages should not have a significant impact on Red fox.

4.47 Impacts on Raccoon. Raccoon are not particularly dependent upon either type of habitat (idle agricultural areas or cornfields) considered in this analysis. Good areas of winter cover are provided in nearby woodlands and in the wooded riparian areas along Tonawanda Creek. Raccoon are generally dormant during most of the winter season and do not frequent field areas. In terms of the quality of food provided, there might be a minor positive benefit to raccoons in converted areas where sweet corn is grown. Raccoons frequently "raid" sweet-corn fields and can cause considerable damage. Generally, they do not feed on field (silage) corn, especially in areas where sweet corn is available.

4.48 Impacts on Red-Tailed Hawks. There could be some significant adverse effect on Red-tail Hawks if populations of their prey species (e.g., Meadow voles and Cottontail rabbits) are significantly affected by the land use changes. Discussions made in upcoming paragraphs of this analysis do not predict any major impacts to either prey species; therefore, the conversion of idle agricultural acreage to active farming should not have any significant impact on Red-tailed hawks.

4.49 Impacts on Mice (White-Footed Mouse, Meadow Vole, and House Mouse). The mice considered here are valuable as sources of prey for other species (e.g., Red-tailed hawk, Red fox, and other predators), but otherwise have little or no significance. Most of the impacts associated with land conversions will be detrimental to Meadow vole populations, particularly the loss of winter cover associated with fall plowing of fields. On the other hand, the House mouse is a frequent and common inhabitant of cornfields, and their

populations should increase with the land conversions. White-footed mice are not common inhabitants of idle fields or cornfields, and there should be little impact on their populations. Meadow voles are most commonly found in open grassy fields such as the idle agricultural areas, and conversions of these areas to active cornfields will have some negative impacts on their populations. Spring and fall plowing and harvesting practices will also kill some mice and have an overall detrimental effect on their numbers.

4.50 Significance of Impact of Land Conversion. The purpose of this section of the analysis is to determine if there are any major damages or losses to significant wildlife resources, as represented by the key species. If such losses or damages will occur, and they are of considerable magnitude or affect a particularly significant wildlife resource, then mitigation to offset the predicted damages or losses is appropriate.

4.51 The previous discussion indicated that the conversion of idle agricultural lands have positive impacts on White-tailed deer, Ring-necked pheasant, and Raccoon. Therefore, the projected impacts on these species are not considered further in determination of significance of impacts to wildlife.

4.52 It appears that the predicted land conversions will have direct negative impacts on Cottontail rabbit and mice (Meadow vole) through habitat loss and indirectly have negative impacts on Red-tailed hawk and Red fox through possible reductions in quantity of prey species. Both cottontails and mice (Meadow vole) prefer fields such as found in the idle agricultural areas to cornfields. Both species reproduce and have den sites in the idle areas and tend to feed on corn to only a minor degree. Cottontail rabbits are prolific breeders and produce several litters per year. Meadow voles are extremely fecund and may go through several generations in a single year. Meadow voles are also extremely cyclic with large populations occurring every 4 years or so, that often lead to severe population crashes that may be related to overpopulation stress factors.

4.53 Cottontail rabbits are probably the most intensively hunted small mammal in the Eastern United States and are widely sought for their meat and, to a lesser extent, for their fur. Meadow voles are of little economic significance except for damages that they may inflict on agricultural crops. Mice, in general, are extremely important as prey species to many predators including, in the study area, the Red-tailed hawk and the Red fox.

4.54 Changes in farming practices in the idle agricultural areas within the SPF boundaries of Tonawanda Creek will probably have little or no significant impact on Meadow vole and other mice populations in this area for the following reasons. Although spring and fall plowing of fields could reduce the resident populations of mice, these populations would be quickly replaced by individuals from other nearby habitats. Considering their reproductive potential, it is likely that the disturbed fields would be quickly repopulated. Where cornfields replace idled areas, Meadow vole populations might be reduced somewhat, but it is expected that this would be offset by increases in House mouse numbers. In any event, natural fluctuations in the

populations of these cratures probably has little to do with farming practices. For these reasons, it is concluded here that the predicted conversion of 1,933 acres of idle agricultural lands will have no significant impact on the key species of mice.

4.55 As previously discussed, Cottontail rabbits are an important species in the study area. The projected land conversions will have some impact on their preferred habitat and numbers. Determining the extent and significance of this impact is difficult as populations of cottontails fluctuate greatly throughout their range. They can quickly populate any newly cleared areas due to their reproductive potential. Cottontails will also den in cornfields, raise young, and consume the products of the fields despite the disturbances created by agricultural uses of the areas. The conclusion reached is that there will be some minor adverse impact to Cottontail rabbits as a result of the predicted land use changes. However, this impact should not be significant. Cottontails will still reproduce and find sources of food in the cornfields, although probably to a lesser extent than in the idle agricultural area. A large amount of heavy brush edge habitat, important to cottontails, will be left along the edges of the fields where farmers cannot plow right up to the tree line.

4.56 As discussed previously, the only apparent impact to Red fox and Red-tailed hawk that might result from the predicted land conversions would be reductions in numbers of prey species. Paragraphs 4.52 through 4.55 of this assessment conclude that the impact on cottontails and mice will not be significant. Both Red fox and Red-tailed hawk range widely and utilize whatever prey they can capture. It does not appear that any significant impact to these two predators will occur as a result of the projected land conversions.

4.57 Conclusions as Related to Providing Mitigation. The overall impact of the conversion of 1,933 acres of idle agricultural acres to active farming for corn should not create significant adverse impact to important wildlife species presently utilizing such idle agricultural habitat. With the exception of Cottontail rabbit, which will experience some slight degradation of habitat, no major impacts are expected. These impacts will be confined to the agricultural areas in question within the SPF boundaries of Tonawanda Creek. These 1,933 acres represent about 0.67 percent of the 286,000 agricultural acres present in the watershed. Much of this agricultural acreage is abandoned farmland (some of it idled during the last 5 to 10 years) which provides excellent Cottontail habitat. The conclusion is, therefore, reached that no significant adverse impacts will occur to Cottontail rabbit or any of the other key species as a result of the conversion of 1,933 acres of idle agricultural land to active corn farming as a result of construction and operation of the Batavia Reservoir Compound (Modified). No wildlife resource mitigation is warranted or recommended for the predicted impacts.

5. CONCLUSIONS ON MITIGATION

5.01 Introduction - The previous section of this report presented an analysis of the predicted impacts of the construction, operation, and predicted land use changes that would occur to fish and wildlife habitats and species if the Batavia Reservoir Compound (Modified) Plan is implemented. The purpose of this section of the report is to determine what mitigation is warranted to offset the predicted fish and wildlife impacts. In this regard, the determination of mitigation warranted is based upon the significance of impact to fish and wildlife habitats and species that is expected and Corps of Engineers policy on mitigation.

5.02 Construction Impacts - As previously discussed, the construction of dams and training dikes will directly destroy a number of acres of various habitat types. Table 4.1 illustrates that about 78 acres of cropland and about 5 acres of pasture will be lost by construction of the project. Cropland and pasture are not significant wildlife habitat and are not scarce in the project area. Therefore, it is concluded that mitigation is not warranted for the 78 acres of cropland and 5 acres of pasture that will be lost.

5.03 Table 4.1 indicates that about 12 acres of forested wetland, 33 acres of shrub swamp, and 10 acres of emergent marsh could be impacted by construction of the Batavia Reservoir Compound (Modified). These wetland areas are significant for several reasons. First of all, being wetlands, they are defined as significant by Federal and State laws and Executive Orders relative to wetland protection. Forested wetland, particularly that which occurs along the banks of Tonawanda Creek, is valuable for the creek's fishery as it provides a heavy shade cover along most of the creek. The creek itself, although highly turbid, is rated as a Class A stream. Class A is the highest classification given to streams in New York State. Forested wetlands within the project area also provide very good nesting habitats for numerous species of birds.

5.04 Emergent marshes within the project area have standing water throughout the year with extensive cattail stands. These areas are valuable to wildlife and are used extensively by migrating waterfowl during the spring and summer. Shrub swamps are dominated by woody species, including dogwoods, cottonwoods, and ashes. Wildlife use of these areas is extensive and many shrub species provide an important food source for migrant and resident wildlife. Additional information on these wetland habitats is contained in the U.S. Fish and Wildlife Coordination Act Report, Appendix H, Part 3 of the Main Report.

5.05 Clearing and Snagging - As discussed in paragraph 4.10 to 4.12 of this analysis, clearing and snagging will result in significant impacts to about 20 acres of forested wetland along Tonawanda Creek within the reservoir compound. As previously discussed, forested wetlands are significant wildlife habitats and the areas of debris jams within the creeks waters provide excellent fishery habitat.

5.06 Project Operation - As discussed in Section 4 of this report, operation of the Batavia Reservoir Compound to control the 2-year flood and floods of greater duration will create conditions under which fish and wildlife habitats present in the compound area will be flooded for a greater duration of time and to greater depths. The conclusion of the impact analysis is that this intermittent, flooding will have little or no impact on these habitats. Therefore, no mitigation is warranted for the project operation impacts.

5.07 Conversion of Idle Agricultural Lands - As discussed in paragraphs 4.34 to 4.57 of this analysis, 1,933 acres of idle agricultural lands are predicted to convert back into active agricultural use soon after the project goes into an operational status. However, the impacts to wildlife habitats and wildlife should not be significant if these conversions occur. Therefore, the conclusion is that no mitigation is warranted for fish and wildlife purposes, due to the conversion of 1,933 acres of idle agricultural lands to active farming.

5.08 Conclusion - The Buffalo District has concluded that mitigation is warranted for the fish and wildlife resources associated with 12 acres of forested wetland, 33 acres of shrub swamp, and 10 acres of emergent marsh that will be destroyed by construction of the Batavia Reservoir Compound (Modified). In addition, mitigation is warranted for 20 acres of forested wetland and creek debris jams that will be destroyed during clearing and snagging of Tonawanda Creek within the compound.

5.09 The following section of this analysis recommends mitigation for the fish and wildlife resources associated with these areas and presents a mitigation plan designed to offset the predicted fish and wildlife impacts.

6. RECOMMENDATIONS ON MITIGATION

6.01 Introduction - This section will discuss the various fish and wildlife mitigation recommendations of the U. S. Fish and Wildlife Service (USF&WS); the New York State Department of Environmental Conservation (NYSDEC); and the Corps of Engineers for the Batavia Reservoir Compound (Modified). It will also present a recommended mitigation plan for the project that would be implemented at the NYSDEC's Oak Orchard Wildlife Management Area. In conclusion, this section will describe the proposed mitigation plan and describe relevant costs and institutional arrangements for implementation of the mitigation plan.


6.02 U. S. Fish and Wildlife Service Recommended Mitigation - As discussed in paragraphs 3.07 to 3.14 of this report the USF&WS has recommended that mitigation is not required for the construction and operational impacts (e.g., mudflat formation) of the project. However, the USF&WS has recommended that a Habitat Evaluation Procedure (HEP) analysis be performed on the 1,933 acres of idle agricultural lands that are predicted to convert to active agriculture if the project is implemented. The USF&WS further recommended that the total amount of mitigation acreage (665 acres) as determined in the Original Coordination Act Report be used as an estimate of the total amount of land acreage required for mitigation, until the HEP analysis is performed.

6.03 The Corps of Engineers does not accept this recommendation because the impacts on these idle agricultural areas and the wildlife they support are not expected to be significant. The Corps of Engineers analysis of these land conversions (paragraphs 4.34 to 4.57) has concluded that mitigation is not warranted for the 1,933 acres of idle agricultural lands in question.

6.04 New York State Department of Environmental Conservation Recommended Mitigation - The NYSDEC in a letter dated 10 March 1983 indicated that they generally preferred on-site mitigation and proposed several alternative mitigation possibilities for the Corps of Engineers predicted wetland losses as a result of the Tonawanda Creek Project (see paragraphs 9.05.1 to 9.05.2 of the FEIS). In another letter, dated 17 March 1983, the NYSDEC made a recommendation that mitigation be jointly developed for the 1,900+ acres of upland habitat lost. This refers to the 1,933 acres of idle agricultural land that will be converted to agricultural uses. As previously discussed, the Corps of Engineers has concluded that mitigation is not warranted for these agricultural conversions.

6.05 The Corps of Engineers has developed a mitigation plan for the predicted construction impacts of the Tonawanda Creek project based upon a suggestion of the NYSDEC presented in their 10 March 1983 letter. As one alternative the NYSDEC recommended a possible offsite mitigation plan that would be implemented at the Oak Orchard Wildlife Management Area. This area is currently owned and operated by the NYSDEC. The plan as presented by NYSDEC in the 10 March 1983 letter would require the acquisition of about 30 acres of agricultural land adjacent to Goose Pond (to the east) on the Oak Orchard WMA and reconstruction of existing dikes to increase storage capacity of the impoundment. The Corps of Engineers has further developed and slightly modified the plan suggested by NYSDEC. The modification was made to reduce the amount of private land that would have to be purchased to implement the mitigation plan. Elevation of the levels of Goose Pond would backflood water out of the existing eastern limits of the Oak Orchard WMA into adjacent privately owned farmlands requiring the acquisition of flowage easements on about 6 acres of private lands (average determined by the Corps of Engineers). To minimize land acquisition, the Corps proposes to elevate the existing access roadway along the eastern limits of the WMA in close proximity to Goose Pond (Plate 6.2). Elevation of this roadway would keep the additional water of Goose Pond on the WMA. One acre of private land would have to be obtained to provide an internal drainage pond for farmlands to the east of Goose Pond.

6.06 The Oak Orchard Wildlife Management Area - The Oak Orchard Wildlife Management Area (WMA) is part of a large wetland complex known as the "Oak Orchard Swamp" and is located about 10 miles to the northwest of Batavia, NY as illustrated on Plate 6.1. The Oak Orchard WMA, about 2,500 acres in size, is part of a larger State and Federal wildlife area about 20,000 acres in total size. The Iroquois National Wildlife Refuge owned by the U. S. Fish and Wildlife Service is about 10,800 acres in size and is located adjacent and to the west of Oak Orchard WMA. Further to the west is the NYSDEC's Tonawanda Wildlife Management Area which is about 6,300 acres in size. The areas, together comprise of some of the best waterfowl resting, feeding, and breeding areas in the eastern United States. Upwards of 50,000 Canada geese



and many other waterfowl species use the areas as feeding and resting areas during spring northward migrations. Large numbers of Wood duck, Canada geese, Mallard and Blue-winged Teal are produced on the areas.

6.07 The Oak Orchard WMA is illustrated in detail on Plate 6.2. The area receives most of its water for the marshes from spring flooding of the Oak Orchard Creek and runoff that fills Goose Pond and Oxbow Marsh at the eastern end of the area. Throughout the summer months water from Goose Pond is released into Windmill Marsh and marshes to the west, eventually draining into Iroquois NWR. Goose Pond is about 82 acres in size and relatively shallow in depth with maximum depths of 2 to 3 feet. At maximum levels it can store about 164 acre feet of water.

6.08 Two problems currently occur at Goose Pond and on the Oak Orchard WMA as a result of the limited storage capacity of Goose Pond. The first is that due to the shallow depth of the pond, it frequently freezes completely during the winter months. This situation creates a winter fish kill that completely kills all Northern pike, bass, sunfish, and forage fish that inhabit the pond. To some extent, the pond is "restocked" with fish during the spring floods from Oak Orchard Creek and from survivors of the winter kill. Winter kill results from the freezing over of a water body that effectively blocks any further absorption of oxygen into the water from the atmosphere. If the ice is sufficiently thick, or snow covered, plants die in the pond and rapidly use up available oxygen during decomposition. Fish residing in the pond frequently die as the result of lack of oxygen. Winter-kill is a fairly common phenomenon of shallow northern ponds with high overwintering fish populations.

6.09 The second problem is related to the frequent summer drawdown of Goose Pond to feed water to Windmill Marsh and other marshes at the Oak Orchard Wildlife Management Area. During the summer of 1982 the WMA suffered a severe shortage of water and it was not possible to keep the marshes fully flooded. Under such conditions the edges of the marshes tend to turn into mudflats which creates conditions that can cause outbreaks of botulism. This occurred in 1982 and over 1,500 ducks (mostly Mallards) died as a result. If it is possible to keep the areas flooded during the summer, the conditions surrounding the botulism outbreaks can be minimized or eliminated.


6.10 In order to minimize the two problems at the Oak Orchard WMA and to provide an offsite mitigation plan for the Batavia Reservoir Compound (Modified) flood control plan, it is proposed that certain improvements be made to Goose Pond on the Oak Orchard WMA to increase its water storage capacity. The Oak Orchard WMA is located about 15 miles to the northwest of the site of the Batavia Reservoir Compound. As the area is New York State owned and operated, the habitat improvements and wildlife productivity improvements made at the area will be completely open to the general public for many types of recreational activities including hiking, birdwatching, and fishing and hunting on a regulated basis. Much of the wetland area that will be impacted by the Batavia Reservoir Compound is privately owned and not open for general public use. The mitigation plan has been developed, as much as possible, to provide positive fish and wildlife benefits to offset the significant adverse fish and wildlife impacts of the flood control project.

Although it is an offsite mitigation plan, it provides mitigation of an in-kind nature (e.g., warm fishery habitat improved). The plan has been designed to alleviate the problems at the Oak Orchard WMA consistent with good fish and wildlife management practices and consistent with the desires of NYSDEC personnel who manage the area. The mitigation plan has not been developed to offset the predicted wetland losses on an acre by acre basis, rather, it provides improvements to the WMA that should more than offset the fish and wildlife productivity lost as a result of the Batavia Reservoir Compound.

6.11 Paragraphs 4.10 to 4.12 of this analysis have predicted that removal of debris jams and clearing snags along Tonawanda Creek will have an adverse effect on about 20 acres of riparian habitat and associated fish and wildlife species. The snags and debris jams provide excellent cover and food sources for fish such as Northern pike, Smallmouth bass, sunfish, and numerous forage species. In addition, dead trees along the streambanks provide nesting and den sites for numerous birds, small mammals, and amphibians. Implementation of the proposed mitigation plan on Goose Pond at the Oak Orchard WMA would roughly double the maximum depth of the pond from 2 to 4 feet and would increase its surface area from about 82 acres to about 217 acres. This increase of the overall size of the pond will help alleviate some of the frequent winter fish kill problems that occur on the pond. The additional land areas that will be flooded consists of about 122 acres of open fields and wet meadows surrounding the pond and a mature stand of cottonwood, box elder, red maple, ash, and other flood tolerant tree species. The tree stand is located at the far eastern end of the pond and is about 10 acres in size. The shallow flooding of this area will kill some of the trees. These dead trees will make excellent nesting habitat for cavity dwelling birds such as woodpeckers, kingfishers and owls. Mammals likely to utilize the dead trees for den sites include weasels and mink, raccons, squirrels, and chipmunks. Flooding of this 10-acre tree stand should offset much of the impact of dead tree removal along Tonawanda Creek during clearing and snagging actions. The area is flooded somewhat under existing conditions, particularly during the Spring of the year. The additional depth and duration of flooding is not expected to have any significant impact on wildlife currently utilizing this habitat.

6.12 The annual amount of duck and other wildlife production lost as a result of the construction of the Batavia Reservoir Compound (Modified) and the associated loss of 55 acres of wetland habitat was not determined as a part of this study. However, it is believed that provision of the needed water at Oak Orchard WMA, that is used to flood upwards of 1,000 acres of waterfowl marsh, will stabilize the waterfowl production at the refuge and reduce the outbreaks of boutulism that can occur during summer dry periods will offset the impact of project construction.

6.13 Plan of Improvement - The general plan of improvement for the 82-acre Goose Pond involves reconstruction and raising the height of the dikes (roadways) surrounding the pond, modifying the control structures to the pond, and construction of a 1-acre internal drainage pond on private lands to the east of Goose Pond. These improvements are illustrated on Plate 6.2. These improvements would more than double the water capacity of Goose Pond to about 400 acre-feet and allow for better control of the outflow of Goose Pond in Windmill Marsh and other marshes at Oak Orchard WMA.



6.14 The following modifications would be made to the western dike control structure at Goose Pond. A new 1,200-foot long dike would be constructed about two feet high adjacent to Albion Road. An existing 36-inch corrugated metal pipe culvert would be left in place. The existing concrete box stop log control structure would also be elevated about 2 feet to install additional stop logs. This stop log structure is used to control drainage from Goose Pond to the Windmill Marsh area to the west.

6.15 Along the south side of Goose Pond, a dike (roadway) runs for about 5,500 feet. About 2,100 feet of this dike would be elevated an average of 2 feet to retain the additional water in Goose Pond. An existing 36-inch corrugated metal pipe culvert located about midway along the dike would be left in place. A concrete stoplog control structure at the same location would be elevated about 2 feet to install additional stop logs. This stoplog structure is used to control drainage from Goose Pond into Oxbow marsh to the south.

6.16 To the east of Goose Pond, a portion of the existing access roadway that runs along the border of the Wildlife Management Area would be elevated about 2 feet for a total length of about 650 feet. Also a new dike would be constructed that would extend 250 feet along the border line of the Oak Orchard WMA. The dike would be constructed totally on State owned lands. About 1 acre of land located adjacent to the WMA would have to be obtained (flowage easement) to provide an internal drainage pond for farmlands to the east of the dike (access road). Two 12-inch corrugated metal pipe culverts would be installed along the dike (roadway) to provide internal drainage from the farmlands into Goose Pond. A flapgate would be installed on an existing 12 inches CMP culvert at the low point of the access roadway. This pipe would drain the internal drainage pond during the summer months. An alternative to the dike and internal drainage scheme in this area would be to allow Goose Pond to naturally backflood into the farmlands to the east. This would require the acquisition of flowage easements on about 6 acres of farmlands to the east. To minimize land acquisition, this alternative is not being proposed at the present time. However, before implementation of the mitigation plan, the landowner would be contacted during the advanced design stage to discuss the real estate acquisition options.

6.17 Agency Coordination of the Mitigation Plan - The basic mitigation plan as described in the previous paragraphs was coordinated with the NYSDEC, Avon, New York, regional headquarters in late April 1983. The NYSDEC, in a letter dated 6 May 1983 (Appendix H, Part 3) provided their concerns about the mitigation plan. In summary, NYSDEC reaffirmed their position that they were not opposed to off-site mitigation and stated that they did "....not feel that simple habitat improvement on existing state-owned lands can adequately mitigate for wetland and wildlife habitat destruction." NYSDEC apparently believes that additional land acquisition and improvement for wildlife purposes is necessary to mitigate for the impacts associated with the Batavia Reservoir Compound.

6.18 Costs and Institutional Arrangements - The total first cost of the plan based upon October, 1982 price levels is estimated to be \$76,000. The annual operations and maintenance (O&M) costs are estimated to be \$1,500. A breakdown of the first costs is presented in Table 6.1. The total first costs of the plan would be entirely a Federal responsibility. Design and ultimate construction of the mitigation plan would also be a total Federal responsibility. As the plan is located at the New York State WMA, design of the plan will be closely coordinated with the NYSDEC. The annual O&M cost (\$1,500) would be the responsibility of the Federal Government.* However, the NYSDEC would remain responsible for operating Goose Pond after construction of the mitigation plan for the best overall management of the wildlife management area.

* The Buffalo District is currently coordinating this operation and maintenance responsibility with the NYSDEC who has been asked to absorb the \$1,500 annual O&M cost.

Table 6.1 - Costs of Fish and Wildlife Mitigation Plan at
the Oak Orchard Wildlife Management Area

Item	Quantity	Unit	Unit Price	Cost
Site Preparation	--	L.S.	—	\$ 3,750
Levee Embankment	6,500	C.Y.	6.00	39,000
Drainage Facilities	--	L.S.	—	1,125
Fertilizing, Seeding, and Mulching	11,800	C.Y.	.40	4,720
Mobilization and Demobilization	--	L.S.	—	<u>1,000</u>
Subtotal				49,595
Contingencies at 25 percent				12,405
Engineering and Design				6,000
Supervision and Administration				<u>7,000</u>
Subtotal				75,000
Lands and Damages				<u>1,000</u>
Total Cost				76,000

APPENDIX H, PART 3

CORRESPONDENCE FROM THE U.S. FISH AND WILDLIFE SERVICE
AND NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

CONTENTS

23 October 1980 U.S. Fish and Wildlife Service Coordination Act Report

23 February 1983 Supplement to the Fish and Wildlife Service Coordination Act Report

10 March 1983 letter from the New York State Department of Environmental Conservation, Avon, NY, Regional Headquarters

17 March 1983 letter from the New York State Department of Environmental Conservation

6 May 1983 letter from the New York State Department of Environmental Conservation, Avon, NY, Regional Headquarters

1 July 1983 letter from the U.S. Fish and Wildlife Service



UNITED STATES
DEPARTMENT OF THE INTERIOR
FISH AND WILDLIFE SERVICE
100 Grange Place
Room 202
Cortland, New York 13045

October 23, 1980

Colonel George P. Johnson
District Engineer, Buffalo District
U.S. Army Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Johnson:

This constitutes our report on effects the flood control project for the Tonawanda Creek Watershed, Towns of Batavia and Alexander, Genesee County, New York, would have on fish and wildlife resources. It was prepared under the authority of and in accordance with Section 2(b) of the Fish and Wildlife Coordination Act (48 Stat. 401, as amended; 16 U.S.C. 661 et seq.). This report supersedes our report of April 16, 1980.

Authorization to study the feasibility of flood management in the Tonawanda Creek Watershed, New York, derives from a resolution of the Senate Committee on Public Works, United States Congress, adopted June 15, 1950. This authorization was expanded by resolutions of the House of Representatives Committee on Public Works, United States Congress, adopted August 16, 1950 and July 23, 1956. Present authorization provides only for a determination of project feasibility, whereas additional feasibility studies (General Design Memorandum), as well as the actual construction, have yet to be authorized and funded by Congress.

Engineering and geophysical data presented in this report are from the Interim Report on Feasibility of Flood Management in Tonawanda Creek Watershed and Technical Appendices (U.S. Army Corps of Engineers, 1979) and from communications with your office prior to February 15, 1980. Biological data are primarily from field reconnaissance conducted by personnel from your office and from our office in Cortland, New York.

Data were also taken from unpublished Hunter Use and Game Survey Reports for the Batavia Cooperative Hunting Area, New York State Department of Environmental Conservation, Avon, New York and from unpublished fisheries surveys conducted in the Tonawanda Creek basin by the State University of New York at Buffalo and Bio Systems Research, Inc., Buffalo, New York. Baseline habitat conditions were evaluated by an interagency team comprised of personnel from your office, the U.S. Fish and Wildlife Service, and the New York State Department of Environmental Conservation using the Service's Habitat Evaluation Procedures. Our analysis is based on a 100-year project life for the years 1980 through 2079.

This report has been reviewed and endorsed by the Division of Fish and Wildlife of the New York State Department of Environmental Conservation as signified by the attached letters from Director Kenneth F. Wich, dated February 20 and September 29, 1980.

DESCRIPTION OF THE PROJECT

The selected plan for flood management in the Tonawanda Creek Watershed is the Batavia Reservoir Compound (modified) (Fig. 1). The proposed plan is to construct two floodwater detention reservoirs (dry dams) on Tonawanda Creek for the primary purpose of reducing average annual flood damages in the lower basin by approximately 74 percent. At maximum floodpool, the reservoirs would inundate a tract of roughly 4,763 acres (1,929 ha) (about 894 acres (362 ha) in the upper reservoir and 3,869 acres (1,567 ha) in the lower reservoir) of bottomland between the Village of Alexander and the City of Batavia, Genesee County, New York.

The upper dam would be located approximately 200 feet (61 m) downstream of the Delaware Lackawanna Railroad (Conrail) embankment and would stretch 5,450 feet (1,661 m) across the Tonawanda Creek Valley (Fig. 1). The width by height dimensions of the dam would be 98 x 19 feet (30 x 5.8 m). This embankment would be designed to function as an emergency spillway with a top elevation of 922.5 feet (281.2 m). Approximately 2 feet (60 cm) of water would flow over the dam during a Standard Project Flood assuming a maximum pool elevation of 924.5 feet (281.8 m).

The principal outlet works for the upper reservoir would consist of a control structure, stilling basin, and outlet channel located at or near the intersection of the upper dam and Tonawanda Creek. The control structure would be a five-conduit reinforced concrete box culvert with the capacity to pass flows of 2,000 cfs (56 cms) under natural flow conditions and up to 10,700 cfs (300 cms) under the 100-year flood condition. Each conduit would be 11 feet wide by 11 feet high (3.4 x

3.4 m) and equipped with an electrically operable fixed wheel control gate. An upstream inlet flume would funnel water into the gated conduits. The inlet flume would consist of a reinforced concrete section located adjacent to the control gates and steel sheetpile wingwalls. The channel bottom between the wingwalls would be protected with 24-inch (60 cm) riprap placed on a 12-inch (30 cm) bedding layer. The riprap would extend from the concrete floor slab to a line 10 feet (3 m) upstream of the wingwalls. The stilling basin would be a reinforced concrete structure 61 feet (18.6 m) wide and 62 feet (18.9 m) long with a raised end sill 4 feet (1.2 m) high. A new outlet channel, starting at the stilling basin end sill, would be excavated normal to the dam and would extend downstream for approximately 1200 feet (366 m) to a junction with the existing creek channel. The outlet channel bottom, flaring from a width of 71 feet (21.6 m) at the stilling basin to 91 feet (27.7 m), would be protected with 24-inch (60 cm) riprap placed on a 12-inch (30 cm) bedding layer for a distance of approximately 100 feet (30.5 m). The meandering Tonawanda Creek channel immediately downstream from the upper dam would be abandoned.

The lower dam would be located approximately one-half mile (0.8 km) south of the City of Batavia and would stretch 5,600 feet (1,707 m) across the Tonawanda Creek valley (Fig. 1). The width by height dimensions of the dam would be 69 x 12 feet (21 x 3.7 m). This embankment is designed to function as an emergency spillway with a top elevation of 900 feet (274.3 m) from Creek Road westward for approximately 4,000 feet (1,219 m). Approximately 2.6 feet (80 cm) of water would flow over the dam during a Standard Project Flood assuming a maximum pool elevation of 902.6 feet (275.1 m). From Creek Road to the east abutment, and for a short distance at the west abutment, the embankment is designed as a non-overflow section with a top elevation of 905.5 feet (275 m) and grassed slopes.

The principal outlet works for the lower reservoir would consist of a control structure, stilling basin, and outlet channel located 900 feet (275 m) east of the intersection of the lower dam and Tonawanda Creek. The control structure would be a four-conduit reinforced concrete box culvert with the capacity to pass flows of up to 6,000 cfs (168 cms) under the 500-year flood condition. Each conduit would be 11 feet wide by 11 feet high (3.4 x 3.4 m) and equipped with an electrically operable fixed wheel control gate. An upstream inlet flume would funnel water into the gated conduits. The inlet flume would consist of a reinforced concrete section located adjacent to the control gates and steel sheetpile wingwalls. The channel bottom between the wingwalls would be protected with 24-inch (60 cm) riprap placed on 12-inch (30 cm) bedding layer. The riprap would extend from the concrete floor slab to a line 10 feet (3 m) upstream of the wingwalls. The stilling basin would be a reinforced concrete structure 48.5 feet (14.8 m) wide and 62 feet (18.9 m) long with a raised end sill 4 feet (1.2 m) high. A new inlet channel, starting at the inlet flume, would be excavated normal to the dam and would extend upstream for approximately 500 feet (152 m) to a junction

with the existing creek channel. A new outlet channel, starting at the stilling basin, would be excavated normal to the lower dam and would extend downstream for approximately 100 feet (30.5 m) to a junction with the existing creek channel. The outlet channel bottom, flaring from a width of 48.5 feet (14.8 m) at the stilling basin to 70 feet (21.3 m), would be protected with 24-inch (60 cm) riprap placed on a 12-inch (30 cm) bedding layer for its entire length. The meandering Tonawanda Creek channel immediately upstream from the lower dam and west of the principal outlet works would be abandoned.

Several non-overflow training dikes would be located along the east and west sides of the Tonawanda Creek valley (Fig. 1). Along the east side, a dike would stretch 950 feet (290 m) across a natural saddle located approximately 1,000 feet (305 m) south of East Road. Along the west side, three dikes would be located approximately 500 feet (152 m) east of Route 98 in the reach between Cookson Road and the Lehigh Valley Railroad (Conrail) embankment. These dikes would stretch 3,330 feet (1,015 m), 600 feet (183 m), and 150 feet (46 m) across low areas in order to prevent possible overtopping of Route 98. The maximum height of these dikes varies from 5.5 to 9 feet (1.7-2.7 m). To provide the required interior drainage, each dike would have a gated culvert consisting of a 24- to 36-inch (60-90 cm) diameter reinforced concrete pipe, reinforced concrete headwalls and wingwalls, and automatic flap gates mounted on the reservoir side of each dike.

The two dams and four training dikes would be earthen fill structures having 1 vertical on 3 horizontal side slopes; the dikes would be seeded and the dams riprapped on both upstream and downstream faces. The riprap would be chinked with 6 inches (15 cm) of topsoil and seeded with crown vetch.

Construction of the dams and dikes would require stripping an area of 35.6 acres (14.4 ha). Of this total, 14.3 acres (5.8 ha) would be cleared and grubbed. Also, construction of the dams and dikes would require the filling-in of 8.9 acres (3.6 ha) of wetland associated with the lower reservoir.

Downstream from the upper reservoir a section of Peaviner Road and the existing bridge over Tonawanda Creek would require relocation due to the realignment of the creek channel in the vicinity of the principal outlet works. A 60-foot (18 m) span highway bridge would be provided over the new outlet channel from the principal outlet works. The abandoned Lehigh Valley Railroad (Conrail) bridge over Tonawanda Creek would be permanently removed to improve hydraulic conditions downstream of the lower reservoir.

The existing Tonawanda Creek channel within the lower reservoir would be cleared of snags and debris jams to ensure a channel capacity of roughly 2,000 cfs (56 cms). Dead trees along the channel banks and overhanging, partially uprooted trees would also be removed. The sections of abandoned creek channel would be utilized as spoil areas for waste materials from clearing and stripping operations associated with the construction of the upper and lower dams and from clearing and snagging operations along the existing creek channel within the lower reservoir.

Under the present plan, all lands lying within the reservoir floodpool boundaries would be placed under flowage easement with the private landowners. These lands could still be farmed, but 37 residences and 3 farmsteads in the lower reservoir and 8 residences in the upper reservoir would have to be purchased and removed.

DESCRIPTION OF AQUATIC AND TERRESTRIAL ECOSYSTEMS

General

The Tonawanda Creek Watershed, an area of about 648 square miles (1,678 square kilometers), is located in western New York and includes portions of Erie, Genesee, Niagara, Orleans, and Wyoming counties. It occupies parts of two physiographic provinces -- the Appalachian upland and the Erie-Ontario lowland. Tonawanda Creek, the major stream of the watershed, rises in the Cattaraugus Hills in the Town of Wethersfield in Wyoming County. From its source, approximately 1,929 feet (588 m) above sea level, the creek flows northward approximately 22 miles (35 km) through deep valleys with steep sides and slopes to enter the Erie Plain near the Village of Attica. From Attica, the creek continues to flow northward for nearly 20 miles (32 km) through essentially flat bottomland to the City of Batavia, where erosion resistant rock formations of the Onondaga Escarpment turn the creek's channel to a westward flow through the Erie Plain. Lands surrounding the creek and its tributaries consist primarily of farm fields and various types of natural open space, including grass fields, wetlands, brush, and forests. The creek also passes through residential, commercial, and industrial areas in the villages of Attica and Alexander, and in the City of Batavia.

Aquatic Resources

The portions of Tonawanda Creek and its tributaries lying within the project area are designated Class "A" waters by the New York State Department of Environmental Conservation (NYSDEC). Class "A" is the highest water quality category in New York's classification system, but the NYSDEC does not consider this area to be trout inhabited water (Class "A(t)"). While trout are not normally stocked in these waters, some brown trout have been found in the Little Tonawanda Creek tributary (Table 1).

A wide diversity of aquatic macro-invertebrates have been collected from Tonawanda Creek and the Little Tonawanda Creek tributary (Great Lakes Laboratory, 1976). In both creeks the aquatic macro-invertebrates collected were primarily indicative of relatively unpolluted stream conditions. The dominant macro-invertebrate groups sampled were amphipods, anisopterans (dragonflies), dipterans (midges, true flies, horse flies, and black flies), coleopterans (water beetles), hemipterans (water boatman, water striders, and water scorpions), decapods (crayfish), ephemeropterans (mayflies), gastropods (snails), isopods, lepidopterans (water moths), megalopterans (alderflies), oligochaetes (aquatic earthworms), sphaeriids (clams), trichopterans (caddisflies), and zygopterans (damselflies).

Tonawanda Creek meanders through numerous farm fields, but is relatively undisturbed by most farm-related activities. However, intensive agricultural practices in the watershed tend to increase water runoff and thereby result in an increased sediment load in the creek during wet periods. The creek also passes through brushlands and forested areas, and is well-shaded for most of its length by a thick growth of riparian vegetation. This shading tends to create a cool, glen-like situation along the creek, even during the warmest days of summer. The banks are steeply sloping and usually consist of sand or clayey mud. Fallen trees and branches stretch across the creek in many places, and these snags tend to collect woody debris behind them. Turbid conditions seem to prevail throughout the year, with the creek being clearest during low-flow conditions (usually in summer) and most turbid during periods of peak runoff. Current in the main creek channel is relatively slow and water depth is variable, ranging from as little as 4 inches (10 cm) in riffle areas to greater than 4.3 feet (1.3 m) in deep pools (Bio Systems Research, 1979). The largest tributary of Tonawanda Creek, Little Tonawanda Creek, varies greatly in character: the upstream stretches are low, clear, rocky, and have moderate flow, whereas the downstream stretches are more turbid, silt-laden, and have a slow current (ibid.). Several other tributaries are present and their physical conditions vary like those of Little Tonawanda Creek. A number of ponds and oxbows are located in the project area. These lentic environs are warm, turbid, have mud bottoms, and are sometimes connected to channels having intermittent flow conditions.

Fishing in Tonawanda Creek occurs primarily in the vicinity of automobile and railroad bridges, where access is best. Float-fishing is possible, but difficult because of snags and debris jams in the creek. Small tributaries, ponds, and oxbows are fished quite readily from shore. Sport fishes sought include smallmouth bass, largemouth bass, and northern pike. Brown trout are present in Little Tonawanda Creek and they probably sustain some fishing pressure. Available panfish species include the pumpkinseed, bluegill, green sunfish, rock bass, yellow

perch, and brown bullhead. Numerous forage fish are also present. A total of 29 species of fish have been found to occur in this portion of the watershed (Table 1).

Terrestrial Resources

Terrestrial vegetation consists primarily of cropland, hayfield, pasture, emergent marsh, shrub swamp, and forested wetland. These cover types also encompass wet meadows, riparian hardwood stands, and vegetation associated with railroad rights-of-way. Farmlands consisting of hay, pasture, and crops of corn, sunflowers, and beans tend to dominate the landscape.

Wet meadows are the most homogeneous of existing cover types and are dominated by introduced species of yellow and white iris. Other plants found in association with the iris were skunk cabbage, purple loosestrife, and various sedges and grasses. Few vertebrates were found in association with this cover type and those that do occur are usually associated with open water pools, or are only seasonally present. Gray treefrogs, leopard frogs, bullfrogs, kingbirds, bobolinks, red-winged blackbirds, barn swallows, spotted sandpipers, mallard ducks, and muskrats have been found in association with this cover type in late spring and summer, and migrating shorebirds and waterfowl have been observed to make extensive use of these areas in spring and fall.

Emergent marshlands typically have a heterogeneous mixture of open water and several species of cattail. Other plants found in association with cattail marshes were willow, purple loosestrife, yellow iris, white iris, water parsnip, water hemlock, nightshade, sensitive fern, and various horsetails, sedges, and grasses. These areas usually have some standing water throughout the year and have much intrinsic value to wildlife. Some species, including many frogs, toads, salamanders, and birds, require these areas for their seasonal breeding activities and for the development and the raising of young. Other species, such as barn swallows, tree swallows, and kingfishers, use these areas solely for feeding, whereas fish, green frogs, bullfrogs, water snakes, aquatic turtles, and some birds are year-round residents. Migrating waterfowl, herons, and shorebirds use these areas extensively in spring and fall.

Shrub swamps are comprised of woody species such as red-osier dogwood, silky dogwood, arrow-wood, buckthorn, slippery elm, hawthorne, willow, eastern cottonwood, and white and green ash. Herbaceous species present include purple loosestrife, yellow iris, bindweed, Joe-Pye-weed, and various grasses, sedges, and legumes. Wildlife use is extensive and many resident and non-resident species have been observed in these areas (Table 2). Most shrub species provide an important winter food resource for resident birds and mammals, and for migrant birds in spring and fall.

Forested wetlands vary from permanently flooded to seasonally dry and the plant species composition tends to vary with the moisture regime. The wettest areas are dominated by green ash, silver maple, red maple, and willow. Other species associated with wet areas include silky dogwood, buttonbush, slippery elm, honeysuckle, water parsnip, water plantain, cardinal flower, and fringed loosestrife. Drier sites are dominated by American beech, shagbark hickory, bitternut hickory, red oak, white oak, and sugar maple. Other species in dry sites include silver maple, green ash, choke cherry, ironwood, witch-hazel, buckthorn, hawthorne, wild grape, wild rose, woodbine, Christmas fern, blue cohosh, enchanter's nightshade, beggarticks, and May-apple. Forested wetlands have a diverse vertebrate fauna associated with them (Table 2) and are an important component of the terrestrial ecosystem, providing, for example, many nesting sites for birds, denning sites for snakes and mammals, and cover for terrestrial amphibians.

Railroad rights-of-way possess a diverse floral association that includes forests, shrublands, and old-field herbaceous situations. Species most intimately associated with these rights-of-way include hawthorne, slippery elm, staghorn sumac, willow, box-elder, common elderberry, arrow-wood, buckthorn, red-osier dogwood, woodbine, and wild grape. Herbaceous species found were numerous and include teasel, milkweed, Queen Anne's lace, poison-ivy, cow parsnip, touch-me-not, sorrel, curled dock, and various grass species. The faunal component was equally diverse (Table 2), while the diversity of both the flora and fauna seemed richest on the unmanaged and abandoned rights-of-way.

In general, and as a group, amphibians are well represented in the project area (Table 2) and they are quite abundant. The consistently damp soil conditions seem to favor frogs and toads, but may be limiting for salamanders. Seasonal ponds, emergent marshes, shrub swamps, and forested wetlands are used by these species for their spring breeding activities. Green frogs and bullfrogs spend both their larval and adult life stages in these aquatic habitats, whereas wood frogs, gray tree frogs, spring peepers, American toads, and the Jefferson's and blue-spotted salamanders spend their adult life in shrubby and wooded areas. Adult western chorus frogs and northern leopard frogs spend the summer in grassy fields and wet meadows. The more aquatic amphibians, including the green frog, bullfrog, and northern leopard frog, overwinter in the mud at the bottom of aquatic habitats, whereas the more terrestrial species tunnel into the soil of upland habitats.

Reptiles are represented by at least six snakes and three turtle species (Table 2), but this group is generally quite secretive and could be more diverse than is indicated by the available information. Snakes are wide ranging and utilize most of the various habitats available to them in the project area, with the exception of water snakes which are restricted to aquatic areas. The three turtle species are primarily aquatic; the

painted turtles and snapping turtles being most common in ponds, marshes and swamps, whereas the wood turtles are restricted to streams and associated riparian habitats and forested wetlands.

The avian component constitutes a visible and integral part of the Tonawanda Creek basin fauna. In numbers of species, birds were the most abundant vertebrate group. A diversity of habitat types interspersed with intensive agriculture provided what seemed to be excellent conditions for successful avian reproduction. Avian species observed during spring and summer breeding bird surveys in 1979 are listed in Tables 2 and 3. Birds observed in the basin during spring and summer, but not known to breed there, were the great blue heron, great egret, American bittern, and red-bellied woodpecker.

Aside from the use of the basin by breeding birds, there is considerable use of the area during spring and fall by migrants, and in summer by non-breeders. In the spring of 1979, two separate flocks of approximately 800-1,000 Canada geese each were observed on partially flooded farmlands at two locations near the main creek channel and within the bounds of the lower reservoir floodpool. The basin seems to serve as an alternative feeding and resting area for the enormous numbers of migrating ducks and geese that stop at nearby Iroquois National Wildlife Refuge each spring. Great blue herons, usually single but sometimes in flocks of 10-12, were observed throughout the basin during the spring and summer of 1979. One such flock was observed regularly in the large wetland complex near the junction of the Erie and Delaware Lackawanna (Conrail) railroads.

A diverse mammalian fauna is present in the Tonawanda Creek watershed (Table 2) and a wide variety of habitats are utilized, including marshes, swamps, forests, and agricultural lands. Mink, muskrats, raccoon and white-tailed deer seemed most abundant and were found in very close association with Tonawanda Creek and adjacent forested wetlands. Two important fur-bearers, beaver and river otter, were not observed during field reconnaissance, but both species have been previously reported from the Batavia-Alexander area by State biologists.

Public hunting is permitted on many private lands through cooperative agreements between landowners and the New York State Department of Environmental Conservation. The trapping of furbearers is also pursued, but there is no provision for this activity on Coop lands. Game species taken by hunters include raccoon, red fox, eastern gray squirrels, eastern cottontail rabbits, white-tailed deer, woodcock, ring-necked pheasant, and various ducks, geese, and rails. Furbearers taken by trappers include mink, muskrat, and raccoon.

The five major terrestrial habitat or land-use types in the project area were evaluated by an interagency team on September 20-21, 1979 using the Service's Habitat Evaluation Procedures (U.S. Fish and Wildlife Service, 1979a). Baseline habitat data were established by measuring and/or estimating the physical and vegetative habitat characteristics important to the wildlife species used in the evaluation. The evaluation elements (wildlife species) utilized (Table 4) were selected as being representative of the wildlife forms present in the project area and include species that are: (1) economically important; (2) of high public interest; (3) good indicators of habitat quality; and (4) of particular interest due to restricted range, high vulnerability, and/or special habitat requirements. The habitat inventory characteristics measured and/or estimated (Table 5) were derived from life history accounts developed for this particular evaluation (U.S. Fish and Wildlife Service, 1979b). Cover maps were prepared (Figures 2 and 3) and surface area was estimated based on maximum floodpool elevations provided by your staff in August, 1979, (922.5 feet (281.2 m), upper floodpool; 900 feet (274.3 m), lower floodpool). Table 6 depicts the baseline Habitat Suitability Indices (HSI), the surface area (hectares), and the Habitat Units (HSI x hectares) determined for each habitat type. HSI is an estimate of the relative value of a particular habitat type to the wildlife species used in the evaluation. For comparison, forested wetland received the highest rating for wildlife (HSI=0.803) and cropland the lowest (HSI=0.605).

PROJECT IMPACTS ON AQUATIC AND TERRESTRIAL ECOSYSTEMS

General

No comprehensive studies have been made to assess the effects of dry dams and their operation on either aquatic or terrestrial ecosystems; therefore the beneficial and adverse impacts of the Batavia Reservoir Compound on fish and wildlife are treated primarily in terms of the impacts that we are best able to evaluate. These are generally short-term effects, but the long-term effects of dry dams are also considered where there is sufficient information available to undertake a cogent analysis of potential project impacts.

Aquatic Resources

The construction of dry dams, lateral dikes, and outlet works could result in the potential for erosion of soil into the creek and the re-suspension of bottom sediments, resulting in an increased level of turbidity in the creek in the immediate vicinity of and downstream from project construction and maintenance activities. The increased level of

turbidity could then stress fish and macro-invertebrate populations, especially fish eggs and larvae, which are particularly sensitive to changes in the concentration of suspended solids. Filter-feeding invertebrates would be the most adversely affected invertebrate group. However, fish are usually more sensitive to suspended solids than are most invertebrates. Stern and Stickle (1978) reviewed the effects of turbidity in aquatic environments and listed: (a) thickening of gill lamellae, (b) excessive mucous secretion, (c) abrasion of branchial epithelium, and (d) respiratory distress as the potential stressing effects on fish from high concentrations of suspended solids. They also cited the clogging of opercular cavities and gill filaments with clay particles as factors leading to death. Suspended solids were reported to cause a delay in the hatching of fish eggs, often for several hours. Turbidity and suspended solids concentrations lower than those necessary to cause death or physiological injury may also produce other responses, including a disturbance in the normal population social structure and a general reduction in activity that may reduce the fishes ability to locate food and increase their susceptibility to predation (Heimstra et al., 1969). Many of these effects would be expected to occur during and immediately following construction activities. They would be particularly adverse if construction were to take place during late spring and early summer when most fish breed (spawn) and when eggs, larvae, and young fish are developing. High suspended solids concentrations would be least harmful to fish if they were present during the winter months rather than in summer.

The retention of flood waters and their regulated release would have both beneficial and adverse effects on the aquatic ecosystem. Reservoir regulated discharges, which are held at or below the bank-full stage most of the time, would reduce bank erosion and bed scour and decrease the amount of sediment picked up from the stream bed or brought in from the flooding of bottomlands (Neel, 1963). These same conditions would extend under some conditions the period of increased turbidity in Tonawanda Creek beyond that found under flooding conditions without the project. Whereas most flooding would pass suspended particulate matter through in less than three days, the project would hold and release turbid floodwaters for as long as 9.8 days. Despite the settling out of suspended particulates in the reservoirs, some of the material would be resuspended by waters leaving the reservoir compounds. The prolonged turbid conditions could then severely stress fish and macro-invertebrate populations both downstream from and within each of the reservoir compounds. The potentially adverse effects of these conditions on aquatic resources would be essentially the same as those discussed in the above paragraph and they warrant no further discussion here. It should be noted, however, that while most fish will survive the normal increase in turbidity experienced under annual flooding, the effects of prolonged turbidity could be adverse.

The severity of any adverse effects would be increased if flooding were to occur during late spring or summer when many fish species are breeding (spawning) and when eggs, larvae, and young fish are developing.

The removal of snags and debris from the main creek channel would result in both beneficial and adverse impacts. Snag removal would permit the free passage of boats along the creek and therefore result in greater opportunities for public use of fish and wildlife resources. On the other hand, the snags, debris, and associated sediment deposits create significant habitat for macro-invertebrates, fish, frogs, and turtles. Their removal would reduce both the availability and the diversity of aquatic habitats. Many aquatic insects, including collectors (caddisflies), scrapers (mayflies), and predators (stoneflies and hellgrammites), are all common inhabitants of log and debris jams (Hynes, 1970). Many fish species congregate near obstructions (*ibid.*), and frogs and wood turtles use them for shelter and basking sites. Sediment deposits (which would be eroded if the snags were to be removed) serve as substrates for burrowing invertebrates such as chironomids, ephemeropterans, anisopterans, annelids, crustacea, and molluscs (Hynes, 1970; Anderson *et al.*, 1977). Detritivorous invertebrates utilize the organic matter and/or the micro-flora of sediments as a food resource (Anderson *et al.*, 1977). Any shift or reduction in the macro-invertebrate population would cause a reduction in the productivity of fish species dependent upon that resource.

Riparian vegetation damaged or destroyed during snag removal could result in increased stream temperatures through increased incipient solar radiation received at the surface of the creek (Ringler and Hall, 1975). Increased water temperatures would significantly affect the quality of the aquatic environment, potentially resulting in a change in the structure of the aquatic community.

The construction of dry dam outlet works would inhibit to some extent the normal movements of fish species present in Tonawanda Creek. Northern pike, white suckers, and various other fish species are known to migrate to spawning areas; therefore if the outlet structures impede their passage, either physically or through changes in fish behavior, then reduced reproduction would likely occur for the affected species, along with a change in the structure of the fish community.

The flooding of one or both of the reservoir floodpools would result in some fish moving out of their normal habitat and into the temporary reservoirs. With subsequent drawdown, some stream species could become stranded in permanent pond habitats, whereas others could become stranded in ponds or pools of water that eventually go dry. In either case, some fish mortality could be expected. Should flooding occur during the spawning season of a particular species then these activities would likely be suspended and in some cases an entire season of reproduction

could be delayed or possibly lost. If developing eggs should become covered with sediments deposited by flood waters then significant mortality could be expected at that life stage.

Terrestrial Resources

Construction of the Tonawanda Creek Flood Control Project would necessitate the stripping of about 35.6 acres (14.4 ha) of wildlife habitat for dry dam and lateral dike placement. These habitats provide shelter, food resources and breeding sites for many amphibians, reptiles, birds, and mammals found in and around the location of the proposed flood management structures. We estimate that approximately 9.2 Habitat Units would be lost due to the construction of these structures (Table 7).

Streamside activities necessary for snag removal would disturb riparian vegetation that both stabilizes the creek banks and provides wildlife cover. Riparian areas would be further affected by the placement of dams across the creek and the abandonment and filling-in of portions of the creek channel. These areas provide optimal habitat for some species such as the mink and wood turtle, thus damage to riparian areas could have significantly adverse effects on wildlife found in that habitat, including a significant reduction in species diversity and carrying capacity in remaining habitat.

Many amphibians, reptiles, birds, and mammals could be significantly affected by complete inundation of terrestrial habitats. Whereas most vertebrate communities can adapt to a permanent change in water level, they cannot respond effectively to rapid and irregular short-term inundation; therefore significant mortality could occur, especially during the breeding/nesting season should inundation occur at that time. For reptiles and birds, inundated eggs and/or young would result in a significant loss of embryos and/or nestlings for a particular year. Similar mortality could occur for mammalian young should their dens or nests become flooded while the young are still in early stages of development. Flood-water inundation would force many wildlife forms to higher, unflooded areas resulting in unnaturally high concentrations of wildlife on floating debris and on projecting trees and land areas. These concentrations would then result in increased predation and competition, and also in increased stress that would likely result in death for some individuals. Thus, the short-term effects of flood-water inundation could be significantly adverse.

The physical presence of the dry dams would act as a barrier to the normal movement and dispersal of many vertebrate species. Smaller vertebrates, such as salamanders that migrate to breeding ponds, would be most affected, whereas large species, such as deer, would have sufficient mobility to pass around the ends of the flood control structures and therefore would be less affected.

The inundation of terrestrial habitats by flood waters retained by the proposed dry dams would result in some significant adverse impacts on wildlife resources and their habitats. The most severe changes in plant species composition and abundance would likely occur in areas immediately upstream of the dry dams. These areas often become "mudflats", as they are flooded most frequently and for the longest duration, and because suspended sediments and debris tend to be deposited there. Erosion and sedimentation are continuous processes on reservoir mudflats and successive floodings tend to keep vegetation in an immature state (Wilson and Landers, 1973). The current trend of keeping much of the upper reservoir lands in hay and rowcrops (about 37 percent of the total area), as well as the greater duration of flooding expected with project implementation, will act to hasten the early development of mudflats in the upper floodpool. Mudflat formation in the lower reservoir is expected to be less severe due to the lesser frequency of flooding there, although the percentage of land in hay and pasture is essentially the same (about 39 percent of the total area).

Flooding imposes complex stresses on many vascular plants, most of which arise from the depletion of oxygen in the flooded soil (Whitlow and Harris, 1979). In addition to anaerobic soil conditions, plant age, plant size, flood depth, flood duration, flood timing, substrate composition, siltation, and wave and ice action are all factors that determine survivorship when plants are flooded (McKim et al., 1975; Whitlow and Harris, 1979). The time at which a flood occurs during the growing season, along with the duration or period that an area is flooded, can have a significant impact on the survival of vegetation. Whereas dormant season flooding usually has no effect on woody plants, seedlings flooded after leaf flush are very susceptible to damage (Broadfoot and Williston, 1973). In a study of six New England flood control reservoirs, McKim et al. (1975) observed that smaller (less than 14-inch diameter) and younger trees were more affected by inundation than larger, mature trees, but that all trees inundated for more than 90 hours were affected to some degree. These authors further observed that ice conditions associated with winter flooding caused extensive damage to trees on floodplains. Low-growing, shrubby vegetation is very susceptible to flood damage, but may recover quickly through resprouting.

To determine the effects of operating the proposed Batavia Reservoir Compound (modified) on the terrestrial ecosystem, we estimated without- and with-the-project Habitat Unit changes and net average annual gain and loss of Habitat Units according to habitat type (Tables 8, 9, and 10, respectively). The data show a net gain of 103.4 Habitat Units for emergent marsh (EM) and pasture (P) habitat, and a net loss of 421.2 Habitat Units for shrub swamp (SS), forested wetland (FO), and cropland

(C) habitat. The indicated Habitat Unit changes reflect predicted annual changes in plant species composition and community structure that would likely result from flood-water inundation, mudflat formation (sedimentation), and natural and project-influenced plant succession, and presume that the following assumptions would hold true should the project, as described herein, be implemented:

1. That current land-use patterns would remain unchanged over the life of the project (100 years).
2. That 35% of the upper floodpool lands and 5% of the lower floodpool lands would develop into unstable mudflats under with-the-project conditions and that all mudflats would form within the first 25 years of project life.
3. That all habitat types would be equally affected by mudflat formation, except that emergent marshlands in the lower floodpool would remain unaffected (0% loss) and that cropland in the upper floodpool would be severely affected (60% loss).
4. That the mudflats would have little or no wildlife value (HSI=0.000).
5. That the following changes in habitat composition would occur over the period of analysis due to natural and project-induced plant succession:

	<u>Without-the-Project Conditions</u>			<u>With-the-Project Conditions</u>		
	<u>Present Habitat</u>	<u>% of Habitat Converted</u>	<u>Resulting Habitat</u>	<u>Present Habitat</u>	<u>% of Habitat Converted</u>	<u>Resulting Habitat</u>
<u>Upper Pool</u>	EM	0%	EM	EM	0%	EM
	SS	75%	FO	SS	50%	FO
	FO	0%	FO	SS	25%	EM
	P	25%	SS	FO	20%	EM
	C	0%	C	P	25%	SS
	--	---	--	P	25%	EM
	--	---	--	C	20%	SS
<u>Lower Pool</u>	--	---	--	C	20%	EM
	EM	0%	EM	EM	0%	EM
	SS	80%	FO	SS	80%	FO
	FO	0%	FO	FO	10%	EM
	P	10%	SS	P	10%	SS
	C	0%	C	P	10%	EM
	--	---	--	C	20%	SS

Construction of the project would result in the loss of some public access to lands and waterways in the basin and in the freedom of movement across lands and along watercourses. The loss of public access to terrestrial and aquatic areas would occur primarily through construction of the dry dams. These structures would deter, to some extent, the public's ability to enjoy the benefits of the area's wildlife resources. Of particular significance would be the severing of the Batavia-Alexander Recreational Trail by the lower dam. The trail is currently owned by Genesee County and is essentially that portion of the abandoned Erie Railroad right-of-way that runs from Law Street to Peaviner Road. This elevated pathway passes through a diverse assemblage of habitat types (Fig. 3) and possesses a unique floral association that is attractive to various forms of wildlife. The trail is currently used for hiking and cross-country skiing, as well as for fish and wildlife related recreational activities such as fishing and bird-watching. Genesee County plans to resurface and in other ways improve this pathway for multiple recreational uses. Estimates of public use show moderate (present) to heavy (projected) use of the trail:

	Present Use/Unimproved (persons-per-day)	Projected Use/with Improvements (persons-per-day)
Weekdays	15-25	60-80
Weekends	30-40	100-250

With the construction of the lower dam the right-of-way would become a dead-ended structure and decrease in its realized and potential recreational value.

PLAN OF DEVELOPMENT FOR AQUATIC AND TERRESTRIAL ECOSYSTEMS

In order to protect aquatic resources, a plan should be developed by the Corps of Engineers in cooperation with and approved by the New York State Department of Environmental Conservation, the U.S. Fish and Wildlife Service, the U. S. Soil Conservation Service, and the U. S. Environmental Protection Agency, to minimize the amount of project-caused erosion, siltation, and water pollution in Tonawanda Creek and its tributaries during and immediately after construction.

To mitigate the potentially adverse effects of the dry dams on normal fish movements in Tonawanda Creek, outlet works associated with the upper and lower dams should be constructed in such a manner as to permit upstream-downstream fish passage during normal flow (non-flood) conditions. A plan detailing the provisions and/or facilities for fish passage through the outlet works should be prepared by the Corps of Engineers in cooperation with and approved by the New York State Department of Environmental Conservation and the U. S. Fish and Wildlife Service. All necessary structures should be incorporated into the overall design, construction, operation, and maintenance plan for this project, and they should be provided at project cost.

All construction activities associated with instream or streambank areas, including snag removal, should be restricted to a period when impacts on fish and wildlife resources would be minimal. We anticipate that the least damage to those resources would be incurred if construction were to take place during the period from July 15 through November 15, when surface runoff and stream flow are generally lowest, and thus avoiding both the critical overwintering period and the breeding season of many fish and wildlife species.

Prior to the removal of snags from the creek and dead trees from along its banks, a plan should be developed by the Corps of Engineers in cooperation with and approved by the New York State Department of Environmental Conservation and the U.S. Fish and Wildlife Service to minimize the adverse effects of these activities on fish and wildlife resources. The following provisions should be included in the plan: (a) that stumps and logs embedded in the creek banks be cut rather than pulled and that logs deeply embedded in the creek bottom be left undisturbed in order to maintain complexity and hence diversity in the aquatic ecosystem; (b) that large dead trees along the channel banks which are in no imminent danger of toppling into the creek be left standing to provide essential denning, nesting, resting, and feeding sites for wildlife; and (c) that streamside activities be avoided where mature riparian growth, particularly box-elder and willow, could be damaged.

Sections of Tonawanda Creek that are cut off or abandoned should be plugged at their upstream and downstream ends with clean fill to provide conservation pools for fish and wildlife and all riparian vegetation associated with these areas should be left undisturbed.

The banks of Tonawanda Creek and upland areas surrounding the proposed dry dams and lateral dikes that are disturbed during construction activities, as well as riparian areas disturbed during snag and dead tree removal, should be revegetated as soon as possible after construction to mitigate the loss of wildlife habitat. A revegetation plan should be

developed for the project in cooperation with and approved by the New York State Department of Environmental Conservation and the U. S. Fish and Wildlife Service. The plan should include the monitoring of growth conditions to ensure that revegetation is successful and the replacement of dead or dying plant species. All replanting, maintenance, and monitoring activities should be funded as project costs.

To mitigate the potentially adverse effects of prolonged flooding on fish and wildlife and their habitats, flood waters should be retained in the reservoir for the shortest period of time necessary to reduce downstream flood damages. Fish and wildlife and their habitats would then have a greater potential for recovery if the duration of flooding was minimized; however, the immediate and irreversible effects of complete inundation would still be realized and could not be mitigated.

Valuable wetland complexes should be protected from complete inundation. The more important of these areas are those wetlands located east of Old Creek Road and within the upper reservoir floodpool (stippling in Fig. 2) and east of Creek Road and within the lower reservoir floodpool (stippling in Fig. 3). Wetlands in the lower floodpool could be protected by shallow dikes and flap gates; those in the upper floodpool would require either a lengthy dike running parallel to the Erie-Delaware Lackawanna Railroad (Conrail) embankment or the raising of the railroad bed to an elevation above that of the maximum floodpool, the latter method being most desirable. However, the estimated cost for the protection of upper reservoir wetlands is \$2,400,000. Because of this high cost and the potential adverse environmental effects that could result during the replacement of the railroad embankment, a more practicable solution would be to compensate for predicted resource damage and losses through in-kind compensation; that is, by purchasing another equally valuable wetland complex outside of the maximum floodpool boundaries, and subsequently managing it for fish and wildlife. The area of wetland that would need replacement is approximately 111.6 acres (45.2 ha), including 37.3 acres (15.1 ha) of emergent marsh and 74.6 acres (30.2 ha) of shrub swamp. We estimate that the protection of wetlands in the lower reservoir floodpool would cost \$19,000 (\$15,500 for initial construction and \$3,500 for annual operation and maintenance) and that the purchase and management of wetland habitat to compensate in-kind for resource damage and losses in upper reservoir floodpool wetlands would cost \$69,600 (\$67,800 for initial land purchase and \$1,800 for annual operation and maintenance). All funds for wetlands protection, and replacement and management, should be funded as project costs, and all needed protective structures should be incorporated into the overall design, construction, and maintenance of the flood control project.

Project-caused Habitat Unit losses should be compensated for through the purchase and management of habitat that is equivalent in wildlife value and located outside of the maximum floodpool boundary. Estimates of areas needed for compensation were determined through the coordinated efforts of biologists from the Corps of Engineers, the New York State Department of Environmental Conservation, and the U. S. Fish and Wildlife Service. Relative Importance Values (RIV's) were developed for each of the habitat types in the project area (Tables 11-13). Using the RIV's, adjustments were made from predominately cropland acreage to predominately forested wetland acreage (Table 14). Forested wetland was selected as the habitat type most desirable for acquisition (a) because it is the wetland type that would be most affected by this project, and (b) because of its high value (HSI=0.803, RIV=0.91). To ensure equitable compensation of habitat losses, all lands considered for purchase should first be rated for wildlife value by an interagency habitat evaluation team comprised of biologists from the Corps of Engineers, the New York State Department of Environmental Conservation, and the U. S. Fish and Wildlife Service. We estimate that approximately \$335,700 would be needed to purchase lands for compensation of Habitat Unit losses and that \$8,950 would be needed for management (annual operation and maintenance) of lands during the life of the project. All costs indicated should be funded as project costs and all lands acquired to compensate for Habitat Unit losses should be administered by the New York State Department of Environmental Conservation under a mutually agreeable plan developed by the Corps of Engineers, the New York State Department of Environmental Conservation, and the U. S. Fish and Wildlife Service. The New York State Department of Environmental Conservation has responded favorably to the possibility of managing mitigation lands resulting from this project and would most favor the purchase of lands adjacent to or near the site of the flood control project. State biologists have identified areas most desirable for acquisition (see attached Letter of Concurrence dated September 29, 1980). These areas should be given first priority for purchase when mitigation plans are finalized.

Loss of public access to lands and waterways and of free movement across lands and along watercourses should be compensated for by providing some means to walk and/or portage boats across the dams in the vicinity of the main creek channel and to permit passage along the Batavia-Alexander Recreational Trail. These problems could be remedied by (a) the construction of paths or stairways across the dams in the vicinity of the main creek channel, and (b) the construction of a sloping, earthen-fill ramp from the surface of the recreational trail to the top of the lower dam where it crosses the trail. With snag removal in the main creek channel, it

could be expected that float-fishing and other boating recreation in the creek would increase; therefore it would be essential to provide a means to facilitate portaging, as well as to provide safe passage across the dams for hunters, fishermen, etc. The construction of paths or stairways would facilitate public use of fish and wildlife resources and compensate, in part, for loss of public access to and across lands in the basin. Use of the Batavia-Alexander Recreational Trail is also expected to increase as Genesee County plans to resurface and in other ways improve this pathway for multiple recreational uses. Bird-watching, fishing, and other fish and wildlife related recreational activities are permitted on and along the trail. The raising of the recreational trail (where it would be crossed by the lower dam) would serve to maintain the trail's integrity and would ensure full public use of the trail and access to and across lands in the basin. We estimate that approximately \$14,500 would be needed to provide for stone stairways on each of the dry dams (\$11,500 for initial construction and \$3,000 for annual operation and maintenance) and that \$10,000 would be needed to elevate the recreational trail (\$8,000 for initial construction and \$2,000 for annual operation and maintenance). These costs should be funded as project costs and the recommended structures should be incorporated into the overall design, construction, operation, and maintenance plan for this project. Further, all Federal lands and waters in the project area should be open to the public for fish and wildlife related recreational uses.

The Batavia Reservoir Compound (modified) should be used as a model for future assessments of beneficial and adverse effects of irregularly flooded dry dam structures and of measures necessary to mitigate any adverse effects. Since no studies have ever been made of the effects of dry dams and their operation on aquatic and terrestrial ecosystems, such studies should be undertaken in association with this flood management project. Studies should be planned to collect biological data on both aquatic and terrestrial ecosystems prior to and during the construction phase of the project and on ecosystem conditions during a period of at least four years following project completion. In addition to its potential use in relation to other dry dam projects, this study could also provide information useful in mitigating the adverse effects of the Batavia Reservoir Compound (when completed) through procedures such as correcting the rate of outflow or lowering maximum floodpool elevations. We estimate that approximately \$96,000 would be needed to fund studies necessary to determine:

1. The short-and long-term effects of irregular inundation on plant and animal community structure.
2. The degree of silting and sedimentation that can be expected from dry-dam operation and the effects of sedimentation on plant and animal communities.

3. The effects of dry-dams, dikes and outlet works on fish and wildlife movements in the area of project influence..
4. The effects of snag removal on the structure and functioning of the aquatic community and on public uses of the creek.
5. How reservoir outflow might be manipulated to achieve needed flood protection and to concurrently minimize the adverse effects of the project on fish and wildlife.

Prior to project construction, a plan of study should be developed by the Corps of Engineers in cooperation with and approved by the U. S. Fish and Wildlife Service and the New York State Department of Environmental Conservation. The estimated \$96,000 needed to fund the studies should be applied for through the Corps of Engineers Research and Development Program.

AN ALTERNATIVE PLAN FOR FLOOD MANAGEMENT

Of the alternatives presented by your agency for flood management in the Tonawanda Creek watershed, the Batavia Reservoir Compound (unmodified plan) was selected by the Service as having the least potential adverse impact on fish and wildlife resources. We feel, however, that an additional alternative exists that has not previously been considered by your agency. This alternative would likely have fewer impacts on fish and wildlife and could actually enhance existing aquatic and terrestrial ecosystems. This alternative is a combination of both natural and managed flood control.

Existing bottomland habitats in the watershed have the potential for use as a system of natural flood control utilizing some management features. Under present conditions, many wet meadow, emergent marsh, shrub swamp, and forested wetland habitats are only seasonally flooded and during the course of spring and summer months they lose much standing water. These habitats would have greater intrinsic value to fish and wildlife if water levels were more stable. A diverse group of vertebrates, including many fish, amphibians, reptiles, waterfowl, herons, and furbearing mammals, would benefit from the stabilization of water levels, and fish and wildlife related recreational opportunities, including fishing, trapping, hunting, and bird-watching would be greatly improved.

Existing wetland habitats in the watershed could be modified with structures such as shallow levees with overflow outlet works that would retain floodwaters and maintain more seasonally stable water levels as well as increase flood storage capacity. Additional floodwater storage could be created in suitable areas through the construction of overflow diversion channels that would divert high flow water to some existing retention areas as well as to newly-created off-channel impoundments. These impoundments should be slow-draining with minimum-level conservation pools that would permit the development of aquatic and semi-aquatic plant associations. Off-channel impoundments, as opposed to the proposed dry-dams, would preserve the integrity of the Tonawanda Creek channel, as well as its ecology, and would provide needed floodwater storage, as well as create good fish and wildlife habitat.

Our proposal to use wetlands for floodwater storage is not a new concept, but even in the most ideal situation there is a need for man's assistance to promote natural watershed storage. For example, along the Charles River in Massachusetts, upper and middle watershed wetlands retain floodwaters and release them slowly, thereby lessening potential flooding problems in the lower reaches; but even so, many of the watershed's roadways have undersized culverts and bridge openings which turn the roadways into effective floodwater retention structures that increase the capacity and effectiveness of existing wetlands (U. S. Corps of Engineers, 1972). The Tonawanda Creek watershed has many wetlands whose flood retention capability could be enhanced and many non-wetland areas that could be developed into wetland/flood retention features of the ecosystem; however, such a plan would require the combined efforts and cooperation of engineers and biologists to formulate a managed/natural flood control plan for the Tonawanda Creek Watershed that is both engineeringly feasible and ecologically sound.

Since a managed/natural flood control plan would be an alternative to the Batavia Reservoir Compound (modified), all land and flowage easement purchases, and construction, and annual operation and maintenance costs should be funded as project costs. The lands and management structures could be administered by the New York State Department of Environmental Conservation under a mutually agreeable plan developed by the Corps of Engineers, the New York State Department of Environmental Conservation, and the U. S. Fish and Wildlife Service.

RECOMMENDATIONS

We recommend that:

1. A system of managed/natural flood control, as described herein, be given full consideration by your agency as a project alternative -- one that can potentially protect fish and wildlife resources and preserve ecosystem integrity, as well as provide the needed flood control in Tonawanda Creek Watershed. We further recommend that the managed/natural flood control alternative be developed through the combined efforts of the Corps of Engineers, the U. S. Fish and Wildlife Service, and the New York State Department of Environmental Conservation, and that if found feasible be implemented in lieu of the Batavia Reservoir Compound (modified).
2. The Batavia Reservoir Compound (modified), if constructed, be used as a model for future assessments of beneficial and adverse effects of irregularly flooded dry dam structures on aquatic and terrestrial ecosystems, and that the studies described herein be undertaken to provide the data base necessary for such assessments. We further recommend that, prior to project construction, a plan of study be developed by the Corps of Engineers in cooperation with and approved by the U. S. Fish and Wildlife Service and the New York State Department of Environmental Conservation, and that the estimated \$96,000 needed to fund the studies be applied for through the Corps of Engineers Research and Development Program.
3. Prior to project construction, a plan be developed by the Corps of Engineers in cooperation with and approved by the New York State Department of Environmental Conservation, the U. S. Fish and Wildlife Service, the U. S. Soil Conservation Service, and the U. S. Environmental Protection Agency, to minimize the amount of project-caused erosion, siltation, and water pollution in Tonawanda Creek and its tributaries during and immediately after construction.
4. To mitigate the potentially adverse effects of the dry dams on normal fish movements in Tonawanda Creek, outlet works associated with the upper and lower dams be constructed in such a manner as to permit upstream-downstream fish passage during normal flow (non-flood) conditions. We further recommend that a plan detailing the provisions and/or facilities for fish passage through the outlet works be prepared by the Corps of Engineers in cooperation with and approved by the New York State Department of Environmental Conservation and the U. S. Fish and Wildlife Service, that all necessary structures be incorporated into the overall design, construction, operation, and maintenance plan for this project, and that they be provided at project cost.

5. All construction activities associated with instream or streambank areas, including snag removal, be restricted to the period from July 15 through November 15, when surface runoff and stream flow are generally lowest, and thus avoiding both the critical over-wintering period and the breeding season of many fish and wildlife species.
6. Prior to removal of snags from the creek and dead trees from along its banks, a plan be developed by the Corps of Engineers in cooperation with and approved by the New York State Department of Environmental Conservation and the U. S. Fish and Wildlife Service to minimize the adverse effects of these activities on fish and wildlife resources. We further recommend that the following provisions be included in the plan: (a) that stumps and logs embedded in the creek banks be cut rather than pulled, and that logs deeply embedded in the creek bottom be left undisturbed in order to maintain complexity and hence diversity in the aquatic ecosystem; (b) that large dead trees along the channel banks which are in no imminent danger of toppling into the creek be left standing to provide essential denning, nesting, resting, and feeding sites for wildlife; and (c) that streamside activities be avoided where mature riparian growth, particularly box-elder and willow, could be damaged.
7. Sections of Tonawanda Creek that are cut off or abandoned be plugged at their upstream and downstream ends with clean fill to provide conservation pools for fish and wildlife and that all riparian vegetation associated with these areas be left undisturbed.
8. Streambanks and upland areas surrounding the proposed dry dams and lateral dikes disturbed during construction activities as well as riparian areas disturbed during snag and dead tree removal, be revegetated as soon as possible after construction to mitigate the loss of wildlife habitat. We further recommend that prior to project construction, a revegetation plan be developed for the project in cooperation with and approved by the New York State Department of Environmental Conservation and the U. S. Fish and Wildlife Service, that the plan include the monitoring of growth conditions to ensure that revegetation is successful and the replacement of dead or dying plant species, and that all replanting, maintenance, and monitoring activities be funded as project costs.
9. To mitigate the potentially adverse effects of prolonged flooding on fish and wildlife and their habitats, that flood waters be retained in the reservoirs for the shortest period of time necessary to reduce downstream flood damages. We further recommend that prior to project construction, operating criteria for flood water

retention and regulated release be established in cooperation with and approved by the New York State Department of Environmental Conservation and the U. S. Fish and Wildlife Service for the conservation and development of fish and wildlife resources, and that these criteria be adhered to by the Corps of Engineers as long as it exercises direct operational control of project features, and that any agreements entered into for the delegation or release of operational control to another agency include stipulations to prevent deviation from these criteria.


10. Valuable wetland complexes, located east of Creek Road and within the lower reservoir floodpool, be protected from complete inundation through the construction of lateral dikes with flap gates. We further recommend that the estimated \$19,000 needed to provide protective structures (\$15,500 for initial construction and \$3,500 for annual operation and maintenance) be provided as a project cost and that all such structures be incorporated into the overall design, construction, operation, and maintenance plan for this project.
11. Project-caused Habitat Unit losses, including losses associated with upper reservoir wetlands, be compensated for through the purchase and management of habitat that is equivalent in wildlife value and located outside of the maximum floodpool boundary. We further recommend that the estimated \$403,500 needed to purchase lands for compensation and \$10,760 needed for annual management (operation and maintenance) of the lands be funded as project costs, that the management area be administered by the New York State Department of Environmental Conservation under a mutually agreeable plan developed by the Corps of Engineers, the New York State Department of Environmental Conservation, and the U. S. Fish and Wildlife Service, and that the report of the District Engineer, Corps of Engineers, include language calling specifically for Congressional authorization for the necessary land acquisition and management described herein.
12. Loss of public access to lands and waterways and of free movement across lands and along watercourses should be compensated for by providing (a) paths or stairways across the dams in the vicinity of the main creek channel, and (b) a sloping, earthen-fill ramp from the surface of the Batavia-Alexander Recreational Trail to the top of the lower dam where it crosses the trail. We further recommend that the estimated \$40,000 needed to provide for stone stairways on each of the dry dams (\$11,500 for initial construction and \$3,000 for annual operation and maintenance) and for elevation of the recreational trail (\$8,000 for initial construction and \$2,000 for

annual operation and maintenance) be funded as a project cost and that these structures be incorporated into the overall design, construction, operation, and maintenance of the flood control project. Further, all Federal lands and waters in the project area should be open to the public for fish and wildlife related recreational uses.

13. All mitigation activities, including land purchases and fish and wildlife studies, be conducted under the auspices of an interagency monitoring team comprised of biologists from the Corps of Engineers, the U. S. Fish and Wildlife Service, and the New York State Department of Environmental Conservation, and that all of the activities of the monitoring team be funded as a project cost.

Please continue to coordinate this project with us as it develops, and advise us of any changes or additions to the project so that consideration may be given to revise or supplement this report.

Sincerely yours,

A handwritten signature in cursive script, reading "Paul P. Hamilton". The signature is written in dark ink and is positioned above the printed name and title.

Paul P. Hamilton
Field Supervisor

REFERENCES

- Anderson, N.H., J.R. Sedell, L.M. Roberts, and F.J. Triska. 1977. The role of aquatic invertebrates in processing of wood debris in coniferous forest streams. *American Midland Naturalist* 100(1):64-82.
- Bio Systems Research. 1979. Fish survey, Tonawanda Creek watershed, Batavia to Alexander, Genesee County, New York, June-July 1979. Report on contract DACW49-79-C-0052 prepared for U. S. Department of the Army, Corps of Engineers, Buffalo District, Buffalo, New York. 14pp., 3 tables, 1 map.
- Broadfoot, W.M., and H.L. Williston. 1973. Flooding effects on southern forests. *Journal of Forestry* 71:584-587.
- Great Lakes Laboratory. 1976. Final report: benthic study on Tonawanda Creek, New York. Report on contract DACW49-76-C-0039 prepared for U. S. Department of the Army, Corps of Engineers, Buffalo District, Buffalo, New York. 15pp.
- Heimstra, Norman W., David K. Damkot, and Norman G. Benson. 1969. Some effects of silt turbidity on behavior of juvenile largemouth bass and green sunfish. U. S. Department of the Interior, Fish and Wildlife Service, Technical Paper No. 20. 9pp.
- Hynes, H.B.N. 1970. The ecology of flowing waters in relation to management. *Journal Water Pollution Control Federation* 42(3):418-424.
- McKim, Harlan L., Lawrence W. Gatto, and Carolyn J. Merry. 1975. Inundation damage to vegetation at selected New England flood control reservoirs. U. S. Department of the Army, Engineering Division, Cold Regions Research and Engineering Laboratory, Special report No. 220. 53pp.
- Neel, Joe Kendall. 1963. Impact of reservoirs. Pages 575-593 in David G. Frey, ed. *Limnology in North America*. University of Wisconsin Press, Madison.
- Ringler, Neil H., and James D. Hall. 1975. Effects of logging on water temperature and dissolved oxygen in spawning beds. *Transactions of the American Fisheries Society* 104(1):111-121.
- Stern, Edward M., and William B. Stickle. 1978. Effects of turbidity and suspended material in aquatic environments. U. S. Army Engineer Waterways Experiment Station, Technical Report D-78-21. 117pp.

- U.S. Army Corps of Engineers. 1972. Water resources development plan, Charles River watershed, Massachusetts. Appendix H. Flood management - plan formulation. U. S. Department of the Army, Corps of Engineers, New England Division, Waltham, Massachusetts.
- U. S. Army Corps of Engineers. 1979. Interim report on feasibility of flood management in Tonawanda Creek watershed: final feasibility report. Main report and technical appendices. U. S. Department of the Army, Corps of Engineers, Buffalo District, Buffalo, New York. (Preliminary Draft)
- U. S. Fish and Wildlife Service. 1979a. Habitat evaluation procedures. U. S. Department of the Interior, Fish and Wildlife Service, Project Impact Evaluation Team, Fort Collins, Colorado. 66pp. + appendices. (Draft)
- U. S. Fish and Wildlife Service. 1979b. A species characterization handbook for habitat evaluation - Tonawanda Creek flood control. U. S. Department of the Interior, Fish and Wildlife Service, Division of Ecological Services, Cortland, New York. 77pp. (Revised)
- Whitlow, Thomas H., and Richard W. Harris. 1979. Flood tolerance in plants: a state-of-the-art review. U. S. Department of the Army, Engineering Division, Waterways Experiment Station Technical Report E-79-2. 161pp. + appendices.
- Wilson, James A., and Roger Q. Landers. 1973. Plant species as wildlife cover and erosion control on "mudflats" in Iowa's large reservoir systems. Iowa State Water Resources Institute Publication No. 51. 10pp. + 32 figures.

Table 1. -- Fish species determined to be present in Tonawanda Creek and associated waters in the vicinity of the Towns of Alexander, Batavia, and Bethany, New York. A plus sign (+) denotes the observed presence of a species in a particular area or habitat type. Data are taken from unpublished fisheries survey reports provided by the State University of New York at Buffalo (left column) and Bio Systems Research, Inc., Buffalo, New York (right column; enclosed by parentheses).

	Tonawanda Creek ¹ (upper)	Tonawanda Creek ² (lower)	Little Tonawanda Creek	Other Tributary	Oxbow or Pond
Brown Trout	(+)	(+)	(+)	(+)	(+)
White Sucker	(+)	(+)	(+)	(+)	(+)
Northern Hog Sucker	(+)	(+)	(+)	(+)	(+)
Carp	(+)	(+)	(+)	(+)	(+)
Stoneroller	(+)	(+)	(+)	(+)	(+)
Blacknose Dace	(+)	(+)	(+)	(+)	(+)
Creek Chub	(+)	(+)	(+)	(+)	(+)
Hornyhead Chub	(+)	(+)	(+)	(+)	(+)
Fallfish	(+)	(+)	(+)	(+)	(+)
Golden Shiner	(+)	(+)	(+)	(+)	(+)
Bluntnose Minnow	(+)	(+)	(+)	(+)	(+)
Fathead Minnow	(+)	(+)	(+)	(+)	(+)
Common Shiner	(+)	(+)	(+)	(+)	(+)
River Shiner	(+)	(+)	(+)	(+)	(+)
Sand Shiner	(+)	(+)	(+)	(+)	(+)
Brown Bullhead	(+)	(+)	(+)	(+)	(+)
Central Mudminnow	(+)	(+)	(+)	(+)	(+)
Northern Pike	(+)	(+)	(+)	(+)	(+)
Yellow Perch	(+)	(+)	(+)	(+)	(+)
Logperch	(+)	(+)	(+)	(+)	(+)
Johnny Darter	(+)	(+)	(+)	(+)	(+)
Iowa Darter	(+)	(+)	(+)	(+)	(+)
Fantail Darter	(+)	(+)	(+)	(+)	(+)
Smallmouth Bass	(+)	(+)	(+)	(+)	(+)
Largemouth Bass	(+)	(+)	(+)	(+)	(+)
Green Sunfish	(+)	(+)	(+)	(+)	(+)
Pumpkinseed	(+)	(+)	(+)	(+)	(+)
Bluegill	(+)	(+)	(+)	(+)	(+)
Rock Bass	(+)	(+)	(+)	(+)	(+)

¹Includes sampling conducted in the main channel between N.Y. Route 20 and Dorman Road. This area not sampled by SUNY-Buffalo.

²Includes sampling conducted in the main channel from the vicinity of Dorman Road to Main Street in the City of Batavia.

Table 2. -- Amphibians, reptiles, birds, and mammals and their associated habitats in the proposed Batavia Reservoir Compound and vicinity, Towns of Alexander and Batavia, New York. Data are summarized from field reconnaissance conducted between March 28 and July 13, 1979.

Species	Habitat									
	Tonawanda Creek	Tributary Stream	Pond or Wet Ditch	Emergent Marsh	Shrub Swamp	Forested Wetland	Riparian Hardwood	Railroad Right-of-Way	Hayfield or Pasture	Residential
<u>Amphibians</u>										
Wood Frog			X		X	X				X
Northern Leopard Frog		X	X	X	X					
Bullfrog		X	X	X			X			
Green Frog		X	X	X	X	X	X	X	X	
Gray Tree Frog				X	X	X				
Spring Peeper				X	X	X				
Western Chorus Frog				X						
American Toad	X			X	X	X	X	X	X	X
Blue-spotted Salamander			X			X		X		
Jefferson's Salamander								X		
<u>Reptiles</u>										
Eastern Milk Snake										X
Northern Water Snake			X	X				X		
Eastern Garter Snake		X				X	X	X	X	X
Northern Ribbon Snake								X	X	
Northern Brown Snake								X	X	
Northern Red-bellied Snake								X	X	
Common Snapping Turtle			X	X	X	X	X	X	X	
Midland Painted Turtle			X	X		X		X		X
Wood Turtle								X		
<u>Birds</u>										
Great Blue Heron*			X	X		X	X		X	
Great Egret*				X						
Green Heron			X	X	X	X		X		
American Bittern									X	
Canada Goose	X		X	X		X			X	X
Wood Duck				X		X	X			
Mallard	X	X		X	X	X	X		X	X

Table 2 (Continued).

Species	Habitat										
	Tonawanda Creek	Tributary Stream	Pond or Wet Ditch	Emergent Marsh	Shrub Swamp	Forested Wetland	Riparian Hardwood	Railroad Right-of-Way	Hayfield or Pasture	Cropland	Residential
American Widgeon*				X		X					
Blue Winged Teal			X	X							
Turkey Vulture						X			X	X	
Red-tailed Hawk						X	X		X		
Marsh Hawk**									X		
American Kestrel					X				X	X	
Ring-necked Pheasant										X	X
Wild Turkey						X					
Common Gallinule				X							
Killdeer	X			X			X	X	X	X	X
American Woodcock						X		X			
Common Snipe				X					X		
Greater Yellowlegs**				X						X	
Spotted Sandpiper**	X		X	X			X				
Herring Gull**									X		
Black Tern**				X							
Rock Dove							X		X	X	X
Mourning Dove					X	X	X	X	X	X	X
Black-billed Cuckoo					X			X			X
Great Horned Owl							X				
Common Nighthawk											X
Chimney Swift									X	X	X
Belted Kingfisher			X	X		X	X		X		
Common Flicker				X	X	X	X	x	X		X
Red-bellied Woodpecker						X					
Red-headed Woodpecker						X	X				X
Hairy Woodpecker						X	X				
Downy Woodpecker							X				
Eastern Kingbird				X	X				X	X	
Great Crested Flycatcher						X	X				
Eastern Phoebe					X	X		X			
Least Flycatcher						X	X				
Eastern Wood Pewee						X	X	X			
Horned Lark									X	X	
Tree Swallow				X							
Barn Swallow			X	X		X	X		X	X	X

Table 2 (Continued).

Species	Habitat										
	Tonawanda Creek	Tributary Stream	Pond or Wet Ditch	Emergent Marsh	Shrub Swamp	Forested Wetland	Riparian Hardwood	Railroad Right-of-Way	Hayfield or Pasture	Cropland	Residential
Blue Jay					X	X	X		X		X
American Crow						X	X	X	X	X	
Black-capped Chickadee					X	X	X				
White-breasted Nuthatch					X	X	X				
House Wren						X	X				
Gray Catbird				X	X	X	X	X			
Brown Thrasher**						X					
American Robin					X	X	X	X	X	X	X
Wood Thrush						X	X	X			
Veery					X	X					
Cedar Waxwing					X		X	X			
Red-eyed Vireo						X	X				
Warbling Vireo						X	X				
Yellow Warbler					X	X	X	X			X
Common Yellowthroat				X	X	X	X	X			
Yellow-rumped Warbler**						X					
Blue-winged Warbler**						X					
Bobolink				X					X		
Eastern Meadowlark									X		
Red-winged Blackbird				X	X	X	X	X	X	X	X
Northern Oriole						X	X	X			
Common Grackle				X	X	X	X		X	X	X
Brown-headed Cowbird					X	X	X			X	X
Rusty Blackbird**						X					
Common Starling											X
House Sparrow										X	X
Scarlet Tanager						X	X				
Common Cardinal					X	X	X	X			X
Rose-breasted Grosbeak						X	X	X			
Indigo Bunting						X	X				
American Goldfinch					X	X	X	X	X	X	
Rufous-sided Towhee**							X				
Savannah Sparrow									X	X	
Henslow's Sparrow				X							
Vesper Sparrow									X	X	
Chipping Sparrow					X						X

Table 2 (Continued).

Species	Habitat										
	Tonawanda Creek	Tributary Stream	Pond or Wet Ditch	Emergent Marsh	Shrub Swamp	Forested Wetland	Riparian Hardwood	Railroad Right-of-Way	Hayfield or Pasture	Cropland	Residential
Field Sparrow					X		X		X		
Slate-colored Junco**											
White-throated Sparrow**					X		X	X			
Swamp Sparrow				X	X						
Song Sparrow					X	X	X	X		X	
House Finch											X
<u>Mammals</u>											
Opossum	X					X			X	X	
Masked Shrew							X				
Short-tailed Shrew			X	X	X		X	X	X		
Eastern Cottontail Rabbit					X	X		X			
Eastern Chipmunk					X	X	X	X		X	X
Woodchuck					X	X	X	X	X		
Eastern Gray Squirrel						X		X			X
Red Squirrel						X					X
Deer Mouse						X	X				
White-footed Mouse						X					
Muskrat		X	X	X	X			X			
Meadow Jumping Mouse							X				
Raccoon	X		X			X	X		X		
Mink							X				
Striped Skunk					X	X	X		X	X	
White-tailed Deer	X		X	X	X	X	X	X	X	X	

* Non-breeding spring resident.

** Spring migrant.

Table 3. -- Results of 1979 breeding bird censuses taken along stands of riparian growth on Tonawanda Creek, Towns of Alexander and Batavia, New York. Numbers indicate counts of singing birds.

Species	Dates/Transect #1 ^a			Dates/Transect #2 ^b		
	6-6-79	6-27-79	7-11-79	6-6-79	6-27-79	7-11-79
Yellow Warbler	17	10	9	11	12	4
Red-winged Blackbird	10	7	7	0	2	1
Song Sparrow	8	10	12	3	10	9
House Wren	6	5	7	6	7	6
American Robin	5	6	8	5	4	3
Brown-headed Cowbird	0	0	3	4	4	4
Gray Catbird	2	4	3	1	2	4
Common Cardinal	2	0	1	0	1	0
Rose-breasted Grosbeak	2	0	1	0	0	0
Eastern Wood Pewee	0	2	2	1	0	1
Least Flycatcher	1	0	2	2	0	1
Red-headed Woodpecker	0	0	0	2	0	0
White-breasted Nuthatch	1	0	1	0	0	2
American Goldfinch	1	1	3	0	1	3
Common Grackle	1	1	0	0	0	0
Spotted Sandpiper	0	1	0	1	1	0
Mourning Dove	1	1	0	0	0	0
Great Crested Flycatcher	1	0	0	0	0	0
Wood Thrush	1	0	0	0	0	0
Mallard	1	0	0	0	0	0
Warbling Vireo	0	1	1	0	0	0
Northern Oriole	0	1	0	0	1	0
Downy Woodpecker	0	1	0	0	0	0
Belted Kingfisher	0	0	1	0	0	0
Red-eyed Vireo	0	0	1	0	0	0
Common Yellowthroat	0	0	1	0	0	0
Indigo Bunting	0	0	0	0	0	1

^a Transect #1 ran 1,295 meters north along Tonawanda Creek from Peaviner Road.

^b Transect #2 ran 1,029 meters northeast along Tonawanda Creek from where the creek intersects the Erie Railroad embankment.

Table 4. -- Evaluation elements (species) used to evaluate wildlife habitat in the area of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

Evaluation Element (Species)	Habitat Types					
	Emergent Marsh	Shrub Swamp	Forested Wetland	Pasture	Cropland	
<u>Amphibians</u>						
Wood Frog (<u>Rana sylvatica</u>)			X			
Blue-spotted Salamander (<u>Ambystoma laterale</u>)			X			
<u>Reptiles</u>						
Eastern Garter Snake (<u>Thamnophis sirtalis</u>)					X	
<u>Birds</u>						
Indigo Bunting (<u>Passerina cyanea</u>)		X				
Eastern Meadowlark (<u>Sturnella magna</u>)				X		
Red-winged Blackbird (<u>Agelaius phoeniceus</u>)	X					
Horned Lark (<u>Eremophila alpestris</u>)					X	
Spotted Sandpiper (<u>Actitis macularia</u>)	X					
Belted Kingfisher (<u>Megaceryle alcyon</u>)			X			
Kestrel (<u>Falco sparverius</u>)				X	X	
<u>Mammals</u>						
Meadow Vole (<u>Microtus pennsylvanicus</u>)	X	X				
Eastern Cottontail Rabbit (<u>Sylvilagus floridanus</u>)		X				
Red Fox (<u>Vulpes vulpes</u>)				X		
White-tailed Deer (<u>Odocoileus Virginianus</u>)		X	X	X	X	
Total Species	14	3	4	4	4	4

Table 5. -- Inventory characteristics used to evaluate wildlife habitat in the area of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

Inventory Characteristics	Habitat Types				
	Emergent Marsh	Shrub Swamp	Forested Wetland	Pasture	Cropland
% Herbaceous Ground Cover	X	X		X	X
% Shrub Crown Cover		X		X	
% Tree Canopy Closure			X		
Composition of Vegetation	X	X		X	
Type of Rowcrop					X
No. of Browse Species Present/Acre			X		
Av. Height of Herbaceous Vegetation	X	X		X	X
Av. Height of Shrubs		X			
Av. Height of Trees			X		
% Treeland within 1Km Radius					X
Distance to Woodland or Brushy Cover		X		X	X
Distance to Cutbanks for Nesting			X		
Distance to Feeding Area			X		
Distance to Water	X	X		X	X
Abundance of Water Bodies			X		
Water Depth	X		X		
Abundance of Dead Logs, Stumps, Etc.			X		
Depth of Leaf Litter			X		
% Forest Floor Covered by Leaf Litter			X		
% Pool Bottom Covered by Plant Debris			X		
Soil Type				X	
Relative Soil Moisture	X	X	X		X
Consecutive Days of Snow Cover				X	X
Abundance of Perch Sites		X	X	X	X
Abundance of Nest Cavities or Boxes				X	X

Table 6. -- Summary of baseline habitat conditions in the area of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

Habitat Type	HSI ¹	Habitat Units ² (Number of Hectares)		
		Upper Pool	Lower Pool	Total
Emergent Marsh (EM)	0.664	29.0(43.7)	23.9(36.0)	52.9(79.7)
Shrub Swamp (SS)	0.750	38.0(50.6)	96.9(129.2)	134.9(179.8)
Forested Wetland (FO)	0.803	63.7(79.4)	295.0(367.3)	358.7(446.7)
Pasture (P)	0.754	28.1(37.3)	98.6(130.8)	126.7(168.1)
Cropland (C) ³	0.605	75.5(124.7)	256.8(424.4)	332.3(549.1)
Total	-----	234.3(335.7)	771.2(1087.7)	1005.5(1423.4)

¹Habitat Suitability Index.

²Habitat Unit=HSIX hectares.

³Includes hayfields.

Table 7. -- Estimated loss of Habitat Units due to the construction of dry dams and lateral dikes for the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

Flood Management Structures	Habitat Units (Number of Hectares)					Totals
	Emergent Marsh	Shrub Swamp	Forested Wetland	Pasture	Cropland	
Lower Dam	0.0(0.0)	-1.3(1.7)	-1.2(0.3)	0.0(0.0)	-3.0(5.0)	-4.5(6.9)
Upper Dam	-0.7(1.0)	0.0(0.0)	-0.3(0.4)	0.0(0.0)	-2.2(3.6)	-3.2(5.0)
Lateral Dikes	0.0(0.0)	-0.1(0.1)	-0.1(0.2)	0.0(0.0)	-1.4(2.3)	-2.6(2.6)
Totals	-0.7(1.0)	-1.4(1.8)	-0.7(0.8)	0.0(0.0)	-6.5(10.8)	-9.2(14.4)

Table 8. -- Annualized Habitat Unit changes for without-the-project conditions and within the flood pool boundaries of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

		Upper Reservoir Pool			Lower Reservoir Pool			
Habitat Type (HSI) ¹	Target Year	Hectares	Habitat Units	Annualized Habitat Unit Change	Hectares	Habitat Units	Annualized Habitat Unit Change	Total Annualized Habitat Unit Change
Emergent Marsh (0.664)	0	43.7	29.0		36.0	23.9	0.0	0.0
	25	43.7	29.0		36.0	23.9		
	50	43.7	29.0		36.0	23.9		
	75	43.7	29.0		36.0	23.9		
	100	43.7	29.0	0.0	36.0	23.9	0.0	0.0
Shrub Swamp (0.750)	0	50.6	38.0		129.2	96.9		
	25	43.4	32.5		106.6	79.9		
	50	36.3	27.2		84.1	63.1		
	75	29.1	21.8		61.5	46.1		
	100	22.0	16.5	-27.2	38.9	29.2	-63.0	-90.2
Forested Wetland (0.803)	0	79.4	63.7		367.3	295.0		
	25	88.9	71.4		393.1	315.7		
	50	98.4	79.0		419.0	336.5		
	75	107.9	86.6		444.8	357.2		
	100	117.3	94.2	+79.0	470.7	378.0	+337.2	+416.2
Pasture (0.754)	0	37.3	28.1		130.8	98.6		
	25	35.0	26.4		127.5	96.1		
	50	32.6	24.6		124.3	93.7		
	75	30.3	22.8		121.0	91.2		
	100	28.0	21.1	-24.6	117.7	88.7	-93.7	-118.3
Cropland (0.605)	0	124.7	75.5		424.4	256.8		
	25	124.7	75.5		424.4	256.8		
	50	124.7	75.5		424.4	256.8		
	75	124.7	75.5		424.4	256.8		
	100	124.7	75.5	0.0	424.4	256.8	0.0	0.0
Total Annualized Habitat Unit Change				+27.2			+180.5	+207.7

¹Habitat Suitability Index.

Table 9. -- Annualized Habitat Unit changes for with-the-project conditions and within the flood pool boundaries of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

Upper Reservoir Pool					Lower Reservoir Pool				
Habitat Type (HSI) ¹	Target Year	Hectares	Habitat Units	Annualized Habitat Unit Change	Hectares	Habitat Units	Annualized Habitat Unit Change	Total Annualized Habitat Unit Change	
Emergent Marsh									
(0.664)	0	43.7	29.0		36.0	23.9			
	25	44.1	29.3		48.5	32.2			
	50	59.8	39.7		60.9	40.4			
	75	75.5	50.1		73.4	48.7			
	100	91.2	60.6	+41.0	85.8	57.0	+40.5	+81.5	
Shrub Swamp									
(0.750)	0	50.6	38.0		129.2	96.9			
	25	32.0	24.0		121.3	91.0			
	50	31.0	23.2		120.0	90.0			
	75	30.1	22.6		118.6	88.9			
	100	29.2	21.8	-24.9	117.3	88.0	-90.6	-115.5	
Forested Wetland									
(0.803)	0	79.4	63.7		367.3	295.0			
	25	54.0	43.4		365.6	293.6			
	50	56.3	45.2		382.2	306.9			
	75	58.7	47.1		398.9	320.3			
	100	61.0	49.0	-48.0	415.5	333.7	+308.8	+260.8	
Pasture									
(0.754)	0	37.3	28.1		130.8	98.6			
	25	19.6	14.8		117.0	88.2			
	50	14.9	11.2		110.4	83.2			
	75	10.3	7.8		103.9	78.3			
	100	5.6	4.2	-12.5	97.3	73.4	-83.9	-96.4	
Cropland									
(0.605)	0	124.7	75.5		424.4	256.8			
	25	37.4	22.6		382.0	231.1			
	50	24.9	18.8		360.7	218.2			
	75	12.5	9.4		339.5	205.4			
	100	0.0	0.0	-20.7	318.3	192.6	-219.8	-240.5	
Total Annualized Habitat Unit Change				-65.1				-45.0	-110.1

¹Habitat Suitability Index.

Table 10. -- Average annual change in Habitat Units within the flood pool boundaries of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York, and area required for in-kind compensation of Habitat Unit losses.

Habitat Types	Average Annual Change in Habitat Units ¹		Net Average ² Annual Change HU's	Area Required for Compensation (Hectares)
	Without the Project	With the Project		
Emergent Marsh	0.0	+81.5	+81.5	0.0
Shrub Swamp	-90.2	-115.5	+25.3	33.7
Forested Wetland	+416.2	+260.8	-155.4	193.5
Pasture	-118.3	-96.4	+21.9	0.0
Cropland	0.0	-240.5	-240.5	397.5
Total	+207.7	-110.1	-317.8	624.7

¹Average annual change in Habitat Units from Tables 8 and 9.

²Does not include Habitat Units lost due to the construction of the dry dams and lateral dikes (Table 7).

Table 11. -- Relative Importance Value Criteria determined for each habitat type in the area of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, Genesee County, New York.

RIV Criteria	Range of Value ¹	Habitat Type			
		Emergent Marsh	Shrub Swamp	Forested Wetland	Cropland
Abundance	1-most abundant 10-least abundant	10	8	3	1
Vulnerability	1-lowest probability 10-greatest probability	6	1	1	10
Replaceability	1-easily managed and/or created 10-little or no possibility to manage or create	5	8	10	1
Aesthetic Value	1-lowest value 10-highest value	9	5	10	1
Recreational Diversity	1-low 10-high	10	7	10	2
Species Richness	1-lowest 10-highest	7	8	10	1

¹A scale of 1-10 was used for filling each square of this matrix.

Table 12. --Pairwise comparison of Relative Importance Value Criteria, and weighting factors used in the development of Relative Importance Values.

RIV Criteria	Pairwise Comparisons ¹										Sum	Weight ²
Abundance	1	1	1	0	0	1					4	0.19
Vulnerability	0					1	1	1	0	1	4	0.19
Replaceability		0				0			1	1	3	0.14
Aesthetic Value			0			0	0	0	0	1	1	0.05
Recreational Diversity				1		0	0	1		0	3	0.14
Species Richness					1				1	1	6	0.29
Dummy Variables						0	1	0	0	0	0	0.00
Total											21	1.00

¹This technique requires that each criterion be compared to every other criterion, and a decision made as to which criterion of any pair is the most significant. A dummy criterion is included to insure that all criteria will have some weighting value.

²The sum total is divided into each criterion sum and the resulting value entered in the weight column representing the relative importance of each criterion.

Table 13. -- Relative Importance Values determined for each habitat type in the area of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, Genesee County, New York.

RIV Criteria	Habitat Types				
	Emergent Marsh	Shrub Swamp	Forested Wetland	Pasture	Cropland
Abundance	1.90 ¹	1.52	0.57	1.52	0.19
Vulnerability	1.14	0.19	0.19	1.71	1.90
Replaceability	0.70	1.12	1.40	0.28	0.14
Aesthetic Value	0.45	0.25	0.50	0.15	0.05
Recreational Diversity	1.40	0.98	1.40	0.28	0.28
Species Richness	2.03	2.32	2.90	0.87	0.29
Total	7.62	6.38	6.96	4.81	2.85
Relative Importance Value (RIV) ²	1.00	0.84	0.91	0.63	0.37

¹Represents the product of the values from Tables 11 and 12.

²The Relative Importance Value is obtained by dividing the sum for each habitat type by the greatest individual sum.

Table 14. -- Adjustment of Habitat Unit losses and gains using Relative Importance Values, and areas required for compensation of Habitat Unit losses expected from the construction and operation of the Tonawanda Creek Flood Control Project, Town of Alexander and Batavia, Genesee County, New York.

Habitat Type	RIV ¹	Net Gain or loss ² of HU's ²	$\frac{\text{RIV Habitat Type 1}}{\text{RIV Habitat Type 2}}$	$\frac{\text{HU's Type 2}}{\text{HU's Type 1}}$	X HU's	Adjusted HU's	Area Required for compensation (Hectares)
Pasture (A)	0.63	+21.9	$\frac{0.63(A)}{0.37(B)}$	$= \frac{X(B)}{21.9(A)}$	-21.9	0.0	0.0
Cropland (B)	0.37	-247.0			+37.3	-209.7	---
Emergent Marsh (C)	1.00	+80.8	$\frac{1.00(C)}{0.37(B1)}$	$= \frac{X(B1)}{80.8(C)}$	-80.8	0.0	0.0
Cropland (B1)	0.37	-209.7			+218.4	+8.7	---
Cropland (B2)	0.37	+4.3 ³	$\frac{0.37(B2)}{0.84(D)}$	$= \frac{X(D)}{4.3(B2)}$	-4.3	0.0	0.0
Shrub Swamp (D)	0.84	-25.4			+1.9	-23.5	31.4
Cropland (B3)	0.37	+4.3 ³	$\frac{0.37(B3)}{0.91(E)}$	$= \frac{X(E)}{4.3(B3)}$	-4.3	0.0	0.0
Forested Wetland(E)	0.91	-156.1			+1.7	-154.4	192.3
Total adjusted area required for compensation							223.7

¹Relative Importance Values from Table 13.

²Includes Habitat Unit losses from the construction of dry dams and lateral dikes (Table 7).

³Habitat Unit losses in cropland habitat (B1) are distributed evenly among shrub swamp and forested wetland for compensation purposes.

Table 15. -- Estimated costs for the acquisition and the operation and maintenance of wildlife habitat needed (a) to compensate for Habitat Unit losses and (b) for the in-kind replacement of upper reservoir floodpool wetlands, Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, Genesee County, New York.

Habitat Types	Number ¹ of Hectares	Acquisitions Costs ^{2,3}		Operation and Maintenance Costs ^{3,4}	
		Cost/Hectare	Total Cost	Cost/Hectare	Total Cost
Emergent Marsh	15.1	\$1,500	\$22,650	\$40	\$604
Shrub Swamp	61.6	\$1,500	\$92,400	\$40	\$2,464
Forested Wetland	192.3	\$1,500	\$288,450	\$40	\$7,692
Pasture	0.0	-----	-----	---	-----
Cropland	0.0	-----	-----	---	-----
Totals			\$403,500		\$10,760

¹Sum of areas shown in Table 14 and areas required for in-kind replacement of the 45.2 ha wetland complex in the upper-reservoir floodpool.

²Land acquisition costs estimated by the Corps of Engineers, Buffalo District, based on 1980 dollars.

³Field costs estimated by the New York State Department of Environmental Conservation and the U. S. Fish and Wildlife Service based on 1980 dollars.

⁴Annualized cost over period of analysis (100 years).





Figure 1.--Features of the proposed Batavia Reservoir Compound (modified), Towns of Batavia and Alexander, Genesee County, New York (adapted from U.S. Army Corps of Engineers, 1979).







Figure 3.--Cover map for upper floodpool of the proposed Batavia Reservoir Compound (modified), Towns of Batavia and Alexander, Genesee County, New York. Habitat Key: C=Cropland; EM=Emergent Marsh; FO=Forested Wetland; P=Pasture; SS=Shrub Swamp.

New York State Department of Environmental Conservation
50 Wolf Road, Albany, New York 12233



Robert F. Flacke
Commissioner

February 20, 1980

Mr. Paul P. Hamilton
Field Supervisor
United States Department of
the Interior
Fish and Wildlife Service
100 Grange Place, Room 202
Cortland, New York 13045

Dear Mr. Hamilton:

The Division of Fish and Wildlife is in general accord with the findings and recommendations of the report on the proposed flood control project along Tonawanda Creek in the towns of Batavia and Alexander, Genesee County, New York. But we do feel that instead of using the term "selective snagging", you should indicate that stumps embedded in the bank should be cut rather than pulled, and where they would not materially affect the roughness of the bottom, deeply embedded logs are to remain in the bottom. We also believe that instead of building a stairway or path traversing the dams, the Batavia-Alexander Recreational Trail should be re-routed around the structures.


Sincerely,

Kenneth Wich

Kennth F. Wich
Director
Division of Fish and Wildlife

cc: James Kelley

New York State Department of Environmental Conservation
6274 E. Avon-Lima Rd., Avon, New York 14414



Robert F. Flacke
Commissioner

Eric A. Seiffer
Regional Director

September 29, 1980

Mr. Paul B. Hamilton
Field Supervisor
United States Department of the Interior
Fish and Wildlife Service
100 Grange Place, Room 202
Cortland, New York 13045

Dear Mr. Hamilton:

The Division of Fish and Wildlife concurs with the findings and recommendations of the report on the Corps of Engineers Tonawanda Creek Flood Control Project, Towns of Batavia and Alexander, Genesee County, New York prepared under the authority of the Fish and Wildlife Coordination Act (16 USC 661).

We would also like to make some specific recommendations for sites to be considered as mitigation (see attached).

Site #1 - Shallow fresh marsh, deep fresh marsh, wood wetland, gets heavy use by waterfowl and heavy hunting pressure; great potential for enhancement with water control structures.

Sites #2 and #3 - High vulnerability to filling for industrial development, shallow fresh marsh, wooded swamp, has good potential for enhancement.

Sites #4 and 5 - Wooded swamp, low potential for enhancement.

Sites #7, 7 and 8 - Shallow fresh to deep fresh marsh, good potential for enhancement.


Mr. Paul B. Hamilton

-2-

September 29, 1980

If you have any questions concerning these areas, please contact Jack Cooper or Dan Carroll at our Regional Office. Our continued coordination on this project should help to ensure an environmentally acceptable project.

Very truly yours,




Edward D. Holmes
Regional Supervisor
Fish & Wildlife
Region #8



Kenneth Wich
Director
Division of Fish & Wildlife

JC:er
enc.



USGS 7.5' Quad, Batavia South, 1950



UNITED STATES
DEPARTMENT OF THE INTERIOR
FISH AND WILDLIFE SERVICE

100 Grange Place
Room 202
Cortland, New York 13045

February 23, 1983

Colonel Robert R. Hardiman
District Engineer
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hardiman:

This constitutes a supplement to our report dated October 23, 1980 on effects the proposed flood control project for the Tonawanda Creek watershed, located in the Towns of Batavia and Alexander, Genesee County, New York, would have on fish and wildlife resources. It was prepared under the authority of and in accordance with Section 2(b) of the Fish and Wildlife Coordination Act (48 Stat. 401, as amended; 16 U.S.C. 661 et seq.).

This supplement is intended to provide additional technical assistance on effects of the proposed project, and recommendations for mitigation of these effects.

It has been coordinated with the Division of Fish and Wildlife of the New York State Department of Environmental Conservation.

Agricultural Intensification

The proposed project will provide flood protection for farmland in the Tonawanda Creek floodplain, and more intensified agriculture is expected to occur there over the project life. Average annual agricultural benefits of \$1,444,200 are claimed as a result of this flood protection (U.S. Army Corps of Engineers, 1981). Most of the agricultural intensification would occur in the lower reservoir area (upstream of Batavia) and on the Huron Plain Floodland (between the Tonawanda Indian Reservation and the New York State Barge Canal).

Among the land use changes associated with agricultural intensification is the shift of "idle" land to agricultural use. Idle land is characterized as 1) absentee or residential ownership land used for speculative purposes; 2) disinterested or debilitated ownership land resulting from the owner's retirement; or 3) temporarily inactive land due to flooding or crop rotation. A total of 1,933 acres of idle land would be shifted to active agricultural use as a result of the proposed project. Of this total, 760 acres (39%) would be located in the lower reservoir area.

During our field reconnaissance of these idle lands, it was apparent that the majority are located close to Tonawanda Creek or a major tributary and are probably flooded too frequently to be permanently active. Most idle land is in an early successional stage, having been idle for less than five years. Vegetation is dominated by annual plants and grasses, with remnants of unharvested corn crops in some sites. A few of the sites have been abandoned for longer periods of time and support shrubs.

The idle lands have value as wildlife habitat, and add to ecological diversity in the watershed. The early successional stage is a less common habitat type in the watershed, and is transitory in nature - it requires alternating periods of active and idle management as now practiced in the watershed. A number of animals would be expected to utilize this habitat for food, cover, and/or nesting. Game animals would include the white-tailed deer, eastern cottontail rabbit, raccoon, common snipe, ringnecked pheasant, mallard, and Canada goose. A variety of nongame animals would also be present. The conversion of these lands to active agricultural use would reduce their value as wildlife habitat considerably, but not totally. We would consider conversion of lands among the active agricultural categories (cropland, pasture, hay) to be a minor impact to wildlife.

Habitat Evaluation Procedures

As a result of comments received, we have undertaken a thorough review of our application of Habitat Evaluation Procedures (HEP) to this project. Some changes have been made in the assumptions used, and some procedural changes were made in order to conform with current HEP methodology. Page 15 of our 1980 report lists five assumptions used in the HEP. Number 2 assumes that "35% of the upper floodpool lands and 5% of the lower floodpool lands would develop into unstable mudflats under with-the-project conditions and that all mudflats would form within the first 25 years of project life." After reviewing what limited data and literature are available on this subject, we believe that this assumption is valid for three of the five habitat types found within the floodpools - emergent marsh, pasture, and cropland. We do not believe that the effects of flooding and sedimentation would be severe enough, however, to convert shrub swamp and forested wetland habitats to mudflat. Although it is difficult to predict the nature of the mudflats that would form, we believe that at least some portions of the mudflat area would be vegetated with annual plants, grasses, and perhaps other vegetation at some time.

Assumption Number 4 states that "the mudflats would have little or no wildlife value (HSI = 0.000)." In our professional judgement, these mudflats would have low value for wildlife, but not a zero value. We have therefore assigned a value of HSI = 0.300 to the mudflat habitat type.

These changes in assumptions were entered into the HEP calculations, and the revised figures are shown in revised tables which follow. The original fieldwork in which the three agencies (USACOE, NYSDEC, USFWS) participated, and data which were generated from it remain valid and unchanged. Rather, it is the treatment of these data which has changed. We begin with Table 7, in which minor mathematical errors are corrected. In Table 8, results are expressed in average annual habitat units, (AAHU), instead of annualized habitat unit changes, to reflect current methodology and provide greater clarity. This change is also made in Table 9, which incorporates the changed assumptions for shrub swamp, forested wetland, and mudflat. Table 10 reveals the net impact of the project in AAHU. In Tables 11 and 13, the Relative Importance Value concept is expanded to the mudflat habitat type. Finally, in Table 14, AAHU are all converted into AAHU for forested wetland. This habitat type was judged the most desirable because 1) it was found to be the best wildlife habitat (HSI = 0.803); 2) there was a net loss of AAHU for this habitat, while other desirable habitats (emergent marsh, shrub swamp) showed net gains, and 3) it is less expensive to acquire than pasture or cropland, other habitats which showed a net loss. Our revised analysis, which includes direct impacts due to dam construction, shows that gains and losses in AAHU among the six habitat types balance each other out, and that the net impact of the project over all habitat types is close to zero (-2.9 AAHU).

Recommendations for Mitigation


As a result of our revised analysis, we no longer request mitigation for habitat unit losses within the reservoir compounds on the basis of the Habitat Evaluation Procedures detailed in our original report. However, we continue to recommend compensation for the 45.2 hectare (111.6 acre) wetland complex in the upper reservoir floodpool. Wildlife habitat value would be lost on a total of 1,933 acres of idle land which would be shifted to agricultural use with the project. There was insufficient time for habitat unit losses to be calculated for this impact. We recommend that, to mitigate for these losses, land be acquired in fee title and subsequently managed for wildlife. This land should be located outside and downstream of the floodpools. The size, location, cost, management, and other details of this land acquisition cannot be determined precisely without the application of Habitat Evaluation Procedures. Therefore, we further recommend that HEP be applied to the lands involved in order to accurately determine the nature of the recommended land acquisition. We estimate that the HEP application would cost approximately \$10,000 in 1983.

Until the HEP can be completed, we recommend that our original figures shown in Table 15 of our October 23, 1980 report be used as estimates of the land acquisition required. This Table estimates that a total of 223.8 hectares (552.8 acres) would be necessary to compensate for habitat unit losses, in addition to the 45.2 hectares (111.6 acres) described above. We anticipate that our compensation request would be in this range after completion of HEP. However, we do not recommend specific habitat types to be acquired at this time. One option for this

mitigation land which deserves serious consideration is the acquisition of a buffer strip along Tonawanda Creek. Such a strip would 1) preserve riparian wildlife habitat from agricultural encroachment; 2) revert cropland to riparian wildlife habitat; 3) protect Tonawanda Creek from bank and sheet erosion; and 4) allow access to the creek for operations and maintenance and public recreation.

These recommendations are intended to revise Recommendation 11 on page 25 of our report. All other recommendations are current except number 1 which has been eliminated. Especially timely is number 13 which calls for coordination of mitigation activities among the agencies involved. We continue to offer our technical assistance in this matter.

Sincerely yours,


Paul P. Hamilton
Field Supervisor

Literature Cited

U.S. Army Corps of Engineers. 1981. Buffalo Metropolitan Area, New York, Water Resources Management. Interim Report on Feasibility of Flood Management in Tonawanda Creek Watershed. Final Feasibility Report. Buffalo District, Buffalo, New York. Page S-26.

cc: NYSDEC, Avon
NYSDEC, Albany
EPA, N.Y.
SCS, Syracuse

Table 7. -- Estimated loss of Habitat Units due to the construction of dry dams and lateral dikes for the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

Flood Management Structures	Habitat Units (Number of Hectares)					Totals
	Emergent Marsh	Shrub Swamp	Forested Wetland	Pasture	Cropland	
Lower Dam	0.0(0.0)	-1.3(1.7)	-0.2(0.3)	0.0(0.0)	-3.0(4.9)	-4.5(6.9)
Upper Dam	-0.7(1.0)	0.0(0.0)	-0.3(0.4)	0.0(0.0)	-2.2(3.6)	-3.2(5.0)
Lateral Dikes	0.0(0.0)	-0.1(0.1)	-0.1(0.2)	0.0(0.0)	-1.4(2.3)	-1.6(2.6)
Totals	-0.7(1.0)	-1.4(1.8)	-0.7(0.8)	0.0(0.0)	-6.5(10.8)	-9.2(14.4)

Table 8. -- Average Annual Habitat Units for without-the-project conditions and within the flood pool boundaries of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

Upper Reservoir Pool					Lower Reservoir Pool			
Habitat Type (HSI) ¹	Target Year	Hectares	Habitat Units	Average Annual Habitat Units	Hectares	Habitat Units	Average Annual Habitat Units	Total Average Annual Habitat Units
Emergent Marsh (0.664)	0	43.7	29.0		36.0	23.9		
	25	43.7	29.0		36.0	23.9		
	50	43.7	29.0		36.0	23.9		
	75	43.7	29.0		36.0	23.9		
	100	43.7	29.0	29.0	36.0	23.9	23.9	52.9
Shrub Swamp (0.750)	0	50.6	38.0		129.2	96.9		
	25	43.4	32.5		106.6	79.9		
	50	36.3	27.2		84.1	63.1		
	75	29.1	21.8		61.5	46.1		
	100	22.0	16.5	27.2	38.9	29.2	63.0	90.2
Rested Wetland (0.803)	0	79.4	63.7		367.3	295.0		
	25	88.9	71.4		393.1	315.7		
	50	98.4	79.0		419.0	336.5		
	75	107.9	86.6		444.8	357.2		
	100	117.3	94.2	79.0	470.7	378.0	337.2	416.2
Pasture (0.754)	0	37.3	28.1		130.8	98.6		
	25	35.0	26.4		127.5	96.1		
	50	32.6	24.6		124.3	93.7		
	75	30.3	22.8		121.0	91.2		
	100	28.0	21.2	24.6	117.7	88.7	93.7	118.3
Cropland (0.605)	0	124.7	75.5		424.4	256.8		
	25	124.7	75.5		424.4	256.8		
	50	124.7	75.5		424.4	256.8		
	75	124.7	75.5		424.4	256.8		
	100	124.7	75.5	75.5	424.4	256.8	256.8	332.3
Total Average Annual Habitat Units								1009.9

¹Habitat Suitability Index.

Table 9. -- Average Annual Habitat Units for with-the-project conditions and within the flood pool boundaries of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

Upper Reservoir Pool					Lower Reservoir Pool			
Habitat Type (HSI) ¹	Target Year	Hectares	Habitat Units	Average Annual Habitat Units	Hectares	Habitat Units	Average Annual Habitat Units	Total Average Annual Habitat Units
Emergent Marsh (0.664)	0	43.7	29.0		36.0	23.9		
	25	44.1	29.3		48.5	32.2		
	50	59.8	39.7		60.9	40.4		
	75	75.5	50.1		73.4	48.7		
	100	91.2	60.6	41.0	85.8	57.0	40.5	81.5
Shrub Swamp (0.750)	0	50.6	38.0		129.2	96.9		
	25	49.7	37.3		127.9	95.9		
	50	48.8	36.6		126.5	94.9		
	75	47.8	35.9		125.2	93.9		
	100	46.9	35.2	36.6	123.8	92.9	94.9	131.5
Forested Wetland (0.803)	0	79.4	63.8		367.3	294.9		
	25	81.7	65.6		384.0	308.4		
	50	84.1	67.5		400.6	321.7		
	75	86.4	69.4		417.3	335.1		
	100	88.8	71.3	67.5	434.0	348.5	321.7	389.2
Pasture (0.754)	0	37.3	28.1		130.8	98.6		
	25	19.6	14.8		117.0	88.2		
	50	14.9	11.2		110.4	83.2		
	75	10.3	7.8		103.9	78.3		
	100	5.6	4.2	12.5	97.3	73.4	83.9	96.4
Cropland (0.605)	0	124.7	75.5		424.4	256.8		
	25	37.4	22.6		382.0	231.1		
	50	24.9	18.8		360.7	218.2		
	75	12.5	9.4		339.5	205.4		
	100	0.0	0.0	20.7	318.3	192.6	219.8	240.5
Mudflat ² (0.300)	0	0.0	0.0					
	25	130.9	39.3					
	50	130.9	39.3					
	75	130.9	39.3					
	100	130.9	39.3	32.8				

Total Average Annual
Habitat Units

971.9

¹Habitat Suitability Index.

²Totals for upper and lower pools combined.

Table 10. -- Average Annual Habitat Units within the flood pool boundaries of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, New York.

Habitat Types	Average Annual Habitat Units ¹		Net Average ² Annual HU's
	Without the Project	With the Project	
Emergent Marsh	52.9	81.5	+28.6
Shrub Swamp	90.2	131.5	+41.3
Forested Wetland	416.2	389.2	-27.0
Pasture	118.3	96.4	-21.9
Cropland	332.3	240.5	-91.8
Mudflat	0.0	32.8	+32.8
Total	1009.9	971.9	-38.0

¹Average Annual Habitat Units from Tables 8 and 9.

²Does not include Habitat Units lost due to the construction of the dry dams and lateral dikes.

Table 11. -- Relative Importance Value Criteria determined for each habitat type in the area of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, Genesee County, New York.

RIV Criteria	Range of Value ¹	Habitat Type				
		Emergent Marsh	Shrub Swamp	Forested Wetland	Pasture	Cropland Mudflat
Abundance	1-most abundant 10-least abundant	10	8	3	8	1 8
Vulnerability	1-lowest probability 10-greatest probability	6	1	1	9	10 1
Reproducibility	1-easily managed and/or created 10-little or no possibility to manage or create	5	8	10	2	1 2
Aesthetic Value	1-lowest value 10-highest value	9	5	10	3	1 1
Recreational Diversity	1-low 10-high	10	7	10	2	2 2
Species Richness	1-lowest 10-highest	7	8	10	3	1 2

¹A scale of 1-10 was used for filling each square of this matrix.

Table 13. -- Relative Importance Values determined for each habitat type in the area of the proposed Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, Genesee County, New York.

RIV Criteria	Habitat Types					
	Emergent Marsh	Shrub Swamp	Forested Wetland	Pasture	Cropland	Mudflat
Abundance	(.19)	1.52	0.57	1.52	0.19	1.52
Vulnerability	(.19)	0.19	0.19	1.71	1.90	.19
Replaceability	(.14)	1.12	1.40	0.28	0.14	.28
Aesthetic Value	(.05)	0.25	0.50	0.15	0.05	.05
Recreational Diversity	(.14)	0.98	1.40	0.28	0.28	.28
Species Richness	(.29)	2.32	2.90	0.87	0.29	.58
Total	7.62	6.38	6.96	4.81	2.85	2.90
Relative Importance Value (RIV) ²	1.00	0.84	0.91	0.63	0.37	.38

¹Represents the product of the values from Tables 11 and 12.

²The Relative Importance Value is obtained by dividing the sum for each habitat type by the greatest individual sum.

Table 14. -- Conversion of Average Annual Habitat Unit gains and losses using Relative Importance Values for the Tonawanda Creek Flood Control Project, Towns of Alexander and Batavia, Genesee County, New York.

Habitat Type	RIV ¹	Net Gain or Loss of HU ²	$\frac{\text{RIV Habitat Type 1}}{\text{RIV Habitat Type 2}}$	=	$\frac{\text{HU Type 2}}{\text{HU Type 1}}$	X HU
Emergent Marsh Forested Wetland	$\frac{1.00}{0.91}$	27.9	$\frac{1.00}{0.91}$	=	$\frac{X}{27.9}$	30.7
Shrub Swamp Forested Wetland	$\frac{0.84}{0.91}$	39.6	$\frac{0.84}{0.91}$	=	$\frac{X}{39.6}$	36.6
Pasture Forested Wetland	$\frac{0.63}{0.91}$	-21.9	$\frac{0.63}{0.91}$	=	$\frac{X}{21.9}$	-15.2
Cropland Forested Wetland	$\frac{0.37}{0.91}$	-98.3	$\frac{0.37}{0.91}$	=	$\frac{X}{98.3}$	-40.0
Mudflat Forested Wetland	$\frac{0.38}{0.91}$	32.8	$\frac{0.38}{0.91}$	=	$\frac{X}{32.8}$	13.7
Forested Wetland	-	-28.7	-		-	-28.7
Total						-2.9

¹Relative Importance Values from Table 13.

²Includes Habitat Unit losses from construction of dry dams and lateral dikes (Table 7).

AD-A133 910


BUFFALO METROPOLITAN AREA NEW YORK WATER RESOURCES
MANAGEMENT INTERIM REP. (U) CORPS OF ENGINEERS BUFFALO
NY BUFFALO DISTRICT JUL 83

9/9


UNCLASSIFIED

F/G 13/2

NL




END



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

New York State Department of Environmental Conservation
6274 East Avon-Lima Road, Avon, New York 14414
TELEPHONE: 716/226-2466



Henry G. Williams
Commissioner

Eric A. Seiffer
Regional Director

March 10, 1983

Mr. Philip Berkeley
Department of the Army
Buffalo District
Corps of Engineers
1776 Niagara Street
Buffalo, N.Y. 14207

Dear Phil:

We have reviewed the material sent on February 3, 1983, and offer the following comments.

The Division of Fish and Wildlife has a general policy to recommend on-site mitigation as the primary objective in compensating for loss to fish and wildlife habitat through project losses. However, we are not totally inflexible and will consider other alternatives as the need arises. The following alternatives were recommended by our Wildlife unit for mitigation of wetland losses through construction of dikes and dams.

1. Acquisition and development of 100 acres of wetland located just south of Pike Road and west of Route 98. We anticipate costs of this on-site mitigation to be \$25,000-\$50,000.
2. Restoration of existing wet meadow area within the flood control project by level ditching and island construction. This on-site mitigation would cost approximately \$15,000 (200+ hours with a Drot (40 at \$75/hour).
3. Acquisition of approximately 30 acres of agricultural land adjacent to Goose Pond on the Oak Orchard WMA and reconstruction of existing dikes to increase storage capacity of impoundment. The approximate cost of this off-site mitigation would be \$45,000 - \$60,000.

Regional Fish and Wildlife staff do not feel that simple habitat improvement on existing state owned lands would provide adequate mitigation for loss on the project site.


The above recommendations are made only for losses to wetlands through actual construction impacts. Losses to other habitats as a result of changes

Mr. Philip Berkeley
March 10, 1983
Page Two

in land use should be addressed in the final report after coordinating with the USFWS and NYSDEC. I have had some brief discussions with Doug Ryan of the USFWS concerning modifications of the Fish and Wildlife Coordination Act Report. I believe they will include some potential mitigation measures which we will want to discuss at some future date at a joint meeting between our respective agencies.

If I can be of further assistance, please contact me at the Avon Office.

Sincerely yours,




Jack G. Cooper
Wetlands Violation Coordinator

JGC:mp

cc: Paul Hamilton, USFWS
DRA

New York State Department of Environmental Conservation
60 Wolf Road, Albany, New York 12233



Henry G. Williams
Commissioner

March 17, 1983

Mr. Robert R. Hardiman
Colonel, Corps of Engineers
District Engineer, Buffalo District
1776 Niagara Street
Buffalo, NY 14207

RE: Final Environmental Impact Statement
Regional Flood Control, Tonawanda Creek
Genesee County, New York
DEC #089-007

Dear Colonel Hardiman:

This Department of Environmental Conservation (DEC) has reviewed the above referenced document. The comments provided express recommendations of DEC Regional Fish and Wildlife staff and reflect concerns with the FEIS only.

The following mitigation measures are recommended.

1. For wetlands lost to construction activities, approximately 60 acres either on-site or as additional land purchased at the Orchard Game Management Area.
2. Mitigation for the loss of 1900+ acres (Fish and Wildlife Coordination Act Report) of upland habitat lost. It is recommended that this mitigation be developed in cooperation between the Corps, U.S. Fish and Wildlife Service and this Department.

The Department notes that the Corps has contacted DEC Fish and Wildlife personnel to discuss and recommend alternatives to on-site mitigation.

Thank you for the opportunity for review and comment.

Sincerely,

Louis M. Concra, Jr.
Director, Division of Regulatory Affairs


LMC/ERM:dh

cc: E. Wagner
D. Konsella
E. Miller
File

24 MAR 83 10 23
OFC. MGMT. D.A.S.

New York State Department of Environmental Conservation
6274 E. Avon - Lima Rd., Avon, NY 14414
TELEPHONE: 716/226-2466

9 MAY 83 12 38



Henry G. Williams
Commissioner

Eric A. Seiffer
Regional Director

May 6, 1983

Colonel Robert R. Hardiman
District Engineer
Buffalo District Corp of Engineers
1776 Niagara Street
Buffalo, New York 14207

Re: Tonawanda Creek Flood Control Project, Proposed Fish and Wildlife
Mitigation Plan


Dear Colonel Hardiman:

This is in response to your letter of April 29, 1983 relative to fish and wildlife habitat mitigation in the above referenced project. We have indicated in our past communications that we prefer on-site mitigation to off-site mitigation. However, we did agree to consider mitigation at the Oak Orchard Wildlife Management area if additional land was acquired.

The DEC Division of Fish and Wildlife does not feel that simple habitat improvement on existing state-owned lands can adequately mitigate for wetland and wildlife habitat destruction. The proposal presented in your recent letter essentially offers only habitat improvement and not additional acquisition, therefore, we cannot support this concept as adequate compensation for the loss of 65 plus or minus acres of wetland/riparian habitat (as discussed in your letter of February 3, 1983).

I think that it is very important for all of the involved agencies (U.S. Fish and Wildlife Service, Corps of Engineers and DEC) to reach some kind of agreement on the type and scope of mitigation adequate to compensate for wetland and habitat losses. Therefore, I would recommend that a joint meeting be held in the near future in order to resolve these problems. The Regional Fish and Wildlife staff is very concerned with impacts to wetland and wildlife habitats associated with this project, and cannot support this project unless adequate measures are taken to compensate for losses. If I can be of any further assistance, please contact me at (716) 226-2466.

Sincerely yours,


Jack G. Cooper
Conservation Biologist II (Eco.)
Region 8

JGC:bf
cc: U.S. Fish & Wildlife Service



UNITED STATES
DEPARTMENT OF THE INTERIOR
FISH AND WILDLIFE SERVICE
100 Grange Place
Room 202
Cortland, New York 13045

July 1, 1983

OF.C. MGMT. OAS
5 JUL 83 13 15

Colonel Robert R. Hardiman
District Engineer, Buffalo District
U.S. Army Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Colonel Hardiman:

We reviewed the wildlife loss mitigation analysis provided with Major Creeden's letter of June 9, 1983 concerning the Tonawanda Creek Project. Inherent in this analysis are several faulty assumptions which inevitably lead to the seriously flawed conclusion of little or no adverse impact on fish and wildlife thus obviating the need to purchase land for loss mitigation purposes.

The above mentioned assumptions are as follow:

- 1). no increased habitat value from interspersions of "idle" lands;
- 2). only so called "significant" wildlife species evaluated;
- 3). no impacts from farming activities to top of streambank;
- 4). little change in farming practices regarding harvest; and
- 5). only corn will be planted in the "idle" lands.


Although the "idle" lands in themselves are important habitats, their greatest value is the additional diversification they provide to the total complex of habitats. This attribute was largely ignored in your analysis. Although the analysis mentions the interspersions of these lands as being valuable, it only considers key wildlife species actually supported on these lands. Our report lists 120 wildlife species. An important reason for such a variety is the interspersions provided by the "idle" lands. Your concentration on "key species" automatically results in seriously under-valuing the interspersions provided by "idle" lands under without-the-project conditions.

The last 3 assumptions result in over-valuing the with-the-project habitat conditions. Experience shows that most farmers will clear these lands to the very edge of the streambanks once they are protected from floods. This would reduce the "edge" and travel corridors used by wildlife, resulting in reduced populations. In addition it would adversely impact the aquatic habitat in the stream because of reduced shading and increased erosion and siltation.

The assumption that harvesting practices would be unchanged and corn would be left standing in the field is a contradiction. With flood control, this corn would inevitably be harvested and many of the fields would be plowed in the fall resulting in little value to wildlife. Also to assume all of the "idle" lands would be planted to corn is faulty. It is just as logical to assume that a large percentage would be used for pasture that would be even lower in habitat value than the corn.

We submit that our assumptions are as logical or more logical than yours and that a significant decrease in wildlife habitat value on the 1900+ acres of "idle" lands would result from the project. We, therefore, strongly urge you to accept the recommendations of our 10/23/80 report and 2/23/83 supplement or join with us and NYSDEC in conducting a modified HEP on these lands this summer. Only in this way could we be assured that losses to wildlife would be mitigated or that you could be assured that the mitigation measures are necessary. We certainly hope to avoid the unpleasantness of submitting a new recommendation on this project, one of opposition to its construction.

Sincerely yours,



Paul P. Hamilton
Field Supervisor

cc:
NYSDEC, Albany, NY - Ken Wich
NYSDEC, Avon, NY

APPENDIX H, PART 4

CULTURAL RESOURCES COORDINATION

The Buffalo District contracted with the Department of Anthropology of the State University of New York at Binghamton, during the summer of 1979, to conduct a Phase I archaeological reconnaissance of the Batavia Reservoir Compound area. The Phase I report has been coordinated with the State Historic Preservation Officer (SHPO), the New York State Archaeologist and the Heritage Conservation and Recreation Service. Letters of Coordination are printed on the next few pages.

Copies of the report entitled "Batavia Reservoir Compound Phase I Archaeological Summary" by J. Terrence McCabe and A. Peter Mair III, et. al. are available through the National Technical Information Service, U.S. Department of Commerce, Springfield, VA 22161.

NCBED-PE

17 October 1980

Dr. Robert Funk
State Archaeologist
University of the State
of New York
State Education Department
Cultural Education Center
Albany, NY 12230

Dear Dr. Funk:

Enclosed for your information is a Final Cultural Resources Report entitled,
Batavia Reservoir Compound: Phase I Archaeological Summary and Appendicies.

If you have any questions regarding this report, please contact Mr. Richard H. Lewis, Staff Archaeologist, at (716) 876-5454, extension 2175.

Sincerely,

3 Incl
as stated

DONALD M. LIDDELL
Chief, Engineering Division

CF:
✓ NCBED-PE

Lewis_____
Berkeley_____
Bennett_____
Pieczynski_____
Hallock_____
Liddell_____

NCRED-PE

17 October 1980

Ms. Ann Webster Smith
Deputy Commissioner for
Historic Preservation
New York State Office of
Parks and Recreation
Agency Building #1
Empire State Plaza
Albany, NY 12338

Dear Ms. Smith:

Enclosed for your information is a Final Cultural Resources Report entitled,
Batavia Reservoir Compound: Phase I Archaeological Summary and Appendicies.

If you have any questions regarding this report, please contact Mr. Richard H.
Lewis, Staff Archaeologist, at (716) 876-5454, extension 2175.

Sincerely,

3 Incl
as stated

DONALD M. LIDDELL
Chief, Engineering Division

CP:
✓ NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

NCBED-PE

17 October 1980

Dr. Bennie Keel
Departmental Consulting Archaeologist
Heritage Conservation and
Recreation Service
U. S. Department of the Interior
Washington, DC 20243

Dear Dr. Keel:

Enclosed for your information is a Final Cultural Resources Report entitled,
Batavia Reservoir Compound: Phase I Archaeological Summary and Appendicies.

If you have any questions regarding this report, please contact Mr. Richard H.
Lewis, Staff Archaeologist, at (716) 876-5454, extension 2175.

Sincerely,

2 Incl
as stated

DONALD M. LIDDELL
Chief, Engineering Division

CF:
✓ NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

NCBED-PE

17 October 1980

Mrs. Myra Harrison
Division of Archaeology
Heritage Conservation and
Recreation Service
William J. Green Federal Building
600 Arch Street
Room 9310
Philadelphia, PA 19106

Dear Ms. Harrison:

Enclosed for your information is a Final Cultural Resources Report entitled,
Batavia Reservoir Compound: Phase I Archaeological Summary and Appendicies.

If you have any questions regarding this report, please contact Mr. Richard H.
Lewis, Staff Archaeologist, at (716) 876-5454, extension 2175.

Sincerely,

2 Incl
as stated

DONALD M. LIDDELL
Chief, Engineering Division

CF:
✓ NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

NCBED-PE

17 October 1980

Defense Technical Information Center
ATTN: DTIS/DDA-2/Paul F. Cooper
Alexandria, VA 22314

Dear Mr. Cooper:

Enclosed are 12 copies of the report entitled, "Batavia Reservoir Compound Archaeological Summary," and appendicies. Please make the necessary arrangements to have this report and appendicies available from the National Technical Information Service, Springfield, VA.

If you require any further input, please feel free to contact me at the above address.

Sincerely,

1 Incl (12 cys)
as stated

THOMAS VAN WART
District Librarian

CF:
✓ NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
VanWart _____



United States Department of the Interior
HERITAGE CONSERVATION AND RECREATION SERVICE
SOUTHEAST REGIONAL OFFICE
75 Spring Street S.W., Suite 1176
Atlanta, Georgia 30303

IN REPLY REFER TO:

W540

JUL 15 1980

Mr. Richard H. Lewis
Buffalo District, Corps
of Engineers
1776 Niagara Street
Buffalo, New York 14207

Dear Mr. Lewis:

Due to staff reductions within the Office of Interagency Archeological Services-Atlanta, we are unable to review the report "Batavia Reservoir Compound, Phase I Archeological Survey." We will be happy to continue to receive reports for review from your office and will notify you on an as received basis which ones we will review. If you have any questions, please contact Mr. James Thomson at (404) 221-2633.

Sincerely,


Victor A. Carbone
Acting Chief



NEW YORK STATE PARKS & RECREATION Agency Building 1, Empire State Plaza, Albany, New York 12238 Information 518 474 0650
Orin Lehman, Commissioner

June 27, 1980

Mr. Donald Liddell
Chief, Engineering Division
Dept. of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, N.Y. 14207

Dear Mr. Liddell:

Batavia Reservoir Compound
Genesee County, New York

We have reviewed the cultural resource reconnaissance report on this project and wish to make a few comments. The survey seems to be complete and the recommendations are in order. However, the structure survey forms do not provide sufficient information for us to evaluate them. The contact prints are not adequate particularly in cases where the structure may well be eligible for the National Register. Photos should be attached to the form as indicated on the form and in the enclosed manual. Also, an overall map should be included with forms keyed to it. This can be a USGS map if scale is a problem. We suggest you have your consultants follow the instructions in the manual for architectural and historical information as well.

Due to the large number of structures included in this study, it may be beneficial to wait until you know which structures are to be affected before a detail study is made.

Please call Bruce Fullem at 518-474-3176 should you wish to discuss this matter in detail.

Sincerely,

Stephen J. Raiche
Director
Historic Preservation Field
Services

ALL DONE

Checked by

Filed by

52
ERK

BF:mr

Enc.

NCBED-PE

9 June 1980

Dr. Robert Funk, State Archaeologist
New York State Museum and Science Service
Anthropological Survey
Albany, NY 12234

Dear Dr. Funk:

Enclosed for your review and comment is a cultural resources reconnaissance report entitled "Batavia Reservoir Compound, Phase I Archaeological Summary" prepared for the Buffalo District by the State University of New York at Binghamton. This report is an update (which was required by project changes) of the cultural resources report provided for your review in November 1979.

If we do not receive your comments within 30 days of your receipt of this letter, we will assume you are in agreement with the contents of the report. Comments received after the expiration of the comment period cannot be considered in the preparation of the final report.

If you have any questions regarding this matter, please contact my staff Archaeologist, Mr. Richard H. Lewis at (716) 876-5454, extension 2171.

Sincerely,

DONALD M. LIDDELL
Chief, Engineering Division

CF:
✓NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

NCBED-PE

9 June 1980

Dr. Stephanie H. Rodeffer, Acting Chief
Interagency Archaeological Services - Atlanta
Heritage Conservation and Recreation Service
Richard B. Russel Federal Building
75 Spring Street
Atlanta, GA 30303

Dear Dr. Rodeffer:

Enclosed for your review and comment is a cultural resources reconnaissance report entitled "Batavia Reservoir Compound, Phase I Archaeological Summary" prepared for the Buffalo District by the State University of New York at Binghamton. This report is an update (which was required by project changes) of the cultural resources report provided for your review in November 1979.

If we do not receive your comments within 30 days of your receipt of this letter, we will assume you are in agreement with the contents of the report. Comments received after the expiration of the comment period cannot be considered in the preparation of the final report.

If you have any questions regarding this matter, please contact my staff Archaeologist, Mr. Richard H. Lewis at (716) 876-5454, extension 2171.

Sincerely,

DONALD M. LIDDELL
Chief, Engineering Division

CF:
NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

NCBED-PE

9 June 1980

Dr. Ann Webster-Smith, Deputy Commissioner
for Historic Preservation
Division for Historic Preservation
New York State Office of Parks and
Recreation
Agency Building No. 1
Empire State Plaza
Albany, NY 12238

Dear Dr. Webster-Smith:

Enclosed for your review and comment is a cultural resources reconnaissance report entitled "Batavia Reservoir Compound, Phase I Archaeological Summary" prepared for the Buffalo District by the State University of New York at Binghamton. This report is an update (which was required by project changes) of the cultural resources report provided for your review in November 1979.

If we do not receive your comments within 30 days of your receipt of this letter, we will assume you are in agreement with the contents of the report. Comments received after the expiration of the comment period cannot be considered in the preparation of the final report.


If you have any questions regarding this matter, please contact my staff Archaeologist, Mr. Richard H. Lewis at (716) 876-5454, extension 2171.

Sincerely,

DONALD M. LIDDELL
Chief, Engineering Division

CF:
NCBED-PE

Lewis _____
Berkeley _____
Bennett _____
Pieczynski _____
Hallock _____
Liddell _____

TELEPHONE OR VERBAL CONVERSATION RECORD <small>For use of this form, see AR 340-15; the proponent agency is The Adjutant General's Office.</small>		<small>DATE</small> 4January 1980
<small>SUBJECT OF CONVERSATION</small> Letter from The New York State Historic Preservation Office Regarding the Batavia Reservoir Compound Phase I Archaeological Summary.		
INCOMING CALL		
<small>PERSON CALLING</small>	<small>ADDRESS</small>	<small>PHONE NUMBER AND EXTENSION</small>
<small>PERSON CALLED</small>	<small>OFFICE</small>	<small>PHONE NUMBER AND EXTENSION</small>
OUTGOING CALL		
<small>PERSON CALLING</small>	<small>OFFICE</small>	<small>PHONE NUMBER AND EXTENSION</small>
Richard H. Lewis	NCBED-PE	FTS 4732171
<small>PERSON CALLED</small>	<small>ADDRESS</small>	<small>PHONE NUMBER AND EXTENSION</small>
Bruce Fullem	NYSHPO	FTS 456-3176
<small>SUMMARY OF CONVERSATION</small> <p>Mr. Fullem was called in order to explain how the Buffalo District was planning to handle the data deficiencies in the above referenced report. It was explained that a contract modification was being considered that would require the contractor to survey those portions of the project area which were not included in the initial scope of work. In addition it would be required that the contractor fill out the Building-Structure Inventory Form, which is required by the state, for each structure which would be affected by the project. Mr Fullem indicated that this approach would satisfy the concerns of the SHPO.</p> <div style="text-align: right; margin-top: 100px;">  Richard H. Lewis Archaeologist Environmental Resources Section </div> <div style="margin-top: 100px;"> CF: NCBED-P NCBED-PN NCBED-PE </div>		

DA FORM 751
APR 88

REPLACES EDITION OF 1 FEB 58 WHICH WILL BE USED.



NEW YORK STATE PARKS & RECREATION Agency Building 1 Empire State Plaza Albany, New York 12238 Information 518-474-0456
Orin Lehman, Commissioner

December 21, 1979

Kenneth R. Hallock
Acting Chief, Engineering Division
Department of the Army
Buffalo District, Corps of Engineers
1776 Niagara Street
Buffalo, New York 14207

Attention: Richard Lewis

Gentlemen:

"Batavia Reservoir Compound Phase I
Archaeological Summary"
Batavia Reservoir Compound
Tonawanda Creek, between Alexander and
Batavia
Genesee County

Thank you for consulting with the State Historic Preservation Officer (SHPO) concerning the above-referenced report.

It is the opinion of the SHPO that the report represents a professional effort, and that the further archeological investigation that is recommended should be undertaken. Further, we understand that the nature and scope of the project have changed a bit recently, and that we do not have a current assessment of what specific structures may be affected by the proposed undertaking. When you have determined what structures may be affected, please provide us with additional information on each so that our office can provide you with additional comments. For each structure, we request:

1. mapped location (one master map could also be used)
2. original photograph
3. blue building/structure inventory form (see enclosed sample)
4. description of potential effect upon building.

If you should have any questions, please contact the project review staff at 518-474-3176.

Sincerely,


STATE HISTORIC PRESERVATION OFFICER


By Stephen J. Raiche, Director
Historic Preservation Field
Services

LRK:mr
Enc.

TELEPHONE OR VERBAL CONVERSATION RECORD <small>For use of this form, see AR 340-15; the proponent agency is The Adjutant General's Office.</small>		<small>DATE</small> 12 December 1979
<small>SUBJECT OF CONVERSATION</small> Review of the Cultural Resources Report for the Batavia Reservoir Compound by the Interagency Archaeological Services (IAS)		
INCOMING CALL		
<small>PERSON CALLING</small> 	<small>ADDRESS</small> 	<small>PHONE NUMBER AND EXTENSION</small>
<small>PERSON CALLED</small> 	<small>OFFICE</small> 	<small>PHONE NUMBER AND EXTENSION</small>
OUTGOING CALL		
<small>PERSON CALLING</small> Richard H. Lewis	<small>OFFICE</small> NCBED-PE	<small>PHONE NUMBER AND EXTENSION</small>
<small>PERSON CALLED</small> Jim Thompson	<small>ADDRESS</small> IAS	<small>PHONE NUMBER AND EXTENSION</small>
<small>SUMMARY OF CONVERSATION</small> Mr. Thompson was called in order to find out if IAS was planning to comment on the subject report. He indicated that they were not.		

Richard H. Lewis
 Richard H. Lewis
 Archaeologist
 Environmental Resources Section

TELEPHONE OR VERBAL CONVERSATION RECORD <small>For use of this form, see AR 340-13; the proponent agency is The Adjutant General's Office.</small>		<small>DATE</small> 10 December 1979
<small>SUBJECT OF CONVERSATION</small> Review of the Cultural Resources Report for the Batavia Reservoir Compound by the Office of the State Archaeologist (OSA)		
INCOMING CALL		
<small>PERSON CALLING</small>	<small>ADDRESS</small>	<small>PHONE NUMBER AND EXTENSION</small>
<small>PERSON CALLED</small>	<small>OFFICE</small>	<small>PHONE NUMBER AND EXTENSION</small>
OUTGOING CALL		
<small>PERSON CALLING</small>	<small>OFFICE</small>	<small>PHONE NUMBER AND EXTENSION</small>
Richard H. Lewis	NCRED-PE	
<small>PERSON CALLED</small>	<small>ADDRESS</small>	<small>PHONE NUMBER AND EXTENSION</small>
Phil Lord	OSA	
<small>SUMMARY OF CONVERSATION</small> Mr. Lord was called in order to find out if the OSA was planning to comment on the subject report. He indicated that his office did review the report but was not going to submit written comments.		
 Richard H. Lewis Archaeologist Environmental Resources Section		

TELEPHONE OR VERBAL CONVERSATION RECORD <small>For use of this form, see AR 340-15; the proponent agency is The Adjutant General's Office.</small>		<small>DATE</small> 10 December 1979
<small>SUBJECT OF CONVERSATION</small> Review of the Cultural Resources Report for the Batavia Reservoir Compound by the New York State Historic Preservation Office (NYSHPO)		
INCOMING CALL		
<small>PERSON CALLING</small> 	<small>ADDRESS</small> 	<small>PHONE NUMBER AND EXTENSION</small>
<small>PERSON CALLED</small> 	<small>OFFICE</small> 	<small>PHONE NUMBER AND EXTENSION</small>
OUTGOING CALL		
<small>PERSON CALLING</small> Richard H. Lewis	<small>OFFICE</small> NCBED-PE	<small>PHONE NUMBER AND EXTENSION</small> FTS 4732171
<small>PERSON CALLED</small> Lemore Kuwik	<small>ADDRESS</small> NYSHPO	<small>PHONE NUMBER AND EXTENSION</small> FTS 5643176
<small>SUMMARY OF CONVERSATION</small> <p>Ms. Kuwik was called to find out the status of the subject report in the NYSHPO'S review process and to find out if the comments which we requested would be recieved within the 30 day review peroid.</p> <p>She indicated that the report had been circulated and the review about 50% completed, however it did not appear that the comments would be submitted to Buffalo District within the review peroid. She fúrter indicated that the comments should be recieved by 30 December 1979.</p> <div style="text-align: right; margin-top: 100px;">  Richard H. Lewis Archaeologist Environmental Resources Section </div>		

NCBED-PE

13 November 1979

Mr. Bruce Fullen
Office of Orin Lehman, Commissioner
State Historic Preservation Officer
Division for Historic Preservation
New York State Office of Parks
and Recreation
Agency Building, 1 Empire State Plaza
Albany, NY 12238

Dear Mr. Fullen:

Enclosed for your review and comment is a report entitled "Batavia Reservoir Compound Phase I Archaeological Summary." This report was undertaken in partial fulfillment of E. O. 11593 and the National Historic Preservation Act.

If we do not receive your comments within 30 days of your receipt of this letter, we will assume you are in agreement with the contents of the report.

If you have any questions regarding this action, please contact staff archaeologist, Richard H. Lewis at (716) 876-5454, ext. 2171.

Thank you for your consideration in this matter.

Sincerely,

1 Incl
as stated
✓ CF:
NCBED-PE

KENNETH R. HALLOCK
Acting Chief, Engineering Division

Lewis _____
Berkeley _____
Bennett _____
Gilbert _____
Hallock _____

NCBED-PE

13 November 1979

Robert Funk, State Archaeologist
New York State Museum and Science Service
Anthropological Survey
Albany, NY 12234

Dear Mr. Funk:

Enclosed for your review and comment is a report entitled "Batavia Reservoir Compound Phase I Archaeological Summary." This report was undertaken in partial fulfillment of E. O. 11593 and the National Historic Preservation Act.

If we do not receive your comments within 30 days of your receipt of this letter, we will assume you are in agreement with the contents of the report.

If you have any questions regarding this action, please contact staff archaeologist, Richard H. Lewis at (716) 876-5454, ext. 2171.

Thank you for your consideration in this matter.

Sincerely,

1 Incl
as stated
Cf:

✓ NCBED-PE.

KENNETH R. HALLOCK
Acting Chief, Engineering Division

Lewis _____
Berkeley _____
Bennett _____
Gilbert _____
Hallock _____

NCBED-PE

13 November 1979

Bennie Keel, Chief
Interagency Archaeological
Services - Atlanta
Heritage Conservation and
Recreation Service
Richard Brussel Federal Building
75 Spring Street
Atlanta, GA 30303

Dear Mr. Keel:

Enclosed for your review and comment is a report entitled "Batavia Reservoir Compound Phase I Archaeological Summary." This report was undertaken in partial fulfillment of E. O. 11593 and the National Historic Preservation Act.

If we do not receive your comments within 30 days of your receipt of this letter, we will assume you are in agreement with the contents of the report.

If you have any questions regarding this action, please contact staff archaeologist, Richard H. Lewis at (716) 876-5454, ext. 2171.

Thank you for your consideration in this matter.

Sincerely,

1 Incl
as stated
CF:
✓ NCBED-PE

KENNETH R. HALLOCK
Acting Chief, Engineering Division

Lewis _____
Berkeley _____
Bennett _____
Gilbert _____
Hallock _____

